



I-4 Beyond the Ultimate

Current and Future Construction Projects as of September 2019

Stay Informed:

- » Project Hotline: 844-ULT-INFO (858-4636)
- » Sign up for email and text alerts at i4Beyond.com/alerts
- » Subscribe to our monthly newsletter at i4Beyond.com/news
- » Follow us on Twitter at [fdot.tips/twitter](https://twitter.com/fdot.tips/twitter)
- » Subscribe to our YouTube channel at [fdot.tips/youtube](https://www.youtube.com/channel/fdot.tips/youtube)

I-4 Beyond the Ultimate NORTH

I-4 Ultimate

I-4 Beyond the Ultimate SOUTH



Current I-4 Beyond the Ultimate Construction Projects

- 1 E.E. Williamson Rd. Bridge Reconstruction at I-4** — Construction began in Sept. 2019. Completion expected in Spring 2021. (FPID: 439682-4)
- 2 EB I-4 New Auxiliary Lane from I-4 Ultimate to Lake Mary Blvd.** — Project includes milling and resurfacing EB I-4 from I-4 Ultimate to the EB I-4 exit to Lake Mary Blvd. Construction began in Sept. 2019. Completion expected in Spring 2021. (FPID: 439682-3)
- 3 Repaving EB I-4 between C.R. 46A and U.S. 17-92** — Milling and resurfacing EB I-4 from west of Lake Mary Blvd. to west of County Road (C.R.) 46A and from west of State Road (S.R.) 46 to east of U.S. 17-92. Construction began in Aug. 2019. Completion expected in February 2020. (FPIDs: 439682-2,-5)

Other I-4 Construction Projects

- 4 I-4 Ultimate** — Reconstruction of 21 miles of I-4 from west of Kirkman Road (S.R. 435) to east of S.R. 434. (FPID: 432193-1)
- 5 Wekiva Pkwy. (S.R. 429)** — Section 8 of the Wekiva Pkwy. project will build 2.63 miles of limited access toll road from Orange Blvd. to east of Rinehart Road. This section will include the new interchange at I-4 that will connect with S.R. 417. (FPID: 240200-4)

Future Construction Projects

- A Championsgate Interchange Improvements** — A diverging diamond interchange is being designed for C.R. 532 at the I-4 interchange. Construction anticipated in Fall 2021. (FPID: 444187-1)
- B EB/WB I-4 New Auxiliary Lanes between S.R. 429 and C.R. 532** — New auxiliary lanes are proposed on I-4, one in each direction, between the ramps of S.R. 429 and C.R. 532, and an auxiliary lane on NB S.R. 429 between I-4 and Sinclair Road. Project also includes milling and resurfacing EB and WB I-4 from the Polk-Osceola county line to west of S.R. 417. Construction anticipated in Fall 2021. (FPIDs: 444329-1, 443958-1)
- C Daryl Carter Pkwy. and I-4 Interchange** — Three new ramps will connect I-4 to Daryl Carter Pkwy. These include exit ramps from both directions of I-4 and an entrance ramp to EB I-4. Project will also convert the existing Daryl Carter Pkwy. overpass to a diverging diamond interchange. Construction anticipated late 2021/early 2022. (FPID: 441113-1)
- D Sand Lake Road (S.R. 482) and I-4 Interchange Improvements** — Interchange will be reconfigured into a diverging diamond. Left turns from WB Sand Lake Road to SB Turkey Lake Road will be eliminated. Instead, access to Turkey Lake Road will be via a new loop ramp. Construction anticipated late 2021/early 2022. (FPID: 444315-1)
- E Repaving WB I-4 in Seminole County** — Milling and resurfacing WB I-4 from the Seminole-Volusia county line to Lake Mary Blvd. Project excludes the section of WB I-4 between C.R. 46A and S.R. 46 that will be improved during construction of the Wekiva Pkwy. Construction anticipated in Summer 2020. (FPID: 439682-1)



Sign up for I-4 Construction Alerts from the I-4 Beyond the Ultimate, I-4 Ultimate, and Wekiva Parkway at I4Beyond.com/alerts

Learn more about current and future I-4 Beyond the Ultimate construction projects at I4Beyond.com