

Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd
 Date October 6, 2011
 Time Period AM Peak Hour
 All Vehicles

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	1	0	35	0	0	45
7:15 - 7:30	0	0	38	0	0	60
7:30 - 7:45	0	0	39	0	0	60
7:45 - 8:00	0	0	39	0	0	89
8:00 - 8:15	0	0	40	0	0	84
8:15 - 8:30	0	1	33	0	0	80
8:30 - 8:45	0	0	49	0	0	82
8:45 - 9:00	0	0	38	0	0	79
TOTAL	1	1	311	0	0	579

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	52	120	0	0	361	78
7:15 - 7:30	96	132	0	0	477	91
7:30 - 7:45	88	142	0	0	479	132
7:45 - 8:00	74	156	0	0	456	101
8:00 - 8:15	52	107	0	0	444	88
8:15 - 8:30	42	119	0	0	379	59
8:30 - 8:45	33	131	0	0	402	46
8:45 - 9:00	49	135	0	0	394	56
TOTAL	486	1,042	0	0	3,392	651

North / South	293	0	0	412
I-4 EB Ramps				1,856
East / West				0
Saxon Blvd				
Peak Hour				
7:15 - 8:15	310			
Peak Hour Factor	537			
0.95				
Total Pk Hr Volume	0			
3,564				

Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd


Date October 6, 2011

Time Period AM Peak Hour Trucks

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	0	0	1	0	0	7
7:15 - 7:30	0	0	0	0	0	4
7:30 - 7:45	0	0	1	0	0	5
7:45 - 8:00	0	0	1	0	0	3
8:00 - 8:15	0	0	0	0	0	3
8:15 - 8:30	0	0	0	0	0	3
8:30 - 8:45	0	0	0	0	0	2
8:45 - 9:00	0	0	0	0	0	1

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	0	3	0	0	1	0
7:15 - 7:30	3	2	0	0	4	0
7:30 - 7:45	1	1	0	0	1	0
7:45 - 8:00	5	1	0	0	1	1
8:00 - 8:15	0	2	0	0	1	0
8:15 - 8:30	1	2	0	0	2	1
8:30 - 8:45	0	0	0	0	2	1
8:45 - 9:00	1	4	0	0	1	1



Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd


Date October 6, 2011

Time Period AM Peak Hour U-Turn & Right Turn on Red (RTOR)

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	0	0	0	0	0	0
7:15 - 7:30	0	0	0	0	0	0
7:30 - 7:45	0	0	0	0	0	0
7:45 - 8:00	0	0	0	0	0	0
8:00 - 8:15	0	0	0	0	0	0
8:15 - 8:30	0	0	0	0	0	0
8:30 - 8:45	0	0	0	0	0	0
8:45 - 9:00	0	0	0	0	0	0

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
7:00 - 7:15	0	0	0	0	0	0
7:15 - 7:30	0	0	0	0	0	0
7:30 - 7:45	1	0	0	0	0	0
7:45 - 8:00	0	0	0	0	0	0
8:00 - 8:15	1	0	0	0	0	0
8:15 - 8:30	0	0	0	0	0	0
8:30 - 8:45	0	0	0	0	0	0
8:45 - 9:00	0	0	0	0	0	0



Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd
 Date October 6, 2011
 Time Period PM Peak Hour
 All Vehicles

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	0	0	140	0	0	128
4:15 - 4:30	0	0	181	0	0	131
4:30 - 4:45	0	0	165	0	0	114
4:45 - 5:00	0	0	199	0	0	160
5:00 - 5:15	0	0	207	0	0	150
5:15 - 5:30	0	0	160	0	0	179
5:30 - 5:45	0	0	173	0	0	164
5:45 - 6:00	0	0	236	0	0	172
TOTAL	0	0	1,461	0	0	1,198

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	66	394	0	0	302	32
4:15 - 4:30	78	353	0	0	265	53
4:30 - 4:45	66	362	0	0	284	31
4:45 - 5:00	67	354	0	0	350	48
5:00 - 5:15	89	445	0	0	299	59
5:15 - 5:30	74	416	0	0	321	65
5:30 - 5:45	72	412	0	0	309	60
5:45 - 6:00	54	357	2	0	290	51
TOTAL	566	3,093	2	0	2,420	399

North / South	653	0	0	232
I-4 EB Ramps				1,279
East / West				0
Saxon Blvd				
Peak Hour	302			
4:45 - 5:45	1,627			
Peak Hour Factor	0			
0.97				
Total Pk Hr Volume				
4,832				

Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd


Date October 6, 2011

Time Period PM Peak Hour Trucks

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	0	0	0	0	0	2
4:15 - 4:30	0	0	0	0	0	2
4:30 - 4:45	0	0	0	0	0	3
4:45 - 5:00	0	0	0	0	0	1
5:00 - 5:15	0	0	0	0	0	1
5:15 - 5:30	0	0	0	0	0	2
5:30 - 5:45	0	0	1	0	0	1
5:45 - 6:00	0	0	0	0	0	2

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	0	2	0	0	2	0
4:15 - 4:30	1	3	0	0	2	0
4:30 - 4:45	5	0	0	0	4	0
4:45 - 5:00	1	0	0	0	1	0
5:00 - 5:15	1	1	0	0	0	1
5:15 - 5:30	0	0	0	0	1	0
5:30 - 5:45	0	1	0	0	1	0
5:45 - 6:00	0	0	0	0	0	0



Roadway Count Summary

GMB Engineers & Planners, Inc.

Intersection I-4 EB Ramps & Saxon Blvd

Date October 6, 2011

Time Period PM Peak Hour U-Turn & Right Turn on Red (RTOR)

GMB Project #: 10-024.06

Time Period	Northbound			Southbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	0	0	0	0	0	0
4:15 - 4:30	0	0	0	0	0	0
4:30 - 4:45	0	0	0	0	0	0
4:45 - 5:00	0	0	0	0	0	0
5:00 - 5:15	0	0	0	0	0	0
5:15 - 5:30	0	0	1	0	0	0
5:30 - 5:45	0	0	0	0	0	0
5:45 - 6:00	0	0	0	0	0	0

Time Period	Eastbound			Westbound		
	Left	Through	Right	Left	Through	Right
4:00 - 4:15	1	0	0	0	0	0
4:15 - 4:30	1	0	0	0	0	0
4:30 - 4:45	0	0	0	0	0	0
4:45 - 5:00	1	0	0	0	0	0
5:00 - 5:15	0	0	0	0	0	0
5:15 - 5:30	1	0	0	0	0	0
5:30 - 5:45	0	0	0	0	0	0
5:45 - 6:00	0	0	0	0	0	0

