# I-4 BtU SEGMENT 3

SR 400 (I-4) 1 mile E of SR 434 to E of US 17/92 in Seminole County

# POND SITING REPORT ADDENDUM

Financial Project No: 242592-4-52-01









Prepared for

**Florida Department of Transportation**
**District Five**

July 2017

# POND SITING REPORT ADDENDUM

## SR 400 (I-4) Segment 3

**From One Mile East of SR 434 to East of SR 15-600/US 17-92**

## Seminole County, Florida

**Financial Project ID 242592-4-52-01**

**Prepared for:**

FLORIDA DEPARTMENT OF TRANSPORTATION

District Five
DeLand, Florida

**Prepared By:**

WSP USA, Inc.
2202 North West Shore Blvd., Suite 300
Tampa, Florida 33607

July 2017

## Executive Summary

The Florida Department of Transportation (FDOT) is proposing to widen State Road 400 (SR 400) / Interstate 4 (I-4) from the existing six lane divided urban facility to a divided highway that varies between 10 and 12 lanes. The project limits extend from one mile east of SR 434 to east of SR 15/600-US 17/92 in Seminole County, Florida. The right-of-way requirements for stormwater management were identified in the Pond Siting Report (PSR) during the Project Development and Environmental (PD&E) phase of the project. The PD&E PSR identified twenty-two (22) drainage basins which will require twenty-seven (27) pond sites and one floodplain compensation site (FPC).

The intent of this report is to amend the right-of-way requirements for stormwater management that were presented in the PD&E PSR and are no longer viable options. The Pond Siting Report Addendum (Addendum) is proposing to modify three stormwater facilities, a floodplain compensation site and will add one stormwater pond. The following tables summarize the recommendations from the PD&E PSR and the Addendum recommendations.

As indicated in the following tables, the Addendum will reduce the right-of-way requirements from 17.28 acres to 7.59 acres. ***This is a 9.69 acre reduction in required right-of-way for stormwater management.***

**Table ES-1**
**PD&E Pond Site Recommendation Summary**

| Basin | Pond / FPC | Location/Prop. Owner | Recommendation | Required ROW (Ac.) |
|---|---|---|---|---|
| Basin 300 | Pond 300 | Sta. 2117+00 (Rt)<br>Parcel No. 25-20-29-503-0A00-0000 | Provide stormwater management for Basin 300 | 3.46 |
| | | Parcel No. 25-20-29-510-000-0070 | | 0.58 |
| Basin 300 | FPC 300-A | Sta. 2125+00 (Rt)<br>Parcel No. 25-20-29-300-0050-0000 | Provide floodplain compensation for Basin 300 | 1.14 |
| Basin 303 | Pond 303-A1 | Sta. 2178+00 (Lt)<br>Parcel No. 24-20-29-512-0000-0020 | Provide stormwater management for Basin 303 | 4.39 |
| Basin 308 | Pond 308 | Sta. 2320+00 (Rt)<br>Drainage Easement on Parcel No. 07-20-30-5MK-0000-0020 | Expand existing pond to accommodate the entire Basin 308 basin area | 7.71 |
| | | | **Total Require ROW =** | **17.28** |

**Table ES-2**
**Addendum Pond Site Recommendation Summary**

| Basin | Pond / FPC | Location/Prop. Owner | Recommendation | Required ROW (Ac.) |
|---|---|---|---|---|
| Basin 300 | Pond 300 | Sta. 2140+00 (Rt)<br>FDOT Property (Rest Area) | Provide stormwater management for Basin 300 | 0.00 |
| Basin 303 | Pond 303-B2 | Sta. 2183+00 (Lt)<br>Parcel No. 24-20-29-300-0090-0000 | Least costly alternative for stormwater management | 2.71 |
| Basin 308A | Pond 308A | Sta. 2328+00 (Rt)<br>Drainage Easement on Parcel No. 07-20-30-5MK-0000-0020 | Construct second pond in lieu of expanding the existing pond in Basin 308 | 3.45 |
| Basin 317D | Pond 317D | Sta. 180+00 (Lt)<br>Parcel No. 21-19-30-502-0400-0000 | Proposed pond site | 1.43 |
| | | | **Total Require ROW =** | **7.59** |

Based on the summary tables, the pond sites amended from the PD&E PSR will reduce the right-of-way requirements for stormwater management. However, additional factors were also considered that required amending the pond sites presented in the PD&E PSR. These include public input, geotechnical feasibility, and design revisions.

As indicated in the PD&E PSR, stormwater management for Basin 300 would be accomplished from expanding Pond 300 to the east. However, expanding the pond to the east would impact existing trees along the berm between Lake Grace and SR 400 (I-4). Local residence expressed concerns that removing the trees would result in increased noise levels and diminished aesthetics for the homeowners of Lake Grace. Therefore, Pond 300 and FPC 300-A were relocated to the south side of the rest area for SR 400. Relocating the pond and floodplain compensation utilizes the existing rest area and avoids additional right-of-way cost.

In Basin 308, the PD&E PSR proposed to expand the existing pond to the north to provide the required stormwater management for the roadway improvements. Geotechnical investigation indicated that the seasonal high water table does not support expanding the pond to the north. As a result, the Addendum is proposing to utilize the existing pond with a second pond located further north to provide the remaining stormwater management for the basin.

Lastly, at the request of Seminole County, additional sidewalks and bike lanes were added on both sides of Orange Boulevard around Pond 318B. Seminole County also requested that the contouring for Pond 318B be modified from the PD&E to comply the Highway Beautification Policy. The additional impervious area and the reduction in pond size due to the revised contouring required an additional pond site. The proposed pond is located at the southwest corner of Monroe Road and Orange Boulevard which is currently occupied by Marathon Gas with a Kangaroo Convenience Store. The proposed pond site is referred to in the Addendum as Pond 317D.

# TABLE OF CONTENTS

**EXECUTIVE SUMMARY ---------- I**

**1.0 INTRODUCTION ---------- 1**

1.1 Project Description and Location ---------- 1

1.2 Purpose ---------- 1

**2.0 AMENDED POND SITE ALTERNATIVES ---------- 1**

2.1 Basin 300 ---------- 1

2.1.1 PD&E PSR Basin and Floodplain Description ---------- 1

2.1.2 Addendum ---------- 2

2.2 Basin 303 ---------- 3

2.2.1 PD&E PSR Basin and Pond Description ---------- 3

2.2.2 Addendum ---------- 3

2.3 Basin 308 ---------- 3

2.3.1 PD&E PSR Basin and Pond Description ---------- 3

2.3.2 Addendum ---------- 4

2.4 Basin 317D ---------- 4

2.4.1 PD&E PSR Basin and Pond Description ---------- 4

2.4.2 Addendum ---------- 4

**3.0 SPECIAL BASIN CRITERIA ---------- 5**

3.1 Wekiva Basin Recharge Area ---------- 5

3.2 Outstanding Florida Water (OFW) ---------- 5

3.3 Basin Impairment ---------- 5

**4.0 POND ALTERNATIVE MATRIX ---------- 5**

**5.0 PROPERTY OWNER COORDINATION ---------- 7**

**6.0 ADDENDUM SUMMARY ---------- 7**

# LIST OF TABLES

Table ES-1 PD&E Pond Site Recommendation Summary ---------- i

Table ES-2 Addendum Pond Site Recommendation Summary ---------- ii

Table 3 Pond Alternative Matrix ---------- 6

Table 4 PD&E Pond Site Recommendation Summary ---------- 8

Table 5 Addendum Pond Site Recommendation Summary ---------- 8

# LIST OF APPENDICES

Appendix A PD&E Pond Siting Report Excerpts (August 2016)

Appendix B Geotechnical Pond Boring Summary

Appendix C Basin Drainage Maps, Routing & Calculations

Appendix D Property Owner Coordination

# 1.0 INTRODUCTION

## 1.1 Project Description and Location

The Florida Department of Transportation (FDOT) is proposing to widen State Road 400 (SR 400) / Interstate 4 (I-4) from the existing six lane divided urban facility to a divided highway that varies between 10 and 12 lanes. The intent is to improve traffic operations, enhance connectivity and improve mobility by providing travel choices to the motoring public. The project limits extend from one mile east of SR 434 to east of SR 15/600-US 17/92 in Seminole County, Florida. The project is referred to as Financial Project ID (FPID) Number 432100-1-22-01 in the Florida Department of Transportation (FDOT) system.

As a result of the proposed roadway improvements there will be an increase in stormwater runoff. The additional runoff will need to collected and managed in both existing and proposed stormwater management facilities. A Pond Siting Report (PSR) dated August 2016 was prepared during the Project Development and Environment (PD&E) phase of the project to identify the projects right-of-way requirements for stormwater management. The PD&E PSR identified twenty-two (22) drainage basins that will require twenty-seven (27) pond sites. The project location map from the PD&E PSR is provided in Appendix A.

The vertical datum used for this project and documented in this report is the North American Vertical Datum of 1988 (NAVD 88).

## 1.2 Purpose

The purpose of this report is to amend the right-of-way requirements for stormwater management that were presented in the PD&E PSR and are no longer viable options. The updated right-of-way requirements are based on various factors such as revised roadway design, additional topographic survey, and geotechnical investigation. This document is referred to as the Addendum since it only includes revisions to the pond sites and floodplain compensation sites developed in the PD&E PSR.

# 2.0 AMENDED POND SITE ALTERNATIVES

The recommended pond sites and FPC sites were reviewed with respect to the current roadway design, updated survey and geotechnical data. The Addendum is proposing to modify three stormwater facilities, a floodplain compensation site and will add one stormwater pond. The pond sites and FPC site that will be amended are referred to as Pond 300, FPC 300-A, Pond 303-B2, Pond 308A and Pond 317D.

## 2.1 Basin 300

### 2.1.1 PD&E PSR Basin and Floodplain Description

Basin 300 in the PD&E PSR is a roadway drainage basin that begins at Station 2092+50 and extends north to Station 2125+00. The basin consists of the full right-of-way and the recommended pond site alternative. Both the recommended pond site and the roadway drainage basin lie in a closed basin with discharge. The drainage map from the PD&E PSR is included in Appendix A.

Based on the PD&E PSR, the required stormwater management for Basin 300 will be accomplished from expanding an existing stormwater facility referred to as Pond E in Permit No. 22434-1. The existing pond currently functions as a wet detention facility that discharges north, into an existing cross drain and then drains into Grace Lake. The pond is located on the right side of the roadway between Station 2113+50 and Station 2121+00. The expanded pond site is referred to as Pond 300 in the PD&E PSR and is shown on the drainage map provided in Appendix A. The calculations for Pond 300 are also included in Appendix A. Within Basin 300 the PD&E PSR has also identified a floodplain compensation site referred to as FPC 300-A on the right side of the roadway at Station 2126+00. FPC 300-A is proposed to provide compensation for the floodplain impacts between Station 2106+00 and Station 2125+00 on both the left and the right sides of the roadway.

The proposed Pond 300 expansion, was planned to the north, south and east of the existing pond location. This expansion would require partial right-of-way takes from two separate parcels, impacts an existing billboard and would additionally impact the existing floodplain. FPC 300-A would require a partial right-of-way take from one parcel. The PD&E PSR basin and pond description for Basin 300 are included in Appendix A.

### 2.1.2 Addendum

In order to eliminate the two partial right-of-way takes and impacts to an existing billboard for Pond 300 and the one partial take for FPC 300-A, we evaluated conveying the runoff from Basin 300 to Basin 301 and providing a pond on the existing rest area within the FDOT's right-of-way. Basins 300 and 301 are both part of the overall Myrtle Lake Basin. Our proposed design would involve collecting the storm water runoff from the entire I-4 roadway from Station 243+20 to Station 288+20 along with some minor areas on EE Williams Road and conveying it to Pond 300 located on the rest area, adjacent to Pond 301 near Station 290+00. The proposed Pond 300 will be a wet detention pond. The drainage map for Basin 300 and 301 is included in Appendix C . The existing and proposed basin and pond calculations for Basin 300 and 301 are also provided in Appendix C.

Within Myrtle Lake Basin is a sub basin referred to as Grace Lake which includes the roadway improvement project. The entire Grace Lake watershed was previously modeled in ICPR by Pegasus Engineering for Seminole County. The analysis was part of an approved Environmental Resource Permit by SJRWMD for an alternative sinkhole remediation protocol for Grace Lake dated March 2014. This ICPR model considers the stormwater affects to the watershed if the sinkhole in Grace Lake were plugged. A partial copy of this documentation is included in Appendix C, which includes the general documentation write-up, along with the input and output from the ICPR model. The existing County ICPR model will be used to demonstrate that the proposed roadway improvements will have no adverse impacts to Grace Lake or any of the surrounding offsite areas associated with shifting stormwater runoff from Basin 300 to Basin 301.

In utilizing the existing model the first step was to revise the model to accurately represent the areas with the FDOT's right-of-way. Modifications to the model included the following: revising onsite curve numbers, revising storage areas based on topographic survey within the FDOT right-of-way as well as updating existing drainage structures and pipes based on new survey data. All areas outside the FDOT right-of-way remain unchanged from the original model. The results of this modified model are referred to as our "Existing Conditions, Grace Lake" model and can be found in Appendix C. We then updated this model to represent the proposed conditions, which included adding Pond 300 and Pond 301. In

addition, the existing Pond E has been modified by removing the existing berms and lowering the ground to elevation 61.0 thus allowing it to provide additional floodplain storage within the Grace Lake Basin. The results of the "Proposed Conditions, Grace Lake" model are included in Appendix C.

## 2.2 Basin 303

### 2.2.1 PD&E PSR Basin and Pond Description

Basin 303 in the PD&E PSR is a roadway drainage basin that begins at Station 2162+00 and extends north to Station 2189+00. The basin consists of the full right-of-way and the recommended pond site alternative. Both the recommended pond site and the roadway drainage basin lie in a closed basin with discharge. The drainage map from the PD&E PSR is included in Appendix A.

### 2.2.2 Addendum

According to Section 5.3.6 in the PD&E PSR, Pond 303-A1 is the least costly alternative and is the recommended alternative for this basin. However, Table 7 in the PD&E PSR indicates that Pond 303-B2 is the least costly alternative. Based on the cost analysis provided in the PD&E PSR, the recommended pond site alternative for the addendum is Pond 303-B2. Section 5.3.6 and Table 7 from the PD&E PSR are provided in Appendix A.

## 2.3 Basin 308

### 2.3.1 PD&E PSR Basin and Pond Description

Basin 308 in the PD&E PSR is a roadway drainage basin that begins at Station 2305+00 and extends north to Station 2365+00. The basin consists of the full right-of-way and the recommended pond site alternative. Both the recommended pond site and the roadway drainage basin lie in a closed basin with discharge. The drainage map from the PD&E PSR is included in Appendix A.

Based on the PD&E PSR, the required stormwater management for Basin 308 will be accomplished from expanding an existing stormwater facility referred to as Pond 3 in Permit No. 22142-2. The existing pond currently functions as a dry retention facility that discharges west through the International Parkway storm sewer system. The pond is located on the right side of the roadway between Station 2310+00 and Station 2318+00 in an easement on the Heathrow development property. The expanded pond site is referred to as Pond 308 in the PD&E PSR and is shown on the drainage map provided in Appendix A. The calculations for Pond 308 are also included in Appendix A.

The proposed pond expansion will occur to the north where the existing ground elevation varies from 60.0 feet to 85.0 feet. Recent geotechnical investigation included 4 pond borings indicating that the seasonal high water elevation in the expanded pond area varies between elevation 48.57 feet and elevation 61.23 feet. The average seasonal high water elevation of the four pond borings is 57.40 feet which is above the proposed pond bottom elevation of 50.2 feet. Based on the recent geotechnical borings, the seasonal high water elevations do not support expanding the existing pond to the north for For a dry retention facility. The PD&E PSR basin and pond description for 308 are included in Appendix A. Results from the recent geotechnical investigation for Pond 308 are provided in Appendix B.

### 2.3.2 Addendum

Since the seasonal high water elevations do not support expanding the existing pond to the north, an additional pond is recommended to provide stormwater management for the basin runoff. The proposed pond is approximately 850 feet north of the existing pond at Station 480+00 and is referred to in this addendum as Pond 308A. The basin limits for the runoff discharging to Pond 308A begin at Station 487+50 and extend north to Station 506+00. The basin discharging to the pond is referred to as Basin 308A. The drainage map for Basin 308A is included in Appendix C . The basin and pond calculations for Basin 308A are also provided in Appendix C.

The remaining runoff within the basin will be managed in the existing pond which is referred to in this addendum as Pond 308. The amount of roadway runoff discharging to the existing pond will not require modifying the existing pond and will allow it continue to function as a dry retention facility. The basin limits for runoff discharging to Pond 308 begin at Station 455+00 and extend north to Station 487+50. The basin discharging to Pond 308 is referred to in this addendum as Basin 308. The drainage map for Basin 308 is included in Appendix C. The basin and pond calculations are also provided in Appendix C.

## 2.4 Basin 317D

### 2.4.1 PD&E PSR Basin and Pond Description

Basin 317D and Pond 317D were not included in the PD&E PSR. During Phase II of the project, the need for an additional pond (Pond 317D) and the basin discharging to the pond (Basin 317D) were identified. The following section includes information regarding the basin description and the stormwater management requirements for the basin.

### 2.4.2 Addendum

Basin 317D is a proposed roadway drainage basin that was developed during Phase II of the project. The basin begins at Station 179+44 on CR 15 and extends west to Station 184+80. The basin consists primarily of the proposed roadway and the recommended pond site referred to as Pond 317D. Both the drainage basin and the recommended pond site lie in an open basin that ultimately discharge to Lake Monroe. The basin limits and pond site are shown on the drainage map provided in Appendix C.

During the design phase, Seminole County requested that additional sidewalks and bicycle lanes be placed on both the inside and outside of Orange Boulevard around Pond 318B. The sidewalks and bicycle lanes have increased the amount runoff in Basin 318B and have reduced the size of Pond 318B as presented in the PD&E PSR. Pond 318B has also been reconfigured in the Addendum at the request of Seminole County to comply with the Highway Beautification Policy. The reconfigured pond will result in a reduction in pond volume due to the curvilinear contouring along the pond berm. As a result, an additional pond referred to as Pond 317D has been proposed in the Addendum to provide stormwater management for the increase in runoff and the reduction in pond volume in Pond 318B.

Pond 317D is located at the southwest corner of Monroe Road and Orange Boulevard. The site is currently occupied by a Marathon Gas Station with a Kangaroo Convenience Store. The existing site discharges to the west into a dry retention/detention facility located on the Donnie Myers Luxury Coach site. Runoff from the Donnie Myers stormwater facility discharges to the existing ditch on Orange Boulevard that ultimately outfalls to Lake Monroe. The proposed pond site (Pond 317D) will discharge

directly into the existing ditch on Orange Boulevard and not through the Donnie Myers property. The ditch along Orange Boulevard will continue to outfall to Lake Monroe as in the existing condition.

# 3.0 Special Basin Criteria

## 3.1 Wekiva Basin Recharge Area

Basin 300, Basin 301, & Basin 308 lie in the Wekiva Recharge Area. The pond sites in the Addendum were designed to include the historical recharge volume and the required volume as a result of the proposed roadway improvements. The required recharge volume for the post developed condition was calculated using 3 inches over the impervious area that was previously A type soils. Calculations demonstrating the proposed ponds provide for the required recharge volume are included in Appendix C.

## 3.2 Outstanding Florida Water (OFW)

There are no Outstanding Florida Waters within the project limits.

## 3.3 Basin Impairment

The outfall for Pond 317D is Lake Monroe which has been listed as impaired for nutrients. A Basin Management Action Plan (BMAP) has been developed which includes nutrient reduction calculations for FDOT ponds that ultimately discharge to Lake Monroe. Based on the BMAP, the FDOT ponds that will reduce nutrient loadings into Lake Monroe have been constructed. Calculations demonstrating the proposed roadway improvements will not increase nutrient loadings into Lake Monroe will be provided in the Phase II Drainage Design Document.

# 4.0 Pond Alternative Matrix

The Pond Alternative Matrix provides a summary of the cost and impacts associated with the recommended pond site alternatives. The Total Pond Cost provided in the matrix include associated pond construction costs such as drainage structures, earthwork, and soil remediation. The Pond Alternative Matrix is provide in Table 3.

**Table 3**
**Pond Alternative Matrix**

| Pond | Existing Land Use | Threatened or Endangered Species | Hazardous Materials & Contamination Potential | Major Utility Conflict (Y/N) | Floodplain Impacts (ac-ft) | Wetland & Surface Water Impacts (ac) | Total Pond Cost | Rankings |
|---|---|---|---|---|---|---|---|---|
| 303-A1 | Other | High | Low | N | 0.00 | 0.00 | $3,716,650 | 2 |
| 303-A2 | Vacant Nonresidential | High | Low | N | 0.00 | 0.00 | $24,048 | 1 |
| 303-B2 | Acreage Not Zoned for Agriculture | High | Low | N | 0.00 | 0.00 | $3,321,411 | 1 |
| 300 (Relocated) | Public / Semi-public | High | Low | N | 0.00 | 0.00 | $564,667 | 1 |
| 308A | No Data Available | High | High | N | 0.00 | 0.00 | $1,697,276 | 1 |
| 317D | Commercial | Low | Med | N | 0.00 | 0.00 | $3,850,240 | 1 |

## 5.0 PROPERTY OWNER COORDINATION

Coordination with affected property owners was initiated with a first letter mailing on December 7th, 2016. The letter informed property owners that their property has been selected for a preferred site for a stormwater management facility and requested any input with regards to pond location and configuration. A second letter was sent on February 27th, 2017 informing the property owners that their property has been selected for a preferred pond site and requesting any input with regards to pond configuration. The coordination letters with the affected property owners is included in Appendix D.

## 6.0 ADDENDUM SUMMARY

The Addendum is proposing to modify three stormwater facilities, a floodplain compensation site and will add one stormwater pond. The following tables summarize the stormwater facilities recommended in the PD&E PSR and the ponds that have been modified from the PD&E. As indicated in the following summary tables, the recommended pond sites in the Addendum will reduce right-of-way requirements approximately 9.69 acres.

**Table 4**
**PD&E Pond Site Recommendation Summary**

| Basin | Pond / FPC | Location/Prop. Owner | Recommendation | Required ROW (Ac.) |
|---|---|---|---|---|
| Basin 300 | Pond 300 | Sta. 2117+00 (Rt)<br>Parcel No. 25-20-29-503-0A00-0000 | Provide stormwater management for Basin 300 | 3.46 |
| | | Parcel No. 25-20-29-510-000-0070 | | 0.58 |
| Basin 300 | FPC 300-A | Sta. 2125+00 (Rt)<br>Parcel No. 25-20-29-300-0050-0000 | Provide floodplain compensation for Basin 300 | 1.14 |
| Basin 303 | Pond 303-A1 | Sta. 2178+00 (Lt)<br>Parcel No. 24-20-29-512-0000-0020 | Provide stormwater management for Basin 303 | 4.39 |
| Basin 308 | Pond 308 | Sta. 2320+00 (Rt)<br>Drainage Easement on Parcel No. 07-20-30-5MK-0000-0020 | Expand existing pond to accommodate the entire Basin 308 basin area | 7.71 |
| | | | **Total Require ROW =** | **17.28** |

**Table 5**
**Addendum Pond Site Recommendation Summary**

| Basin | Pond / FPC | Location/Prop. Owner | Recommendation | Required ROW (Ac.) |
|---|---|---|---|---|
| Basin 300 | Pond 300 | Sta. 2140+00 (Rt)<br>FDOT Property (Rest Area) | Provide stormwater management for Basin 300 | 0.00 |
| Basin 303 | Pond 303-B2 | Sta. 2183+00 (Lt)<br>Parcel No. 24-20-29-300-0090-0000 | Least costly alternative for stormwater management | 2.71 |
| Basin 308A | Pond 308A | Sta. 2328+00 (Rt)<br>Drainage Easement on Parcel No. 07-20-30-5MK-0000-0020 | Construct second pond in lieu of expanding the existing pond in Basin 308 | 3.45 |
| Basin 317D | Pond 317D | Sta. 180+00 (Lt)<br>Parcel No. 21-19-30-502-0400-0000 | Proposed pond site | 1.43 |
| | | | **Total Require ROW =** | **7.59** |

**Appendix A**
**PD&E Pond Siting Report Excerpts (August 2016)**

PD&E Pond Siting Report

Project Location Map




Figure 1 – Project Location Map

# PD&E Pond Siting Report

## Pond Engineering Data & Analysis Summary

## Table 5 – Pond Engineering Data & Analysis

| Pond | Location | Soil Names & Hydrologic Groups | Estimated SHWT El. (ft) | Lowest Edge of Roadway (ft) | Outfall Location | Roadway Drainage Area (ac) | Method of Treatment | Required Treatment & Attenuation Volume (ac-ft) | Provided Treatment & Attenuation Volume (ac-ft) | Required Add. Pond Area Including Access (ac) | Total Parcel Available (ac) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| HH | Station 2050+00<br>FDOT Property | Basinger, Samsula, & Hontoon (A/D) & Urban Land (A/D) | 50.00 | 56.00 | Little Wekiva River | 9.30 | Dry Retention | N/A | N/A | N/A | N/A |
| II | Station 2065+00<br>FDOT Property | Astatula-Apopka (A) | 60.00 | 56.00 | Little Wekiva River | 11.98 | Dry Retention | N/A | N/A | N/A | N/A |
| 300 | Station 2112+00<br>FDOT Property &<br>Parcel No. 25-20-29-503-0A00-0000 | Astatula (A) &<br>Myakka & EauGallie (A/D) | 59.96 | 65.00 | Grace Lake | 32.83 | Wet Detention | 12.53 | 12.53 | 3.46 | 4.07 |
| | Parcel No. 25-20-29-510-000-0070 | | | | | | | | | 0.58 | 9.46 |
| 301 | Station 2138+00<br>FDOT Property (Rest Area) | Basinger, Samsula & Hontoon (A/D), Astatula-Apopka (A) & Myakka and Eaugallie (A/D) | 47.96 | 55.00 | Depressional Area at Sta. 2133+75 | 9.34 | Dry Retention | 3.57 | 4.85 | N/A | N/A |
| 302 | Station 2153+00<br>FDOT Property | Astatula (A) | 41.46 | 55.00 | Depressional Area at Sta. 2150+00 | 19.05 | Dry Retention | 8.46 | 9.20 | N/A | N/A |
| 303-A1 | Station 2176+00<br>FDOT Property &<br>Parcel No. 24-20-29-512-0000-0020 | Astatula (A) | 45.06 | 66.00 | Lake Myrtle | 19.04 | Dry Retention | 13.22 | 21.06 | 4.39 | 4.56 |
| 303-A2 | Station 2176+00<br>FDOT Property | Astatula (A) | 45.06 | 66.00 | Lake Myrtle | 10.66 | Dry Retention | 6.40 | 6.79 | N/A | N/A |
| 303-B2 | Station 2180+50<br>Parcel No. 24-20-29-300-0090-0000 | Astatula (A) | 55.00 | 66.00 | Lake Myrtle | 8.37 | Dry Retention | 4.72 | 4.90 | 2.71 | 2.71 |
| 304 | Station 2217+00<br>FDOT Property | Astatula (A) | 45.00 | 68.00 | Depressional Area at Sta. 2224+00 | 23.63 | Dry Retention | 15.90 | 16.48 | N/A | N/A |
| 305 & 305A | Station 2248+60<br>FDOT Property | Astatula (A)<br>Myakka & EauGallie (A/D) | 38.96 | 48.66 | Heathrow Development | 79.30 | Dry Retention | 48.09 | 53.08 | N/A | N/A |
| 306 | Station 2268+00<br>FDOT Property | Astatula (A) | 38.33 | 57.68 | Heathrow Development | 18.38 | Dry Retention | 6.90 | 13.02 | N/A | N/A |
| 307 | Station 2296+00<br>Drainage Easement | Basinger, Samsula & Hontoon (A/D) | 39.36 | 60.00 | Primera Development Property | 15.36 | Dry Retention | 6.80 | 6.80 | N/A | N/A |
| 308 | Station 2309+00<br>Drainage Easement &<br>Parcel No. 07-20-30-5MK-0000-0020 | Astatula (A)<br>Basinger, Samsula & Hontoon (A/D) | 47.16 | 60.00 | International Pkwy Storm Sewer System | 43.01 | Dry Retention | 24.81 | 32.32 | 7.71 | 155.33 |
| 309 | 2369+50<br>FDOT Property | Tavares-Millhopper & Astatula (A) | 66.96 | 70.65 | None | 24.72 | Wet Retention | 53.09 | 56.66 | N/A | N/A |

DRAFT

## Table 6 – Floodplain Compensation Pond Engineering Data & Analysis

| FPC Pond | Location | Soil Names & Hydrologic Groups | Estimated SHWT El. (ft) | 100 YR Floodplain Elevation (ft) | Required Compensation (ac-ft) | Storage Provided (ac-ft) | Required Add. Pond Area Including Access (ac) | Total Parcel Available (ac) |
|---|---|---|---|---|---|---|---|---|
| 300-A | Station 2125+00<br>Parcel No. 25-20-29-300-0050-0000 | Myakka & Eau Gallie (A/D) | 55.00 | 66.00 | 3.61 | 3.79 | 1.14 | 3.37 |
| 300-B | Station 2117+00<br>Parcel No. 26-20-29-300-0010-0000 | Myakka & Eau Gallie (A/D) | 57.00 | 66.00 | 3.61 | 3.95 | 1.70 | 11.02 |

## Table 7 – Pond and Floodplain Compensation Pond Impact & Cost Analysis

| Pond | Existing Land Use | **Threatened or Endangered Species Impacts | ***Hazardous Materials & Contamination Potential | Major Utility Conflict Potential (Y/N) | Floodplain Impacts (ac-ft) | Wetland & Surface Water Impacts (ac) | | Total Pond Cost | Rankings |
|---|---|---|---|---|---|---|---|---|---|
| HH | No Data Available | Moderate | Low | N | 0.00 | 0.00 | | $0.00* | 1 |
| II | No Data Available | High | Low | N | 0.00 | 0.00 | | $10,022 | 1 |
| 300 | Residential | Moderate | Medium | N | 6.43 | 0.00 | 1.33 | $3,007,104 | 1 |
| 301 | Public / Semi-Public | High | Low | N | 0.00 | 0.00 | | $147,267 | 1 |
| 302 | Vacant Residential | High | Low | N | 0.00 | 0.00 | | $125,014 | 1 |
| 303-A1 | Other | High | Low | N | 0.00 | 0.00 | | $3,716,650 | 1 |
| 303-A2 | Vacant Nonresidential | High | Low | N | 0.00 | 0.00 | | $24,048 | 2 |
| 303-B2 | Acreage Not Zoned for Agriculture | High | Low | N | 0.00 | 0.00 | | $3,321,411 | |
| 304 | Parcels with no Values | High | Low | N | 0.00 | 0.00 | | $83,427 | 1 |
| 305 & 305A | Parcels with no Values | High | Low | N | 0.00 | 0.00 | | $487,591 | 1 |
| 306 | Parcels with no Values | Moderate | Low | N | 0.00 | 0.00 | | $438,650 | 1 |
| 307 | No Data Available | Moderate | High | N | 0.00 | 0.00 | | $0.00* | 1 |
| 308 | No Data Available | High | High | N | 0.00 | 0.00 | | $4,077,912 | 1 |
| 309 | No Data Available | High | Low | N | 0.00 | 0.00 | | $447,713 | 1 |

| Pond | Existing Land Use | **Threatened or Endangered Species Impacts | ***Hazardous Materials & Contamination Potential | Major Utility Conflict Potential (Y/N) | Floodplain Impacts (ac-ft) | Wetland & Surface Water Impacts (ac) | Total Pond Cost | Rankings |
|---|---|---|---|---|---|---|---|---|
| 310 | No Data Available | High | Low | N | 0.00 | 0.00 | $384,903 | 1 |
| 311 | No Data Available | High | Low | N | 0.00 | 0.00 | $100,239 | 1 |
| 312 | No Data Available | High | Low | N | 0.00 | 0.00 | $0.00* | 1 |
| 313 & 313A | No Data Available | High | Low | N | 0.00 | 0.00 | $0.00* | 1 |
| Swale 313A | No Data Available | Low | Medium | N | 0.00 | 0.00 | $94,893 | 1 |
| 314 | No Data Available | High | Low | N | 0.00 | 0.00 | $0.00* | 1 |
| 315 | No Data Available | High | Low | N | 0.00 | 0.00 | $0.00* | 1 |
| 316 | No Data Available | High | Low | N | 0.00 | 0.00 | $0.00* | 1 |
| 317A | No Data Available & Vacant Residential | High | Low | Y | 0.00 | 4.46 \| 0.00 | $1,698,766 | 1 |
| 317B | No Data Available | High | Low | Y | 0.00 | 0.00 | $0.00* | 1 |
| 317C | No Data Available | Moderate | Low | Y | 0.00 | 0.00 | $9,174 | 1 |
| 318A | Vacant Government | High | Low | N | 0.00 | 0.00 | $888,574 | 1 |
| 318B | Vacant Commercial, Vacant Government & Residential | Low | Low | N | 0.00 | 0.00 | $1,173,120 | 1 |
| FPC 300-A | Residential | Moderate | Medium | N | 0.00 | 0.00 | $493,519 | 1 |
| FPC 300-B | Institutional | Moderate | Medium | N | 0.00 | 0.00 | $638,151 | 2 |

*Since there are no proposed changes to this pond, the total pond cost is $0.
**Refer to the Endangered Species Biological Assessment (ESBA) for more detailed information.
***Refer to the Contamination Screening Evaluation Report (CSER) for more detailed information.

DRAFT

# PD&E Pond Siting Report

Basin 300 & FCP 300-A

(Report Text, Drainage Maps, & Pond Calculations)



## 5.4 Floodplains/Floodways

### 5.4.1 Basin 300

The Federal Emergency Management Agency (FEMA) has developed Flood Insurance Rate Maps (FIRM) for Seminole and Volusia Counties. According to FEMA Map No. 12117C0135F, portions of the roadway and the proposed pond (Pond E in Permit No. 22434-1) within Basin 300 are located in the 100-year floodplain. Based on the FEMA floodplain lines, the roadway widening will impact the floodplain on both sides of the roadway. The widening of the westbound lanes will impact the floodplain from Station 2116+00 to 2124+00 and are located in Zone AE of the floodplain with an elevation of 66.00 ft NAVD. The widening of the eastbound lanes will impact the floodplain from Station 2106+50 to 2124+50 and are located in Zone AE of the floodplain with an elevation of 66.00 ft NAVD. The pond berm for Pond 300 will also impact the floodplain and is located in Zone AE of the floodplain with an elevation of 66.00 ft NAVD. Although the pond berm causes an impact to the floodplain, the area of cut between the existing ground and the design high water will result in the pond providing compensation for the floodplain impacts. The roadway impacts the floodplain for a total of 6.43 ac-ft. There are two (2) feasible alternatives for the floodplain compensation pond in this basin. After consideration from the public involvement meeting and meetings with property owners, it was determined that FPC Pond 300-A has the least amount of impacts.

#### 5.4.1.1 FPC 300-A

The first alternative is FPC 300-A. FPC 300-A would impact one (1) parcel for a total right-of-way take of 1.15 ac from the 3.35 ac parcel. The right-of-way take would not impact the existing house or the billboard on this parcel. FPC 300-A is located east of I-4 from Station 2125+00 to 2126+50. The pond soils are classified in Hydrologic Soil Group A. The floodplain compensation pond is hydraulically connected to the floodplain. FPC 300-A is a modified alternative from Section 2 FEIS under the name Pond CP-1. **FPC 300-A is the recommended alternative for this basin.**

#### 5.4.1.2 FPC 300-B

The second alternative is FPC 300-B. FPC 300-B would impact one (1) parcel for a total right-of-way take of 1.70 ac from the 11.02 ac parcel. There is a 20 foot buffer between the top of pond and the property line on the east and west sides, which allows some of the trees to remain. The right-of-way take would not impact the existing soccer fields north of the pond or the billboard on this parcel. FPC 300-B is located west of I-4 from Station 2114+00 to 2118+50. The pond soils are classified in Hydrologic Soil Group A/D. The floodplain compensation pond is hydraulically connected to the floodplain by an existing crossdrain located at Station 2120+87.

#### 5.4.1.3 FPC 300-C

The third alternative is FPC 300-C. FPC 300-C is an option that was recommended by the Value Engineering Study due to the impacts to an existing billboard within the FPC 300-A parcel. The potential pond site is located within the floodplain of Lake Grace, just east of Pond 300. After receiving additional topographic survey for the site, it was determined that it is not a feasible option. The existing ground elevation for the majority of the potential site is lower than the floodplain elevation of 66.00 ft. NAVD. After this alternative was eliminated, FPC 300-A was reconfigured around the existing billboard as not to impact it.



DRAFT

MODEL: drmprd01
SHEET SIZE: 16.5x10.6 (in.)
PLOT SCALE: 1:200.005

MATCHLINE STA. 2086+00.00

MATCHLINE STA. 2116+00.00

SEMINOLE WEKIVA TRAIL

EE WILLIAMSON

SUNSHINE TREE BLVD.

0 50 200
Feet

100 YEAR FLOODPLAIN

PARCEL ID: 26-20-29-300-0010-0000
AREA TAKEN: 74,021 SF

PROPOSED R/W LINE

FPC 300-B
(ALTERNATIVE)
0.83 AC

BASIN II
55.85 AC

EXIST. LA R/W LINE

MARKHAM WOODS
ANIMAL HOSPITAL

BASIN 300
32.83 AC

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

℄ EXIST I-4

DES PINAR LANE

TOULA AVE

HICKORY TREE AVE

HICKORY TREE RD

PENELOPE DR

SW-3(E)

POND 300
(RECOMMENDED)
4.50 AC

EXISTING R/W

NORTH COVE

SW-5(E)

PARCEL ID: 25-20-29-503-0A00-0000
AREA TAKEN: 150,683 SF

PROPOSED LA R/W LINE

100 YEAR FLOODPLAIN

NORTH RIDGE CT

GRACE LAKE CIR

NORTH COVE BLVD

BASIN II

BASIN 300

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO. A-7

PRINT DRIVER: Color_FDOTPDF.pltcfg
PEN TABLE: FDOT_text-glow.tbl

lphillip 8/16/2016 10:46:27 AM \\LKMw00\pmwork3\Jobs\59219 - I4 SAMR\TECHPROD\43210012201\Segment 3\drainage\drmprd301.dgn

MODEL: drmprd02
SHEET SIZE: 16.5x10.6 (in.)
PLOT SCALE: 1:200

MATCHLINE STA. 2116+00.00

MATCHLINE STA. 2146+00.00

SUNSHINE TREE BLVD.

RUTLEDGE RD.

DIXON RD.

0 50 200
Feet

100 YEAR FLOODPLAIN

PROPOSED R/W LINE

PARCEL ID: 26-20-29-300-0010-0000
AREA TAKEN: 74,021 SF

MARKHAM WOODS
CHURCH & CHRISTIAN ACADEMY

100 FT. ACCESS EASMENT

15 FT. NON-EXCLUSIVE ACCESS EASEMENT

FPC 300-B
(ALTERNATIVE)
0.83 AC

EXIST. LA R/W LINE

EXIST. 48" RCP

BASIN 300
32.83 AC

BASIN 301
9.34 AC

DIXON RD.

EXIST. 54" RCP

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

EXIST I-4

2120 2125 2130 2135 2140 2145

POND 300
(RECOMMENDED)
4.50 AC

PARCEL ID: 25-20-29-503-0A00-0000
AREA TAKEN: 150,683 SF

PROPOSED LA R/W LINE

FPC 300-A
(RECOMMENDED)
0.69 AC

EXIST. LA R/W LINE

PROPOSED LA R/W LINE

NORTHRIDGE DR.

I-4 EB GUL TO
REST AREA

BASIN 302
19.05 AC
EB REST AREA

PROPOSED LA R/W LINE

PARCEL ID: 25-20-29-300-0050-0000
AREA TAKEN: 49,585 SF

PARCEL ID: 25-20-29-510-0000-0070
AREA TAKEN: 25,298 SF

SW-5(E)

100 YEAR FLOODPLAIN

100 YEAR FLOODPLAIN

NORTHRIDGE

POND 301
(RECOMMENDED)
2.03 AC

GRACE LAKE

SW-5(E)

NOTE:
THE EXISTING DRAINAGE STRUCTURES ARE FOR GRAPHIC PURPOSES ONLY. FIELD SURVEY IS REQUIRED TO DETERMINE THE ACTUAL STATIONING.

BASIN 300
BASIN 301
BASIN 302

Color_FDOTPDF.pltcfg
FDOT_text-glow.tbl

PRINT DRIVER:
PEN TABLE:

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-8


lphillip 8/16/2016 10:46:49 AM \\LKMw00\pmwork3\Jobs\59219 - I4 SAMR\TECHPROD\43210012201\Segment 3\drainage\drmprd301.dgn

# APPENDIX C –

# FLOODPLAIN CALCULATIONS

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746

| | | date: |
|---|---|---|
| made by: | SR | 16-Aug-16 |
| checked by: | BJS | 16-Aug-16 |
| HNTB job #: | 59219 | |

**PROJECT:** I-4 PD&E - SEGMENT 3

POND NAME: FPC 300-A

# FLOODPLAIN COMPENSATION CALCULATIONS

## WESTBOUND ROADWAY:

Station Limits: 2116+00 to 2124+00

Roadway Length: 800 ft

Roadway Width: 20 ft

| | |
|---|---|
| 100 YR Floodplain Elevation: | 66.0 ft |
| Ave. Existing Ground Elevation: | 62.0 ft |
| Elevation Difference: | 4.0 ft |

Required Compensation = Roadway Length * Roadway Width * Elevation Difference: 1.47 ac-ft

---

## EASTBOUND ROADWAY:

Station Limits: 2106+50 to 2124+50

Roadway Length: 1800 ft

Roadway Width: 30 ft

| | |
|---|---|
| 100 YR Floodplain Elevation: | 66.0 ft |
| Ave. Existing Ground Elevation: | 62.0 ft |
| Elevation Difference: | 4.0 ft |

Required Compensation = Roadway Length * Roadway Width * Elevation Difference: 4.96 ac-ft

---

**Total Roadway Required Compensation: 6.43 ac-ft**

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746


| | | date: |
|---|---|---|
| made by: | SR | 16-Aug-16 |
| checked by: | BJS | 16-Aug-16 |
| HNTB job #: | 59219 | |

**PROJECT:** I-4 PD&E - SEGMENT 3

POND NAME: FPC 300-A

## FLOODPLAIN COMPENSATION CALCULATIONS

### EXISTING/PROPOSED TREATMENT POND:




**Pond Section**

Area Between Pond Tie Down and Front of Berm: 0.79 ac

Back of Berm Elevation: 66.0 ft
Existing Ground EL./Front of Berm EL.: 65.0 ft
Elevation Difference: 1.0 ft

Amount of Fill = Area * Elevation Difference: 0.79 ac-ft

Ave. Area Between Front of Berm and DHW from Pond: 3.61 ac

Existing Ground EL./Front of Berm EL.: 65.0 ft
DHW Elevation: 64.0 ft
Elevation Difference: 1.0 ft

Amount of Cut = Ave. Area * Elevation Difference: 3.61 ac-ft

Provided Pond Compensation = Amount of Cut - Amount of Fill: 2.82 ac-ft

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746

| | | date: |
|---|---|---|
| made by: | SR | 16-Aug-16 |
| checked by: | BJS | 16-Aug-16 |
| HNTB job #: | 59219 | |

**PROJECT:** I-4 PD&E - SEGMENT 3

POND NAME: FPC 300-A

# FLOODPLAIN COMPENSATION CALCULATIONS

## REQUIRED COMPENSATION

| | |
|---|---|
| Required Roadway Compensation: | 6.43 ac-ft |
| Provided Pond Compensation: | -2.82 ac-ft |
| Total Required Compensation: | 3.61 ac-ft |

## PROPOSED FLOODPLAIN POND:

### FPC 300-A

100 YR Floodplain Elevation: 66.0 ft
Avg. Existing Ground Elevation: 75.0 ft

Seasonal High Water Elevation: 55.0 ft

* Seasonal High Water El. From GEC Borings

| Elevation | Area | Storage |
|---|---|---|
| 66.00 | 0.69 ac | 3.79 ac-ft |
| 66.00 | 0.62 ac | 3.79 ac-ft |
| 65.00 | 0.56 ac | 3.20 ac-ft |
| 55.00 | 0.08 ac | 0.00 ac-ft |

**Total Storage Provided by FPC Ponds:** **3.79 ac-ft**

**Total Compensation Needed:** **3.61 ac-ft**

**Additional Storage Provided:** **0.18 ac-ft**

# PD&E Pond Siting Report

Basin 303-A1

(Report Text, Drainage Maps)

### 5.3.6 Basin 303

Basin 303 begins at the high point north of the eastbound rest area at Station 2162+00 and continues north to the high point at Station 2189+00. The basin consists of the pond site and the full right-of-way. This section is located within the Wekiva Recharge Protection Basin and the Wekiva River Hydrologic Basin. The stormwater runoff from the roadway will be collected by roadside ditches and storm sewer systems that discharge to the pond. There are two alternatives for this basin. Pond 303-A1 is the least costly alternative and is the recommended alternative for this basin.

#### 5.3.6.1 Pond 303-A1

The first alternative is Pond 303-A1. Pond 303-A1 is an existing pond (Pond I in Permit No. 22434-1) that will need to be expanded in order to accommodate the roadway widening. The pond was built under the I-4 Widening from SR 434 to Lake Mary Blvd. project (FPID No. 77160-3601). This pond alternative was evaluated under Section 2 FEIS as Pond LL-2. The existing plans were designed in 1929 NGVD. The existing pond would be expanded to 5.42 acres and the maintenance berm will be regraded and reduced to 15-foot. The proposed pond will impact one parcel. Refer to Table 5 for total right-of-way takes. The pond is located east of I-4 from Station 2176+00 to 2182+00. The pond soils are classified in Hydrologic Soil Group A. The pond will be designed as a dry retention pond. The pond discharges south to an outfall ditch within an FDOT drainage easement that flows to Lake Myrtle. Lake Myrtle is land-locked. Since the pond is located in a closed basin, additional treatment volume for OFW criteria is not required. Gopher tortoise burrows were observed on this pond site. The burrows will be relocated prior to site manipulation in the vicinity of the burrow. The pond construction cost located on Table 7, take this cost into account. For additional information on gopher tortoise impacts, refer to the ESBA provided by Stantec. **Pond 303-A1 is the recommended alternative for this basin.**

#### 5.3.6.2 Ponds 303-A2 and 303-B2

The second alternative consists of two ponds, Ponds 303-A2 and 303-B2. Pond 303-A2 is an existing pond (Pond I in Permit No. 22434-1) where the maintenance berm will be regraded and reduced to 15-foot. The pond was built under the I-4 Widening from SR 434 to Lake Mary Blvd. project (FPID No. 77160-3601). This pond alternative was evaluated under Section 2 FEIS as Pond LL-2. The existing plans were designed in 1929 NGVD. The pond is located east of I-4 from Station 2176+00 to 2181+00. Pond 303-A2 will collect the runoff from the eastbound side of the roadway. Pond 303-B2 is a proposed pond on the west side of the roadway from Station 2180+50 to 2186+00. This pond alternative was evaluated under Section 2 FEIS as Pond LL-1. The pond will collect the runoff form the westbound side of the roadway. Pond 303-B2 will impact one (1) parcel, which has a billboard sign on it. Refer to Table 5 for total right-of-way takes. The pond soils are classified in Hydrologic Soil Group A. The ponds will be designed as dry retention ponds. The ponds will continue to discharge south to an outfall ditch within an FDOT drainage easement that flows to Lake Myrtle. Lake Myrtle is land-locked. Since the ponds are located in a closed basin, additional treatment volume for OFW criteria is not required. Several gopher tortoise burrows were observed on the pond sites. The burrows will be relocated prior to site manipulation in the vicinity of the burrow. The pond construction cost located on Table 7, take this cost into account. For additional information on gopher tortoise impacts, refer to the ESBA provided by Stantec.

[redacted]

drmprd03
16.5x10.6 (in.)
1:200

MODEL:
SHEET SIZE:
PLOT SCALE:

MATCHLINE STA. 2146+00.00

MATCHLINE STA. 2176+00.00

15 FT. NON-EXCLUSIVE ACCESS EASEMENT

POND 302
(RECOMMENDED)
2.02 AC

EXIST. LA R/W LINE

CROWLEY CIR.

BASIN 303
19.04 AC

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

EXIST. I-4
REST AREA TO
I-4 EB GUL

BASIN 302
19.05 AC

EB REST AREA

BEGIN SHOULDER CONCRETE BARRIER
WALL, F SHAPED, WITH 10' NOISE WALL
STA. 2158+38.86

SW-6(E)

100 YEAR FLOODPLAIN

EXIST. LA R/W LINE

END SHOULDER CONCRETE BARRIER
WALL, F SHAPED, WITH 10' NOISE WALL
STA. 2174+82.08

PINE BAY DR

HUNTINGTON POINTE

PERPETUAL EASEMENT

0 50 200
Feet

BASIN 302

BASIN 303

Color_FDOTPDF.pltcfg
FDOT_text-cglow.tbl

PRINT DRIVER:
PEN TABLE:

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-9


lphillip 8/16/2016 10:47:02 AM \\LKMw00\pmwork3\Jobs\59219 - I4 SAMR\TECHPROD\432100122201\Segment 3\drainage\drmprd301.dgn

MODEL: drmprd04
SHEET SIZE: 16.5x10.6 (in.)
PLOT SCALE: 1:200

MATCHLINE STA. 2176+00.00

MATCHLINE STA. 2206+00.00

CROWLEY CIR.

LONG POND DR.

WALDENS POND COVE

0 50 200
Feet

PARCEL ID: 24-20-29-300-0090-0000
AREA TAKEN: 18,19 SF

PROPOSED LA R/W LINE

PROPOSED LA R/W LINE

POND 303-B2
(ALTERNATIVE)
1.48 AC

EXIST LA R/W LINE

BASIN 303
19.04 AC

℄ EXIST I-4

I-4 WB GUL

BASIN 304
23.63 AC

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

EXIST LA R/W LINE

POND 303-A2
(ALTERNATIVE)
1.80 AC

SKYLINE DR

POND 303-A1
(RECOMMENDED)
5.42 AC

PROPOSED LA R/W LINE

SUN TECH COMMERCE PARK

PROPOSED LA R/W LINE

PARCEL ID: 24-20-29-512-0000-0020
AREA TAKEN: 191,299 SF

FL POWER CORP

FOX 35 WOFL

GOOD LIFE BROADCASTING

SKYLINE DR

ATRIUM CORPORATE CENTER

BASIN 303

BASIN 304

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-10

PRINT DRIVER: Color_FDOTPDF.pltcfg
PEN TABLE: FDOT_text-glow.tbl


lphillip 8/16/2016 10:47:07 AM \\LKMw00\pmwork3\Jobs\59219 - I4 SAMR\TECHPROD\432100122201\Segment 3\drainage\drmprd301.dgn

# PD&E Pond Siting Report

Basin 308

(Report Text, Drainage Maps, & Pond Calculations)

[redacted]

### 5.3.11 Basin 308

Basin 308 begins at Station 2305+00 and continues north to Station 2365+00. The basin limits for the proposed condition was extended to the north by 1,250 ft. Since there is not enough room for expansion near the ponds (Ponds 309, 309A and 310) to the north, the additional pavement added for the ultimate condition was sent to Pond 308. The basin consists of the pond site and the full right-of-way. The stormwater runoff from the roadway will be collected by storm sewer systems that discharge to the pond. There is only one alternative for this basin.

#### 5.3.11.1 Pond 308

Pond 308 is an existing pond (Pond 3 in Permit No. 22124-2) that will be expanded to the north and east of the pond and the maintenance berm will be regraded and reduced to 15-foot. The pond was sized to store the additional area from the north that was not previously draining to it. The pond was built under the I-4 Widening from West of Lake Mary Blvd to West of SR 15 project (FPID No. 242598-1-52-01). The existing plans were designed in 1929 NGVD. This pond was shown as designed by others in the Section 2 FEIS. The pond is located east of I-4 from Station 2309+00 to 2321+76. The proposed pond will impact one (1) parcel. Refer to Table 5 for total right-of-way takes. The pond soils are classified in Hydrologic Soil Group A and A/D and is designed as a dry retention pond. The pond is located in a drainage easement so that the property owners can relocate the pond in the future if needed. The pond will continue to discharge west through the International Parkway storm sewer system, and is located in the Heathrow development property which is land-locked. Two active gopher tortoise burrows were observed on this pond site. The burrows will be relocated prior to site manipulation in the vicinity of the burrow. The pond construction cost located on Table 7, take this cost into account. For additional information on gopher tortoise impacts, refer to the ESBA provided by Stantec. **Pond 308 is the recommended alternative for this basin.**

[redacted]

[redacted]

drmprd08
16.5x10.6 (in.)
1:200

MODEL:
SHEET SIZE:
PLOT SCALE:

MATCHLINE STA. 2296+00.00

MATCHLINE STA. 2326+00.00

AAA

100 YEAR FLOODPLAIN

0 50 200
Feet

PARCEL ID: 07-20-30-300-005D-0000
AREA TAKEN: 8,185 SF

PARCEL ID: 06-20-30-300-0320-0000
AREA TAKEN: 5,732 SF

PARCEL ID: 06-20-30-300-0140-0000
AREA TAKEN: 25,938 SF

SEMINOLE COUNTY WASTEWATER TREATMENT

INTERNATIONAL PKWY.

SEMINOLE WEKIVA TRAIL

80

81

82

EXIST. LA R/W LINE

BASIN 307
15.36 AC

BASIN 308
43.01 AC

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

2300

2305

2310

2315

2320

2325

℄ EXIST I-4

EXIST. LA R/W LINE

POND 307
(RECOMMENDED)
1.82 AC

EXIST. EASEMENT

POND 308
(RECOMMENDED)
8.67 AC

79

EXIST. EASEMENT

WL-2(E)

PROPOSED EASEMENT

100 YEAR FLOODPLAIN

REMAX LAKE

PARCEL ID: 07-20-30-5MK-0000-0020
AREA TAKEN: 28,813 SF

PARCEL ID: 07-20-30-5MK-0000-0020
AREA TAKEN: 335,708 SF

BASIN 307

BASIN 308

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-14

Color: FDOTPDF.pltctg
FDOT_text-xglow.tbl

PRINT DRIVER:
PEN TABLE:

lphillip 8/16/2016 10:48:25 AM \\LKMw00\pmwork3\Jobs\59219 - I4 SAMR\TECHPROD\432100122O1\Segment 3\drainage\drmprd301.dgn

drmprd09
16.5x10.6 (in.)
1:200

MODEL:
SHEET SIZE:
PLOT SCALE:

MATCHLINE STA. 2326+00.00

MATCHLINE STA. 2356+00.00

INTERNATIONAL PKWY.

SEMINOLE WEKIVA TRAIL

CROSS SEMINOLE TRAIL

100 YEAR FLOODPLAIN

0 50 200
Feet

PARCEL ID: 06-20-30-300-0140-0000
AREA TAKEN: 25,938 SF

PARCEL ID: 06-20-30-300-016D-0000
AREA TAKEN: 8,761 SF

BASIN 308
43.01 AC

PARCEL ID: 06-20-30-300-002D-0000
AREA TAKEN: 4,461 SF

PARCEL ID: 06-20-30-300-002B-0000
AREA TAKEN: 3,946 SF

PARCEL ID: 06-20-30-300-002G-0000
AREA TAKEN: 25 SF

PARCEL ID: 06-20-30-300-002E-0000
AREA TAKEN: 387 SF

PARCEL ID: 06-20-30-300-002F-0000
AREA TAKEN: 31 SF

EXIST. LA R/W LINE

EXIST. LA R/W LINE

EXIST. LA R/W LINE

83 84 87 88 41 91 90

2330 2335 2340 2345 2350 2355

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

℄ EXIST I-4

PARCEL ID: 07-20-30-5MK-0000-0020
AREA TAKEN: 28,813 SF

PARCEL ID: 06-20-30-509-0000-0010
AREA TAKEN: 7,350 SF

PARCEL ID: 06-20-30-508-0000-01A0
AREA TAKEN: 1,487 SF

79 85 86 89

RINEHART RIDGE IV
660 CENTURY POINT

21ST CENTURY INSURANCE

ABB

BASIN 308

Color_FDOTPDF.pltcfg
FDOT_text-glow.tbl

PRINT DRIVER:
PEN TABLE:

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-15

drmprd10
16.5x10.6 (in.)
1:200

MODEL:
SHEET SIZE:
PLOT SCALE:

MATCHLINE STA. 2356+00.00

MATCHLINE STA. 2386+00.00

0 50 200
Feet

92B

92A

41

89

93

94B

94A

186

187

PARCEL ID: 31-19-30-509-0000-0140
AREA TAKEN: 2,432 SF

PARCEL ID: 31-19-30-509-0000-0120
AREA TAKEN: 7,997 SF

EXIST. LA R/W LINE

100 YEAR FLOODPLAIN

POND 309
(RECOMMENDED)
13.46 AC

PARCEL ID: 31-19-30-509-0C00-0000
AREA TAKEN: 117,324 SF

CR 46A GUL RAMP TO I-4 WB GUL

PARCEL ID: 06-20-30-300-0026-0000
AREA TAKEN: 25 SF

SR 417 GUL RAMP TO I-4 WB GUL

EXIST. LA R/W LINE

PARCEL ID: 06-20-30-300-002X-0000
AREA TAKEN: 1,325 SF

AIRSPACE AGREEMENT

BASIN 308
43.01 AC

BASIN 309
24.72 AC

SW-4(W)

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

2360 2365 2370 2375 2380 2385

I-4 EB GUL RAMP TO CR 46A GUL

BASIN 310
14.77 AC

BASIN 311
41.27 AC

℄ EXIST I-4

EXISTING BRIDGE
TO REMAIN

CROSS SEMINOLE TRAIL

POST OFFICE

EXIST. LA R/W LINE

POND 310 (RECOMMENDED)
BY OTHERS

100 YEAR FLOODPLAIN

100 YEAR FLOODPLAIN

CENTENNIAL
BANK

(CR 46A ALTERNATE 3 SHOWN)

UNITED STATES POST OFFICE

BASIN 308
BASIN 309
BASIN 310
BASIN 311

Color_FDOTPDF.pltcfg
FDOT_text-glow.tbl

PRINT DRIVER:
PEN TABLE:

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


HNTB CORPORATION
610 CRESCENT EXECUTIVE CT
SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. OF AUTH. NO. 6500

ENGINEER OF RECORD: SANAM RAI, P.E.
FL. REGISTRATION NO. 69089


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 432100-1-22-01 |

# I-4 PD&E STUDY
# DRAINAGE MAP
# SEGMENT 3

SHEET NO.
A-16

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746

| | | date: |
|---|---|---|
| made by: | LDP | 26-Mar-15 |
| checked by: | BJS | 26-Mar-15 |
| HNTB job #: | 59219 | |

**PROJECT: I-4 PD&E - SEGMENT 3**

BASIN NAME: 308
POND NAME: 308 (Pond 3 from Permit No. 22124-2)

STATION LIMITS: From: 2305+00 To: 2365+00
Roadway Length: 6000 ft
R/W Width: 300 ft

## EXISTING CONDITION

Note: Existing condition reflects the previous condition before the current pond was built.

**Roadway Area:**

| Description | Width | Quantity | Total Width |
|---|---|---|---|
| Travel Lane | 12 ft | 4 | 48 ft |
| Inside Shoulder | 10 ft | 2 | 20 ft |
| Outside Shoulder | 8 ft | 2 | 16 ft |
| | Total Impervious Width: | | 84 ft |

Additional Impervious: 0.00 ac
(ramps, turn lanes, etc.)

Impervious Roadway Area: 11.57 ac
Pervious Roadway Area: 31.44 ac
Total Roadway Area: 43.01 ac

**Pond Area:**

Pervious Pond Area: 8.67 ac
Water Surface Area: 0.00 ac
Total Pond Area: 8.67 ac

**Total Area:**

Impervious Area: 11.57 ac
Pervious Area: 40.11 ac
Water Surface Area: 0.00 ac
Total Area: 51.68 ac

---

**Curve Number:**

| Land Use Description | Soil Group | CN | Area | CN*Area |
|---|---|---|---|---|
| Impervious Area | --- | 98 | 11.57 ac | 1133.9 |
| Water Area | --- | 100 | 0.00 ac | 0.0 |
| Open Land (Grass cover 50% - 75%) | A | 49 | 35.24 ac | 1726.7 |
| Open Land (Grass cover 50% - 75%) | A/D | 84 | 4.87 ac | 409.1 |
| | | Total: | 51.68 ac | 3269.7 |

CN = Total CN * Area / Total Area = **63.3**

---

**Runoff:**

Soil Capacity (S) = $\frac{1000}{CN} - 10$ = 5.81 in

Precipitation (P) = 18.5 in (for 100yr/10dy storm event)

Runoff (Q) = $\frac{(P - 0.2S)^2}{(P + 0.8S)}$ = **12.99 in**

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746

| | | date: |
|---|---|---|
| made by: | LDP | 26-Mar-15 |
| checked by: | BJS | 26-Mar-15 |
| HNTB job #: | 59219 | |

**PROJECT: I-4 PD&E - SEGMENT 3**

BASIN NAME: 308
POND NAME: 308 (Pond 3 from Permit No. 22124-2)

## PROPOSED CONDITION

STATION LIMITS: From: 2305+00 To: 2365+00 Roadway Length: 6000 ft R/W Width: 300 ft

**Roadway Area:**

| Description | Width | Quantity | Total Width |
|---|---|---|---|
| Travel Lane | 12 ft | 14 | 168 ft |
| Wall | 2 ft | 7 | 14 ft |
| Shoulder | 12 ft | 3 | 36 ft |
| Shoulder | 6 ft | 2 | 12 ft |
| Shoulder | 10 ft | 3 | 30 ft |
| | Total Impervious Width: | | 260 ft |

Additional Impervious: 2.66 ac
(ramps, turn lanes, etc.)

Impervious Roadway Area: 38.47 ac
Pervious Roadway Area: 4.54 ac
Total Roadway Area: 43.01 ac

**Pond Area:**

Pervious Pond Area: 2.40 ac
Water Surface Area: 6.27 ac (At the Treatment Volume Stage)
Total Pond Area: 8.67 ac

**Total Area:**

Impervious Area: 38.47 ac
Pervious Area: 6.93 ac
Water Surface Area: 6.27 ac
Total Area: 51.68 ac

---

**Curve Number:**

| Land Use Description | Soil Group | CN | Area | CN*Area |
|---|---|---|---|---|
| Impervious Area | --- | 98 | 38.47 ac | 3770.3 |
| Water Area | --- | 100 | 6.27 ac | 627.4 |
| Open Land (Grass cover 50% - 75%) | A | 49 | 3.54 ac | 173.6 |
| Open Land (Grass cover 50% - 75%) | A/D | 84 | 3.39 ac | 284.8 |
| | | Total: | 51.68 ac | 4856.1 |

CN = Total CN * Area / Total Area = **94.0**

---

**Runoff:**

Soil Capacity (S) = $\frac{1000}{CN} - 10$ = 0.64 in

Precipitation (P) = 18.5 in (for 100yr/10dy storm event)

Runoff (Q) = $\frac{(P - 0.2S)^2}{(P + 0.8S)}$ = **17.75 in**

**HNTB Corporation**
610 Crescent Executive Court, Suite 400
Lake Mary, FL 32746

| | | date: |
|---|---|---|
| made by: | LDP | 26-Mar-15 |
| checked by: | BJS | 26-Mar-15 |
| HNTB job #: | 59219 | |

**PROJECT: I-4 PD&E - SEGMENT 3**

BASIN NAME: 308
POND NAME: 308 (Pond 3 from Permit No. 22124-2)

## POND SIZING : DRY RETENTION POND (CLOSED BASIN) - SJRWMD (W/ OUTFALL)

**Required Treatment Volume:**

1.25" over Impervious Area + 0.5" over Total Area= 4.01 ac-ft
1" over Total Area = 4.31 ac-ft

**Treatment $V_{req}$ = Largest of Trt. Vol. = 4.31 ac-ft**

---

**Required Attenuation Volume:**

Total Runoff:
$Q_{pre}$ = 12.99 in
$Q_{post}$ = 17.75 in
$\Delta Q$ = 4.76 in


**Attenuation $V_{req}$ = $\Delta Q/12$ x Total Area= 20.51 ac-ft**

---

Maintenance Area Width = 15.0 ft @ 1:15
Pond Tie-In Width = 18.0 ft @ 1:4

Existing Ground Elevation = 55.0 ft
Seasonal High Water Elevation* = 47.16 ft
Lowest EOP Elevation = 60.0 ft

* Seasonal High Water El. From Existing Permit




**Pond Section**

| Elevation | Description | Area | Dimensions | | Storage |
|---|---|---|---|---|---|
| | | | Length | Width | |
| 57.00 | Back of Maintenance Berm | 8.67 ac | | | 47.66 ac-ft |
| 56.00 | Front of Maintenance Berm | 7.44 ac | | | 39.60 ac-ft |
| 55.00 | --- | 7.12 ac | | | 32.32 ac-ft |
| 52.00 | --- | 6.64 ac | | | 11.68 ac-ft |
| 50.16 | Pond Bottom | 6.06 ac | | | 0.00 ac-ft |

| | | | |
|---|---|---|---|
| Required Treatment Volume: | 4.31 ac-ft | Required Treat. Vol. + Atten.: | 24.81 ac-ft |
| Top El. Of Treatment Volume: | 50.84 | Top El. Of Treat. Vol. + Atten.: | 53.91 |

**Appendix B**
**Geotechnical Pond Boring Summary**

Geotechnical and Environmental Consultants, Inc.

**Table 11**
**POND SUMMARY TABLE**
I-4 Segment 3 BTU
FPID:232592-4-32-01
GEC Project No. 3763G

| Project Element | Boring No. | Northing | Easting | GSE (NAVD 88) | Boring Depth (ft) | Boring Type | Date Drilled | Field Perm Depth (ft) | Soil Type | Hydraulic Conductivity Kh (ft/day) | Enc. GWT Depth (ft) | Enc. GWT Elev. (NAVD88) | Enc. GWT Date | SHWT Depth (ft) | SHWT Elev. (NAVD88) | Bottom of Aquifer Elevation (NAVD88) | Porosity (%) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Pond 301 | P301-1 | 1595366.233 | 536205.696 | 51.7 | 20 | AB | 11/16/15 | --- | --- | --- | 7.1 | +44.6 | 11/17/15 | 6.1 | +45.6 | +31.7 | 0.25 |
| | P301-2 | 1595365.492 | 536328.918 | 51.4 | 20 | AB | 11/16/15 | 3 - 5 | A-3 | 40 | 6.9 | +44.5 | 11/17/15 | 5.9 | +45.5 | +31.4 | |
| | P301-3 | 1595489.160 | 536116.121 | 52.3 | 20 | AB | 11/16/15 | 6 - 8 | A-3 | 40 | 7.2 | +45.1 | 11/17/15 | 6.2 | +46.1 | +32.3 | |
| | P301-4 | 1595528.683 | 536265.808 | 51.0 | 20 | AB | 11/16/15 | --- | --- | --- | 6.9 | +44.1 | 11/17/15 | 5.9 | +45.1 | +31.0 | |
| Pond 300 | P300-1 | 1595521.052 | 536565.863 | 57.9 | 30 | AB | 02/14/17 | 9 - 11 | A-7-6 | 0 | 17 | +40.9 | 02/17/17 | 9.0 | +48.9 | +48.9 | 0.25 |
| | P300-2 | 1595530.484 | 536741.886 | 57.2 | 30 | AB | 02/14/17 | --- | --- | --- | 15 | +42.2 | 02/17/17 | 10.0 | +47.2 | +46.2 | |
| Pond 301A | P301A-1 | 1596030.172 | 536620.845 | 63.5 | 30 | AB | 02/17/17 | 10 - 12 | A-3 | 2.2 | 10 | +53.5 | 02/20/17 | 7.0 | +56.5 | +48.5 | 0.25 |
| | P301A-2 | 1596409.601 | 536685.690 | 54.3 | 30 | AB | 02/17/17 | --- | --- | --- | 6.8 | +47.5 | 02/20/17 | 3.8 | +50.5 | +28.8 | |
| Pond 302 | P302-1 | 1596813.381 | 535947.946 | 56.5 | 20 | AB | 11/25/15 | --- | --- | --- | 13.3 | +43.2 | 11/29/15 | 12.0 | +44.5 | +36.5 | 0.25 |
| | P302-2 | 1596867.508 | 536049.737 | 49.9 | 20 | AB | 11/25/15 | 7 - 9 | A-2-4 | 23.4 | 6.7 | +43.2 | 11/29/15 | 5.7 | +44.2 | +31.9 | |
| | P302-3 | 1596988.403 | 535995.854 | 48.6 | 20 | AB | 11/25/15 | 2 - 4 | A-3 | 1.0 | 4.8 | +43.8 | 11/29/15 | 4.0 | +44.6 | +28.6 | |
| | P302-4 | 1597062.595 | 536117.400 | 50.2 | 20 | AB | 11/25/15 | --- | --- | --- | 7.0 | +43.2 | 11/29/15 | 6.0 | +44.2 | +30.2 | |
| Pond 303-A2 | P303-A2-1 | 1599034.774 | 537192.597 | 55.3 | 20 | AB | 11/17/15 | 5 - 7 | A-7-6 | 0.0 | 15.2 | +40.1 | 11/18/15 | 14.0 | +41.3 | * +37.3 | 0.25 |
| | P303-A2-2 | 1599135.971 | 537288.866 | 55.0 | 20 | AB | 11/17/15 | --- | --- | --- | 14.6 | +40.4 | 11/18/15 | 13.5 | +41.5 | * +41.0 | |
| | P303-A2-3 | 1599393.030 | 537294.346 | 54.7 | 20 | AB | 11/17/15 | 7 - 9 | A-3 | 32 | 13.1 | +41.6 | 11/18/15 | 12.0 | +42.7 | +37.2 | |
| Pond 303-B2 | P303-B2-1 | 1599876.659 | 536931.659 | 77.4 | 30 | AB | 11/30/15 | 13 - 15 | A-3 | 27.7 | GNE @ 30.0 | --- | 11/30/15 | 25.0 | +52.4 | * +47.4 | 0.25 |
| | 303-B2-2 | 1599589.629 | 536977.133 | 72.2 | 30 | AB | 02/17/17 | 12 - 14 | A-3 | 7.0 | 18 | +54.2 | 02/20/17 | 15.0 | +57.2 | +42.2 | |
| Pond 304 | P304-1 | 1603171.418 | 538041.150 | 55.4 | 20 | AB | 11/17/15 | --- | --- | --- | 18 | +37.4 | 11/29/15 | 16.5 | +38.9 | +43.4 | 0.25 |
| | P304-2 | 1603320.310 | 537958.171 | 54.7 | 20 | AB | 11/17/15 | --- | --- | --- | 17.1 | +37.6 | 11/29/15 | 16.1 | +38.6 | +43.7 | |
| | P304-3 | 1603359.102 | 538121.969 | 55.4 | 20 | AB | 11/24/15 | 6 - 8 | A-3 | 40 | 18.3 | +37.1 | 11/29/15 | 17.0 | +38.4 | +46.4 | |
| | P304-4 | 1603472.795 | 538013.290 | 54.6 | 20 | AB | 11/24/15 | 2 - 4 | A-2-4 | 3.6 | 16.0 | +38.6 | 11/29/15 | 15.0 | +39.6 | +50.1 | |
| | P304-5 | 1603537.478 | 538155.171 | 54.7 | 20 | AB | 11/24/15 | --- | --- | --- | 17.5 | +37.2 | 11/29/15 | 16.0 | +38.7 | +44.7 | |
| Pond 305 | P305-1 | 1605977.621 | 539354.144 | 40.4 | 20 | AB | 11/18/15 | 2 - 4 | A-3 | 5.3 | +0.4 | +40.8 | 11/18/15 | AGS | --- | +20.4 | 0.25 |
| | P305-2 | 1606168.802 | 539475.706 | 40.0 | 20 | AB | 11/18/15 | --- | --- | --- | +0.8 | +40.8 | 11/18/15 | AGS | --- | +25.0 | |
| | P305-3 | 1606294.019 | 539575.388 | 40.1 | 20 | AB | 11/19/15 | --- | --- | --- | +0.5 | +40.6 | 11/19/15 | AGS | --- | +20.1 | |
| | P305-4 | 1606427.898 | 539509.533 | 40.6 | 20 | AB | 11/19/15 | --- | --- | --- | +0.2 | +40.8 | 11/19/15 | AGS | --- | +30.6 | |
| | P305-5 | 1606350.252 | 539746.376 | 39.8 | 20 | AB | 11/19/15 | 8 - 10 | A-2-4 | 0.6 | +1.0 | +40.8 | 11/19/15 | AGS | --- | +34.8 | |
| | P305-6 | 1606583.455 | 539729.449 | 40.5 | 20 | AB | 11/19/15 | --- | --- | --- | +0.4 | +40.9 | 11/19/15 | AGS | --- | +25.5 | |
| | P305-7 | 1606773.015 | 539608.459 | 40.9 | 20 | AB | 11/19/15 | 4 - 6 | A-3 | 1.8 | 0.0 | +40.9 | 11/19/15 | AGS | --- | +22.4 | |
| | P305-8 | 1606673.801 | 539937.632 | 39.7 | 20 | AB | 11/19/15 | --- | --- | --- | +1.0 | +40.7 | 11/19/15 | AGS | --- | +19.7 | |
| | P305-9 | 1606897.999 | 539851.265 | 39.9 | 20 | AB | 11/19/15 | --- | --- | --- | +0.7 | +40.6 | 11/19/15 | AGS | --- | +19.9 | |
| | P305-10 | 1607105.921 | 539724.594 | 40.8 | 20 | AB | 11/19/15 | --- | --- | --- | +0.4 | +41.2 | 11/19/15 | AGS | --- | +20.8 | |
| | P305-11 | 1606995.247 | 540112.545 | 40.8 | 20 | AB | 11/18/15 | 8 - 10 | A-2-4 | 1.4 | 0.0 | +40.8 | 11/19/15 | AGS | --- | +21.8 | |
| | P305-12 | 1607578.132 | 539951.922 | 47.6 | 25 | AB | 02/20/17 | 5 - 7 | A-3 | 20.1 | 10 | +57.6 | 02/21/17 | 7.0 | +40.6 | +22.6 | |
| Pond 306 | P306-1 | 1608551.656 | 539784.661 | 45.8 | 20 | AB | 11/17/15 | --- | --- | --- | 6.2 | +39.6 | 11/19/15 | 5.2 | +40.6 | +25.8 | 0.25 |
| | P306-2 | 1608671.910 | 539612.269 | 45.1 | 20 | AB | 11/17/15 | 3 - 5 | A-3 | 0.7 | 6.9 | +38.2 | 11/19/15 | 5.9 | +39.2 | +25.1 | |
| | P306-3 | 1608701.886 | 539759.247 | 45.3 | 20 | AB | 11/17/15 | --- | --- | --- | 6.6 | +38.7 | 11/19/15 | 5.6 | +39.7 | +25.3 | |
| | P306-4 | 1608822.477 | 539860.529 | 46.1 | 20 | AB | 11/17/15 | 6 - 8 | A-3 | 4.2 | 5.8 | +40.3 | 11/19/15 | 4.8 | +41.3 | +26.1 | |
| | P306-5 | 1608403.879 | 539672.741 | 47.2 | 25 | AB | 02/20/17 | 2.5 - 5<br>10 - 12 | A-2-4<br>A-2-4 | 4.9<br>1.0 | 10 | +37.2 | 02/21/17 | 7.0 | +40.2 | +22.2 | |

Geotechnical and Environmental Consultants, Inc.

**Table 11**
**POND SUMMARY TABLE**
I-4 Segment 3 BTU
FPID:232592-4-32-01
GEC Project No. 3763G

| Project Element | Boring No. | Northing | Easting | GSE (NAVD 88) | Boring Depth (ft) | Boring Type | Date Drilled | Field Perm Depth (ft) | Soil Type | Hydraulic Conductivity Kh (ft/day) | Enc. GWT Depth (ft) | Enc. GWT Elev. (NAVD88) | Enc. GWT Date | SHWT Depth (ft) | SHWT Elev. (NAVD88) | Bottom of Aquifer Elevation (NAVD88) | Porosity (%) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Pond 307 | P307-1 | 1610553.388 | 540861.881 | 49.3 | 20 | AB | 11/16/15 | 5 - 7 | A-2-4 | 1.6 | 10.6 | +38.7 | 11/19/15 | 9.6 | +39.7 | * +29.3 | 0.25 |
| | P307-2 | 1610554.987 | 540978.190 | 48.7 | 20 | AB | 11/16/15 | --- | --- | --- | 10.8 | +37.9 | 11/19/15 | 9.8 | +38.9 | +28.7 | |
| | P307-3 | 1610669.903 | 540892.221 | 49.2 | 20 | AB | 11/16/15 | --- | --- | --- | 11.0 | +38.2 | 11/19/15 | 10.0 | +39.2 | +29.2 | |
| | P307-4 | 1610671.532 | 541021.976 | 47.9 | 20 | AB | 11/16/15 | 3 - 5 | A-2-4 | 0.3 | 10.2 | +37.7 | 11/19/15 | 9.2 | +38.7 | +27.9 | |
| | P307-5 | 1610602.317 | 540952.393 | 48.9 | 15 | AB | 03/06/17 | 3 - 5 | A-2-4 | 0.9 | 12.8 | +36.1 | 03/07/17 | 9.8 | +39.1 | +33.9 | |
| Pond 308 | P308-1 | 1611719.494 | 541226.218 | 52.1 | 20 | AB | 11/16/15 | 4 - 6 | A-3 | 40 | 10.0 | +42.1 | 11/17/15 | 9.0 | +43.1 | +42.1 | 0.25 |
| | P308-2 | 1611788.485 | 541402.518 | 51.1 | 20 | AB | 11/30/15 | --- | --- | --- | 10.5 | +40.6 | 12/01/15 | 9.5 | +41.6 | +38.1 | |
| | P308-3 | 1612043.045 | 541337.211 | 50.6 | 20 | AB | 11/15/15 | --- | --- | --- | 7.9 | +42.7 | 11/19/15 | 6.9 | +43.7 | +30.6 | |
| | P308-4 | 1612279.179 | 541399.973 | 50.5 | 20 | AB | 11/16/15 | 3 - 5 | A-3 | 40 | 7.5 | +43.0 | 11/16/15 | 6.5 | +44.0 | +30.5 | |
| | P308-5 | 1612544.237 | 541535.448 | 56.8 | 20 | AB | 11/16/15 | --- | --- | --- | 8.4 | +48.4 | 11/19/15 | 7.4 | +49.4 | +38.8 | |
| | P308-6 | 1612461.853 | 541805.559 | 61.9 | 20 | AB | 11/16/15 | 7 - 9 | A-3 | 36 | 14.3 | +47.6 | 11/17/15 | 13.3 | +48.6 | +41.9 | |
| | P308-7 | 1612652.805 | 541744.169 | 75.7 | 20 | AB | 11/17/15 | --- | --- | --- | 18 c/o | +57.7 | --- | 16.0 | +59.7 | +55.7 | |
| | P308-8 | 1612789.661 | 541617.554 | 74.1 | 20 | AB | 11/16/15 | 6 - 8 | A-2-4 | 34.7 | 16 c/o | +58.1 | --- | 14.0 | +60.1 | +54.1 | |
| | P308-9 | 1612680.771 | 541955.340 | 74.2 | 20 | AB | 11/17/15 | --- | --- | --- | 15 c/o | +59.2 | --- | 13.0 | +61.2 | +54.2 | |
| Pond 308A | P308A-1 | 1613410.972 | 541801.863 | 72.3 | 25 | AB | 02/14/17 | --- | --- | --- | 16.5 | +55.8 | 02/17/15 | 13.5 | +58.8 | +56.3 | 0.25 |
| | P308A-2 | 1613413.745 | 541977.278 | 71.7 | 25 | AB | 02/14/17 | 7 - 9 | A-3 | 3.8 | 12.5 | +59.2 | 02/17/17 | 10.0 | +61.7 | +56.7 | |
| Pond 311 | P311-1 | 1618909.182 | 544746.449 | 64.6 | 30 | AB (on berm) | 02/17/17 | 2 - 4 | A-3 | 7.8 | 7 | +57.6 | 02/21/17 | ** | ** | +34.7 | 0.25 |
| LOCH LEHMAN | LL-1 | 1619482.780 | 543920.497 | 64.3 | 25 | AB (on berm) | 02/17/17 | 2 - 4 | A-3 | 12.8 | 6 c/o | +58.3 | 02/20/17 | ** | ** | +39.3 | 0.25 |
| Pond 317D | P317D-1 | 1634025.900 | 552639.967 | 10.9 | 10 | AB | 07/06/17 | --- | --- | --- | 3.8 | +4.9 | 07/07/17 | 2.4 | +8.5 | +5.9 | 0.25 |
| | P317D-2 | 1633804.864 | 552582.164 | 12.5 | 10 | AB | 07/06/17 | --- | --- | --- | 5.8 | +6.5 | 07/07/17 | 4.0 | +8.5 | +7.0 | |
| Pond 318B | P318B-1 | 1633603.631 | 552969.553 | 10.0 | 15 | AB | 02/17/17 | --- | --- | --- | 5.5 | +4.5 | 02/20/17 | 3.0 | +7.0 | +0.0 | 0.25 |

Notes: GNE = Ground Water Not Encountered Within the Depth Explored, AGS = At or Above the Ground Surface, --- = N/A, c/o = borehole caved off at depth


* Indicates that the value is only valid if the clayey soils are removed per the hatched cross section

** Seasonal high groundwater level controlled by the adjacent stormwater ponds and their control elevation

**Appendix C**
**Basin Drainage Maps, Routing & Calculations**

Basin 300 & 301

- Drainage Maps
- Basin and Pond Calculations
- Basin and Pond Routing (ICPR)
  - Pre-Development
  - Post-Development
- Grace Lake Stormwater Model
  - SJRWMD ERP for Grace Lake, March 2014
  - Existing Conditions for Grace Lake
  - Proposed Conditions for Grace Lake
- Existing Permits (Supporting Documentation)




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462



STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# EXISTING BASIN 300 & 301

SHEET NO. 1


Littlec 7/18/2017 11:30:31 AM T:\Sys\Projects\24259245201\drainage\REPORT\DRMP_Basin300_Exist.dgn




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# PROPOSED BASIN 300 & 301

SHEET NO. 2


Littlec 7/18/2017 11:30:48 AM T:\Sys\Projects\24259245201\drainage\REPORT\DRMP_Basin300_Prop.dgn

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

I ***PRE DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 300 & 301***

| | |
|---|---|
| COMPUTED R/W AREA (Ac) | 50.23 |

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

***FDOT R/W Area in Basin 300 & 301***

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| I-4 & EE Williams Rd. | - | 98 | 16.70 | 1636.60 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 16.70 | 1636.60 |
| Pervious | | | | |
| Open Space, Fair Condition | A | 49 | 11.32 | 554.68 |
| Open Space, Fair Condition | A | 51 | 5.59 | 285.09 |
| Open Space, Fair Condition | D / B/D | 80 | 16.62 | 1329.60 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 33.53 | 2169.37 |
| | | TOTAL | 50.23 | 3805.97 |

| | |
|---|---|
| **COMPOSITE CN** | **75.8** |

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 3.20 | 8.11 | 33.93 |
| 100 yr / 10-day | FDOT | 18.50 | 3.20 | 15.15 | 63.41 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 3.20 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 15.15 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 63.41 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

II ***POST DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 300 & 301***

| | |
|---|---|
| COMPUTED R/W AREA (Ac) | 50.96 |

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

***Basin 300***

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| Impervious | | | | |
| I-4 Pavement Draining to Pond 300 | - | 98 | 17.77 | 1741.46 |
| | | | | |
| Pervious | | | | |
| Open Space, Fair Condition | A | 49 | 0.88 | 43.12 |
| Open Space, Fair Condition | A | 51 | 5.59 | 285.09 |
| Open Space, Fair Condition | D / B/D | 80 | 3.43 | 274.40 |
| Sub-total for Pervious Land Uses | | | 9.90 | 602.61 |
| Pond 300 (Water) | - | 100 | 2.11 | 211.00 |
| Sub-total for Pond Land Uses | | | 2.11 | 211.00 |
| | | TOTAL | 29.78 | 2555.07 |

| | |
|---|---|
| **COMPOSITE CN** | **85.8** |

***Basin 301***

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| I-4 Pavement Draining to Pond 301 | - | 98 | 13.62 | 1334.76 |
| | | | | |
| Pervious | | | | |
| Open Space, Fair Condition | A | 49 | 1.69 | 82.81 |
| Open Space, Fair Condition | D / B/D | 80 | 3.41 | 272.80 |
| Sub-total for Pervious Land Uses | | | 5.10 | 355.61 |
| | | TOTAL | 18.72 | 1690.37 |

| | |
|---|---|
| **COMPOSITE CN** | **90.3** |

***Remaining Area within the FDOT R/W***

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| EE Williams West of I-4 | - | 98 | 0.73 | 71.54 |
| EE Williams East of I-4 | - | 98 | 0.89 | 87.22 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 1.62 | 158.76 |
| Pervious | | | | |
| Open Space, Fair Condition - EE Williams West of I-4 | A | 49 | 0.12 | 5.88 |
| Open Space, Fair Condition - EE Williams East of I-4 | D / B/D | 80 | 0.72 | 57.60 |
| Sub-total for Pervious Land Uses | | | 0.84 | 63.48 |
| | | TOTAL | 2.46 | 222.24 |

| | |
|---|---|
| **COMPOSITE CN** | **90.3** |
| **BASIN COMPOSITE CN** | **87.7** |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 1.41 | 9.67 | 41.08 |
| 100 yr / 10-day | FDOT | 18.50 | 1.41 | 16.91 | 71.82 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 1.41 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 16.91 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 71.82 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

## III *GEOTECHNICAL INFORMATION*

***Pond 300***

| **Estimated Seasonal High Water Table (SHWT)** | |
|---|---|
| | **Estimated SHWT (Ft)** |
| Pond Borings (Avg. of Borings P300-1 to P300-2) | 48.05 |
| | |
| **Estimated SHWT** | 49.0 |

***Pond 301***

| **Estimated Seasonal High Water Table (SHWT)** | |
|---|---|
| | **Estimated SHWT (Ft)** |
| Existing Permit No. 22434-1 Pond F | 48.0 |
| Pond Borings (Avg. of Borings P301-1 to P301-4) | 45.58 |
| | |
| **SHWT Used** | 45.6 |

## IV *SUMMARY OF REQUIRED ATTENUATION AND TREATMENT VOLUME*

***Basin 300 & 301***

**REQUIRED ATTENUATION CACULATION**

| **PRE-DEVELOPED CONDITION** | | **POST-DEVELOPED CONDITION** | |
|---|---|---|---|
| AREA (AC): | 50.23 | AREA (AC): | 50.96 |
| CN: | 75.8 | CN: | 87.7 |
| IMPERVIOUS AREA (AC): | 15.94 | IMPERVIOUS AREA (AC): | 33.03 |
| PERVIOUS AREA (AC): | 34.29 | PERVIOUS AREA (AC): | 17.93 |
| | | NEW IMPERVIOUS AREA (AC): | 17.09 |

**SUMMARY OF WATER MANAGEMENT DISTRICT ATTENUATION ESTIMATES**

| AGENCY | DESIGN STORM | RUNOFF VOLUME V[R] PRE [ AC-FT ] | POST [ AC-FT ] | TOTAL RETENTION [ AC-FT ] |
|---|---|---|---|---|
| SJRWMD | 25 yr / 96 hr | 33.93 | 41.08 | **7.15** |
| FDOT | 100 yr / 10-day | 63.41 | 71.82 | **8.42** |

**Basin 300**

| **Required Treatment Volume Calculation** | | AC-FT | Basin Area | |
|---|---|---|---|---|
| Wet Detention Treatment Req. = | 1" x Basin Area | 2.48 | 29.78 | |
| or | 2.5" x Impervious Area | 3.70 | | ***<Controls>*** |

**Basin 301**

| **Required Treatment Volume Calculation** | | AC-FT | Basin Area | |
|---|---|---|---|---|
| Dry Retention Treatment Req. = | 1" x Basin Area | 1.56 | 18.72 | |
| or | 1.25" x Impervious Area + 0.5" x Basin Area | 2.20 | | ***<Controls>*** |

| **Required Wekiva Basin Most Effective Recharge Volume** | **AC** | **AC-FT** | |
|---|---|---|---|
| Pre Devp. A Soils = | 16.91 | | |
| Post Devp. A Soils = | 8.28 | | |
| Post Devp. Impervious Area - Pre Devp. Impervious Area = | 8.63 | | |
| Wekiva Recharge Area required by previous project (Basin E) = | 1.92 | | Permit No. 22434-1 Pond E |
| Wekiva Recharge Area required by previous project (Basin F) = | 1.79 | | Permit No. 22434-1 Pond F |
| Sum of Current + prevous project impervous area added = | 12.34 | | |
| 3" x Total Impervous Area on A Soils = | | **3.09** | |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

| **Required Closed Basin Volume - SJRWMD 25-yr / 96-hr** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 33.93 | |
| Post Devp. Runoff Volume | 41.08 | |
| Current Project Delta | 7.15 | |
| Previous Project Required Volume | 1.67 | Permit No. 22434-1 for Pond E |
| Previous Project Required Volume | 1.29 | Permit No. 22434-1 for Pond F |
| Current Project Delta + Prevous Project Required Volume | **10.11** | |

| **Required Closed Basin Volume - FDOT 100-yr / 10-day** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 63.41 | |
| Post Devp. Runoff Volume | 71.82 | |
| Current Project Delta | 8.42 | |
| Previous Project Required Volume | 2.15 | Permit No. 22434-1 for Pond E |
| Previous Project Required Volume | 1.80 | Permit No. 22434-1 for Pond F |
| Current Project Delta + Prevous Project Required Volume | **12.37** | |

V ***PROVIDED TREATMENT & ATTENUATION VOLUME CALCULATIONS***

***Pond 300***

| **POND STAGE, AREA & STORAGE** | | | |
|---|---|---|---|
| **DESCRIPTION** | **STAGE (FT)** | **AREA (AC)** | **CUMMULATIVE STORAGE (AC-FT)** |
| Pond Bottom Elevation | 40.50 | 1.25 | 0.00 |
| SHWT Elevation | 49.00 | 2.11 | 14.28 |
| Water Quality Treatment Elevation | 50.67 | 2.32 | 17.98 |
| Top of Bank Elevation | 57.00 | 3.11 | 35.16 |
| Top of Berm Elevation | 57.00 | 3.56 | 35.16 |

| **Provided Treatment Volume Calculation** | AC-FT |
|---|---|
| Treatment Volume Provided = Volume between SHWT El. and the Water Quality Treatment El. | 3.70 |

***Pond 301***

| **POND STAGE, AREA & STORAGE** | | | |
|---|---|---|---|
| **DESCRIPTION** | **STAGE (FT)** | **AREA (AC)** | **CUMMULATIVE STORAGE (AC-FT)** |
| Pond Bottom Elevation | 52.00 | 2.83 | 0.00 |
| Water Quality Treatment Elevation | 52.76 | 2.94 | 2.20 |
| Wekiva Recovery El. (Wekiva Criteria) | 53.07 | 2.98 | 3.09 |
| FDOT Closed Basin El. (7 day - half Vol) | 54.08 | 3.12 | 6.18 |
| SJRWMD Closed Basin El. (14-day) | 55.30 | 3.29 | 10.11 |
| Weir Crest El. (FDOT Closed Basin) | 55.98 | 3.39 | 12.37 |
| Top of Bank Elevation | 57.00 | 3.53 | 15.90 |
| Top of Berm Elevation | 57.00 | 3.21 | 15.90 |

| **Provided Treatment Volume Calculation** | AC-FT |
|---|---|
| Treatment Volume Provided = Volume between Pond Bottom El. and the Water Quality Treatment El. | 2.20 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

VI ***PERMANENT POOL VOLUME CALCULATIONS FOR POND 300***

$$PPV = \frac{DA * C * R * RT}{WS * CF}$$

PPV: Permanent Pool Volume (ac-ft)
DA: Drainage Area to the Pond (ac)(excluding water body)
C: Drainage Area Runoff Coefficient
R: Wet Season Rainfall Depth (in)(Figure 29-1)
RT: Residence Time (days)
WS: Length of Wet Season (June - October = 153 days)(days)
CF: Conversion Factor (12 in/ft)

Special Basin: N/A
Additional 50% (7-days) for OFW or Class I or Class II or Class III

| | | | |
|---|---|---|---|
| DA = | 29.78 | acres | |
| C = | 0.83 | | |
| R = | 31 | inches | (See Figure 26-1, SJRWMD) |
| WS = | 153 | days | |
| RT = | 14 | days | |
| Non-Littoral Zone Option RT = | 7 | days | |
| Special Water RT = | 0 | days | (OFW or Class I or Class II or Class III) |
| Design RT = | 21 | days | |

**Required Permanent Pool Volume:**

| | | |
|---|---|---|
| PPV = | 8.805 | ac-ft |
| | 383543 | cu.ft |

**Permanent Pool Volume Check:**

Proposed Orifice Invert Elevation: 49.00 feet

| | | |
|---|---|---|
| Actual Pond Volume: | 14.28 | ac-ft |
| | 622037 | cu.feet |

| | | |
|---|---|---|
| Required Permanent Pool Volume: | 8.805 | ac-ft |
| Actual Permanent Pool Volume: | 14.280 | ac-ft |
| Additional Permanent Pool Volume: | 5.475 | ac-ft |

**Exceeds Requirement**

**POND DEPTH**

Pond Depth Criteria:
*Maximum Pond Depth Shall Not Exceed 12 feet*

| | | |
|---|---|---|
| Control Elevation: | 49.00 | feet |
| Pond Bottom Elevation: | 40.50 | feet |
| Pond Depth: | 8.50 | feet |

**Does Not Exceed Maximum Pond Depth Requirement**

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 30, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 300 & 301 | **CHECKED BY:** | MB |

## PERMANENT POOL MEAN DEDPTH

Mean Depth Equation:

$$\text{Mean Depth} = \frac{\text{Pond Volume at Control Elevation}}{\text{Pond Area at Control Elevation}}$$


Mean Depth Criteria:

*Permanent Pool Depth Shall Vary Between 2 and 8 feet*

| | | |
|---|---|---|
| Control Elevation: | 49.00 | feet |
| Volume at Control Elevation: | 14.28 | ac-ft |
| Area at Control Elevation: | 2.11 | ac |
| Mean Depth: | 6.77 | feet |

**Meets Mean Depth Requirement**

Pre Development




FLIGHT DATE: 2015

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

PARSONS BRINCKERHOFF, INC.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM EXISTING BASIN 300-301

SHEET NO. N/A

AndersonT 4/27/2017 11:02:15 AM T:\Sys\Projects\24259245201\drainage\REPORT\ICPR Link_Node\Basin300_301_Exist_Link

BASIN 300 & 301
Existing Conditions Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| SC-0800 | BASIN300&301 | 100Y240H | 11.02 | 52.00 | 52.00 | 0.00 | 0 | 183.91 | 7.91 | 0.00 | 0.00 |
| SC-0800 | BASIN300&301 | SJRWMD | 11.00 | 52.00 | 52.00 | 0.00 | 0 | 60.00 | 51.81 | 0.00 | 0.00 |
| SC-0815 | BASIN300&301 | 100Y240H | 0.00 | 55.00 | 56.00 | 0.00 | 0 | 216.05 | 0.19 | 0.00 | 0.00 |
| SC-0815 | BASIN300&301 | SJRWMD | 0.00 | 55.00 | 56.00 | 0.00 | 0 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-0820 | BASIN300&301 | 100Y240H | 216.05 | 55.05 | 56.00 | 0.00 | 63275 | 183.91 | 4.86 | 39.99 | 2.14 |
| SC-0820 | BASIN300&301 | SJRWMD | 64.27 | 53.30 | 56.00 | 0.00 | 50720 | 60.08 | 28.37 | 61.21 | 5.84 |
| SC-0820 GRND | BASIN300&301 | 100Y240H | 0.00 | 45.60 | 45.60 | 0.00 | 0 | 39.99 | 2.14 | 0.00 | 0.00 |
| SC-0820 GRND | BASIN300&301 | SJRWMD | 0.00 | 45.60 | 45.60 | 0.00 | 0 | 61.21 | 5.84 | 0.00 | 0.00 |

Existing Discharge Rates:
Basin 300
Q-FDOT (100-yr/240-hr)= 7.91 cfs
Q-SJRWMD (25-yr/96-hr)= 51.81 cfs

Basin 301
Q-FDOT (100-yr/240-hr)= 0.19 cfs
Q-SJRWMD (25-yr/96-hr)= 0.00 cfs

==========
==== Basins ==========
==========

Name: SC-0820A Node: SC-0820 Status: Onsite
Group: BASIN300&301 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 11.00
Area(ac): 3.320 Time Shift(hrs): 0.00
Curve Number: 73.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

Area draining directly to Existing Pond F

---

Name: SC-0820B Node: SC-0820 Status: Onsite
Group: BASIN300&301 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 30.00
Area(ac): 4.480 Time Shift(hrs): 0.00
Curve Number: 81.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

I-4 Roadway Area draining directly to Existing Pond F

---

Name: SC-800A Node: SC-0800 Status: Onsite
Group: BASIN300&301 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 13.00
Area(ac): 8.850 Time Shift(hrs): 0.00
Curve Number: 75.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

Northridge Depressional Area

---

Name: SC-800B Node: SC-0800 Status: Onsite
Group: BASIN300&301 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 12.00
Area(ac): 4.030 Time Shift(hrs): 0.00
Curve Number: 70.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

I-4 Rest Area - Wooded Area

==========
==== Nodes ==========
==========

Name: SC-0800 Base Flow(cfs): 0.000 Init Stage(ft): 49.000
Group: BASIN300&301 Warn Stage(ft): 52.000
Type: Time/Stage

Depressional Area in Northridge Community

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 49.000 |
| 11.00 | 52.000 |
| 16.00 | 52.000 |
| 24.00 | 52.000 |
| 96.00 | 49.000 |

---

Name: SC-0815 Base Flow(cfs): 0.000 Init Stage(ft): 55.000
Group: BASIN300&301 Warn Stage(ft): 56.000
Type: Time/Stage

Depressional area on east side of I-4 R/W at the upstream end of the existing 54" Crossdrain under I-4.

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 55.000 |
| 96.00 | 55.000 |

Name: SC-0820 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: BASIN300&301 Warn Stage(ft): 56.000
Type: Stage/Area

Existing Pond F - FDOT Permit No. 22434-1 (Used same node name as the Grace Lake Model)

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 1.0600 |
| 53.000 | 1.1400 |
| 54.000 | 1.2200 |
| 55.000 | 1.4400 |
| 56.000 | 1.6700 |

Name: SC-0820 GRND Base Flow(cfs): 0.000 Init Stage(ft): 45.600
Group: BASIN300&301 Warn Stage(ft): 45.600
Type: Time/Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 45.600 |
| 336.00 | 45.600 |

## Weirs

Name: SC-0820-W1 From Node: SC-0820
Group: BASIN300&301 To Node: SC-0815
Flow: Both Count: 1
Type: Vertical: Mavis Geometry: Trapezoidal

Bottom Width(ft): 5.00
Left Side Slope(h/v): 6.00
Right Side Slope(h/v): 6.00
Invert(ft): 55.000
Control Elevation(ft): 55.000
Struct Opening Dim(ft): 9999.00
TABLE
Bottom Clip(ft): 0.000
Top Clip(ft): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

Existing Pond F Weir

## Percolation Links

Name: SC-0820-PERC From Node: SC-0820 Flow: Both
Group: BASIN300&301 To Node: SC-0820 GRND Count: 1

Surface Area Option: Vary based on Stage/Area Table
Vertical Flow Termination: Horizontal Flow Algorithm
Aquifer Base Elev(ft): 31.600 Perimeter 1(ft): 1038.000
Water Table Elev(ft): 45.600 Perimeter 2(ft): 1352.000
**********-9999.000 Perimeter 3(ft): 3859.000
Horiz Conductivity(ft/day): 20.000 Distance 1 to 2(ft): 50.000
Vert Conductivity(ft/day): 10.000 Distance 2 to 3(ft): 450.000
Effective Porosity(dec): 0.250 Num Cells 1 to 2: 10
Suction Head(in): 4.000 Num Cells 2 to 3: 45
Layer Thickness(ft): 6.400

## Hydrology Simulations

Name: 100Y240H

```
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\100Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 18.50

Time(hrs)       Print Inc(min)
--------------- ---------------
336.000         5.00

-------------------------------------------------------------------------------------------------
         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.R32

      Override Defaults: No

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
96.000          5.00

=================================================================================
==== Routing Simulations ========================================================
=================================================================================

         Name: 100Y240H            Hydrology Sim: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\100Y240H.I32

      Execute: Yes         Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 336.00
     Min Calc Time(sec): 0.5000               Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:



Time(hrs)       Print Inc(min)
--------------- ---------------
336.000         15.000

Group           Run
--------------- -----
BASIN300&301    Yes


-------------------------------------------------------------------------------------------------
         Name: SJRWMD              Hydrology Sim: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.I32

      Execute: Yes         Restart: No            Patch: No
  Alternative: No


        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 120.00
     Min Calc Time(sec): 0.5000               Max Calc Time(sec): 1.0000
        Boundary Stages:                         Boundary Flows:



Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.000
14.000          1.000
96.000          5.000
120.000         5.000

Group           Run
--------------- -----
BASIN300&301    Yes
```

Post Development




FLIGHT DATE: 2015

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

PARSONS BRINCKERHOFF, INC.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM
# PROPOSED BASIN 300-301

SHEET NO.
N/A

AndersonT 4/27/2017 11:12:47 AM T:\Sys\Projects\24259245201\drainage\REPORT\ICPR Link_Node\Basin300_301_Prop_Link

Basin 300 & 301
Proposed Condition Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GRND 301 | BASIN300&301 | 100Y240H | 0.00 | 45.60 | 45.60 | 0.0000 | 0 | 39.99 | 6.18 | 0.00 | 0.00 |
| GRND 301 | BASIN300&301 | SJRWMD | 0.00 | 45.60 | 45.60 | 0.0000 | 0 | 59.20 | 14.27 | 0.00 | 0.00 |
| SC-0800 | BASIN300&301 | 100Y240H | 11.00 | 52.00 | 52.00 | 0.0041 | 0 | 184.00 | 9.67 | 0.00 | 0.00 |
| SC-0800 | BASIN300&301 | SJRWMD | 11.00 | 52.00 | 52.00 | 0.0021 | 0 | 60.00 | 26.39 | 0.00 | 0.00 |
| SC-810 | BASIN300&301 | 100Y240H | 0.00 | 55.00 | 55.00 | 0.0000 | 0 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-810 | BASIN300&301 | SJRWMD | 0.00 | 55.00 | 55.00 | 0.0000 | 0 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-POND300 | BASIN300&301 | 100Y240H | 184.99 | 55.45 | 56.00 | 0.0031 | 127013 | 183.91 | 18.93 | 184.99 | 6.62 |
| SC-POND300 | BASIN300&301 | SJRWMD | 63.24 | 55.97 | 56.00 | 0.0021 | 129844 | 60.17 | 104.94 | 64.25 | 7.34 |
| SC-POND301 | BASIN300&301 | 100Y240H | 216.94 | 55.91 | 56.00 | 0.0023 | 147090 | 183.91 | 11.97 | 39.99 | 6.18 |
| SC-POND301 | BASIN300&301 | SJRWMD | 72.40 | 54.23 | 56.00 | 0.0013 | 136846 | 60.08 | 75.51 | 59.20 | 14.27 |

Proposed Discharge Rates:
Basin 300

Q-FDOT (100-yr/240-hr)= 9.67 cfs
Q-SJRWMD (25-yr/96-hr)= 26.39 cfs

Basin 301
Q-FDOT (100-yr/240-hr)= 0.00 cfs
Q-SJRWMD (25-yr/96-hr)= 0.00 cfs

Basin 301 (Pond 301)
SJRWMD Treatment/Wekiva Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | SC-POND301 | BASIN300&301 | 0.00 | 53.07 | 56.00 | 129800 | 0.000 | 0.000 | 0.00 | 0.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.02 | 53.06 | 56.00 | 129768 | 0.000 | 15.019 | 0.00 | 0.01 |
| PERC | SC-POND301 | BASIN300&301 | 0.03 | 53.06 | 56.00 | 129725 | 0.000 | 15.015 | 0.00 | 0.03 |
| PERC | SC-POND301 | BASIN300&301 | 0.05 | 53.05 | 56.00 | 129683 | 0.000 | 15.010 | 0.00 | 0.05 |
| PERC | SC-POND301 | BASIN300&301 | 0.07 | 53.04 | 56.00 | 129640 | 0.000 | 15.005 | 0.00 | 0.07 |
| PERC | SC-POND301 | BASIN300&301 | 0.08 | 53.04 | 56.00 | 129597 | 0.000 | 15.000 | 0.00 | 0.09 |
| PERC | SC-POND301 | BASIN300&301 | 0.10 | 53.03 | 56.00 | 129555 | 0.000 | 14.995 | 0.00 | 0.11 |
| PERC | SC-POND301 | BASIN300&301 | 0.12 | 53.02 | 56.00 | 129512 | 0.000 | 14.990 | 0.00 | 0.14 |
| PERC | SC-POND301 | BASIN300&301 | 0.13 | 53.02 | 56.00 | 129469 | 0.000 | 14.985 | 0.00 | 0.16 |
| PERC | SC-POND301 | BASIN300&301 | 0.15 | 53.01 | 56.00 | 129426 | 0.000 | 14.980 | 0.00 | 0.18 |
| PERC | SC-POND301 | BASIN300&301 | 0.17 | 53.00 | 56.00 | 129384 | 0.000 | 14.975 | 0.00 | 0.20 |
| PERC | SC-POND301 | BASIN300&301 | 0.18 | 52.99 | 56.00 | 129341 | 0.000 | 14.970 | 0.00 | 0.22 |
| PERC | SC-POND301 | BASIN300&301 | 0.20 | 52.99 | 56.00 | 129298 | 0.000 | 14.965 | 0.00 | 0.24 |
| PERC | SC-POND301 | BASIN300&301 | 0.22 | 52.98 | 56.00 | 129256 | 0.000 | 14.960 | 0.00 | 0.26 |
| PERC | SC-POND301 | BASIN300&301 | 0.24 | 52.97 | 56.00 | 129213 | 0.000 | 14.955 | 0.00 | 0.28 |
| PERC | SC-POND301 | BASIN300&301 | 0.25 | 52.97 | 56.00 | 129170 | 0.000 | 14.950 | 0.00 | 0.30 |
| PERC | SC-POND301 | BASIN300&301 | 0.27 | 52.96 | 56.00 | 129128 | 0.000 | 14.945 | 0.00 | 0.32 |
| PERC | SC-POND301 | BASIN300&301 | 0.29 | 52.95 | 56.00 | 129085 | 0.000 | 14.940 | 0.00 | 0.34 |
| PERC | SC-POND301 | BASIN300&301 | 0.30 | 52.95 | 56.00 | 129042 | 0.000 | 14.935 | 0.00 | 0.36 |
| PERC | SC-POND301 | BASIN300&301 | 0.32 | 52.94 | 56.00 | 128999 | 0.000 | 14.930 | 0.00 | 0.38 |
| PERC | SC-POND301 | BASIN300&301 | 0.34 | 52.93 | 56.00 | 128957 | 0.000 | 14.926 | 0.00 | 0.41 |
| PERC | SC-POND301 | BASIN300&301 | 0.35 | 52.92 | 56.00 | 128914 | 0.000 | 14.921 | 0.00 | 0.43 |
| PERC | SC-POND301 | BASIN300&301 | 0.37 | 52.92 | 56.00 | 128871 | 0.000 | 14.916 | 0.00 | 0.45 |
| PERC | SC-POND301 | BASIN300&301 | 0.39 | 52.91 | 56.00 | 128829 | 0.000 | 14.911 | 0.00 | 0.47 |
| PERC | SC-POND301 | BASIN300&301 | 0.40 | 52.90 | 56.00 | 128786 | 0.000 | 14.906 | 0.00 | 0.49 |
| PERC | SC-POND301 | BASIN300&301 | 0.42 | 52.90 | 56.00 | 128743 | 0.000 | 14.901 | 0.00 | 0.51 |
| PERC | SC-POND301 | BASIN300&301 | 0.44 | 52.89 | 56.00 | 128700 | 0.000 | 14.896 | 0.00 | 0.53 |
| PERC | SC-POND301 | BASIN300&301 | 0.45 | 52.88 | 56.00 | 128658 | 0.000 | 14.891 | 0.00 | 0.55 |
| PERC | SC-POND301 | BASIN300&301 | 0.47 | 52.88 | 56.00 | 128615 | 0.000 | 14.886 | 0.00 | 0.57 |
| PERC | SC-POND301 | BASIN300&301 | 0.49 | 52.87 | 56.00 | 128572 | 0.000 | 14.881 | 0.00 | 0.59 |
| PERC | SC-POND301 | BASIN300&301 | 0.50 | 52.86 | 56.00 | 128530 | 0.000 | 14.876 | 0.00 | 0.61 |
| PERC | SC-POND301 | BASIN300&301 | 0.52 | 52.85 | 56.00 | 128487 | 0.000 | 14.871 | 0.00 | 0.63 |
| PERC | SC-POND301 | BASIN300&301 | 0.54 | 52.85 | 56.00 | 128444 | 0.000 | 14.866 | 0.00 | 0.65 |
| PERC | SC-POND301 | BASIN300&301 | 0.55 | 52.84 | 56.00 | 128402 | 0.000 | 14.861 | 0.00 | 0.67 |
| PERC | SC-POND301 | BASIN300&301 | 0.57 | 52.83 | 56.00 | 128359 | 0.000 | 14.856 | 0.00 | 0.70 |
| PERC | SC-POND301 | BASIN300&301 | 0.59 | 52.83 | 56.00 | 128316 | 0.000 | 14.851 | 0.00 | 0.72 |
| PERC | SC-POND301 | BASIN300&301 | 0.61 | 52.82 | 56.00 | 128273 | 0.000 | 14.846 | 0.00 | 0.74 |
| PERC | SC-POND301 | BASIN300&301 | 0.62 | 52.81 | 56.00 | 128231 | 0.000 | 14.842 | 0.00 | 0.76 |
| PERC | SC-POND301 | BASIN300&301 | 0.64 | 52.81 | 56.00 | 128188 | 0.000 | 14.837 | 0.00 | 0.78 |
| PERC | SC-POND301 | BASIN300&301 | 0.66 | 52.80 | 56.00 | 128145 | 0.000 | 14.832 | 0.00 | 0.80 |
| PERC | SC-POND301 | BASIN300&301 | 0.67 | 52.79 | 56.00 | 128103 | 0.000 | 14.827 | 0.00 | 0.82 |
| PERC | SC-POND301 | BASIN300&301 | 0.69 | 52.78 | 56.00 | 128060 | 0.000 | 14.822 | 0.00 | 0.84 |
| PERC | SC-POND301 | BASIN300&301 | 0.71 | 52.78 | 56.00 | 128017 | 0.000 | 14.817 | 0.00 | 0.86 |
| PERC | SC-POND301 | BASIN300&301 | 0.72 | 52.77 | 56.00 | 127975 | 0.000 | 14.812 | 0.00 | 0.88 |
| PERC | SC-POND301 | BASIN300&301 | 0.74 | 52.76 | 56.00 | 127932 | 0.000 | 14.807 | 0.00 | 0.90 |
| PERC | SC-POND301 | BASIN300&301 | 0.76 | 52.76 | 56.00 | 127889 | 0.000 | 14.802 | 0.00 | 0.92 |
| PERC | SC-POND301 | BASIN300&301 | 0.77 | 52.75 | 56.00 | 127846 | 0.000 | 14.797 | 0.00 | 0.94 |
| PERC | SC-POND301 | BASIN300&301 | 0.79 | 52.74 | 56.00 | 127804 | 0.000 | 14.792 | 0.00 | 0.96 |
| PERC | SC-POND301 | BASIN300&301 | 0.81 | 52.74 | 56.00 | 127761 | 0.000 | 14.787 | 0.00 | 0.98 |
| PERC | SC-POND301 | BASIN300&301 | 0.82 | 52.73 | 56.00 | 127718 | 0.000 | 14.782 | 0.00 | 1.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.84 | 52.72 | 56.00 | 127676 | 0.000 | 14.777 | 0.00 | 1.02 |
| PERC | SC-POND301 | BASIN300&301 | 0.86 | 52.71 | 56.00 | 127633 | 0.000 | 14.772 | 0.00 | 1.04 |
| PERC | SC-POND301 | BASIN300&301 | 0.87 | 52.71 | 56.00 | 127590 | 0.000 | 14.767 | 0.00 | 1.07 |
| PERC | SC-POND301 | BASIN300&301 | 0.89 | 52.70 | 56.00 | 127548 | 0.000 | 14.762 | 0.00 | 1.09 |
| PERC | SC-POND301 | BASIN300&301 | 0.91 | 52.69 | 56.00 | 127505 | 0.000 | 14.758 | 0.00 | 1.11 |
| PERC | SC-POND301 | BASIN300&301 | 0.92 | 52.69 | 56.00 | 127462 | 0.000 | 14.753 | 0.00 | 1.13 |
| PERC | SC-POND301 | BASIN300&301 | 0.94 | 52.68 | 56.00 | 127419 | 0.000 | 14.748 | 0.00 | 1.15 |
| PERC | SC-POND301 | BASIN300&301 | 0.96 | 52.67 | 56.00 | 127377 | 0.000 | 14.743 | 0.00 | 1.17 |
| PERC | SC-POND301 | BASIN300&301 | 0.97 | 52.67 | 56.00 | 127334 | 0.000 | 14.738 | 0.00 | 1.19 |
| PERC | SC-POND301 | BASIN300&301 | 0.99 | 52.66 | 56.00 | 127291 | 0.000 | 14.733 | 0.00 | 1.21 |
| PERC | SC-POND301 | BASIN300&301 | 1.01 | 52.65 | 56.00 | 127249 | 0.000 | 14.728 | 0.00 | 1.23 |
| PERC | SC-POND301 | BASIN300&301 | 1.02 | 52.65 | 56.00 | 127227 | 0.000 | 14.725 | 0.00 | 1.24 |
| PERC | SC-POND301 | BASIN300&301 | 1.03 | 52.64 | 56.00 | 127185 | 0.000 | 14.720 | 0.00 | 1.26 |
| PERC | SC-POND301 | BASIN300&301 | 1.05 | 52.63 | 56.00 | 127142 | 0.000 | 14.715 | 0.00 | 1.28 |
| PERC | SC-POND301 | BASIN300&301 | 1.07 | 52.63 | 56.00 | 127099 | 0.000 | 14.711 | 0.00 | 1.30 |
| PERC | SC-POND301 | BASIN300&301 | 1.08 | 52.62 | 56.00 | 127056 | 0.000 | 14.706 | 0.00 | 1.32 |
| PERC | SC-POND301 | BASIN300&301 | 1.10 | 52.61 | 56.00 | 127014 | 0.000 | 14.701 | 0.00 | 1.34 |
| PERC | SC-POND301 | BASIN300&301 | 1.12 | 52.61 | 56.00 | 126971 | 0.000 | 14.696 | 0.00 | 1.36 |
| PERC | SC-POND301 | BASIN300&301 | 1.13 | 52.60 | 56.00 | 126928 | 0.000 | 14.691 | 0.00 | 1.38 |
| PERC | SC-POND301 | BASIN300&301 | 1.15 | 52.59 | 56.00 | 126886 | 0.000 | 14.686 | 0.00 | 1.40 |
| PERC | SC-POND301 | BASIN300&301 | 1.17 | 52.59 | 56.00 | 126843 | 0.000 | 14.681 | 0.00 | 1.42 |
| PERC | SC-POND301 | BASIN300&301 | 1.18 | 52.58 | 56.00 | 126800 | 0.000 | 14.676 | 0.00 | 1.44 |
| PERC | SC-POND301 | BASIN300&301 | 1.20 | 52.57 | 56.00 | 126758 | 0.000 | 14.671 | 0.00 | 1.46 |
| PERC | SC-POND301 | BASIN300&301 | 1.22 | 52.56 | 56.00 | 126715 | 0.000 | 14.666 | 0.00 | 1.48 |
| PERC | SC-POND301 | BASIN300&301 | 1.24 | 52.56 | 56.00 | 126672 | 0.000 | 14.661 | 0.00 | 1.50 |
| PERC | SC-POND301 | BASIN300&301 | 1.25 | 52.55 | 56.00 | 126629 | 0.000 | 14.656 | 0.00 | 1.53 |
| PERC | SC-POND301 | BASIN300&301 | 1.27 | 52.54 | 56.00 | 126587 | 0.000 | 14.651 | 0.00 | 1.55 |
| PERC | SC-POND301 | BASIN300&301 | 1.29 | 52.54 | 56.00 | 126544 | 0.000 | 14.646 | 0.00 | 1.57 |
| PERC | SC-POND301 | BASIN300&301 | 1.30 | 52.53 | 56.00 | 126501 | 0.000 | 14.641 | 0.00 | 1.59 |
| PERC | SC-POND301 | BASIN300&301 | 1.32 | 52.52 | 56.00 | 126459 | 0.000 | 14.636 | 0.00 | 1.61 |
| PERC | SC-POND301 | BASIN300&301 | 1.34 | 52.52 | 56.00 | 126416 | 0.000 | 14.631 | 0.00 | 1.63 |

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| PERC | SC-POND301 | BASIN300&301 | 1.35 | 52.51 | 56.00 | 126373 | 0.000 | 14.627 | 0.00 | 1.65 |
| PERC | SC-POND301 | BASIN300&301 | 1.37 | 52.50 | 56.00 | 126330 | 0.000 | 14.622 | 0.00 | 1.67 |
| PERC | SC-POND301 | BASIN300&301 | 1.39 | 52.49 | 56.00 | 126288 | 0.000 | 14.617 | 0.00 | 1.69 |
| PERC | SC-POND301 | BASIN300&301 | 1.40 | 52.49 | 56.00 | 126245 | 0.000 | 14.612 | 0.00 | 1.71 |
| PERC | SC-POND301 | BASIN300&301 | 1.42 | 52.48 | 56.00 | 126202 | 0.000 | 14.607 | 0.00 | 1.73 |
| PERC | SC-POND301 | BASIN300&301 | 1.44 | 52.47 | 56.00 | 126160 | 0.000 | 14.602 | 0.00 | 1.75 |
| PERC | SC-POND301 | BASIN300&301 | 1.45 | 52.47 | 56.00 | 126117 | 0.000 | 14.597 | 0.00 | 1.77 |
| PERC | SC-POND301 | BASIN300&301 | 1.47 | 52.46 | 56.00 | 126074 | 0.000 | 14.592 | 0.00 | 1.79 |
| PERC | SC-POND301 | BASIN300&301 | 1.49 | 52.45 | 56.00 | 126032 | 0.000 | 14.587 | 0.00 | 1.81 |
| PERC | SC-POND301 | BASIN300&301 | 1.50 | 52.45 | 56.00 | 125989 | 0.000 | 14.582 | 0.00 | 1.83 |
| PERC | SC-POND301 | BASIN300&301 | 1.52 | 52.44 | 56.00 | 125946 | 0.000 | 14.577 | 0.00 | 1.85 |
| PERC | SC-POND301 | BASIN300&301 | 1.54 | 52.43 | 56.00 | 125903 | 0.000 | 14.572 | 0.00 | 1.87 |
| PERC | SC-POND301 | BASIN300&301 | 1.55 | 52.42 | 56.00 | 125861 | 0.000 | 14.567 | 0.00 | 1.89 |
| PERC | SC-POND301 | BASIN300&301 | 1.57 | 52.42 | 56.00 | 125818 | 0.000 | 14.562 | 0.00 | 1.91 |
| PERC | SC-POND301 | BASIN300&301 | 1.59 | 52.41 | 56.00 | 125775 | 0.000 | 14.557 | 0.00 | 1.93 |
| PERC | SC-POND301 | BASIN300&301 | 1.60 | 52.40 | 56.00 | 125733 | 0.000 | 14.552 | 0.00 | 1.95 |
| PERC | SC-POND301 | BASIN300&301 | 1.62 | 52.40 | 56.00 | 125690 | 0.000 | 14.547 | 0.00 | 1.97 |
| PERC | SC-POND301 | BASIN300&301 | 1.64 | 52.39 | 56.00 | 125647 | 0.000 | 14.543 | 0.00 | 1.99 |
| PERC | SC-POND301 | BASIN300&301 | 1.66 | 52.38 | 56.00 | 125605 | 0.000 | 14.538 | 0.00 | 2.01 |
| PERC | SC-POND301 | BASIN300&301 | 1.67 | 52.38 | 56.00 | 125562 | 0.000 | 14.533 | 0.00 | 2.03 |
| PERC | SC-POND301 | BASIN300&301 | 1.69 | 52.37 | 56.00 | 125519 | 0.000 | 14.528 | 0.00 | 2.05 |
| PERC | SC-POND301 | BASIN300&301 | 1.71 | 52.36 | 56.00 | 125476 | 0.000 | 14.523 | 0.00 | 2.07 |
| PERC | SC-POND301 | BASIN300&301 | 1.72 | 52.35 | 56.00 | 125434 | 0.000 | 14.518 | 0.00 | 2.09 |
| PERC | SC-POND301 | BASIN300&301 | 1.74 | 52.35 | 56.00 | 125391 | 0.000 | 14.513 | 0.00 | 2.11 |
| PERC | SC-POND301 | BASIN300&301 | 1.76 | 52.34 | 56.00 | 125348 | 0.000 | 14.508 | 0.00 | 2.13 |
| PERC | SC-POND301 | BASIN300&301 | 1.77 | 52.33 | 56.00 | 125306 | 0.000 | 14.503 | 0.00 | 2.15 |
| PERC | SC-POND301 | BASIN300&301 | 1.79 | 52.33 | 56.00 | 125263 | 0.000 | 14.498 | 0.00 | 2.17 |
| PERC | SC-POND301 | BASIN300&301 | 1.81 | 52.32 | 56.00 | 125220 | 0.000 | 14.493 | 0.00 | 2.19 |
| PERC | SC-POND301 | BASIN300&301 | 1.82 | 52.31 | 56.00 | 125177 | 0.000 | 14.488 | 0.00 | 2.21 |
| PERC | SC-POND301 | BASIN300&301 | 1.84 | 52.30 | 56.00 | 125135 | 0.000 | 14.483 | 0.00 | 2.23 |
| PERC | SC-POND301 | BASIN300&301 | 1.86 | 52.30 | 56.00 | 125092 | 0.000 | 14.478 | 0.00 | 2.25 |
| PERC | SC-POND301 | BASIN300&301 | 1.87 | 52.29 | 56.00 | 125049 | 0.000 | 14.473 | 0.00 | 2.27 |
| PERC | SC-POND301 | BASIN300&301 | 1.89 | 52.28 | 56.00 | 125007 | 0.000 | 14.468 | 0.00 | 2.29 |
| PERC | SC-POND301 | BASIN300&301 | 1.91 | 52.28 | 56.00 | 124964 | 0.000 | 14.463 | 0.00 | 2.31 |
| PERC | SC-POND301 | BASIN300&301 | 1.92 | 52.27 | 56.00 | 124921 | 0.000 | 14.458 | 0.00 | 2.33 |
| PERC | SC-POND301 | BASIN300&301 | 1.94 | 52.26 | 56.00 | 124879 | 0.000 | 14.454 | 0.00 | 2.35 |
| PERC | SC-POND301 | BASIN300&301 | 1.96 | 52.26 | 56.00 | 124836 | 0.000 | 14.449 | 0.00 | 2.37 |
| PERC | SC-POND301 | BASIN300&301 | 1.97 | 52.25 | 56.00 | 124793 | 0.000 | 14.444 | 0.00 | 2.39 |
| PERC | SC-POND301 | BASIN300&301 | 1.99 | 52.24 | 56.00 | 124750 | 0.000 | 14.439 | 0.00 | 2.41 |
| PERC | SC-POND301 | BASIN300&301 | 2.01 | 52.23 | 56.00 | 124708 | 0.000 | 14.434 | 0.00 | 2.43 |
| PERC | SC-POND301 | BASIN300&301 | 2.02 | 52.23 | 56.00 | 124686 | 0.000 | 14.431 | 0.00 | 2.44 |
| PERC | SC-POND301 | BASIN300&301 | 2.03 | 52.22 | 56.00 | 124644 | 0.000 | 14.426 | 0.00 | 2.46 |
| PERC | SC-POND301 | BASIN300&301 | 2.05 | 52.22 | 56.00 | 124601 | 0.000 | 14.421 | 0.00 | 2.48 |
| PERC | SC-POND301 | BASIN300&301 | 2.07 | 52.21 | 56.00 | 124558 | 0.000 | 14.416 | 0.00 | 2.50 |
| PERC | SC-POND301 | BASIN300&301 | 2.08 | 52.20 | 56.00 | 124516 | 0.000 | 14.412 | 0.00 | 2.52 |
| PERC | SC-POND301 | BASIN300&301 | 2.10 | 52.20 | 56.00 | 124473 | 0.000 | 14.407 | 0.00 | 2.54 |
| PERC | SC-POND301 | BASIN300&301 | 2.12 | 52.19 | 56.00 | 124430 | 0.000 | 14.402 | 0.00 | 2.56 |
| PERC | SC-POND301 | BASIN300&301 | 2.13 | 52.18 | 56.00 | 124387 | 0.000 | 14.397 | 0.00 | 2.58 |
| PERC | SC-POND301 | BASIN300&301 | 2.15 | 52.18 | 56.00 | 124345 | 0.000 | 14.392 | 0.00 | 2.60 |
| PERC | SC-POND301 | BASIN300&301 | 2.17 | 52.17 | 56.00 | 124302 | 0.000 | 14.387 | 0.00 | 2.62 |
| PERC | SC-POND301 | BASIN300&301 | 2.18 | 52.16 | 56.00 | 124259 | 0.000 | 14.382 | 0.00 | 2.64 |
| PERC | SC-POND301 | BASIN300&301 | 2.20 | 52.15 | 56.00 | 124217 | 0.000 | 14.377 | 0.00 | 2.66 |
| PERC | SC-POND301 | BASIN300&301 | 2.22 | 52.15 | 56.00 | 124174 | 0.000 | 14.372 | 0.00 | 2.68 |
| PERC | SC-POND301 | BASIN300&301 | 2.24 | 52.14 | 56.00 | 124131 | 0.000 | 14.367 | 0.00 | 2.70 |
| PERC | SC-POND301 | BASIN300&301 | 2.25 | 52.13 | 56.00 | 124089 | 0.000 | 14.362 | 0.00 | 2.72 |
| PERC | SC-POND301 | BASIN300&301 | 2.27 | 52.13 | 56.00 | 124046 | 0.000 | 14.357 | 0.00 | 2.74 |
| PERC | SC-POND301 | BASIN300&301 | 2.29 | 52.12 | 56.00 | 124003 | 0.000 | 14.352 | 0.00 | 2.76 |
| PERC | SC-POND301 | BASIN300&301 | 2.30 | 52.11 | 56.00 | 123960 | 0.000 | 14.347 | 0.00 | 2.78 |
| PERC | SC-POND301 | BASIN300&301 | 2.32 | 52.11 | 56.00 | 123918 | 0.000 | 14.342 | 0.00 | 2.80 |
| PERC | SC-POND301 | BASIN300&301 | 2.34 | 52.10 | 56.00 | 123875 | 0.000 | 14.337 | 0.00 | 2.82 |
| PERC | SC-POND301 | BASIN300&301 | 2.35 | 52.09 | 56.00 | 123832 | 0.000 | 14.332 | 0.00 | 2.84 |
| PERC | SC-POND301 | BASIN300&301 | 2.37 | 52.08 | 56.00 | 123790 | 0.000 | 14.328 | 0.00 | 2.86 |
| PERC | SC-POND301 | BASIN300&301 | 2.39 | 52.08 | 56.00 | 123747 | 0.000 | 14.323 | 0.00 | 2.88 |
| PERC | SC-POND301 | BASIN300&301 | 2.40 | 52.07 | 56.00 | 123704 | 0.000 | 14.318 | 0.00 | 2.90 |
| PERC | SC-POND301 | BASIN300&301 | 2.42 | 52.06 | 56.00 | 123662 | 0.000 | 14.313 | 0.00 | 2.92 |
| PERC | SC-POND301 | BASIN300&301 | 2.44 | 52.06 | 56.00 | 123619 | 0.000 | 14.308 | 0.00 | 2.94 |
| PERC | SC-POND301 | BASIN300&301 | 2.45 | 52.05 | 56.00 | 123576 | 0.000 | 14.303 | 0.00 | 2.96 |
| PERC | SC-POND301 | BASIN300&301 | 2.47 | 52.04 | 56.00 | 123533 | 0.000 | 14.298 | 0.00 | 2.98 |
| PERC | SC-POND301 | BASIN300&301 | 2.49 | 52.04 | 56.00 | 123491 | 0.000 | 14.293 | 0.00 | 3.00 |
| PERC | SC-POND301 | BASIN300&301 | 2.50 | 52.03 | 56.00 | 123448 | 0.000 | 14.288 | 0.00 | 3.02 |
| PERC | SC-POND301 | BASIN300&301 | 2.52 | 52.02 | 56.00 | 123405 | 0.000 | 14.283 | 0.00 | 3.04 |
| PERC | SC-POND301 | BASIN300&301 | 2.54 | 52.01 | 56.00 | 123363 | 0.000 | 14.278 | 0.00 | 3.06 |
| PERC | SC-POND301 | BASIN300&301 | 2.55 | 52.01 | 56.00 | 123320 | 0.000 | 14.273 | 0.00 | 3.08 |
| PERC | SC-POND301 | BASIN300&301 | 2.57 | 52.00 | 56.00 | 123277 | 0.000 | 3.231 | 0.00 | 3.09 |
| PERC | SC-POND301 | BASIN300&301 | 2.59 | 52.00 | 56.00 | 123275 | 0.000 | 0.000 | 0.00 | 3.10 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | SC-POND301 | BASIN300&301 | 0.00 | 55.30 | 56.00 | 143400 | 0.000 | 0.000 | 0.00 | 0.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.02 | 55.29 | 56.00 | 143367 | 0.000 | 16.593 | 0.00 | 0.01 |
| PERC | SC-POND301 | BASIN300&301 | 0.03 | 55.29 | 56.00 | 143325 | 0.000 | 16.589 | 0.00 | 0.03 |
| PERC | SC-POND301 | BASIN300&301 | 0.05 | 55.28 | 56.00 | 143282 | 0.000 | 16.584 | 0.00 | 0.06 |
| PERC | SC-POND301 | BASIN300&301 | 0.07 | 55.27 | 56.00 | 143239 | 0.000 | 16.579 | 0.00 | 0.08 |
| PERC | SC-POND301 | BASIN300&301 | 0.08 | 55.27 | 56.00 | 143197 | 0.000 | 16.574 | 0.00 | 0.10 |
| PERC | SC-POND301 | BASIN300&301 | 0.10 | 55.26 | 56.00 | 143154 | 0.000 | 16.569 | 0.00 | 0.13 |
| PERC | SC-POND301 | BASIN300&301 | 0.12 | 55.25 | 56.00 | 143111 | 0.000 | 16.564 | 0.00 | 0.15 |
| PERC | SC-POND301 | BASIN300&301 | 0.13 | 55.25 | 56.00 | 143069 | 0.000 | 16.559 | 0.00 | 0.17 |
| PERC | SC-POND301 | BASIN300&301 | 0.15 | 55.24 | 56.00 | 143026 | 0.000 | 16.554 | 0.00 | 0.20 |
| PERC | SC-POND301 | BASIN300&301 | 0.17 | 55.23 | 56.00 | 142983 | 0.000 | 16.549 | 0.00 | 0.22 |
| PERC | SC-POND301 | BASIN300&301 | 0.18 | 55.22 | 56.00 | 142940 | 0.000 | 16.544 | 0.00 | 0.24 |
| PERC | SC-POND301 | BASIN300&301 | 0.20 | 55.22 | 56.00 | 142898 | 0.000 | 16.539 | 0.00 | 0.26 |
| PERC | SC-POND301 | BASIN300&301 | 0.22 | 55.21 | 56.00 | 142855 | 0.000 | 16.534 | 0.00 | 0.29 |
| PERC | SC-POND301 | BASIN300&301 | 0.24 | 55.20 | 56.00 | 142812 | 0.000 | 16.529 | 0.00 | 0.31 |
| PERC | SC-POND301 | BASIN300&301 | 0.25 | 55.20 | 56.00 | 142770 | 0.000 | 16.524 | 0.00 | 0.33 |
| PERC | SC-POND301 | BASIN300&301 | 0.27 | 55.19 | 56.00 | 142727 | 0.000 | 16.519 | 0.00 | 0.36 |
| PERC | SC-POND301 | BASIN300&301 | 0.29 | 55.18 | 56.00 | 142684 | 0.000 | 16.514 | 0.00 | 0.38 |
| PERC | SC-POND301 | BASIN300&301 | 0.30 | 55.18 | 56.00 | 142642 | 0.000 | 16.509 | 0.00 | 0.40 |
| PERC | SC-POND301 | BASIN300&301 | 0.32 | 55.17 | 56.00 | 142599 | 0.000 | 16.504 | 0.00 | 0.43 |
| PERC | SC-POND301 | BASIN300&301 | 0.34 | 55.16 | 56.00 | 142556 | 0.000 | 16.500 | 0.00 | 0.45 |
| PERC | SC-POND301 | BASIN300&301 | 0.35 | 55.15 | 56.00 | 142513 | 0.000 | 16.495 | 0.00 | 0.47 |
| PERC | SC-POND301 | BASIN300&301 | 0.37 | 55.15 | 56.00 | 142471 | 0.000 | 16.490 | 0.00 | 0.49 |
| PERC | SC-POND301 | BASIN300&301 | 0.39 | 55.14 | 56.00 | 142428 | 0.000 | 16.485 | 0.00 | 0.52 |
| PERC | SC-POND301 | BASIN300&301 | 0.40 | 55.13 | 56.00 | 142385 | 0.000 | 16.480 | 0.00 | 0.54 |
| PERC | SC-POND301 | BASIN300&301 | 0.42 | 55.13 | 56.00 | 142343 | 0.000 | 16.475 | 0.00 | 0.56 |
| PERC | SC-POND301 | BASIN300&301 | 0.44 | 55.12 | 56.00 | 142300 | 0.000 | 16.470 | 0.00 | 0.59 |
| PERC | SC-POND301 | BASIN300&301 | 0.45 | 55.11 | 56.00 | 142257 | 0.000 | 16.465 | 0.00 | 0.61 |
| PERC | SC-POND301 | BASIN300&301 | 0.47 | 55.11 | 56.00 | 142215 | 0.000 | 16.460 | 0.00 | 0.63 |
| PERC | SC-POND301 | BASIN300&301 | 0.49 | 55.10 | 56.00 | 142172 | 0.000 | 16.455 | 0.00 | 0.65 |
| PERC | SC-POND301 | BASIN300&301 | 0.50 | 55.09 | 56.00 | 142129 | 0.000 | 16.450 | 0.00 | 0.68 |
| PERC | SC-POND301 | BASIN300&301 | 0.52 | 55.08 | 56.00 | 142086 | 0.000 | 16.445 | 0.00 | 0.70 |
| PERC | SC-POND301 | BASIN300&301 | 0.54 | 55.08 | 56.00 | 142044 | 0.000 | 16.440 | 0.00 | 0.72 |
| PERC | SC-POND301 | BASIN300&301 | 0.55 | 55.07 | 56.00 | 142001 | 0.000 | 16.435 | 0.00 | 0.75 |
| PERC | SC-POND301 | BASIN300&301 | 0.57 | 55.06 | 56.00 | 141958 | 0.000 | 16.430 | 0.00 | 0.77 |
| PERC | SC-POND301 | BASIN300&301 | 0.59 | 55.06 | 56.00 | 141916 | 0.000 | 16.425 | 0.00 | 0.79 |
| PERC | SC-POND301 | BASIN300&301 | 0.61 | 55.05 | 56.00 | 141873 | 0.000 | 16.420 | 0.00 | 0.81 |
| PERC | SC-POND301 | BASIN300&301 | 0.62 | 55.04 | 56.00 | 141830 | 0.000 | 16.416 | 0.00 | 0.84 |
| PERC | SC-POND301 | BASIN300&301 | 0.64 | 55.04 | 56.00 | 141787 | 0.000 | 16.411 | 0.00 | 0.86 |
| PERC | SC-POND301 | BASIN300&301 | 0.66 | 55.03 | 56.00 | 141745 | 0.000 | 16.406 | 0.00 | 0.88 |
| PERC | SC-POND301 | BASIN300&301 | 0.67 | 55.02 | 56.00 | 141702 | 0.000 | 16.401 | 0.00 | 0.91 |
| PERC | SC-POND301 | BASIN300&301 | 0.69 | 55.01 | 56.00 | 141659 | 0.000 | 16.396 | 0.00 | 0.93 |
| PERC | SC-POND301 | BASIN300&301 | 0.71 | 55.01 | 56.00 | 141617 | 0.000 | 16.391 | 0.00 | 0.95 |
| PERC | SC-POND301 | BASIN300&301 | 0.72 | 55.00 | 56.00 | 141574 | 0.000 | 16.386 | 0.00 | 0.97 |
| PERC | SC-POND301 | BASIN300&301 | 0.74 | 54.99 | 56.00 | 141531 | 0.000 | 16.381 | 0.00 | 1.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.76 | 54.99 | 56.00 | 141489 | 0.000 | 16.376 | 0.00 | 1.02 |
| PERC | SC-POND301 | BASIN300&301 | 0.77 | 54.98 | 56.00 | 141446 | 0.000 | 16.371 | 0.00 | 1.04 |
| PERC | SC-POND301 | BASIN300&301 | 0.79 | 54.97 | 56.00 | 141403 | 0.000 | 16.366 | 0.00 | 1.06 |
| PERC | SC-POND301 | BASIN300&301 | 0.81 | 54.97 | 56.00 | 141360 | 0.000 | 16.361 | 0.00 | 1.09 |
| PERC | SC-POND301 | BASIN300&301 | 0.82 | 54.96 | 56.00 | 141318 | 0.000 | 16.356 | 0.00 | 1.11 |
| PERC | SC-POND301 | BASIN300&301 | 0.84 | 54.95 | 56.00 | 141275 | 0.000 | 16.351 | 0.00 | 1.13 |
| PERC | SC-POND301 | BASIN300&301 | 0.86 | 54.94 | 56.00 | 141232 | 0.000 | 16.346 | 0.00 | 1.16 |
| PERC | SC-POND301 | BASIN300&301 | 0.87 | 54.94 | 56.00 | 141190 | 0.000 | 16.341 | 0.00 | 1.18 |
| PERC | SC-POND301 | BASIN300&301 | 0.89 | 54.93 | 56.00 | 141147 | 0.000 | 16.336 | 0.00 | 1.20 |
| PERC | SC-POND301 | BASIN300&301 | 0.91 | 54.92 | 56.00 | 141104 | 0.000 | 16.332 | 0.00 | 1.22 |
| PERC | SC-POND301 | BASIN300&301 | 0.92 | 54.92 | 56.00 | 141062 | 0.000 | 16.327 | 0.00 | 1.25 |
| PERC | SC-POND301 | BASIN300&301 | 0.94 | 54.91 | 56.00 | 141019 | 0.000 | 16.322 | 0.00 | 1.27 |
| PERC | SC-POND301 | BASIN300&301 | 0.96 | 54.90 | 56.00 | 140976 | 0.000 | 16.317 | 0.00 | 1.29 |
| PERC | SC-POND301 | BASIN300&301 | 0.97 | 54.90 | 56.00 | 140933 | 0.000 | 16.312 | 0.00 | 1.31 |
| PERC | SC-POND301 | BASIN300&301 | 0.99 | 54.89 | 56.00 | 140891 | 0.000 | 16.307 | 0.00 | 1.34 |
| PERC | SC-POND301 | BASIN300&301 | 1.01 | 54.88 | 56.00 | 140848 | 0.000 | 16.302 | 0.00 | 1.36 |
| PERC | SC-POND301 | BASIN300&301 | 1.02 | 54.88 | 56.00 | 140827 | 0.000 | 16.299 | 0.00 | 1.37 |
| PERC | SC-POND301 | BASIN300&301 | 1.03 | 54.87 | 56.00 | 140784 | 0.000 | 16.294 | 0.00 | 1.39 |
| PERC | SC-POND301 | BASIN300&301 | 1.05 | 54.86 | 56.00 | 140741 | 0.000 | 16.289 | 0.00 | 1.42 |
| PERC | SC-POND301 | BASIN300&301 | 1.07 | 54.86 | 56.00 | 140699 | 0.000 | 16.285 | 0.00 | 1.44 |
| PERC | SC-POND301 | BASIN300&301 | 1.08 | 54.85 | 56.00 | 140656 | 0.000 | 16.280 | 0.00 | 1.46 |
| PERC | SC-POND301 | BASIN300&301 | 1.10 | 54.84 | 56.00 | 140613 | 0.000 | 16.275 | 0.00 | 1.48 |
| PERC | SC-POND301 | BASIN300&301 | 1.12 | 54.84 | 56.00 | 140570 | 0.000 | 16.270 | 0.00 | 1.51 |
| PERC | SC-POND301 | BASIN300&301 | 1.13 | 54.83 | 56.00 | 140528 | 0.000 | 16.265 | 0.00 | 1.53 |
| PERC | SC-POND301 | BASIN300&301 | 1.15 | 54.82 | 56.00 | 140485 | 0.000 | 16.260 | 0.00 | 1.55 |
| PERC | SC-POND301 | BASIN300&301 | 1.17 | 54.82 | 56.00 | 140442 | 0.000 | 16.255 | 0.00 | 1.57 |
| PERC | SC-POND301 | BASIN300&301 | 1.18 | 54.81 | 56.00 | 140400 | 0.000 | 16.250 | 0.00 | 1.60 |
| PERC | SC-POND301 | BASIN300&301 | 1.20 | 54.80 | 56.00 | 140357 | 0.000 | 16.245 | 0.00 | 1.62 |
| PERC | SC-POND301 | BASIN300&301 | 1.22 | 54.79 | 56.00 | 140314 | 0.000 | 16.240 | 0.00 | 1.64 |
| PERC | SC-POND301 | BASIN300&301 | 1.24 | 54.79 | 56.00 | 140272 | 0.000 | 16.235 | 0.00 | 1.66 |
| PERC | SC-POND301 | BASIN300&301 | 1.25 | 54.78 | 56.00 | 140229 | 0.000 | 16.230 | 0.00 | 1.69 |
| PERC | SC-POND301 | BASIN300&301 | 1.27 | 54.77 | 56.00 | 140186 | 0.000 | 16.225 | 0.00 | 1.71 |
| PERC | SC-POND301 | BASIN300&301 | 1.29 | 54.77 | 56.00 | 140143 | 0.000 | 16.220 | 0.00 | 1.73 |
| PERC | SC-POND301 | BASIN300&301 | 1.30 | 54.76 | 56.00 | 140101 | 0.000 | 16.215 | 0.00 | 1.75 |
| PERC | SC-POND301 | BASIN300&301 | 1.32 | 54.75 | 56.00 | 140058 | 0.000 | 16.210 | 0.00 | 1.78 |
| PERC | SC-POND301 | BASIN300&301 | 1.34 | 54.75 | 56.00 | 140015 | 0.000 | 16.205 | 0.00 | 1.80 |

Basin 300 & 301 (Pond 301)
SJRWMD Closed Basin Recovery
14-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | SC-POND301 | BASIN300&301 | 81.00 | 52.00 | 56.00 | 123295 | 0.000 | 0.321 | 0.00 | 10.08 |
| PERC | SC-POND301 | BASIN300&301 | 81.02 | 52.00 | 56.00 | 123294 | 0.000 | 0.321 | 0.00 | 10.08 |
| PERC | SC-POND301 | BASIN300&301 | 81.04 | 52.00 | 56.00 | 123293 | 0.000 | 0.321 | 0.00 | 10.08 |
| PERC | SC-POND301 | BASIN300&301 | 81.05 | 52.00 | 56.00 | 123292 | 0.000 | 0.321 | 0.00 | 10.08 |
| PERC | SC-POND301 | BASIN300&301 | 81.07 | 52.00 | 56.00 | 123291 | 0.000 | 0.321 | 0.00 | 10.08 |
| PERC | SC-POND301 | BASIN300&301 | 81.09 | 52.00 | 56.00 | 123290 | 0.000 | 0.321 | 0.00 | 10.09 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | SC-POND301 | BASIN300&301 | 0.00 | 55.98 | 56.00 | 147546 | 0.000 | 0.000 | 0.00 | 0.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.02 | 55.97 | 56.00 | 147514 | 0.000 | 17.073 | 0.00 | 0.01 |
| PERC | SC-POND301 | BASIN300&301 | 0.03 | 55.97 | 56.00 | 147472 | 0.000 | 17.068 | 0.00 | 0.04 |
| PERC | SC-POND301 | BASIN300&301 | 0.05 | 55.96 | 56.00 | 147429 | 0.000 | 17.064 | 0.00 | 0.06 |
| PERC | SC-POND301 | BASIN300&301 | 0.07 | 55.95 | 56.00 | 147386 | 0.000 | 17.059 | 0.00 | 0.08 |
| PERC | SC-POND301 | BASIN300&301 | 0.08 | 55.95 | 56.00 | 147344 | 0.000 | 17.054 | 0.00 | 0.11 |
| PERC | SC-POND301 | BASIN300&301 | 0.10 | 55.94 | 56.00 | 147301 | 0.000 | 17.049 | 0.00 | 0.13 |
| PERC | SC-POND301 | BASIN300&301 | 0.12 | 55.93 | 56.00 | 147258 | 0.000 | 17.044 | 0.00 | 0.15 |
| PERC | SC-POND301 | BASIN300&301 | 0.13 | 55.93 | 56.00 | 147215 | 0.000 | 17.039 | 0.00 | 0.18 |
| PERC | SC-POND301 | BASIN300&301 | 0.15 | 55.92 | 56.00 | 147173 | 0.000 | 17.034 | 0.00 | 0.20 |
| PERC | SC-POND301 | BASIN300&301 | 0.17 | 55.91 | 56.00 | 147130 | 0.000 | 17.029 | 0.00 | 0.22 |
| PERC | SC-POND301 | BASIN300&301 | 0.18 | 55.90 | 56.00 | 147087 | 0.000 | 17.024 | 0.00 | 0.25 |
| PERC | SC-POND301 | BASIN300&301 | 0.20 | 55.90 | 56.00 | 147045 | 0.000 | 17.019 | 0.00 | 0.27 |
| PERC | SC-POND301 | BASIN300&301 | 0.22 | 55.89 | 56.00 | 147002 | 0.000 | 17.014 | 0.00 | 0.30 |
| PERC | SC-POND301 | BASIN300&301 | 0.24 | 55.88 | 56.00 | 146959 | 0.000 | 17.009 | 0.00 | 0.32 |
| PERC | SC-POND301 | BASIN300&301 | 0.25 | 55.88 | 56.00 | 146917 | 0.000 | 17.004 | 0.00 | 0.34 |
| PERC | SC-POND301 | BASIN300&301 | 0.27 | 55.87 | 56.00 | 146874 | 0.000 | 16.999 | 0.00 | 0.37 |
| PERC | SC-POND301 | BASIN300&301 | 0.29 | 55.86 | 56.00 | 146831 | 0.000 | 16.994 | 0.00 | 0.39 |
| PERC | SC-POND301 | BASIN300&301 | 0.30 | 55.86 | 56.00 | 146788 | 0.000 | 16.989 | 0.00 | 0.41 |
| PERC | SC-POND301 | BASIN300&301 | 0.32 | 55.85 | 56.00 | 146746 | 0.000 | 16.984 | 0.00 | 0.44 |
| PERC | SC-POND301 | BASIN300&301 | 0.34 | 55.84 | 56.00 | 146703 | 0.000 | 16.980 | 0.00 | 0.46 |
| PERC | SC-POND301 | BASIN300&301 | 0.35 | 55.83 | 56.00 | 146660 | 0.000 | 16.975 | 0.00 | 0.48 |
| PERC | SC-POND301 | BASIN300&301 | 0.37 | 55.83 | 56.00 | 146618 | 0.000 | 16.970 | 0.00 | 0.51 |
| PERC | SC-POND301 | BASIN300&301 | 0.39 | 55.82 | 56.00 | 146575 | 0.000 | 16.965 | 0.00 | 0.53 |
| PERC | SC-POND301 | BASIN300&301 | 0.40 | 55.81 | 56.00 | 146532 | 0.000 | 16.960 | 0.00 | 0.56 |
| PERC | SC-POND301 | BASIN300&301 | 0.42 | 55.81 | 56.00 | 146490 | 0.000 | 16.955 | 0.00 | 0.58 |
| PERC | SC-POND301 | BASIN300&301 | 0.44 | 55.80 | 56.00 | 146447 | 0.000 | 16.950 | 0.00 | 0.60 |
| PERC | SC-POND301 | BASIN300&301 | 0.45 | 55.79 | 56.00 | 146404 | 0.000 | 16.945 | 0.00 | 0.63 |
| PERC | SC-POND301 | BASIN300&301 | 0.47 | 55.79 | 56.00 | 146361 | 0.000 | 16.940 | 0.00 | 0.65 |
| PERC | SC-POND301 | BASIN300&301 | 0.49 | 55.78 | 56.00 | 146319 | 0.000 | 16.935 | 0.00 | 0.67 |
| PERC | SC-POND301 | BASIN300&301 | 0.50 | 55.77 | 56.00 | 146276 | 0.000 | 16.930 | 0.00 | 0.70 |
| PERC | SC-POND301 | BASIN300&301 | 0.52 | 55.76 | 56.00 | 146233 | 0.000 | 16.925 | 0.00 | 0.72 |
| PERC | SC-POND301 | BASIN300&301 | 0.54 | 55.76 | 56.00 | 146191 | 0.000 | 16.920 | 0.00 | 0.74 |
| PERC | SC-POND301 | BASIN300&301 | 0.55 | 55.75 | 56.00 | 146148 | 0.000 | 16.915 | 0.00 | 0.77 |
| PERC | SC-POND301 | BASIN300&301 | 0.57 | 55.74 | 56.00 | 146105 | 0.000 | 16.910 | 0.00 | 0.79 |
| PERC | SC-POND301 | BASIN300&301 | 0.59 | 55.74 | 56.00 | 146063 | 0.000 | 16.905 | 0.00 | 0.81 |
| PERC | SC-POND301 | BASIN300&301 | 0.61 | 55.73 | 56.00 | 146020 | 0.000 | 16.900 | 0.00 | 0.84 |
| PERC | SC-POND301 | BASIN300&301 | 0.62 | 55.72 | 56.00 | 145977 | 0.000 | 16.895 | 0.00 | 0.86 |
| PERC | SC-POND301 | BASIN300&301 | 0.64 | 55.72 | 56.00 | 145934 | 0.000 | 16.891 | 0.00 | 0.88 |
| PERC | SC-POND301 | BASIN300&301 | 0.66 | 55.71 | 56.00 | 145892 | 0.000 | 16.886 | 0.00 | 0.91 |
| PERC | SC-POND301 | BASIN300&301 | 0.67 | 55.70 | 56.00 | 145849 | 0.000 | 16.881 | 0.00 | 0.93 |
| PERC | SC-POND301 | BASIN300&301 | 0.69 | 55.69 | 56.00 | 145806 | 0.000 | 16.876 | 0.00 | 0.95 |
| PERC | SC-POND301 | BASIN300&301 | 0.71 | 55.69 | 56.00 | 145764 | 0.000 | 16.871 | 0.00 | 0.98 |
| PERC | SC-POND301 | BASIN300&301 | 0.72 | 55.68 | 56.00 | 145721 | 0.000 | 16.866 | 0.00 | 1.00 |
| PERC | SC-POND301 | BASIN300&301 | 0.74 | 55.67 | 56.00 | 145678 | 0.000 | 16.861 | 0.00 | 1.03 |
| PERC | SC-POND301 | BASIN300&301 | 0.76 | 55.67 | 56.00 | 145635 | 0.000 | 16.856 | 0.00 | 1.05 |
| PERC | SC-POND301 | BASIN300&301 | 0.77 | 55.66 | 56.00 | 145593 | 0.000 | 16.851 | 0.00 | 1.07 |
| PERC | SC-POND301 | BASIN300&301 | 0.79 | 55.65 | 56.00 | 145550 | 0.000 | 16.846 | 0.00 | 1.10 |
| PERC | SC-POND301 | BASIN300&301 | 0.81 | 55.65 | 56.00 | 145507 | 0.000 | 16.841 | 0.00 | 1.12 |
| PERC | SC-POND301 | BASIN300&301 | 0.82 | 55.64 | 56.00 | 145465 | 0.000 | 16.836 | 0.00 | 1.14 |
| PERC | SC-POND301 | BASIN300&301 | 0.84 | 55.63 | 56.00 | 145422 | 0.000 | 16.831 | 0.00 | 1.17 |
| PERC | SC-POND301 | BASIN300&301 | 0.86 | 55.62 | 56.00 | 145379 | 0.000 | 16.826 | 0.00 | 1.19 |
| PERC | SC-POND301 | BASIN300&301 | 0.87 | 55.62 | 56.00 | 145337 | 0.000 | 16.821 | 0.00 | 1.21 |
| PERC | SC-POND301 | BASIN300&301 | 0.89 | 55.61 | 56.00 | 145294 | 0.000 | 16.816 | 0.00 | 1.24 |
| PERC | SC-POND301 | BASIN300&301 | 0.91 | 55.60 | 56.00 | 145251 | 0.000 | 16.811 | 0.00 | 1.26 |
| PERC | SC-POND301 | BASIN300&301 | 0.92 | 55.60 | 56.00 | 145208 | 0.000 | 16.807 | 0.00 | 1.28 |
| PERC | SC-POND301 | BASIN300&301 | 0.94 | 55.59 | 56.00 | 145166 | 0.000 | 16.802 | 0.00 | 1.31 |
| PERC | SC-POND301 | BASIN300&301 | 0.96 | 55.58 | 56.00 | 145123 | 0.000 | 16.797 | 0.00 | 1.33 |
| PERC | SC-POND301 | BASIN300&301 | 0.97 | 55.58 | 56.00 | 145080 | 0.000 | 16.792 | 0.00 | 1.35 |
| PERC | SC-POND301 | BASIN300&301 | 0.99 | 55.57 | 56.00 | 145038 | 0.000 | 16.787 | 0.00 | 1.38 |
| PERC | SC-POND301 | BASIN300&301 | 1.01 | 55.56 | 56.00 | 144995 | 0.000 | 16.782 | 0.00 | 1.40 |
| PERC | SC-POND301 | BASIN300&301 | 1.02 | 55.56 | 56.00 | 144974 | 0.000 | 16.779 | 0.00 | 1.41 |
| PERC | SC-POND301 | BASIN300&301 | 1.03 | 55.55 | 56.00 | 144931 | 0.000 | 16.774 | 0.00 | 1.43 |
| PERC | SC-POND301 | BASIN300&301 | 1.05 | 55.54 | 56.00 | 144888 | 0.000 | 16.769 | 0.00 | 1.46 |
| PERC | SC-POND301 | BASIN300&301 | 1.07 | 55.54 | 56.00 | 144845 | 0.000 | 16.765 | 0.00 | 1.48 |
| PERC | SC-POND301 | BASIN300&301 | 1.08 | 55.53 | 56.00 | 144803 | 0.000 | 16.760 | 0.00 | 1.50 |
| PERC | SC-POND301 | BASIN300&301 | 1.10 | 55.52 | 56.00 | 144760 | 0.000 | 16.755 | 0.00 | 1.53 |
| PERC | SC-POND301 | BASIN300&301 | 1.12 | 55.52 | 56.00 | 144717 | 0.000 | 16.750 | 0.00 | 1.55 |
| PERC | SC-POND301 | BASIN300&301 | 1.13 | 55.51 | 56.00 | 144675 | 0.000 | 16.745 | 0.00 | 1.57 |
| PERC | SC-POND301 | BASIN300&301 | 1.15 | 55.50 | 56.00 | 144632 | 0.000 | 16.740 | 0.00 | 1.60 |
| PERC | SC-POND301 | BASIN300&301 | 1.17 | 55.50 | 56.00 | 144589 | 0.000 | 16.735 | 0.00 | 1.62 |
| PERC | SC-POND301 | BASIN300&301 | 1.18 | 55.49 | 56.00 | 144547 | 0.000 | 16.730 | 0.00 | 1.64 |
| PERC | SC-POND301 | BASIN300&301 | 1.20 | 55.48 | 56.00 | 144504 | 0.000 | 16.725 | 0.00 | 1.67 |
| PERC | SC-POND301 | BASIN300&301 | 1.22 | 55.47 | 56.00 | 144461 | 0.000 | 16.720 | 0.00 | 1.69 |
| PERC | SC-POND301 | BASIN300&301 | 1.24 | 55.47 | 56.00 | 144418 | 0.000 | 16.715 | 0.00 | 1.71 |
| PERC | SC-POND301 | BASIN300&301 | 1.25 | 55.46 | 56.00 | 144376 | 0.000 | 16.710 | 0.00 | 1.74 |
| PERC | SC-POND301 | BASIN300&301 | 1.27 | 55.45 | 56.00 | 144333 | 0.000 | 16.705 | 0.00 | 1.76 |
| PERC | SC-POND301 | BASIN300&301 | 1.29 | 55.45 | 56.00 | 144290 | 0.000 | 16.700 | 0.00 | 1.78 |
| PERC | SC-POND301 | BASIN300&301 | 1.30 | 55.44 | 56.00 | 144248 | 0.000 | 16.695 | 0.00 | 1.81 |
| PERC | SC-POND301 | BASIN300&301 | 1.32 | 55.43 | 56.00 | 144205 | 0.000 | 16.690 | 0.00 | 1.83 |
| PERC | SC-POND301 | BASIN300&301 | 1.34 | 55.43 | 56.00 | 144162 | 0.000 | 16.685 | 0.00 | 1.85 |

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| PERC | SC-POND301 | BASIN300&301 | 5.41 | 54.11 | 56.00 | 136165 | 0.000 | 3.455 | 0.00 | 6.07 |
| PERC | SC-POND301 | BASIN300&301 | 5.42 | 54.11 | 56.00 | 136159 | 0.000 | 3.443 | 0.00 | 6.07 |
| PERC | SC-POND301 | BASIN300&301 | 5.44 | 54.11 | 56.00 | 136148 | 0.000 | 3.419 | 0.00 | 6.08 |
| PERC | SC-POND301 | BASIN300&301 | 5.45 | 54.11 | 56.00 | 136142 | 0.000 | 3.407 | 0.00 | 6.08 |
| PERC | SC-POND301 | BASIN300&301 | 5.47 | 54.11 | 56.00 | 136130 | 0.000 | 3.384 | 0.00 | 6.09 |
| PERC | SC-POND301 | BASIN300&301 | 5.49 | 54.11 | 56.00 | 136119 | 0.000 | 3.361 | 0.00 | 6.09 |
| PERC | SC-POND301 | BASIN300&301 | 5.50 | 54.11 | 56.00 | 136113 | 0.000 | 3.350 | 0.00 | 6.10 |
| PERC | SC-POND301 | BASIN300&301 | 5.52 | 54.10 | 56.00 | 136102 | 0.000 | 3.328 | 0.00 | 6.10 |
| PERC | SC-POND301 | BASIN300&301 | 5.54 | 54.10 | 56.00 | 136096 | 0.000 | 3.317 | 0.00 | 6.10 |
| PERC | SC-POND301 | BASIN300&301 | 5.56 | 54.10 | 56.00 | 136085 | 0.000 | 3.296 | 0.00 | 6.11 |
| PERC | SC-POND301 | BASIN300&301 | 5.57 | 54.10 | 56.00 | 136079 | 0.000 | 3.285 | 0.00 | 6.11 |
| PERC | SC-POND301 | BASIN300&301 | 5.59 | 54.10 | 56.00 | 136068 | 0.000 | 3.264 | 0.00 | 6.12 |
| PERC | SC-POND301 | BASIN300&301 | 5.61 | 54.10 | 56.00 | 136057 | 0.000 | 3.244 | 0.00 | 6.12 |
| PERC | SC-POND301 | BASIN300&301 | 5.62 | 54.10 | 56.00 | 136052 | 0.000 | 3.234 | 0.00 | 6.13 |
| PERC | SC-POND301 | BASIN300&301 | 5.64 | 54.09 | 56.00 | 136041 | 0.000 | 3.214 | 0.00 | 6.13 |
| PERC | SC-POND301 | BASIN300&301 | 5.65 | 54.09 | 56.00 | 136035 | 0.000 | 3.204 | 0.00 | 6.14 |
| PERC | SC-POND301 | BASIN300&301 | 5.68 | 54.09 | 56.00 | 136022 | 0.000 | 3.180 | 0.00 | 6.14 |
| PERC | SC-POND301 | BASIN300&301 | 5.69 | 54.09 | 56.00 | 136015 | 0.000 | 3.168 | 0.00 | 6.15 |
| PERC | SC-POND301 | BASIN300&301 | 5.70 | 54.09 | 56.00 | 136008 | 0.000 | 3.156 | 0.00 | 6.15 |
| PERC | SC-POND301 | BASIN300&301 | 5.73 | 54.09 | 56.00 | 135995 | 0.000 | 3.133 | 0.00 | 6.16 |
| PERC | SC-POND301 | BASIN300&301 | 5.74 | 54.08 | 56.00 | 135988 | 0.000 | 3.122 | 0.00 | 6.16 |
| PERC | SC-POND301 | BASIN300&301 | 5.76 | 54.08 | 56.00 | 135982 | 0.000 | 3.111 | 0.00 | 6.16 |
| PERC | SC-POND301 | BASIN300&301 | 5.77 | 54.08 | 56.00 | 135975 | 0.000 | 3.100 | 0.00 | 6.17 |
| PERC | SC-POND301 | BASIN300&301 | 5.80 | 54.08 | 56.00 | 135962 | 0.000 | 3.078 | 0.00 | 6.17 |
| PERC | SC-POND301 | BASIN300&301 | 5.81 | 54.08 | 56.00 | 135956 | 0.000 | 3.067 | 0.00 | 6.18 |
| PERC | SC-POND301 | BASIN300&301 | 5.82 | 54.08 | 56.00 | 135949 | 0.000 | 3.056 | 0.00 | 6.18 |
| PERC | SC-POND301 | BASIN300&301 | 5.83 | 54.08 | 56.00 | 135943 | 0.000 | 3.046 | 0.00 | 6.18 |
| PERC | SC-POND301 | BASIN300&301 | 5.86 | 54.08 | 56.00 | 135930 | 0.000 | 3.025 | 0.00 | 6.19 |
| PERC | SC-POND301 | BASIN300&301 | 5.87 | 54.07 | 56.00 | 135923 | 0.000 | 3.015 | 0.00 | 6.19 |
| PERC | SC-POND301 | BASIN300&301 | 5.89 | 54.07 | 56.00 | 135917 | 0.000 | 3.004 | 0.00 | 6.20 |
| PERC | SC-POND301 | BASIN300&301 | 5.90 | 54.07 | 56.00 | 135911 | 0.000 | 2.994 | 0.00 | 6.20 |
| PERC | SC-POND301 | BASIN300&301 | 5.93 | 54.07 | 56.00 | 135898 | 0.000 | 2.974 | 0.00 | 6.21 |
| PERC | SC-POND301 | BASIN300&301 | 5.94 | 54.07 | 56.00 | 135892 | 0.000 | 2.965 | 0.00 | 6.21 |
| PERC | SC-POND301 | BASIN300&301 | 5.95 | 54.07 | 56.00 | 135885 | 0.000 | 2.955 | 0.00 | 6.21 |
| PERC | SC-POND301 | BASIN300&301 | 5.98 | 54.07 | 56.00 | 135873 | 0.000 | 2.936 | 0.00 | 6.22 |
| PERC | SC-POND301 | BASIN300&301 | 5.99 | 54.06 | 56.00 | 135867 | 0.000 | 2.927 | 0.00 | 6.22 |
| PERC | SC-POND301 | BASIN300&301 | 6.01 | 54.06 | 56.00 | 135860 | 0.000 | 2.917 | 0.00 | 6.23 |
| PERC | SC-POND301 | BASIN300&301 | 6.02 | 54.06 | 56.00 | 135854 | 0.000 | 2.908 | 0.00 | 6.23 |
| PERC | SC-POND301 | BASIN300&301 | 6.04 | 54.06 | 56.00 | 135842 | 0.000 | 2.890 | 0.00 | 6.23 |
| PERC | SC-POND301 | BASIN300&301 | 6.06 | 54.06 | 56.00 | 135836 | 0.000 | 2.881 | 0.00 | 6.24 |
| PERC | SC-POND301 | BASIN300&301 | 6.07 | 54.06 | 56.00 | 135830 | 0.000 | 2.872 | 0.00 | 6.24 |
| PERC | SC-POND301 | BASIN300&301 | 6.08 | 54.06 | 56.00 | 135824 | 0.000 | 2.863 | 0.00 | 6.24 |
| PERC | SC-POND301 | BASIN300&301 | 6.11 | 54.06 | 56.00 | 135811 | 0.000 | 2.846 | 0.00 | 6.25 |
| PERC | SC-POND301 | BASIN300&301 | 6.12 | 54.05 | 56.00 | 135805 | 0.000 | 2.837 | 0.00 | 6.25 |
| PERC | SC-POND301 | BASIN300&301 | 6.14 | 54.05 | 56.00 | 135799 | 0.000 | 2.828 | 0.00 | 6.26 |
| PERC | SC-POND301 | BASIN300&301 | 6.16 | 54.05 | 56.00 | 135787 | 0.000 | 2.812 | 0.00 | 6.26 |
| PERC | SC-POND301 | BASIN300&301 | 6.18 | 54.05 | 56.00 | 135781 | 0.000 | 2.803 | 0.00 | 6.27 |
| PERC | SC-POND301 | BASIN300&301 | 6.19 | 54.05 | 56.00 | 135775 | 0.000 | 2.795 | 0.00 | 6.27 |
| PERC | SC-POND301 | BASIN300&301 | 6.20 | 54.05 | 56.00 | 135770 | 0.000 | 2.787 | 0.00 | 6.27 |
| PERC | SC-POND301 | BASIN300&301 | 6.23 | 54.05 | 56.00 | 135758 | 0.000 | 2.771 | 0.00 | 6.28 |
| PERC | SC-POND301 | BASIN300&301 | 6.24 | 54.05 | 56.00 | 135752 | 0.000 | 2.763 | 0.00 | 6.28 |
| PERC | SC-POND301 | BASIN300&301 | 6.25 | 54.04 | 56.00 | 135746 | 0.000 | 2.755 | 0.00 | 6.28 |
| PERC | SC-POND301 | BASIN300&301 | 6.27 | 54.04 | 56.00 | 135740 | 0.000 | 2.747 | 0.00 | 6.29 |
| PERC | SC-POND301 | BASIN300&301 | 6.29 | 54.04 | 56.00 | 135729 | 0.000 | 2.732 | 0.00 | 6.29 |
| PERC | SC-POND301 | BASIN300&301 | 6.31 | 54.04 | 56.00 | 135723 | 0.000 | 2.724 | 0.00 | 6.30 |
| PERC | SC-POND301 | BASIN300&301 | 6.32 | 54.04 | 56.00 | 135717 | 0.000 | 2.717 | 0.00 | 6.30 |
| PERC | SC-POND301 | BASIN300&301 | 6.33 | 54.04 | 56.00 | 135711 | 0.000 | 2.709 | 0.00 | 6.30 |
| PERC | SC-POND301 | BASIN300&301 | 6.36 | 54.04 | 56.00 | 135700 | 0.000 | 2.694 | 0.00 | 6.31 |
| PERC | SC-POND301 | BASIN300&301 | 6.37 | 54.04 | 56.00 | 135694 | 0.000 | 2.687 | 0.00 | 6.31 |
| PERC | SC-POND301 | BASIN300&301 | 6.39 | 54.04 | 56.00 | 135688 | 0.000 | 2.680 | 0.00 | 6.31 |
| PERC | SC-POND301 | BASIN300&301 | 6.41 | 54.03 | 56.00 | 135677 | 0.000 | 2.665 | 0.00 | 6.32 |
| PERC | SC-POND301 | BASIN300&301 | 6.43 | 54.03 | 56.00 | 135671 | 0.000 | 2.658 | 0.00 | 6.32 |
| PERC | SC-POND301 | BASIN300&301 | 6.44 | 54.03 | 56.00 | 135666 | 0.000 | 2.651 | 0.00 | 6.32 |
| PERC | SC-POND301 | BASIN300&301 | 6.45 | 54.03 | 56.00 | 135660 | 0.000 | 2.644 | 0.00 | 6.33 |
| PERC | SC-POND301 | BASIN300&301 | 6.48 | 54.03 | 56.00 | 135649 | 0.000 | 2.630 | 0.00 | 6.33 |
| PERC | SC-POND301 | BASIN300&301 | 6.49 | 54.03 | 56.00 | 135643 | 0.000 | 2.623 | 0.00 | 6.34 |
| PERC | SC-POND301 | BASIN300&301 | 6.50 | 54.03 | 56.00 | 135638 | 0.000 | 2.617 | 0.00 | 6.34 |
| PERC | SC-POND301 | BASIN300&301 | 6.52 | 54.03 | 56.00 | 135632 | 0.000 | 2.610 | 0.00 | 6.34 |
| PERC | SC-POND301 | BASIN300&301 | 6.54 | 54.02 | 56.00 | 135621 | 0.000 | 2.597 | 0.00 | 6.35 |
| PERC | SC-POND301 | BASIN300&301 | 6.56 | 54.02 | 56.00 | 135615 | 0.000 | 2.590 | 0.00 | 6.35 |
| PERC | SC-POND301 | BASIN300&301 | 6.57 | 54.02 | 56.00 | 135610 | 0.000 | 2.584 | 0.00 | 6.35 |
| PERC | SC-POND301 | BASIN300&301 | 6.60 | 54.02 | 56.00 | 135599 | 0.000 | 2.571 | 0.00 | 6.36 |
| PERC | SC-POND301 | BASIN300&301 | 6.61 | 54.02 | 56.00 | 135594 | 0.000 | 2.564 | 0.00 | 6.36 |
| PERC | SC-POND301 | BASIN300&301 | 6.62 | 54.02 | 56.00 | 135588 | 0.000 | 2.558 | 0.00 | 6.36 |
| PERC | SC-POND301 | BASIN300&301 | 6.64 | 54.02 | 56.00 | 135583 | 0.000 | 2.552 | 0.00 | 6.37 |
| PERC | SC-POND301 | BASIN300&301 | 6.66 | 54.02 | 56.00 | 135572 | 0.000 | 2.539 | 0.00 | 6.37 |
| PERC | SC-POND301 | BASIN300&301 | 6.67 | 54.02 | 56.00 | 135566 | 0.000 | 2.533 | 0.00 | 6.38 |
| PERC | SC-POND301 | BASIN300&301 | 6.69 | 54.01 | 56.00 | 135561 | 0.000 | 2.527 | 0.00 | 6.38 |
| PERC | SC-POND301 | BASIN300&301 | 6.70 | 54.01 | 56.00 | 135556 | 0.000 | 2.521 | 0.00 | 6.38 |
| PERC | SC-POND301 | BASIN300&301 | 6.73 | 54.01 | 56.00 | 135545 | 0.000 | 2.509 | 0.00 | 6.39 |
| PERC | SC-POND301 | BASIN300&301 | 6.74 | 54.01 | 56.00 | 135540 | 0.000 | 2.503 | 0.00 | 6.39 |

Basin 300 & 301 (Pond 301)
FDOT Closed Basin Recovery
7-Day / 30-day

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| PERC | SC-POND301 | BASIN300&301 | 149.87 | 52.01 | 56.00 | 123310 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.88 | 52.01 | 56.00 | 123309 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.90 | 52.01 | 56.00 | 123308 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.92 | 52.01 | 56.00 | 123308 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.93 | 52.01 | 56.00 | 123307 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.95 | 52.01 | 56.00 | 123306 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.97 | 52.01 | 56.00 | 123306 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 149.98 | 52.00 | 56.00 | 123305 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.00 | 52.00 | 56.00 | 123304 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.02 | 52.00 | 56.00 | 123304 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.03 | 52.00 | 56.00 | 123303 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.05 | 52.00 | 56.00 | 123302 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.07 | 52.00 | 56.00 | 123302 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.08 | 52.00 | 56.00 | 123301 | 0.000 | 0.225 | 0.00 | 12.35 |
| PERC | SC-POND301 | BASIN300&301 | 150.10 | 52.00 | 56.00 | 123300 | 0.000 | 0.225 | 0.00 | 12.35 |

Basin 300
Stormsewer Tailwater - 10-YR. / 240-HR. (Orifice Off & Initial Stage Set at the Weir Elevation)

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| 010Y240H | SC-POND300 | BASIN300&301 | 182.50 | 54.49 | 56.00 | 121826 | 13.66 | 3.99 | 20.28 | 10.50 |
| 010Y240H | SC-POND300 | BASIN300&301 | 182.59 | 54.52 | 56.00 | 121956 | 13.66 | 4.03 | 20.37 | 10.53 |
| 010Y240H | SC-POND300 | BASIN300&301 | 182.67 | 54.54 | 56.00 | 122086 | 13.66 | 4.06 | 20.47 | 10.56 |
| 010Y240H | SC-POND300 | BASIN300&301 | 182.75 | 54.57 | 56.00 | 122215 | 13.67 | 4.10 | 20.56 | 10.58 |
| 010Y240H | SC-POND300 | BASIN300&301 | 182.84 | 54.59 | 56.00 | 122343 | 13.67 | 4.14 | 20.66 | 10.61 |
| 010Y240H | SC-POND300 | BASIN300&301 | 182.92 | 54.61 | 56.00 | 122471 | 13.67 | 4.17 | 20.75 | 10.64 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.00 | 54.64 | 56.00 | 122598 | 13.67 | 4.21 | 20.85 | 10.67 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.08 | 54.66 | 56.00 | 122717 | 13.67 | 4.24 | 20.94 | 10.70 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.17 | 54.68 | 56.00 | 122843 | 13.68 | 4.27 | 21.03 | 10.73 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.25 | 54.70 | 56.00 | 122969 | 13.68 | 4.31 | 21.13 | 10.76 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.34 | 54.73 | 56.00 | 123094 | 13.68 | 4.34 | 21.22 | 10.79 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.42 | 54.75 | 56.00 | 123218 | 13.68 | 4.38 | 21.32 | 10.82 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.50 | 54.77 | 56.00 | 123342 | 13.68 | 4.41 | 21.41 | 10.85 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.59 | 54.80 | 56.00 | 123469 | 13.69 | 4.45 | 21.51 | 10.88 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.67 | 54.82 | 56.00 | 123587 | 13.69 | 4.48 | 21.60 | 10.91 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.76 | 54.84 | 56.00 | 123712 | 13.69 | 4.51 | 21.70 | 10.94 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.84 | 54.86 | 56.00 | 123829 | 13.69 | 4.55 | 21.79 | 10.97 |
| 010Y240H | SC-POND300 | BASIN300&301 | 183.92 | 54.88 | 56.00 | 123954 | 13.69 | 4.58 | 21.89 | 11.00 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.00 | 54.91 | 56.00 | 124069 | 13.69 | 4.61 | 21.98 | 11.03 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.09 | 54.93 | 56.00 | 124191 | 13.47 | 4.65 | 22.07 | 11.07 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.17 | 54.95 | 56.00 | 124299 | 12.94 | 4.68 | 22.16 | 11.10 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.26 | 54.97 | 56.00 | 124406 | 11.85 | 4.71 | 22.25 | 11.13 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.33 | 54.98 | 56.00 | 124485 | 10.65 | 4.73 | 22.32 | 11.16 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.42 | 54.99 | 56.00 | 124554 | 9.37 | 4.75 | 22.39 | 11.19 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.50 | 55.01 | 56.00 | 124609 | 8.24 | 4.77 | 22.45 | 11.23 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.59 | 55.01 | 56.00 | 124650 | 7.31 | 4.78 | 22.51 | 11.26 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.67 | 55.02 | 56.00 | 124677 | 6.63 | 4.79 | 22.55 | 11.29 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.75 | 55.02 | 56.00 | 124697 | 6.00 | 4.79 | 22.60 | 11.33 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.84 | 55.02 | 56.00 | 124710 | 5.49 | 4.80 | 22.64 | 11.36 |
| 010Y240H | SC-POND300 | BASIN300&301 | 184.92 | 55.02 | 56.00 | 124716 | 5.10 | 4.80 | 22.67 | 11.39 |

Basin 300
Stormsewer Tailwater - 50-YR. / 240-HR. (Orifice Off & Initial Stage Set at the Weir Elevation)

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| 050Y240H | SC-POND300 | BASIN300&301 | 182.50 | 55.43 | 56.00 | 126924 | 17.85 | 5.42 | 27.45 | 15.00 |
| 050Y240H | SC-POND300 | BASIN300&301 | 182.59 | 55.46 | 56.00 | 127081 | 17.86 | 5.47 | 27.57 | 15.03 |
| 050Y240H | SC-POND300 | BASIN300&301 | 182.67 | 55.49 | 56.00 | 127237 | 17.86 | 5.51 | 27.69 | 15.07 |
| 050Y240H | SC-POND300 | BASIN300&301 | 182.75 | 55.52 | 56.00 | 127393 | 17.86 | 5.55 | 27.81 | 15.11 |
| 050Y240H | SC-POND300 | BASIN300&301 | 182.84 | 55.55 | 56.00 | 127560 | 17.86 | 5.60 | 27.94 | 15.15 |
| 050Y240H | SC-POND300 | BASIN300&301 | 182.92 | 55.58 | 56.00 | 127714 | 17.86 | 5.64 | 28.06 | 15.19 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.01 | 55.60 | 56.00 | 127874 | 17.86 | 5.69 | 28.19 | 15.23 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.09 | 55.63 | 56.00 | 128033 | 17.87 | 5.73 | 28.31 | 15.27 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.17 | 55.66 | 56.00 | 128175 | 17.87 | 5.77 | 28.43 | 15.30 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.25 | 55.69 | 56.00 | 128333 | 17.87 | 5.82 | 28.55 | 15.34 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.34 | 55.72 | 56.00 | 128489 | 17.87 | 5.86 | 28.68 | 15.38 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.42 | 55.75 | 56.00 | 128645 | 17.87 | 5.91 | 28.81 | 15.43 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.50 | 55.77 | 56.00 | 128785 | 17.87 | 5.95 | 28.92 | 15.46 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.59 | 55.80 | 56.00 | 128940 | 17.88 | 5.99 | 29.05 | 15.51 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.67 | 55.83 | 56.00 | 129093 | 17.88 | 6.04 | 29.17 | 15.55 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.76 | 55.86 | 56.00 | 129246 | 17.88 | 6.08 | 29.30 | 15.59 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.83 | 55.88 | 56.00 | 129383 | 17.88 | 6.12 | 29.41 | 15.63 |
| 050Y240H | SC-POND300 | BASIN300&301 | 183.92 | 55.91 | 56.00 | 129535 | 17.88 | 6.17 | 29.54 | 15.67 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.00 | 55.94 | 56.00 | 129686 | 17.86 | 6.21 | 29.66 | 15.72 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.09 | 55.96 | 56.00 | 129834 | 17.58 | 6.25 | 29.79 | 15.76 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.18 | 55.99 | 56.00 | 129975 | 16.80 | 6.29 | 29.91 | 15.80 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.25 | 56.01 | 56.00 | 130090 | 15.58 | 6.33 | 30.01 | 15.84 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.34 | 56.03 | 56.00 | 130204 | 13.71 | 6.36 | 30.12 | 15.89 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.42 | 56.05 | 56.00 | 130278 | 12.21 | 6.38 | 30.20 | 15.93 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.50 | 56.06 | 56.00 | 130344 | 10.75 | 6.40 | 30.28 | 15.98 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.59 | 56.07 | 56.00 | 130391 | 9.59 | 6.42 | 30.35 | 16.02 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.67 | 56.07 | 56.00 | 130425 | 8.61 | 6.43 | 30.42 | 16.07 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.76 | 56.08 | 56.00 | 130448 | 7.81 | 6.43 | 30.48 | 16.11 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.83 | 56.08 | 56.00 | 130460 | 7.21 | 6.44 | 30.52 | 16.15 |
| 050Y240H | SC-POND300 | BASIN300&301 | 184.92 | 56.08 | 56.00 | 130466 | 6.64 | 6.44 | 30.57 | 16.20 |

Basin 301
Stormsewer Tailwater - 10-YR. / 240-HR. (Initial Stage Set at the Weir Elevation)

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| 010Y240H | SC-POND301 | BASIN300&301 | 182.50 | 55.50 | 56.00 | 144639 | 8.69 | 0.97 | 13.71 | 15.25 |
| 010Y240H | SC-POND301 | BASIN300&301 | 182.59 | 55.52 | 56.00 | 144737 | 8.69 | 0.98 | 13.77 | 15.25 |
| 010Y240H | SC-POND301 | BASIN300&301 | 182.67 | 55.54 | 56.00 | 144835 | 8.69 | 0.98 | 13.83 | 15.26 |
| 010Y240H | SC-POND301 | BASIN300&301 | 182.75 | 55.55 | 56.00 | 144933 | 8.69 | 0.99 | 13.89 | 15.27 |
| 010Y240H | SC-POND301 | BASIN300&301 | 182.84 | 55.57 | 56.00 | 145031 | 8.69 | 0.99 | 13.95 | 15.28 |
| 010Y240H | SC-POND301 | BASIN300&301 | 182.92 | 55.58 | 56.00 | 145129 | 8.69 | 0.99 | 14.01 | 15.28 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.00 | 55.60 | 56.00 | 145226 | 8.69 | 1.00 | 14.07 | 15.29 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.08 | 55.61 | 56.00 | 145318 | 8.70 | 1.00 | 14.13 | 15.30 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.17 | 55.63 | 56.00 | 145416 | 8.70 | 1.00 | 14.19 | 15.30 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.25 | 55.65 | 56.00 | 145513 | 8.70 | 1.00 | 14.25 | 15.31 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.34 | 55.66 | 56.00 | 145610 | 8.70 | 1.01 | 14.31 | 15.32 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.42 | 55.68 | 56.00 | 145708 | 8.70 | 1.01 | 14.37 | 15.32 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.50 | 55.69 | 56.00 | 145805 | 8.70 | 1.01 | 14.43 | 15.33 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.59 | 55.71 | 56.00 | 145904 | 8.70 | 1.02 | 14.49 | 15.34 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.67 | 55.73 | 56.00 | 145997 | 8.70 | 1.02 | 14.55 | 15.34 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.76 | 55.74 | 56.00 | 146097 | 8.70 | 1.02 | 14.61 | 15.35 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.84 | 55.76 | 56.00 | 146189 | 8.70 | 1.03 | 14.67 | 15.36 |
| 010Y240H | SC-POND301 | BASIN300&301 | 183.92 | 55.77 | 56.00 | 146289 | 8.70 | 1.03 | 14.73 | 15.37 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.00 | 55.79 | 56.00 | 146381 | 8.69 | 1.03 | 14.79 | 15.37 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.09 | 55.80 | 56.00 | 146479 | 8.49 | 1.04 | 14.85 | 15.38 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.17 | 55.82 | 56.00 | 146565 | 7.97 | 1.04 | 14.91 | 15.39 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.26 | 55.83 | 56.00 | 146650 | 6.94 | 1.03 | 14.96 | 15.39 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.33 | 55.84 | 56.00 | 146713 | 6.00 | 1.03 | 15.00 | 15.40 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.42 | 55.85 | 56.00 | 146769 | 5.15 | 1.02 | 15.04 | 15.41 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.50 | 55.86 | 56.00 | 146818 | 4.45 | 1.01 | 15.07 | 15.42 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.59 | 55.87 | 56.00 | 146859 | 3.92 | 1.00 | 15.10 | 15.42 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.67 | 55.87 | 56.00 | 146891 | 3.54 | 0.99 | 15.13 | 15.43 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.75 | 55.88 | 56.00 | 146922 | 3.19 | 0.98 | 15.15 | 15.44 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.84 | 55.88 | 56.00 | 146949 | 2.90 | 0.97 | 15.17 | 15.44 |
| 010Y240H | SC-POND301 | BASIN300&301 | 184.92 | 55.89 | 56.00 | 146970 | 2.68 | 0.96 | 15.19 | 15.45 |

# ORIFICE CALCULATIONS

| | |
|---|---|
| Prepared by: | **JLL** |
| Date: | **30-May-17** |
| Checked by: | **MB** |
| Date: | **5-Jun-17** |

| | |
|---|---|
| Project Name: | **I-4 BtU Segment 3** |
| Project Number: | **242592-4-52-01** |

**Drawdown Time: 24 - 30**

| Pond | Drawdown Structure | Area at SHWT Elevation (ac.) | Area at Weir Elevation (ac) | Avg. Area between Weir and SHWT (ac) | Height of Treatment Volume h1 (ft) | Half of the treatment volume h2 (ft) | Orifice flow coefficient Cd | Orifice area Required ($ft^2$) | Orifice Diameter Required (in) | Orifice Diameter Provided (in) | V-Notch Detention Volume (ac-ft) | V-Notch Angle Required | V-Notch Angle Provided | Actual Discharge time for half Volume t (hrs) | Time for Full Discharge of Treatment Volume (hrs) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Pond 300 | Orifice | 2.11 | 2.32 | 2.22 | 1.67 | 0.84 | 0.65 | 0.16 | 5.43 | 5.25 | N/A | N/A | N/A | 25.71 | 89.07 |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

**Remarks:**

```
================================================================================
==== Basins ====================================================================
================================================================================

        Name: SC-800A                 Node: SC-0800               Status: Onsite
       Group: BASIN300&301            Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh256                  Peaking Factor: 256.0
         Rainfall File: Sjrwmd96           Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200               Time of Conc(min): 13.00
           Area(ac): 5.230                   Time Shift(hrs): 0.00
        Curve Number: 82.00              Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-POND300              Node: SC-POND300            Status: Onsite
       Group: BASIN300&301            Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File: Sjrwmd96           Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200               Time of Conc(min): 31.00
           Area(ac): 29.780                  Time Shift(hrs): 0.00
        Curve Number: 85.80              Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-POND301              Node: SC-POND301            Status: Onsite
       Group: BASIN300&301            Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File: Sjrwmd96           Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200               Time of Conc(min): 25.00
           Area(ac): 18.720                  Time Shift(hrs): 0.00
        Curve Number: 90.30              Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



================================================================================
==== Nodes =====================================================================
================================================================================

      Name: GRND 301           Base Flow(cfs): 0.000         Init Stage(ft): 45.600
     Group: BASIN300&301                                     Warn Stage(ft): 45.600
      Type: Time/Stage



      Time(hrs)       Stage(ft)
--------------- ---------------
          0.00          45.600
        336.00          45.600

--------------------------------------------------------------------------------
      Name: SC-0800            Base Flow(cfs): 0.000         Init Stage(ft): 49.000
     Group: BASIN300&301                                     Warn Stage(ft): 52.000
      Type: Time/Stage



      Time(hrs)       Stage(ft)
--------------- ---------------
          0.00          49.000
         11.00          52.000
         16.00          52.000
         24.00          52.000
         96.00          49.000

--------------------------------------------------------------------------------
      Name: SC-810             Base Flow(cfs): 0.000         Init Stage(ft): 55.000
```

Group: BASIN300&301 Warn Stage(ft): 55.000
Type: Time/Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 55.000 |
| 96.00 | 55.000 |

---

Name: SC-POND300 Base Flow(cfs): 0.000 Init Stage(ft): 49.000
Group: BASIN300&301 Warn Stage(ft): 56.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 49.000 | 2.1100 |
| 57.000 | 3.1100 |

---

Name: SC-POND301 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: BASIN300&301 Warn Stage(ft): 56.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 2.8300 |
| 57.000 | 3.5300 |

==========
==== Drop Structures ==========
==========

Name: S-O300 From Node: SC-POND300 Length(ft): 351.00
Group: BASIN300&301 To Node: SC-0800 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 18.00 | 18.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 18.00 | 18.00 | Flow: | Both |
| Invert(ft): | 49.000 | 48.700 | Entrance Loss Coef: | 1.000 |
| Manning's N: | 0.012000 | 0.012000 | Exit Loss Coef: | 0.500 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DBI Type C

*** Weir 1 of 3 for Drop Structure S-O300 ***

TABLE

Count: 1 Bottom Clip(in): 0.000
Type: Vertical: Mavis Top Clip(in): 0.000
Flow: Both Weir Disc Coef: 3.200
Geometry: Circular Orifice Disc Coef: 0.600

Span(in): 5.25 Invert(ft): 49.000
Rise(in): 5.25 Control Elev(ft): 49.000

*** Weir 2 of 3 for Drop Structure S-O300 ***

TABLE

Count: 1 Bottom Clip(in): 0.000
Type: Vertical: Mavis Top Clip(in): 0.000
Flow: Both Weir Disc Coef: 3.200
Geometry: Rectangular Orifice Disc Coef: 0.600

```
              Span(in): 2.00                      Invert(ft): 50.670
              Rise(in): 63.96                 Control Elev(ft): 50.670

*** Weir 3 of 3 for Drop Structure S-O300 ***
                                                                      TABLE
                 Count: 1                    Bottom Clip(in): 0.000
                  Type: Horizontal              Top Clip(in): 0.000
                  Flow: Both                  Weir Disc Coef: 3.200
              Geometry: Rectangular          Orifice Disc Coef: 0.600

              Span(in): 37.00                     Invert(ft): 56.420
              Rise(in): 24.00                 Control Elev(ft): 56.420


-------------------------------------------------------------------------------------------------
         Name: S-O301             From Node: SC-POND301         Length(ft): 413.00
        Group: BASIN300&301         To Node: SC-810                Count: 1

               UPSTREAM       DOWNSTREAM                Friction Equation: Average Conveyance
     Geometry: Circular       Circular                 Solution Algorithm: Automatic
     Span(in): 18.00          18.00                                 Flow: Both
     Rise(in): 18.00          18.00                   Entrance Loss Coef: 0.500
   Invert(ft): 53.900         52.300                      Exit Loss Coef: 1.000
  Manning's N: 0.012000       0.012000                  Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                      Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                        Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DBI Type D

*** Weir 1 of 1 for Drop Structure S-O301 ***
                                                                      TABLE
                 Count: 1                    Bottom Clip(in): 0.000
                  Type: Horizontal              Top Clip(in): 0.000
                  Flow: Both                  Weir Disc Coef: 3.200
              Geometry: Rectangular          Orifice Disc Coef: 0.600

              Span(in): 49.00                     Invert(ft): 55.980
              Rise(in): 37.00                 Control Elev(ft): 55.980


===============================================================================================
==== Percolation Links ========================================================================
===============================================================================================

         Name: PERC 301           From Node: SC-POND301              Flow: Both
        Group: BASIN300&301         To Node: GRND 301               Count: 1

         Surface Area Option: Vary based on Stage/Area Table
   Vertical Flow Termination: Horizontal Flow Algorithm
       Aquifer Base Elev(ft): 31.600                     Perimeter 1(ft): 1561.000
        Water Table Elev(ft): 45.600                     Perimeter 2(ft): 1933.000
 ****************************-9999.000                  Perimeter 3(ft): 4912.000
  Horiz Conductivity(ft/day): 20.000                Distance 1 to 2(ft): 50.000
   Vert Conductivity(ft/day): 10.000                Distance 2 to 3(ft): 450.000
     Effective Porosity(dec): 0.250                    Num Cells 1 to 2: 10
           Suction Head(in): 4.000                     Num Cells 2 to 3: 45
         Layer Thickness(ft): 6.400




===============================================================================================
==== Hydrology Simulations ====================================================================
===============================================================================================

         Name: 010Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.R32

      Override Defaults: Yes
```

```
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 13.50

Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.00

------------------------------------------------------------------------------------------------------
         Name: 050Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 17.50

Time(hrs)       Print Inc(min)
--------------- ---------------
250.000         5.00

------------------------------------------------------------------------------------------------------
         Name: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 18.50

Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.00

------------------------------------------------------------------------------------------------------
         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.R32

      Override Defaults: No

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
96.000          5.00

==============================================================================================
==== Routing Simulations ======================================================================
==============================================================================================

         Name: 010Y240H            Hydrology Sim: 010Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.I32

      Execute: No          Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 240.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:



Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.000

Group           Run
--------------- -----
BASIN300&301    Yes


------------------------------------------------------------------------------------------------------
         Name: 050Y240H            Hydrology Sim: 050Y240H
```

Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 240.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 240.000 | 5.000 |

| Group | Run |
|---|---|
| BASIN300&301 | Yes |

---

Name: 100Y240H Hydrology Sim: 100Y240H
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 336.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 336.000 | 15.000 |

| Group | Run |
|---|---|
| BASIN300&301 | Yes |

---

Name: PERC Hydrology Sim:
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\PERC.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 720.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 720.000 | 1.000 |

| Group | Run |
|---|---|
| BASIN300&301 | Yes |

---

Name: SJRWMD Hydrology Sim: SJRWMD
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.I32

Execute: Yes Restart: No Patch: No

Alternative: No

| | |
|---|---|
| Max Delta Z(ft): 1.00 | Delta Z Factor: 0.00500 |
| Time Step Optimizer: 10.000 | |
| Start Time(hrs): 0.000 | End Time(hrs): 120.00 |
| Min Calc Time(sec): 0.5000 | Max Calc Time(sec): 60.0000 |
| Boundary Stages: | Boundary Flows: |

| Time(hrs) | Print Inc(min) |
|---|---|
| 6.000 | 5.000 |
| 16.000 | 1.000 |
| 96.000 | 5.000 |
| 120.000 | 5.000 |

| Group | Run |
|---|---|
| BASIN300&301 | Yes |

# Grace Lake Stormwater Model

SJRWMD ERP for Grace Lake March 2014

ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)
JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT

# ERP APPLICATION NO. 4-117-121387-2
# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
# SEMINOLE COUNTY, FLORIDA

MARCH 2014

Pegasus ENGINEERING

# SJRWMD Joint Application for Individual Environmental Resource Permit

## ERP Application No. 4-117-121387-2
## Alternative Sinkhole Remediation Protocol for Grace Lake

## Acknowledgements


- Bob Dallari, District 1 Commissioner
- John Horan, District 2 Commissioner
- Lee Constantine, District 3 Commissioner
- Carton Henley, District 4 Commissioner
- Brenda Carey, District 5 Commissioner

Seminole County
Florida's Natural Choice

Antoine Khoury, P.E., Public Works Director
Brett Blackadaar, P.E., County Engineer
Mark Flomerfelt, P.E., Stormwater Capital Projects



## Certification


Pegasus Engineering

301 West SR 434, Suite 309
Winter Springs, Florida 32708
407-992-9160 (Phone) | 407-358-5155 (Fax)



The information contained within the following document was prepared by Pegasus Engineering, LLC under the supervision and direction of the respective undersigned, whose seal as a registered professional engineer is affixed below.

**SJRWMD Permit Application Package**




Greg A. Teague, P.E., CFM
Florida Registration No. 47663
March 28, 2014

**ICPR Stormwater Modeling**




Johan A. Rodriguez, P.E.
Florida Registration No. 66517
March 28, 2014

## FOREWORD

Certifications ..... i

## TAB 1: JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT

Section Description

1.1 Application Section "A" ..... 1

1.2 Application Section "A" (Maps and Other Attachments) ..... 8

1.3 Application Section "C" ..... 11

1.4 Application Section "E" ..... 22

## TAB 2: APPLICATION OVERVIEW

Section Description

2.1 Introduction and Project Overview ..... 1

2.2 Updated Surface Water Analysis ..... 4

2.3 Report Organization ..... 8

2.4 Flood Protection and the Grace Lake Overflow ..... 9
- ✓ Continuous Simulation Model ..... 10
- ✓ ICPR Stormwater Model ..... 11

2.5 Additional Permitting Considerations ..... 14
- ✓ Sovereign Submerged Lands (SSL) ..... 14
- ✓ Wetland Impact Areas ..... 14

2.6 References ..... 15

## TAB 3: SUPPORTING DOCUMENTATION FOR THE UPDATED SURFACE WATER ANALYSIS

Section Description

3.1 Companion Plans
- ✓ Sheet 1 => Cover Sheet ..... 1
- ✓ Sheet 2 => NRCS Soils and FLUCCS Land Use ..... 2
- ✓ Sheet 3 => Drainage Basins and ICPR Nodes ..... 3
- ✓ Sheet 4 => High Level Overflow Path ~ Grace Lake to Myrtle Lake ..... 4
- ✓ Sheet 5 => ICPR Nodes and Links ("Network Builder") ..... 5
- ✓ Sheet 6 => Topographic Survey Coverage ..... 6
- ✓ Sheet 7 => 100-Year Floodplains (Effective and Predicted SFHA's) ..... 7

3.2 Runoff Curve Number Computations
- ✓ Table 3.2.1 => Tabulation of Existing Soils (Organized by NRCS Soil Number) ..... 8
- ✓ Table 3.2.2 => Tabulation of Existing Soils (Organized by Hydrologic Soil Group) ..... 9
- ✓ Table 3.2.3 => Tabulation of FLUCCS Land Use Classifications ..... 10
- ✓ Table 3.2.4 => Tabulation of Runoff Curve Numbers based on Existing Land Use ..... 11
- ✓ Table 3.2.5 => Partial Tabulation of Computed Runoff Curve Numbers ..... 12

3.3 Time of Concentration Computations
- ✓ Table 3.3.1 => Partial Tabulation of Computed Times of Concentration ..... 16

## TAB 4: UPDATED SURFACE WATER ANALYSIS

Section Description

4.1 ICPR Input Data ("Grace Lake" Group) ..... 1

4.2 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 58-Ft, NAVD ..... 48

4.3 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 59-Ft, NAVD ..... 51

4.4 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 60-Ft, NAVD ..... 54

4.5 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 61-Ft, NAVD ..... 57

4.6 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 62-Ft, NAVD ..... 60

4.7 ICPR FIood Routing Results for the 100-Year, 96-Hour Storm Event ("Grace Lake" Group)
- ✓ Initial Stage => Elevation 62.6-Ft, NAVD ..... 63

## TAB 5: SUPPORTING DOCUMENTATION FOR THE CONTINUOUS SIMULATION ANALYSIS

Section Description

5.1 Rainfall vs. Discharge Volume Rating Curve for the "Up-Gradient" Drainage Basins
- ✓ Table No. 5.1.1 ~ Rainfall Events Between 0.25" and 1.25" (AMC I Condition) .....1
- ✓ Table No. 5.1.2 ~ Rainfall Events Between 1.50" and 2.50" (AMC I Condition) .....1
- ✓ Table No. 5.1.3 ~ Rainfall Events Between 3.00" and 5.00" (AMC I Condition) .....1
- ✓ Table No. 5.1.4 ~ Rainfall Events Between 6.00" and 10.00" (AMC I Condition) .....1

5.2 ICPR Flood Routing Results for the "Up-Gradient" Drainage Basins
- ✓ Time vs. Discharge Volume for Node SC-0930 (AMC I Condition).....2
- ✓ Time vs. Discharge Volume for Node SC-0990 (AMC I Condition).....12

5.3 Rainfall vs. Discharge Volume Rating Curve for the "Up-Gradient" Drainage Basins
- ✓ Table No. 5.1.5 ~ Rainfall Events Between 0.25" and 1.25" (AMC II Condition) .....22
- ✓ Table No. 5.1.6 ~ Rainfall Events Between 1.50" and 2.50" (AMC II Condition) .....22
- ✓ Table No. 5.1.7 ~ Rainfall Events Between 3.00" and 5.00" (AMC II Condition) .....22
- ✓ Table No. 5.1.8 ~ Rainfall Events Between 6.00" and 10.00" (AMC II Condition) .....22

5.4 ICPR Flood Routing Results for the "Up-Gradient" Drainage Basins
- ✓ Time vs. Discharge Volume for Node SC-0930 (AMC II Condition).....23
- ✓ Time vs. Discharge Volume for Node SC-0990 (AMC II Condition).....33

## TAB 6: CONTINUOUS SIMULATION ANALYSIS
## (PREPARED BY DEVO ENGINEERING)


## TAB 7: CONSTRUCTION PLANS
## (PREPARED BY DEVO ENGINEERING)

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

# TAB 1.2

## SECTION A: MAPS AND OTHER ATTACHMENTS




PROJECT LOCATION AND WATERSHED MAP
APPLICATION SECTION A, PART 1G

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**


**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

# TAB 2.1

## APPLICATION OVERVIEW

## 2.1 Introduction and Project Overview

Grace Lake is located north of E.E. Williamson Road, east of Interstate 4, south of Northridge Drive and west of South Ridge Lake Circle (shown on most maps as North Ridge Lake Circle) and the Bay Lagoon Subdivision.




Beginning in April of 1986, water levels in Grace Lake have been altered by a sinkhole which formed approximately 120 feet north of the single family home located at 1526 Grace Lake Circle. Although post-sinkhole water levels have fluctuated in response to seasonal weather patterns and natural plugging of the formation, the lake is typically well below the normal water level (elevation 58-ft, NAVD). Subsequently, the lake's water area is most often well below the ±22 acres that would otherwise be occupied at the normal water level.

A remediation protocol[1] for Grace Lake was first developed in 2005, with actual design, engineering, and construction plans and permitting for a different repair approach completed a few years later[2]. The St. Johns River Water Management District (SJRWMD) issued Permit No. 4-117-121387-1 on June 13, 2011 which authorized the following construction activities for the sinkhole repair project.

- Installation of sheet pile panels to form a square-shaped coffer dam around the perimeter of the existing sinkhole formation.

- Backfilling inside and outside the sheet pile panels in alternating layers of rubble riprap and soil.

- Compaction grouting within the sinkhole and around the perimeter of the cofferdam in an effort to stabilize the subsurface soils.

- Although the repairs were focused upon stabilizing the existing sinkhole, water levels within Grace Lake would not be completely restored to pre-sinkhole (historical) conditions.

Because the bid documents[2] for the above sinkhole repairs were never finalized, Seminole County authorized additional work to investigate alternative options that could be more cost-effective and potentially more beneficial in terms of restoring water levels in Grace Lake to pre-sinkhole conditions. As part of this new authorization, the team of Devo Engineering and Pegasus Engineering has been tasked with the following scope of work.

<u>Devo Engineering</u>

- Investigate and evaluate various repair options and develop an alternative sinkhole remediation protocol.

- Develop a continuous simulation model to assess the performance characteristics of the alternative sinkhole remediation protocol in terms of both restoring the lake hydroperiod and maintaining adequate flood protection.

- Develop bid documents (construction plans and technical specifications) for the construction activities associated with the alternative sinkhole remediation protocol.

<u>Pegasus Engineering</u>

- Review and revise (if necessary) the surface water analysis developed for the original sinkhole remediation program. As part of this evaluation process, the high-level overflow path from Grace Lake to Myrtle Lake will also be confirmed, revised and/or refined.

- Utilize the updated surface water analysis to predict 100-year flood elevations, taking into account any changes to the Grace Lake hydroperiod associated with the proposed alternative sinkhole remediation protocol.

[1] Geotechnical Engineering Report for the Grace Lake Sinkhole Restoration (Devo Engineering, April 2005).
[2] Sinkhole repair improvements developed jointly by Professional Service Industries (PSI) and HDR Engineering.

- Evaluate flood protection issues and concerns relative to regulations associated with FEMA's National Flood Insurance Program (NFIP).

- Perform additional stormwater model simulation scenarios in support of the continuous simulation model being developed by Devo Engineering. More specifically, rating curves will be developed to quantify the discharge volume for inflows to Grace Lake that are outside the limits of the "direct rainfall" basin. Simulated rainfall will be increased (on an incremental basis) to encompass the actual rainfall for the period of record to be evaluated by the continuous simulation model.


- Prepare a SJRWMD permit application package to modify the previously approved permit for the alternative sinkhole remediation protocol.


⌖ ⌖ ⌖

## 2.2 Updated Surface Water Analysis

The original sinkhole remediation program included the development of a surface water analysis for the drainage area that contributes stormwater runoff to Grace Lake. Although the surface water analysis was revised several times, research efforts[3] indicate that the final ICPR stormwater model was published within a response to the District's request for information (RAI) entitled "Grace Lake - Analysis of Sinkhole Repair, Permit Application Report RAI Update" (prepared by HDR and dated stamped received by the District on April 26, 2011).

In September 2011, final deliverables were published for the City of Longwood Stormwater Master Plan. More specifically, Phase 3 of Longwood's Stormwater Master Plan provided an existing conditions analysis and stormwater modeling for most of the drainage basins that encompass the City, including a significant portion of the Grace Lake watershed.





The original scope of work for the current project envisioned various activities related to reviewing, updating and revising the original surface water analysis for Grace Lake that was ultimately approved by the District under Permit No. 4-117-121387-1 dated June 13, 2011. However, the existing conditions analysis and stormwater modeling developed as part of Longwood's Stormwater Master Plan provides more current and comprehensive information, with several distinct benefits as summarized below.

- **Watershed Interactions**. As illustrated on the following figure, the Grace Lake watershed can potentially interact with several adjacent watersheds during large storm events that produce stages that rise above topographic ridges that define surface water basins.

[3] Seminole County and SJRWMD archives.




Pegasus ENGINEERING


301 West SR 434, Suite 309 • Winter Springs, Florida 32708

Tel 407-992-9160 | Fax 407-358-5155 | Web www.pegasusengineering.net

**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

**FIGURE NO. 2-1**
**GRACE LAKE WATERSHED INTERACTION**

- **Rock Lake Overflow Patterns**. Although Rock Lake had a historical discharge to Twin Lakes, the pipe connection on Sweetbriar Branch Boulevard was plugged at some point in time. Existing topography indicates that overflow from Rock Lake could potentially occur to the north (across Sweetbriar Branch Boulevard to Twin Lakes) or to the southeast (to Mud Lake within the Soldiers Creek watershed). Both of these high-level overflows, which essentially occur at the same elevation, are included within Longwood's Stormwater Master Plan (as shown below), whereas, only the north overflow was included within the original surface water analysis for Grace Lake.




Excerpt from Longwood's Stormwater Master Plan (Phase 3 - Existing Conditions Analysis and Stormwater Modeling)

It should be noted that the City of Longwood has implemented emergency pumping operations at Rock Lake in the past (during periods of high water and potential flooding), with various force mains and hoses connected to existing drainage systems that eventually result in discharge from Rock Lake to Mud Lake. For this reason, Rock Lake (a ±70-acre watershed) will not be included within the contributing drainage area for the Grace Lake watershed, although overflow discharge is accounted for in the updated surface water analysis as previously discussed.

- **Information Accuracy**. Phase 2 of Longwood's Stormwater Master Plan included the development of a comprehensive drainage inventory, encompassing both primary and secondary drainage systems. To facilitate the existing conditions analysis and stormwater modeling associated with Phase 3 of Longwood's Stormwater Master Plan, topographic surveys were completed for all of the drainage systems to be included within the ICPR stormwater model. Generally speaking, relying on comprehensive survey information is typically more reliable than developing stormwater model input data from "best available information", which is often derived from approximate sources or altered by some type of datum shift to maintain elevation consistency.

- **Elevation Datum Consistency**. Longwood's Stormwater Master Plan was developed with all elevation information referenced to the NAVD vertical datum, which provides for improved accuracy and consistency with information presented within FEMA's National Flood Insurance Program (NFIP).

  Unless specified otherwise, elevations presented throughout this report are referenced to the NAVD vertical datum. In the event that elevation information referenced to the NGVD vertical datum was used, a datum shift of 1.03 feet was applied as a constant conversion to the NAVD vertical datum. In some cases, an approximate datum shift of 1 foot was used.

- **Areal Extent of the Revision Area**. Because Longwood's Stormwater Master Plan included a large portion of the Grace Lake watershed with a northern terminus located just south of E.E. Williamson Road, only the land areas located north of E.E. Williamson Road had to be appended for the purpose of developing the updated surface water analysis. Because the ICPR input data for the updated surface water analysis was obtained from a variety of different sources, substantial information was added to the ICPR comment fields to provide the necessary reference citations. Because portions of the original surface water analysis were used to incorporate the northern extent of the Grace Lake watershed, consistency with current conditions was confirmed by field reviews performed by Pegasus Engineering staff.

- **Minimizing Modeling Assumptions.** A number of modeling assumptions were presented within the engineering narrative for the original surface water analysis, some of which related to a previous drainage study[4] and to various drainage systems and their intended discharge patterns throughout the Grace Lake watershed.

- **SJRWMD Considerations**. Pursuant to previous conversations with District staff, using a stormwater model that was previously developed as part of a comprehensive and/or large scale master plan is acceptable. However, the application submittal should only include whatever portion of the stormwater model that is necessary to support the proposed improvements (i.e., the District does not want to approve the entire model as part of the County's application for this project).

⌖ ⌖ ⌖

[4] Engineering Study and Drainage Inventory for the Soldiers Creek Basin (Singhofen & Associates, December 1996).

## 2.3 Report Organization

In support of this application overview and the updated surface water analysis for Grace Lake, the following full size exhibits (24" x 36" set is to scale) are provided as an external attachment to this report. For the reader's convenience, a reduced size set of exhibits (11" x 17" is not to scale) is also provided later within this narrative. These mapping exhibits should be considered equally important companion material that provides graphical representations of the drainage basins and drainage systems that are germane to the updated surface water analysis for Grace Lake.

| COMPANION PLANS | |
|---|---|
| Sheet | Exhibit Name |
| 1 | Cover Sheet |
| 2 | NRCS Soils and FLUCCS Land Use |
| 3 | Drainage Basins and ICPR Nodes |
| 4 | High Level Overflow Path ~ Grace Lake to Myrtle Lake |
| 5 | ICPR Nodes and Links ("Network Builder") |
| 6 | Topographic Survey Coverage |
| 7 | 100-Year Floodplains (Effective and Predicted SFHA's) |


In keeping with the District's directive relative to submitting information associated with a comprehensive and/or large scale master plan, mapping exhibits (companion plans) and printouts from the stormwater model will be limited to the northern extent of the Grace Lake watershed (ICPR Group "Grace Lake"). Additional information (outside of these limits) can be obtained from Longwood's Stormwater Master Plan and is available upon request.

⌖ ⌖ ⌖

## 2.4 Flood Protection and the Grace Lake Overflow

As part of the alternative sinkhole remediation protocol, County staff emphasized the significance of ensuring adequate flood protection for both existing property and developed parcels located contiguous to Grace Lake and elsewhere within upstream portions of the watershed. Therefore, and in addition to updating the surface water analysis as previously discussed herein, current work efforts focused upon "where" and at "what elevation" Grace Lake overflows.

As shown below, the original drainage basin map for Interstate 4 (circa 1962) provides a historical illustration of Grace Lake before the Interstate was constructed. A narrow waterway (creek or stream) is shown to connect the north and south portions of Grace Lake, with a substantial land area that separates Grace Lake from Myrtle Lake. High water elevations associated with Hurricane Donna (circa September 1960) are shown for Myrtle Lake as well as the north and south portions of Grace Lake at elevations 57.3', 59.9' and 65.5', respectively. Given the age of this information, the high water elevations are believed to be referenced to the NGVD vertical datum.




Because the Interstate 4 alignment bisected both the north and south portions of Grace Lake, culverts were constructed to maintain water conveyance to and from the connecting waterway as discussed above. Current aerial photography indicates that the land areas surrounding Grace Lake are almost entirely developed. Furthermore, development on the west side of Interstate 4 has impacted most of the natural waterway that connected the north and south portions of Grace Lake.

A combination of archival research and field reviews conducted by Pegasus Engineering staff resulted in developing a current illustration of the high-level overflow path(s) between Grace Lake and Myrtle Lake (refer to Sheet 4 of the companion plans), the most important aspects of which are summarized below.

- Once the water flow path(s) was accurately defined, the various conveyance elements (drainage pipes, topographic saddles associated with overland flow, etc.) were identified and surveyed.

- Although the reader is referred to the table that summarizes the conveyance elements and elevations, the critical elevation for the Grace Lake overflow occurs on the west side of Interstate 4 at approximate elevation 62.6-ft, NAVD.

- Two (2) different overflow paths were identified for Grace Lake, with the western (historical) overflow designated as "primary" and the northern overflow designated as "secondary". Although both of these high-level overflows are included within the stormwater model for the updated surface water analysis, the conveyance capacity of the northern ("secondary") overflow is very limited until stages exceed elevation 67.9-ft, NAVD. Therefore, the "primary" overflow path is also considered to be the most probable.

Flood protection for this project will be quantitatively evaluated using two (2) different analysis methodologies as discussed below.

Continuous Simulation Model

Although the reader is referred to the engineering narrative provided within the following **Tabbed Section 6** of this report, the following points are provided to emphasize the significance of the continuous simulation modeling for this project.

- A continuous simulation model was required to address the unique hydrogeology of Grace Lake, including infiltration aspects associated with the natural lake bottom, the existing sinkhole and the post-sinkhole condition after the repairs have been completed.

- The continuous simulation model provides an analysis of actual recorded rainfall over a sufficiently long period of time. Flood protection for proposed conditions (post-sinkhole repairs) can be evaluated and compared to what actually occurred in the past (pre-sinkhole repairs), inclusive of any tropical storms and/or hurricanes during the period of record.


- Prior experience with similar projects indicates that continuous simulation (extended duration) modeling of Grace Lake (including discharge from the up-gradient basins) is an acceptable analysis methodology[5].

[5] In lieu of the District's presumptive criteria related to hypothetical storm events of specific frequency and duration.

ICPR Stormwater Model

The updated surface water analysis for Grace Lake was developed for several different reasons, with some of the most important considerations summarized below.

- It should be noted that most of the narrative discussions presented within the original surface water analysis for Grace Lake were correct in terms of describing the western ("primary") overflow path. However, overflow discharge between the northern culvert crossing Interstate 4 and the existing drainage systems along North Ridge Lake Circle and Windy Bluff Point was not defined and therefore not included within the stormwater model (i.e., the western overflow path was incorrectly terminated within the stormwater model). As shown on the graphic below, this portion of the outfall path that was excluded from the original surface water analysis corresponds to Locations "L" through "Q".




- The original surface water analysis included all of the drainage conveyance elements located between North Ridge Lake Circle, Windy Bluff Point and Myrtle Lake. However, the water surface elevations fall dramatically to the east of North Ridge Lake Circle and Windy Bluff Point. As such, the updated surface water analysis includes a stage versus time boundary condition at a location just east of Windy Bluff Point. Water surface elevations downstream of this location will not influence peak flood stages within Grace Lake or induce tailwater on the Grace Lake overflow (i.e., free discharge).

- Information was obtained from the updated surface water analysis (the ICPR node time series report) in support of the continuous simulation model. More specifically, and as summarized within the following **Tabbed Section 5** of this report, rating curves were developed to quantify the rainfall depth versus discharge volume for inflows to Grace Lake from the "up-gradient" basins. As shown on Sheet 3 of the companion plans, discharge volume from the "up-gradient" basins was obtained from ICPR Node SC-0930 (outfall ditch along the east side of Interstate 4) and ICPR Node SC-0990 (discharge end of the outfall system from the Woodlands Elementary School pond). Seasonal variation in surface runoff volume was encompassed by developing rating curves for both AMC I and AMC II conditions.

- Predicted flood elevations for proposed conditions (post-sinkhole repairs) were used to evaluate flood protection relative to regulations associated with FEMA's National Flood Insurance Program (NFIP). More specifically, the 100-year, 96-hour storm event, with a total rainfall depth of 15-inches, was used to define special flood hazard areas (SFHA's) and the potential for flooding.

| FEMA Flood Insurance Study for Seminole County (September 28, 2007) | | | | |
|---|---|---|---|---|
| Flooding Source | Summary of Stillwater Elevations (ft, NAVD) | | | |
| | 10% (10-Year) | 2% (50 Year) | 1% (100 Year) | 0.2% (500 Year) |
| Grace Lake | 66.3 | 67.0 | 67.1 | 67.2 |

- Rating curves were used in the original surface water analysis to quantify the vertical leakage (infiltration) through the natural lake bottom and/or the sinkhole formation, whereas, vertical leakage (infiltration) will not be included in the updated surface water analysis. Although vertical leakage would have a measurable impact on reducing the duration of flooding (storage recovery), it would have little to no effect upon lowering peak stages which is the primary focus of the updated surface water analysis.

- The updated surface water analysis is defined as a "proposed conditions" evaluation, although it is important to clarify that it could also be defined as a "historic conditions" evaluation before the sinkhole formed (i.e., proposed conditions is attempting to return the lake hydroperiod to the historic condition). An analysis of "current conditions" would be significantly different and would have to include infiltration estimates for the current sinkhole in terms of both discharge volume and altering (lowering) the lake hydroperiod as reflected by the initial stage.


- Because the proposed hydroperiod is somewhat variable, the chart on the following page provides an array of peak flood elevations that were predicted for a range of initial stages that should be representative of post-sinkhole conditions within Grace Lake. It should be noted that the effective base flood elevation (BFE) was computed in accordance with FEMA's criteria[6], which assumes an initial stage in Grace Lake that corresponds to the "brim full" condition (where water is coincident with the lowest overflow elevation).

- Regarding flood protection issues and concerns, the reader is referred to Sheet 7 of the companion plans for a graphical representation of 100-year floodplains. In addition to providing an illustration of FEMA's effective SFHA's for the Grace Lake vicinity, additional floodplains are also shown based on the predicted flood elevations as previously discussed.

  Although finished floor elevations were previously surveyed for all of the residential properties contiguous to Grace Lake, the County should consider additional finished floor elevation surveys in the future to better assess flood protection issues and concerns for all of the floodplains shown on Sheet 7 of the companion plans.

⌖ ⌖ ⌖

[6] Managing Floodplain Development in Approximate Zone "A" Areas: A Guide for Obtaining and Developing Base (100-Year) Flood Elevations (FEMA 265).




Pegasus ENGINEERING

## 2.5 Additional Permitting Considerations

Sovereign Submerged Lands (SSL)

An excerpt from the District's Technical Staff Report (TSR) for SJRWMD Permit No. 4-117-121387-1 dated June 13, 2011 is provided below and should allay any potential SSL issues for the alternative sinkhole remediation protocol and specifically the current permit modification.

> *The proposed activity will be wholly located within Grace Lake. Per correspondence received by the District on May 18, 2004 from the Florida Department of Environmental Protection (FDEP), the proprietary requirements that would normally apply to state owned lands will not be applied to Grace Lake.*

Wetland Impact Areas

The District's Technical Staff Report (TSR) for SJRWMD Permit No. 4-117-121387-1 dated June 13, 2011 also provides the following breakdown for wetland impact areas that were anticipated for the original sinkhole repair project.

- Temporary wetland impact area ..... 3.66 acres
- Permanent wetland impact area ..... 0.06 acres
- Total wetland impact area ..... 3.72 acres

The temporary impact area shown above included clearing and grubbing activities associated with both construction ingress/egress and staging of equipment and materials. Given that the alternative sinkhole remediation protocol for Grace Lake is not significantly different than what was authorized within the previous approval, no change in the wetland impact areas is proposed as part of the current permit modification.

⌖ ⌖ ⌖

## 2.6 References (in chronological order)

1. Original Drainage Map for Interstate 4 (Grace Lake Vicinity) ..... 1962
   - Florida Department of Transportation (FDOT)

2. Seminole County Soil Survey ..... June 1966
   - Soil Conservation Services (SCS)

3. Seminole County Soil Survey Supplement ..... September 1975
   - Soil Conservation Services (SCS)

4. Stormwater Management System Design and
   Permit Calculations for Northridge Subdivision ..... April 1984
   - CPH Engineers, Inc.

5. Revised Surface Water Management Calculations for Northridge Subdivision (Phase 3)..... April 1985
   - CPH Engineers, Inc.

6. As-built Plans for Northridge Subdivision ..... May 1985
   - CPH Engineers, Inc.

7. Permit for the Interstate 4 Widening (SR 434 to Lake Mary Boulevard) ..... January 10, 1995
   - SJRMWD Permit No. 4-117-22434-1

8. Permit for the Interstate 4 Rest Area Expansion at Lake Mary..... July 8, 1998
   - SJRMWD Permit No. 4-117-22434-2

9. Permit for the Woodlands Elementary School Addition and Renovation..... July 27, 1999
   - SJRMWD Permit No. 42-117-49356-2

10. Engineering Study and Drainage Inventory for the Soldiers Creek Basin ..... December 1996
    - Singhofen & Associates (under contract with Seminole County)

11. LiDAR Topography for the Grace Lake Vicinity..... 2005
    - Watershed Concepts (under contract with Seminole County)
    - St. Johns River Water Management District (3-dimensional data set in the form of LAS files)

12. Geotechnical Engineering Report for Grace Lake Sinkhole Restoration ..... April 2005
    - Devo Engineering

13. Topographic surveys for the Grace Lake Vicinity ..... December 2007
    - Southeastern Surveying and Mapping Corporation (Project No. 53087001)

14. Countywide FEMA application for Letter of Map Revision (LOMR)..... 2007
    - Watershed Concepts (under contract with Seminole County)

15. Flood Insurance Study (FIS) for Seminole County ..... September 28, 2007
    - Federal Emergency Management Agency (FEMA)

16. Permit for the Woodlands Elementary School Pond Modification.....November 21, 2007
    - SJRMWD Permit No. 42-117-49356-3

17. Geotechnical Engineering Services Report - Grace Lake Sinkhole Repair Study..... March 2008
    - Professional Service Industries (PSI)

18. Permit for the Bella Tuscany Subdivision..... October 24, 2008
    - SJRMWD Permit No. 42-117-49356-4

19. Grace Lake - Analysis of Sinkhole Repair.....April 2011 (Final Version)
    - HDR Engineering, Inc.

20. Construction Plans (90%) for the Grace Lake Sinkhole Repair Project .....April 2011
    - HDR Engineering, Inc.

21. Permit for the Grace Lake Sinkhole Repair Project..... June 13, 2011
    - SJRMWD Permit No. 4-117-121387-1

22. Topographic surveys for the Grace Lake Vicinity ..... August 2013
    - Southeastern Surveying and Mapping Corporation (Project No. 53087001)

⌖ ⌖ ⌖

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**


# TAB 3.1

SUPPORTING DOCUMENTATION FOR THE
UPDATED SURFACE WATER ANALYSIS


COMPANION PLANS
(11" X 17" NOT TO SCALE)

# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE

**COMPANION PLANS FOR THE UPDATED SURFACE WATER ANALYSIS**


STUDY AREA FOR THE UPDATED SURFACE WATER ANALYSIS
GRACE LAKE WATERSHED
LONGWOOD STUDY AREA (STORMWATER MASTER PLAN)
GRACE LAKE
TWIN LAKES
ISLAND LAKE
WINSOR LAKE
ROCK LAKE
MUD LAKE
MYRTLE LAKE
LAKE ALMA
LAKE TIBERON
WEST LAKE
LAKE SEARCY
EAST LAKE
NORTHSIDE LAKE
LAKE HORTON
LAKE RUTH
CRANE LAKE
BIRD LAKE
PELICAN LAKE
GULL LAKE
BOAT LAKE
LAKE WAYMAN
LAKE LUCERN
LAKE ORANGE
LAKE GEM
LAKE TALMO
LAKE EVERGREEN
LAKE IRENE
LAKE JANE
LAKE WILDMERE
LITTLE LAKE WILDMERE
FERN LAKE
FAIRY LAKE
LAKE KATHRYN
LAKE SEMINOLE
LAKE ELAINE
LAKE PHYLLIS
LAKE MARION
LAKE FRANCES
TROUT LAKE
LAKE GRIFFIN
OAK LAKE
ACORN LAKE
LAKE VERONA
LAKE SUNSET
LAKE SYLVIA
LAKE SUSAN
LAKE SHERWOOD
LAKE DESTINY
LAKE CHARLOTTE
LAKE MARGARET
LAKE EMMA
LAKE BARRINGTON
LAKE SUZY
LAKE WILLIAM
LAKE ANNE
LAKE ANGELINE
LAKE ADELINE
LAKE ROSALIND
LAKE MARY JANE
LAKE HOWELL
LAKE CHARM
LAKE ORIENTA
LAKE MARIAN
LAKE MARIE
LAKE MARTHA
LAKE MARK
LAKE MARGUERITE
LAKE MARIETTA
LAKE MARILYN
LAKE MARVIN
LAKE MARGARET

## NRCS SOILS





**Legend**

- SOIL HSG "A"
- SOIL HSG "D"
- WATER
- SUB-BASIN LIMITS
- XX-XXX SUB-BASIN NAME

NOTE:

1. HYDROLOGIC SOIL GROUPS (HSG) AS PRESENTED WITHIN THE NRCS SOIL SURVEY (LATEST INFORMATION PRESENTED WITHIN THE WEB SOIL SURVEY). HSG FOR SOILS MAPPED AS "URBAN LAND" WAS ASSIGNED BASED UPON INFORMATION PRESENTED WITHIN THE ORIGINAL NRCS SOIL SURVEY (1966) AND SUPPLEMENT (1975) THERETO.

## FLUCCS LAND USE




**Legend**

- SUB-BASIN LIMITS
- XX-XXX SUB-BASIN NAME
- 100 LAND USE FLUCCS CODE

| FLUCCS LAND-USE CLASSIFICATION CODE | FLUCCS LAND-USE CLASSIFICATION DEFINITION |
|---|---|
| 110 | Residential, Low Density (<2 DU/acre) |
| 120 | Residential, Medium Density (2-5 DU/acre) |
| 140 | Commercial and Services |
| 170 | Institutional |
| 172 | Religious |
| 190 | Open Land |
| 400 | Upland Forests |
| 520 | Lakes |
| 530a | Reservoirs (Normally Dry) |
| 530b | Reservoirs (Normally Wet) |
| 640 | Vegetated Non-Forested Wetlands |
| 643 | Wet Prairies |
| 814 | Roads and Highways |

0' 300' 1" = 300'

| REV. | DATE | DESCRIPTION |
|---|---|---|

SEMINOLE COUNTY
FLORIDA'S NATURAL CHOICE

# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE

## NRCS SOILS AND FLUCCS LAND USE


Pegasus Engineering, LLC
301 West SR 434, Suite 309
Winter Springs, Florida 32708

Office (407) 992-9160
Fax (407) 358-5155

State of Florida Board of Professional Engineers
Certificate of Authorization No. 27770


| | |
|---|---|
| JOB NO.: | SMC-014 |
| DESIGNED BY: | JAR |
| DRAWN BY: | JJB |
| APPROVED BY: | DWH |
| DATE: | SEPT 2013 |

SHEET 2 OF 7

NOT A FINAL PLAN UNLESS SIGNED AND SEALED

JOHAN RODRIGUEZ, P.E.
REGISTRATION No. 66517

DATE: _____

0' 200'

1" = 200'

| REV. | DATE | DESCRIPTION |
|---|---|---|
| | | |

SEMINOLE COUNTY
FLORIDA'S NATURAL CHOICE

# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE

## DRAINAGE BASINS AND ICPR NODES


Pegasus ENGINEERING

Pegasus Engineering, LLC
301 West SR 434, Suite 309
Winter Springs, Florida 32708

Office (407) 992-9160
Fax. (407) 358-5155

State of Florida Board of Professional Engineers
Certificate of Authorization No. 27770


| | |
|---|---|
| JOB No.: | SMC-014 |
| DESIGNED BY: | JAR |
| DRAWN BY: | JJB |
| APPROVED BY: | DWH |
| DATE: | SEPT 2013 |


SHEET 3 OF 7

NOT A FINAL PLAN UNLESS SIGNED AND SEALED

JOHAN A. RODRIGUEZ, P.E.
REGISTRATION No. 66517

DATE: _____


## ICPR BASIN AND NODE LEGEND




ICPR NODES
- A: => STAGE / AREA
- V: => STAGE / VOLUME
- T: => STAGE / TIME
- M: => MANHOLE


ICPR BASINS
- O: => OVERLAND FLOW
- U: => SCS UNIT HYDROGRAPH
- S: => SANTA BARBARA

## ICPR LINK LEGEND




ICPR LINKS
- P: => PIPES
- W: => WEIR
- C: => CHANNEL
- D: => DROP STRUCTURE
- B: => BRIDGE
- R: => RATING CURVE
- H: => BREACH

PEGASUS ENGINEERING LINKS
- - P => PIPES
- - W => WEIR
- - R => WEIR (ROADWAY OVERTOPPING)
- - C => CHANNEL
- - D => DROP STRUCTURE
- - B => BRIDGE
- - RC => RATING CURVE




N.T.S.

DATE

REV.

# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE

## ICPR NODES AND LINKS ("NETWORK BUILDER")


Pegasus Engineering, LLC
301 West SR 434, Suite 309
Winter Springs, Florida 32708

Office (407) 992-9160
Fax. (407) 358-5155

State of Florida Board of Professional Engineers
Certificate of Authorization No. 27770



| | |
|---|---|
| JOB No.: | SMC-014 |
| DESIGNED BY: | JAR |
| DRAWN BY: | JJB |
| APPROVED BY: | DWH |
| DATE: | SEPT 2013 |

SHEET 5 OF 7

NOT A FINAL PLAN UNLESS SIGNED AND SEALED

JOHAN A. RODRIGUEZ, P.E.
REGISTRATION No. 66517

DATE: _____




DESCRIPTION | DATE | REV.

SEMINOLE COUNTY
FLORIDA'S NATURAL CHOICE

# ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE

## 100-YEAR FLOOD PLAINS (EFFECTIVE AND PREDICTED SFHA'S)


Pegasus ENGINEERING

Pegasus Engineering, LLC
301 West SR 434, Suite 309
Winter Springs, Florida 32708

Office (407) 992-9160
Fax (407) 358-5155

State of Florida Board of Professional Engineers
Certificate of Authorization No. 27770


| | |
|---|---|
| JOB NO.: | SMC-014 |
| DESIGNED BY: | JAR |
| DRAWN BY: | JJB |
| APPROVED BY: | DWH |
| DATE: | SEPT 2013 |

SHEET 7 OF 7

NOT A FINAL PLAN UNLESS SIGNED AND SEALED

JOHAN RODRIGUEZ, P.E.
REGISTRATION No. 66517

DATE: _____

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

# TAB 3.2

## SUPPORTING DOCUMENTATION FOR THE UPDATED SURFACE WATER ANALYSIS

## RUNOFF CURVE NUMBER COMPUTATIONS

**Alternative Sinkhole Remediation Protocol for Grace Lake**
**Tabulation of Existing Soils (Organized By NRCS Soil Number)**

Table No. 3.2.1

| SOIL NUMBER | SOIL NAME | NRCS HSG [1] | ASSIGNED HSG [1, 2] | FLOODING | | | HIGH WATER TABLE | |
|---|---|---|---|---|---|---|---|---|
| | | | | FREQUENCY | DURATION | MONTHS | DEPTH (ft) [3] | MONTHS |
| 6 | Astatula-Apopka fine sands, 0 to 5 percent slopes | A | A | None | - - - | - - - | > -6.0 | - - - |
| 7 | Astatula-Apopka fine sands, 5 to 8 percent slopes | A | A | None | - - - | - - - | > -6.0 | - - - |
| 8 | Astatula-Apopka fine sands, 8 to 12 percent slopes | A | A | None | - - - | - - - | > -6.0 | - - - |
| 10 | Basinger, Samsula, and Hontoon soils, depressional | A/D | D | None | - - - | - - - | +2.0 to 0.0 | Jun - Feb, Jan - Dec |
| 20 | Myakka and Eau Gallie fine sands | A/D | D | None | - - - | - - - | 0.0 to -1.0 | Jun - Oct |
| 31 | Tavares-Millhopper fine sands, 0 to 5 percent slopes | A | A | None | - - - | - - - | -3.5 to -6.0 | Jul - Dec |
| 34 | Urban land, 0 to 12 percent slopes | - | A | None | - - - | - - - | > -2.0 | - - - |

SOURCE NRCS Soil Survey of Seminole County
Issued September 2012

NOTES

[1] HSG => Hydrologic Soil Group

[2] Assigned HSG applies to any mapping units classified with either a dual hydrologic soil group or if NRCS data was unavailable.

[3] A plus sign under "Depth to high water table" indicates that the water table is above the surface of the soil.

[3] A minus sign under "Depth to high water table" indicates that the water table is below the surface of the soil.

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Tabulation of Existing Soils (Organized By Hydrologic Soil Group)

Table No. 3.2.2

| SOIL NUMBER | SOIL NAME | HYDROLOGIC SOIL GROUP | | SOIL BREAKDOWN | |
|---|---|---|---|---|---|
| | | NRCS | ASSIGNED | AREA (ac) | PERCENT |
| TYPE "A" SOILS | | | | | |
| 6 | Astatula-Apopka fine sands, 0 to 5 percent slopes | A | A | | |
| 7 | Astatula-Apopka fine sands, 5 to 8 percent slopes | A | A | | |
| 8 | Astatula-Apopka fine sands, 8 to 12 percent slopes | A | A | | |
| 31 | Tavares-Millhopper fine sands, 0 to 5 percent slopes | A | A | | |
| 34 | Urban land, 0 to 12 percent slopes | N/A | A | | |
| | | Sub-total | | 332.1 | 84.7% |
| TYPE "B" SOILS | | | | | |
| | | | | | |
| | | Sub-total | | 0.0 | 0.0% |
| TYPE "C" SOILS | | | | | |
| | | | | | |
| | | Sub-total | | 0.0 | 0.0% |
| TYPE "B/D" and "D" SOILS | | | | | |
| 10 | Basinger, Samsula, and Hontoon soils, depressional | A/D | D | | |
| 20 | Myakka and Eau Gallie fine sands | A/D | D | | |
| | | Sub-total | | 60.0 | 15.3% |
| "OTHER" SOILS | | | | | |
| 99 | Water | N/A | W | | |
| | | Sub-total | | 0.0 | 0.0% |
| | | Totals | | 392.1 | 100.0% |

SOURCE NRCS Soil Survey of Seminole County
Issued September 2012

NOTES [1] Hydrologic soil group not identified within the NRCS soil survey, and was therefore assigned using narrative discussions provided within the NRCS map unit descriptions.

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Tabulation of FLUCCS Land Use Classifications

Table No. 3.2.3

| FLUCCS LAND-USE CLASSIFICATION CODE | FLUCCS LAND-USE CLASSIFICATION DEFINITION | LAND USE BREAKDOWN | |
|---|---|---|---|
| | | AREA (ac) | PERCENT |
| 110 | Residential, Low Density (<2 DU/acre) | 89.1 | 22.7% |
| 120 | Residential, Medium Density (2-5 DU/acre) | 168.9 | 43.1% |
| 140 | Commercial and Services | 2.4 | 0.6% |
| 170 | Institutional | 16.5 | 4.2% |
| 172 | Religious | 5.4 | 1.4% |
| 190 | Open Land | 10.7 | 2.7% |
| 400 | Upland Forests | 26.5 | 6.8% |
| 520 | Lakes | 22.1 | 5.6% |
| 530a | Reservoirs (Normally Dry) | 4.1 | 1.0% |
| 530b | Reservoirs (Normally Wet) | 2.3 | 0.6% |
| 640 | Vegetated Non-Forested Wetlands | 6.2 | 1.6% |
| 643 | Wet Prairies | 1.2 | 0.3% |
| 814 | Roads and Highways | 36.8 | 9.4% |
| | Totals | 392.1 | 100.0% |

REFERENCE Florida Land Use, Cover, and Forms Classification System (FLUCCS)
Florida Department of Transportation (FDOT)
January 1999

NOTES Land use delineations dated 2004 were obtained from the St. Johns River Water Management District (SJRWMD) Geographi Information System (GIS) and updated as necessary using aerial photography dated 2008. Land use polygons wer subsequently aggregated to combine land uses with similar FLUCCS codes into larger delineations

**Alternative Sinkhole Remediation Protocol for Grace Lake**
**Tabulation of Runoff Curve Numbers Based On Existing Land Use**

Table No. 3.2.4

| FLUCCS LAND USE CLASSIFICATION [1] | | USDA TR-55 COVER DESCRIPTION | CURVE NUMBER FOR HYDROLOGIC SOIL GROUP [3] | | | |
|---|---|---|---|---|---|---|
| NUMBER | DEFINITION [2] | | A | B | C | D |
| 110 | Residential, Low Density (<2 DU/acre) | 1 acre avg. lot (avg. 20% imp.) | 51 | 68 | 79 | 84 |
| 120 | Residential, Medium Density (2-5 DU/acre) | 1/3 acre avg. lot (avg. 30% imp.) | 57 | 72 | 81 | 86 |
| 140 | Commercial and Services | Commercial and Business (avg. 85% imp.) | 89 | 92 | 94 | 95 |
| 170 | Institutional | Average 50% imp. | 69 | 80 | 86 | 89 |
| 172 | Religious | Average 50% imp. | 69 | 80 | 86 | 89 |
| 185 | Parks | Average 20% imp. | 51 | 68 | 79 | 84 |
| 190 | Open Land | Open space (grass cover 50% to 75%) | 49 | 69 | 79 | 84 |
| 400 | Upland Forests | Woods (good cond.) | 39 | 55 | 70 | 77 |
| 520 | Lakes | Water | 100 | 100 | 100 | 100 |
| 530a | Reservoirs (Normally Dry) | Open space (grass cover 50% to 75%) | 49 | 69 | 79 | 84 |
| 530b | Reservoirs (Normally Wet) | Water and Open Space (grass cover >75%) | 92 | 92 | 92 | 92 |
| 640 | Vegetated Non-Forested Wetlands | SJRWMD Tech Pub. #85-5, Table 2 | 98 | 98 | 98 | 98 |
| 643 | Wet Prairies | SJRWMD Tech Pub. #85-5, Table 2 | 98 | 98 | 98 | 98 |
| 814 | Roads and Highways | Average 50% imp. | 69 | 80 | 86 | 89 |

NOTES

[1] Florida Land Use, Cover, and Forms Classification System (FLUCCS)
Florida Department of Transportation (FDOT)
January 1999

[2] Land use delineations dated 2004 were obtained from the St. Johns River Water Management District (SJRWMD) Geographic Information System (GIS) and updated as necessary using aerial photography flown in 2009.
http://www.sjrwmd.com/gisdevelopment/docs/themes.html

[3] Technical Release 55, Soils Conservation Service, June 1986 (second edition)

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Partial Tabulation of Computed Runoff Curve Numbers

**Table No. 3.2.5**

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0770 | 120 | A | 57 | 16.48 | 939.63 | |
| SC-0770 | 120 | D | 86 | 0.38 | 32.33 | |
| SC-0770 | 190 | A | 49 | 0.49 | 23.88 | |
| SC-0770 | 190 | D | 84 | 0.63 | 52.99 | |
| SC-0770 | 400 | A | 39 | 0.01 | 0.26 | |
| SC-0770 | 814 | D | 89 | 0.03 | 3.00 | |
| | | | **Totals** | **18.02** | **1,052.07** | **58.39** |
| | | | | | | |
| SC-0800A | 120 | A | 57 | 0.12 | 6.85 | |
| SC-0800A | 190 | A | 49 | 0.25 | 12.44 | |
| SC-0800A | 190 | D | 84 | 2.25 | 188.61 | |
| SC-0800A | 400 | A | 39 | 1.18 | 45.95 | |
| SC-0800A | 400 | D | 77 | 2.31 | 177.76 | |
| SC-0800A | 814 | A | 69 | 0.24 | 16.54 | |
| SC-0800A | 814 | D | 89 | 0.40 | 35.43 | |
| SC-0800A | 530a | D | 84 | 2.23 | 187.53 | |
| | | | **Totals** | **8.98** | **671.11** | **74.76** |
| | | | | | | |
| SC-0800B | 120 | A | 57 | 0.92 | 52.55 | |
| SC-0800B | 120 | D | 86 | 0.05 | 3.91 | |
| SC-0800B | 400 | A | 39 | 0.28 | 11.09 | |
| SC-0800B | 400 | D | 77 | 2.78 | 213.86 | |
| | | | **Totals** | **4.03** | **281.41** | **69.84** |
| | | | | | | |
| SC-0810 | 120 | A | 57 | 0.69 | 39.36 | |
| SC-0810 | 120 | D | 86 | 0.07 | 5.72 | |
| SC-0810 | 190 | D | 84 | 0.01 | 0.77 | |
| SC-0810 | 814 | A | 69 | 1.77 | 121.83 | |
| SC-0810 | 814 | D | 89 | 0.94 | 83.31 | |
| | | | **Totals** | **3.47** | **251.00** | **72.37** |
| | | | | | | |
| SC-0820A | 400 | A | 39 | 0.63 | 24.39 | |
| SC-0820A | 400 | D | 77 | 0.71 | 54.40 | |
| SC-0820A | 814 | A | 69 | 0.42 | 28.94 | |
| SC-0820A | 530a | D | 84 | 1.47 | 123.61 | |
| | | | **Totals** | **3.22** | **231.35** | **71.78** |

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Partial Tabulation of Computed Runoff Curve Numbers

**Table No. 3.2.5**

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| | | | | | | |
| SC-0820B | 814 | A | 69 | 4.20 | 290.11 | |
| SC-0820B | 814 | D | 89 | 0.78 | 69.14 | |
| | | | **Totals** | **4.98** | **359.24** | **72.12** |
| | | | | | | |
| SC-0830 | 110 | A | 51 | 0.23 | 11.70 | |
| SC-0830 | 172 | A | 69 | 0.31 | 21.51 | |
| SC-0830 | 172 | D | 89 | 0.04 | 3.87 | |
| SC-0830 | 190 | A | 49 | 1.97 | 96.72 | |
| SC-0830 | 400 | A | 39 | 1.45 | 56.73 | |
| SC-0830 | 400 | D | 77 | 0.08 | 5.82 | |
| SC-0830 | 643 | A | 98 | 0.01 | 0.79 | |
| SC-0830 | 643 | D | 98 | 0.40 | 39.41 | |
| SC-0830 | 814 | A | 69 | 3.71 | 255.65 | |
| SC-0830 | 814 | D | 89 | 1.04 | 92.41 | |
| | | | **Totals** | **9.24** | **584.62** | **63.25** |
| | | | | | | |
| SC-0840 | 110 | A | 51 | 31.08 | 1,585.27 | |
| SC-0840 | 110 | D | 84 | 0.18 | 15.13 | |
| SC-0840 | 172 | A | 69 | 0.99 | 68.41 | |
| SC-0840 | 172 | D | 89 | 0.51 | 45.16 | |
| SC-0840 | 190 | A | 49 | 0.04 | 1.75 | |
| SC-0840 | 400 | A | 39 | 3.17 | 123.49 | |
| SC-0840 | 400 | D | 77 | 4.75 | 365.96 | |
| SC-0840 | 643 | A | 98 | 0.00 | 0.04 | |
| SC-0840 | 643 | D | 98 | 0.82 | 80.59 | |
| | | | **Totals** | **41.54** | **2,285.79** | **55.03** |
| | | | | | | |
| SC-0880 | 110 | A | 51 | 55.38 | 2,824.55 | |
| SC-0880 | 110 | D | 84 | 2.20 | 184.54 | |
| SC-0880 | 140 | A | 89 | 2.37 | 210.76 | |
| SC-0880 | 172 | A | 69 | 3.54 | 244.30 | |
| SC-0880 | 190 | A | 49 | 2.70 | 132.28 | |
| SC-0880 | 190 | D | 84 | 1.05 | 88.22 | |
| SC-0880 | 400 | A | 39 | 0.90 | 35.12 | |
| SC-0880 | 814 | A | 69 | 7.99 | 551.29 | |
| SC-0880 | 814 | D | 89 | 1.70 | 151.36 | |
| | | | **Totals** | **77.83** | **4,422.43** | **56.82** |

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Partial Tabulation of Computed Runoff Curve Numbers

**Table No. 3.2.5**

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| | | | | | | |
| SC-0900A | 190 | A | 49 | 0.36 | 17.73 | |
| SC-0900A | 190 | D | 84 | 0.24 | 19.78 | |
| SC-0900A | 814 | A | 69 | 0.61 | 42.37 | |
| SC-0900A | 814 | D | 89 | 0.68 | 60.56 | |
| SC-0900A | 530a | A | 49 | 0.30 | 14.88 | |
| SC-0900A | 530a | D | 84 | 0.10 | 8.03 | |
| | | | **Totals** | **2.29** | **163.35** | **71.30** |
| | | | | | | |
| SC-0900B | 814 | A | 69 | 4.62 | 318.70 | |
| SC-0900B | 814 | D | 89 | 0.92 | 81.97 | |
| | | | **Totals** | **5.54** | **400.67** | **72.33** |
| | | | | | | |
| SC-0910 | 120 | A | 57 | 1.98 | 112.74 | |
| SC-0910 | 120 | D | 86 | 0.01 | 0.44 | |
| SC-0910 | 190 | D | 84 | 0.02 | 1.79 | |
| SC-0910 | 400 | A | 39 | 0.11 | 4.37 | |
| SC-0910 | 400 | D | 77 | 1.16 | 89.02 | |
| SC-0910 | 640 | A | 98 | 0.95 | 92.92 | |
| SC-0910 | 640 | D | 98 | 0.58 | 56.37 | |
| SC-0910 | 814 | A | 69 | 0.61 | 41.79 | |
| SC-0910 | 814 | D | 89 | 0.69 | 61.25 | |
| | | | **Totals** | **6.09** | **460.69** | **75.65** |
| | | | | | | |
| SC-0920 | 120 | A | 57 | 50.59 | 2,883.68 | |
| SC-0920 | 120 | D | 86 | 0.65 | 55.53 | |
| SC-0920 | 170 | A | 69 | 0.36 | 24.95 | |
| SC-0920 | 190 | A | 49 | 0.43 | 21.06 | |
| SC-0920 | 190 | D | 84 | 0.24 | 20.06 | |
| SC-0920 | 400 | A | 39 | 5.09 | 198.36 | |
| SC-0920 | 400 | D | 77 | 1.93 | 148.66 | |
| SC-0920 | 520 | A | 100 | 0.54 | 54.12 | |
| SC-0920 | 520 | D | 100 | 21.51 | 2,151.07 | |
| SC-0920 | 640 | A | 98 | 1.12 | 109.63 | |
| SC-0920 | 640 | D | 98 | 3.54 | 347.37 | |
| SC-0920 | 814 | A | 69 | 2.63 | 181.13 | |
| | | | **Totals** | **88.62** | **6,195.63** | **69.91** |

## Alternative Sinkhole Remediation Protocol for Grace Lake
## Partial Tabulation of Computed Runoff Curve Numbers

**Table No. 3.2.5**

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| | | | | | | |
| SC-0925 | 120 | A | 57 | 13.12 | 747.80 | |
| SC-0925 | 170 | A | 69 | 0.12 | 8.12 | |
| | | | **Totals** | **13.24** | **755.92** | **57.11** |
| | | | | | | |
| SC-0970 | 120 | A | 57 | 1.39 | 79.26 | |
| SC-0970 | 814 | A | 69 | 2.83 | 195.22 | |
| | | | **Totals** | **4.22** | **274.48** | **65.05** |
| | | | | | | |
| SC-0980A | 120 | A | 57 | 2.73 | 155.53 | |
| SC-0980A | 814 | A | 69 | 0.03 | 2.27 | |
| | | | **Totals** | **2.76** | **157.80** | **57.14** |
| | | | | | | |
| SC-0980B | 120 | A | 57 | 5.83 | 332.19 | |
| SC-0980B | 814 | A | 69 | 0.00 | 0.11 | |
| | | | **Totals** | **5.83** | **332.30** | **57.00** |
| | | | | | | |
| SC-0980C | 120 | A | 57 | 12.31 | 701.60 | |
| | | | **Totals** | **12.31** | **701.60** | **57.00** |
| | | | | | | |
| SC-0985 | 120 | A | 57 | 43.86 | 2,499.94 | |
| | | | **Totals** | **43.86** | **2,499.94** | **57.00** |
| | | | | | | |
| SC-0995 | 120 | A | 57 | 17.74 | 1,011.30 | |
| SC-0995 | 170 | A | 69 | 16.01 | 1,104.93 | |
| SC-0995 | 400 | A | 39 | 0.00 | 0.18 | |
| SC-0995 | 530b | A | 92 | 2.32 | 213.14 | |
| | | | **Totals** | **36.08** | **2,329.55** | **64.57** |

Total Area (acres) = 392.15

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

SEMINOLE COUNTY
FLORIDA'S NATURAL CHOICE

# TAB 3.3

## SUPPORTING DOCUMENTATION FOR THE UPDATED SURFACE WATER ANALYSIS

## TIME OF CONCENTRATION COMPUTATIONS

Pegasus ENGINEERING

**Alternative Sinkhole Remediation Protocol for Grace Lake**
**Partial Tabulation of Computed Times of Concentration**

**Table No. 3.3.1**

| SUB-BASIN I.D. | SHEET FLOW | | | | | | | | SHALLOW CONCENTRATED FLOW | | | | | | | CHANNEL FLOW | | | ACCUMULATED TOTAL TIME OF CONC. | | BASIN I.D. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | SURFACE DESC. | ("n") | FLOW LENGTH (feet) | 2-yr, 24-hr RAINFALL (inch) | UPPER EL. (feet) | LOWER EL. (feet) | CALC'D SLOPE (foot/foot) | TRAVEL TIME (hour) | PAVED OR UNPAVED | FLOW LENGTH (feet) | UPPER EL. (feet) | LOWER EL. (feet) | CALC'D SLOPE (foot/foot) | VEL. (fps) | TRAVEL TIME (hour) | VEL. (fps) | FLOW LENGTH (feet) | TRAVEL TIME (hour) | (hour) | (min.) | |
| SC-0770 | Dense Grass | 0.24 | 100 | 4.50 | 85.00 | 79.00 | 0.0600 | 0.13 | Unpaved | 96 | 79.00 | 70.00 | 0.0938 | 4.9 | 0.01 | 3.00 | 195 | 0.02 | 0.24 | 14 | SC-0770 |
| | | | | | | | | | Paved | 593 | 70.00 | 65.00 | 0.0084 | 1.9 | 0.09 | | | | | | |
| SC-0800A | Dense Grass | 0.24 | 100 | 4.50 | 67.50 | 64.00 | 0.0350 | 0.16 | Unpaved | 512 | 64.00 | 47.00 | 0.0332 | 2.9 | 0.05 | | | | 0.21 | 13 | SC-0800A |
| SC-0800B | Dense Grass | 0.24 | 100 | 4.50 | 65.00 | 61.50 | 0.0350 | 0.16 | Unpaved | 423 | 61.50 | 51.00 | 0.0248 | 2.5 | 0.05 | | | | 0.21 | 12 | SC-0800B |
| SC-0810 | Dense Grass | 0.24 | 100 | 4.50 | 85.00 | 76.00 | 0.0900 | 0.11 | Unpaved | 52 | 76.00 | 70.00 | 0.1154 | 5.5 | 0.00 | 3.00 | 706 | 0.07 | 0.18 | 11 | SC-0810 |
| SC-0820A | Dense Grass | 0.24 | 100 | 4.50 | 68.00 | 64.50 | 0.0350 | 0.16 | Unpaved | 237 | 64.50 | 52.00 | 0.0527 | 3.7 | 0.02 | | | | 0.18 | 11 | SC-0820A |
| SC-0820B | Dense Grass | 0.24 | 100 | 4.50 | 72.00 | 71.00 | 0.0100 | 0.26 | Unpaved | 1071 | 71.00 | 64.00 | 0.0065 | 1.3 | 0.23 | | | | 0.49 | 30 | SC-0820B |
| SC-0830 | Dense Grass | 0.24 | 100 | 4.50 | 84.50 | 84.20 | 0.0030 | 0.43 | Unpaved | 491 | 84.20 | 53.00 | 0.0635 | 4.1 | 0.03 | | | | 0.46 | 28 | SC-0830 |
| SC-0840 | Dense Grass | 0.24 | 100 | 4.50 | 81.00 | 78.00 | 0.0300 | 0.17 | Unpaved | 892 | 78.00 | 62.00 | 0.0179 | 2.2 | 0.11 | 3.00 | 623 | 0.06 | 0.34 | 21 | SC-0840 |
| SC-0880 | Dense Grass | 0.24 | 100 | 4.50 | 86.00 | 85.00 | 0.0100 | 0.26 | Unpaved | 294 | 85.00 | 80.00 | 0.0170 | 2.1 | 0.04 | 3.00 | 1557 | 0.14 | 0.45 | 27 | SC-0880 |
| SC-0900A | Dense Grass | 0.24 | 100 | 4.50 | 70.50 | 62.00 | 0.0850 | 0.11 | Unpaved | 85 | 62.00 | 55.00 | 0.0824 | 4.6 | 0.01 | | | | 0.12 | 7 | SC-0900A |
| SC-0900B | Dense Grass | 0.24 | 100 | 4.50 | 87.00 | 86.00 | 0.0100 | 0.26 | Unpaved | 962 | 86.00 | 75.00 | 0.0114 | 1.7 | 0.15 | 3.00 | 1626 | 0.15 | 0.57 | 34 | SC-0900B |
| SC-0910 | Dense Grass | 0.24 | 100 | 4.50 | 73.00 | 69.00 | 0.0400 | 0.15 | Unpaved | 340 | 69.00 | 55.00 | 0.0412 | 3.3 | 0.03 | | | | 0.18 | 11 | SC-0910 |
| SC-0920 | Dense Grass | 0.24 | 100 | 4.50 | 86.00 | 84.00 | 0.0200 | 0.20 | Unpaved | 431 | 84.00 | 78.00 | 0.0139 | 1.9 | 0.06 | 3.00 | 1152 | 0.11 | 0.37 | 22 | SC-0920 |
| SC-0925 | Dense Grass | 0.24 | 100 | 4.50 | 89.00 | 83.50 | 0.0550 | 0.13 | Unpaved | 235 | 83.50 | 79.00 | 0.0191 | 2.2 | 0.03 | | | | 0.26 | 15 | SC-0925 |
| | | | | | | | | | Paved | 360 | 79.00 | 78.00 | 0.0028 | 1.1 | 0.09 | | | | | | |
| SC-0970 | Dense Grass | 0.24 | 100 | 4.50 | 88.00 | 86.80 | 0.0120 | 0.25 | Unpaved | 302 | 86.80 | 75.00 | 0.0391 | 3.2 | 0.03 | | | | 0.27 | 16 | SC-0970 |
| SC-0980A | Dense Grass | 0.24 | 100 | 4.50 | 88.00 | 87.50 | 0.0050 | 0.35 | Unpaved | 98 | 87.50 | 87.00 | 0.0051 | 1.2 | 0.02 | 3.00 | 1227 | 0.11 | 0.49 | 29 | SC-0980A |
| SC-0980B | Dense Grass | 0.24 | 100 | 4.50 | 86.50 | 85.00 | 0.0150 | 0.23 | Unpaved | 347 | 85.00 | 71.00 | 0.0403 | 3.2 | 0.03 | | | | 0.25 | 15 | SC-0980B |
| SC-0980C | Dense Grass | 0.24 | 100 | 4.50 | 96.50 | 95.50 | 0.0100 | 0.26 | Unpaved | 137 | 95.50 | 95.00 | 0.0036 | 1.0 | 0.04 | | | | 0.34 | 20 | SC-0980C |
| | | | | | | | | | Paved | 180 | 95.00 | 94.00 | 0.0056 | 1.5 | 0.03 | | | | | | |
| SC-0985 | Dense Grass | 0.24 | 100 | 4.50 | 87.00 | 86.00 | 0.0100 | 0.26 | Unpaved | 288 | 86.00 | 72.00 | 0.0486 | 3.6 | 0.02 | | | | 0.29 | 17 | SC-0985 |
| SC-0995 | Dense Grass | 0.24 | 100 | 4.50 | 94.00 | 93.50 | 0.0050 | 0.35 | Unpaved | 294 | 93.50 | 86.00 | 0.0255 | 2.6 | 0.03 | | | | 0.38 | 23 | SC-0995 |

REFERENCE

**URBAN HYDROLOGY FOR SMALL WATERSHEDS**
TECHNICAL RELEASE 55, SOIL CONSERVATION SERVICE
U.S. DEPARTMENT OF AGRICULTURE
JUNE 1986

NOTES

1. Empty cells indicate that the time of concentration for that sub-basin was assumed.

2. In some cases, the assumed time of concentration includes a lag factor to account for stormwater management systems that provide retention storage or attenuation volume that is not otherwise accounted for in the stormwater model.

3. In some cases, and specifically when detailed topographic information is unavailable, time of concentrations for residential land uses assume sheet flow with a minimum lot grade of 1% (FHA minimum standard) and shallow concentrated flow with a minimum road grade of 0.5%.

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

# TAB 4.1

## UPDATED SURFACE WATER ANALYSIS

## ICPR INPUT DATA
## (GROUP "GRACE LAKE")

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

==========
==== Basins ====
==========

Name: SC-0770 Node: SC-0770 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 14.00
Area(ac): 18.020 Time Shift(hrs): 0.00
Curve Number: 58.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0800A Node: SC-0800 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 13.00
Area(ac): 8.980 Time Shift(hrs): 0.00
Curve Number: 75.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0800B Node: SC-0800 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 12.00
Area(ac): 4.030 Time Shift(hrs): 0.00
Curve Number: 70.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0810 Node: SC-0810 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 11.00
Area(ac): 3.470 Time Shift(hrs): 0.00
Curve Number: 72.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0820A Node: SC-0820 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 11.00
Area(ac): 3.220 Time Shift(hrs): 0.00
Curve Number: 72.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

FDOT POND F BASIN AREA

---

Name: SC-0820B Node: SC-0820 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 30.00
Area(ac): 4.980 Time Shift(hrs): 0.00
Curve Number: 72.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

I-4 BASIN AREA CONTRIBUTING RUNOFF TO POND SC-0820

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0830 Node: SC-0830 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 28.00
Area(ac): 9.240 Time Shift(hrs): 0.00
Curve Number: 63.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0840 Node: SC-0840 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 21.00
Area(ac): 41.540 Time Shift(hrs): 0.00
Curve Number: 55.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0880 Node: SC-0880 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 27.00
Area(ac): 77.830 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0900A Node: SC-0900 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 10.00
Area(ac): 2.290 Time Shift(hrs): 0.00
Curve Number: 71.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

FDOT POND E BASIN

---

Name: SC-0900B Node: SC-0900 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 34.00
Area(ac): 5.540 Time Shift(hrs): 0.00
Curve Number: 72.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

I-4 BASIN CONTRIBUTING RUNOFF TO POND E

---

Name: SC-0910 Node: SC-0910 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 11.00
Area(ac): 6.090 Time Shift(hrs): 0.00
Curve Number: 76.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0920 Node: SC-0920 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 22.00
Area(ac): 88.620 Time Shift(hrs): 0.00
Curve Number: 70.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0925 Node: SC-0925 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 15.00
Area(ac): 13.240 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0970 Node: SC-0970 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 16.00
Area(ac): 4.220 Time Shift(hrs): 0.00
Curve Number: 65.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980A Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 29.00
Area(ac): 2.760 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980B Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 15.00
Area(ac): 5.830 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980C Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 20.00
Area(ac): 12.310 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0985 Node: SC-0985 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 17.00
Area(ac): 43.860 Time Shift(hrs): 0.00

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0995 Node: SC-0995 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 23.00
Area(ac): 36.080 Time Shift(hrs): 0.00
Curve Number: 65.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

==========
==== Nodes ==========
==========

Name: SC-0750 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: Grace Lake Warn Stage(ft): 54.000
Type: Time/Stage

ASSUMED TAILWATER AT THE CROWN OF THE OUTFALL PIPE THAT DISCHARGES TO THE BOLLING FARMS SUBDIVISION WETLAND AND POND.
SURVEYED PIPE INVERT ELEVATION IS 48.96 FT, NAVD (SSMC SURVEY DATED DEC. 2007).

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 52.000 |
| 180.00 | 52.000 |

---

Name: SC-0760 Base Flow(cfs): 0.000 Init Stage(ft): 53.080
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

CURB INLET STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY.
PARAMETERS WERE OBTAINED FROM SURVEY DATA BY SSMC (DATED DEC. 2007 AND JULY 2013).

| Stage(ft) | Area(ac) |
|---|---|
| 53.080 | 0.0010 |
| 58.780 | 0.0010 |

---

Name: SC-0770 Base Flow(cfs): 0.000 Init Stage(ft): 57.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

NORTHRIDGE SWALE LOCATED SOUTH OF THE NORTHRIDGE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 55.900 | 0.0100 |
| 57.000 | 0.4100 |
| 58.000 | 0.7700 |

---

Name: SC-0780 Base Flow(cfs): 0.000 Init Stage(ft): 64.240
Group: Grace Lake Warn Stage(ft): 67.270
Type: Stage/Area

DIVERSION STRUCTURE. DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985). REFER TO STRUCTURE

| Stage(ft) | Area(ac) |
|---|---|
| 64.240 | 0.0010 |
| 67.570 | 0.0010 |

---

Name: SC-0790 Base Flow(cfs): 0.000 Init Stage(ft): 64.000
Group: Grace Lake Warn Stage(ft): 67.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED NORTH OF GRACE LAKE, SOUTH OF NORTH RIDGE DR., EAST OF GRACE VIEW CT., AND WEST OF NORTH R
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 64.000 | 0.1800 |
| 65.000 | 0.2300 |
| 66.000 | 0.2900 |
| 67.000 | 0.3900 |

Name: SC-0800 Base Flow(cfs): 0.000 Init Stage(ft): 47.000
Group: Grace Lake Warn Stage(ft): 56.000
Type: Stage/Area

NORTHRIDE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.9700 |
| 48.000 | 1.9200 |
| 49.000 | 2.3000 |
| 50.000 | 2.6500 |
| 51.000 | 2.9900 |
| 52.000 | 3.3100 |
| 53.000 | 3.6200 |
| 54.000 | 4.0400 |
| 55.000 | 4.8500 |
| 56.000 | 6.2700 |
| 57.000 | 7.1700 |

Name: SC-0810 Base Flow(cfs): 0.000 Init Stage(ft): 52.330
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 52.330 | 0.0010 |
| 55.000 | 0.0050 |
| 56.000 | 0.0100 |
| 57.000 | 0.0200 |
| 58.000 | 0.0400 |

Name: SC-0815 Base Flow(cfs): 0.000 Init Stage(ft): 55.000
Group: Grace Lake Warn Stage(ft): 56.000
Type: Stage/Area

SHALLOW SWALE

| Stage(ft) | Area(ac) |
|---|---|
| 55.000 | 0.0200 |
| 56.000 | 0.0300 |

Name: SC-0820 Base Flow(cfs): 0.000 Init Stage(ft): 53.000
Group: Grace Lake Warn Stage(ft): 56.000
Type: Stage/Area

FDOT POND F
STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP AND COMPARED TO THE PERMITTED PARAMETERS (SJRWMD PERMIT NO.

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 0.9100 |
| 53.000 | 1.2100 |
| 54.000 | 1.3300 |
| 55.000 | 1.4800 |
| 56.000 | 1.6100 |
| 57.000 | 1.6900 |

Name: SC-0830 Base Flow(cfs): 0.000 Init Stage(ft): 52.890
Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY WEST (UPSTREAM SIDE) OF THE I-4 CULVERT CROSSING (NORTH PIPE)

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 0.0010 |
| 53.000 | 0.0500 |

| | |
|---|---|
| 54.000 | 0.3100 |
| 55.000 | 0.4800 |
| 56.000 | 0.5900 |
| 57.000 | 0.6800 |
| 58.000 | 0.7900 |
| 59.000 | 0.9200 |

Name: SC-0840 Base Flow(cfs): 0.000 Init Stage(ft): 50.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

DEPRESSIONAL AREA NORTH OF DIXON ROAD AND EAST OF SUNSHINE TREE BOULEVARD.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHI MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.0200 |
| 48.000 | 0.0500 |
| 49.000 | 0.0900 |
| 50.000 | 0.1200 |
| 51.000 | 0.3400 |
| 52.000 | 0.5400 |
| 53.000 | 0.7700 |
| 54.000 | 1.1800 |
| 55.000 | 1.9200 |
| 56.000 | 2.7200 |
| 57.000 | 3.4100 |
| 58.000 | 4.1100 |
| 59.000 | 4.7300 |

Name: SC-0850 Base Flow(cfs): 0.000 Init Stage(ft): 56.690
Group: Grace Lake Warn Stage(ft): 59.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 56.650 | 0.0010 |
| 59.500 | 0.0010 |

Name: SC-0860 Base Flow(cfs): 0.000 Init Stage(ft): 56.920
Group: Grace Lake Warn Stage(ft): 61.550
Type: Stage/Area

DITCH BOTTOM INLET LOCATED AT THE SOUTHEAST CORNER OF THE INTERSECTION OF DIXON RD. AND SUNSHINE TREE BLVD.

| Stage(ft) | Area(ac) |
|---|---|
| 56.920 | 0.0010 |
| 62.650 | 0.0010 |

Name: SC-0870 Base Flow(cfs): 0.000 Init Stage(ft): 59.620
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.
CURB INLET LOCATED ALONG THE SUNSHINE TREE BLVD EAST RIGHT-OF-WAY.

| Stage(ft) | Area(ac) |
|---|---|
| 59.620 | 0.0010 |
| 67.000 | 0.0010 |

Name: SC-0875 Base Flow(cfs): 0.000 Init Stage(ft): 59.710
Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 59.710 | 0.0100 |
| 64.000 | 0.0100 |

Name: SC-0880 Base Flow(cfs): 0.000 Init Stage(ft): 57.840

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

DEPRESSIONAL AREA SOUTH OF THE ONE CHURCH (SOCCER FIELDS)
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 57.840 | 0.0010 |
| 58.000 | 0.0020 |
| 59.000 | 0.0300 |
| 60.000 | 0.5700 |
| 61.000 | 0.7700 |
| 62.000 | 1.6400 |
| 63.000 | 3.0800 |
| 64.000 | 3.8700 |
| 65.000 | 5.6500 |

---

Name: SC-0890 Base Flow(cfs): 0.000 Init Stage(ft): 58.430
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

UPSTREAM END (EAST SIDE) OF THE SOUTHERN CULVERT CROSSING I-4

| Stage(ft) | Area(ac) |
|---|---|
| 58.160 | 0.0100 |
| 66.000 | 0.0100 |

---

Name: SC-0900 Base Flow(cfs): 0.000 Init Stage(ft): 60.000
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.
FDOT POND E (REFER TO THE SJRWMD PERMIT NO. 22434-1)

| Stage(ft) | Area(ac) |
|---|---|
| 59.000 | 0.3000 |
| 60.000 | 0.4400 |
| 61.000 | 0.6200 |
| 62.000 | 0.7900 |
| 63.000 | 0.9200 |
| 64.000 | 1.0400 |
| 65.000 | 1.1900 |
| 66.000 | 1.3900 |
| 67.000 | 1.5400 |

---

Name: SC-0910 Base Flow(cfs): 0.000 Init Stage(ft): 58.000
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY EAST OF THE SOUTH I-4 CROSS CULVERT, ADJACENT TO GRACE LAKE.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 55.000 | 0.1700 |
| 56.000 | 0.3000 |
| 57.000 | 0.4500 |
| 58.000 | 0.6600 |
| 59.000 | 0.9600 |
| 60.000 | 1.4200 |
| 61.000 | 1.8200 |
| 62.000 | 2.2500 |
| 63.000 | 2.6800 |
| 64.000 | 2.9600 |
| 65.000 | 3.2500 |
| 66.000 | 3.4800 |
| 67.000 | 3.6800 |

---

Name: SC-0920 Base Flow(cfs): 0.000 Init Stage(ft): 58.000
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

GRACE LAKE.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 33-54 FT, NAVD, WAS OBTAINED FROM THE SURVEY PREPARED BY SSMC, DATED DEC. 2007.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 55-67, NAVD, IS BASED ON THE 1-FT TOPOGRAPHY.

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

INITIAL STAGE IS BASED ON THE GRACE LAKE "NORMAL" HYDROPERIOD ELEVATION BETWEEN ELEVATION 58-63 FT, NAVD (REFER TO ENGINEERING REPORT FROM DEVO ENGINEERING).

| Stage(ft) | Area(ac) |
|---|---|
| 33.000 | 0.0000 |
| 34.000 | 0.0005 |
| 35.000 | 0.0014 |
| 36.000 | 0.0028 |
| 37.000 | 0.0053 |
| 38.000 | 0.0140 |
| 39.000 | 0.0450 |
| 40.000 | 0.0980 |
| 41.000 | 0.1830 |
| 42.000 | 0.3010 |
| 43.000 | 0.4270 |
| 44.000 | 0.5320 |
| 45.000 | 0.6430 |
| 46.000 | 0.7540 |
| 47.000 | 0.8640 |
| 48.000 | 1.1900 |
| 49.000 | 3.6300 |
| 50.000 | 5.8800 |
| 51.000 | 8.1300 |
| 52.000 | 10.5200 |
| 53.000 | 12.8800 |
| 54.000 | 14.9400 |
| 55.000 | 16.6400 |
| 56.000 | 18.3800 |
| 57.000 | 20.0700 |
| 58.000 | 22.0500 |
| 59.000 | 24.0900 |
| 60.000 | 26.0500 |
| 61.000 | 27.8500 |
| 62.000 | 29.7000 |
| 63.000 | 31.6800 |
| 64.000 | 33.6800 |
| 65.000 | 35.3300 |
| 66.000 | 36.9000 |
| 67.000 | 38.7900 |

---

Name: SC-0925 Base Flow(cfs): 0.000 Init Stage(ft): 68.000
Group: Grace Lake Warn Stage(ft): 76.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED ALONG NORTH RIDGE LAKE CIRCLE, SOUTH OF NORTH RIDGE DR.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAPS.

| Stage(ft) | Area(ac) |
|---|---|
| 68.000 | 0.0300 |
| 69.000 | 0.0800 |
| 70.000 | 0.1000 |
| 71.000 | 0.1300 |
| 72.000 | 0.1600 |
| 73.000 | 0.1800 |
| 74.000 | 0.2200 |
| 75.000 | 0.2500 |
| 76.000 | 0.2900 |
| 77.000 | 0.5100 |
| 78.000 | 0.8700 |
| 79.000 | 1.1900 |

---

Name: SC-0930 Base Flow(cfs): 0.000 Init Stage(ft): 62.900
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 3.

| Stage(ft) | Area(ac) |
|---|---|
| 62.900 | 0.0100 |
| 66.000 | 0.0100 |

---

Name: SC-0940 Base Flow(cfs): 0.000 Init Stage(ft): 65.700
Group: Grace Lake Warn Stage(ft): 69.000
Type: Stage/Area

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 2.

| Stage(ft) | Area(ac) |
|---|---|
| 65.700 | 0.0100 |
| 69.000 | 0.0100 |

---

Name: SC-0950 Base Flow(cfs): 0.000 Init Stage(ft): 66.200
Group: Grace Lake Warn Stage(ft): 72.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 1.

| Stage(ft) | Area(ac) |
|---|---|
| 66.200 | 0.0100 |
| 72.000 | 0.0100 |

---

Name: SC-0960 Base Flow(cfs): 0.000 Init Stage(ft): 68.780
Group: Grace Lake Warn Stage(ft): 73.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 0.

| Stage(ft) | Area(ac) |
|---|---|
| 68.780 | 0.0100 |
| 73.000 | 0.0100 |

---

Name: SC-0970 Base Flow(cfs): 0.000 Init Stage(ft): 65.780
Group: Grace Lake Warn Stage(ft): 71.000
Type: Stage/Area

STAGE AREA ESTIMATED BASED ON THE 1-FT TOPOGRAPHY.
NODE INITIAL STAGE OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE Ghost_I-4_30in.

| Stage(ft) | Area(ac) |
|---|---|
| 65.780 | 0.0100 |
| 71.000 | 0.0400 |

---

Name: SC-0980 Base Flow(cfs): 0.000 Init Stage(ft): 68.100
Group: Grace Lake Warn Stage(ft): 74.000
Type: Stage/Area

STAGE-AREA OBTAINED FROM THE 1-FT TOPO MAPS
INITIAL STAGE IS BASED ON THE DOWNSTREAM PIPE INVERT ELEVATION

| Stage(ft) | Area(ac) |
|---|---|
| 67.000 | 0.0100 |
| 70.000 | 0.0150 |
| 71.000 | 0.0200 |
| 72.000 | 0.1000 |
| 73.000 | 0.1800 |
| 74.000 | 0.3200 |

---

Name: SC-0985 Base Flow(cfs): 0.000 Init Stage(ft): 68.100
Group: Grace Lake Warn Stage(ft): 73.000
Type: Stage/Area

PENELOPE POND (POND LOCATED EAST OF PENELOPE DR AND NORTH OF HICKORY TREE RD)
STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP
INITIAL STAGE WAS ESTIMATED BASED ON THE DOWNSTREAM PIPE INVERT JUST SOUTH OF EE WILLIAMSON RD

| Stage(ft) | Area(ac) |
|---|---|
| 66.000 | 0.1100 |
| 71.000 | 0.2200 |
| 72.000 | 0.3400 |
| 73.000 | 0.5900 |
| 74.000 | 1.2000 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0990 Base Flow(cfs): 0.000 Init Stage(ft): 71.000
Group: Grace Lake Warn Stage(ft): 79.000
Type: Stage/Area

EMERGENCY OVERFLOW MANHOLE

| Stage(ft) | Area(ac) |
|---|---|
| 71.000 | 0.0010 |
| 79.000 | 0.0010 |

---

Name: SC-0995 Base Flow(cfs): 0.000 Init Stage(ft): 77.500
Group: Grace Lake Warn Stage(ft): 84.000
Type: Stage/Area

WET DETENTION POND THAT SERVES THE WOODLAND ELEMENTARY SCHOOL, THE BELLA TUSCANY SUBDIVISION AND A PORTION OF EE WILLIAMSON POND WAS EXPANDED TO PROVIDE WATER QUALITY TREATMENT AND ATTENUATION FROM THE BELLA TUSCANY SUBDIVISION (REFER TO THE SJRMD STAGE-AREA RELATIONSHIP AND INITIAL STAGE WAS OBTAINED FROM THE PERMITTED PARAMETERS. ELEVATIONS SHOWN HEREIN WERE CONVERT SINCE THE ORIGINAL BELLA TUSCANY SUBDIVISION PLANS ARE REFERENCED TO THE NGVD VERTICAL DATUM (CONVERSION USED: NAVD ELEV.

| Stage(ft) | Area(ac) |
|---|---|
| 77.500 | 1.8600 |
| 78.000 | 1.9300 |
| 79.000 | 2.0000 |
| 80.000 | 2.0800 |
| 81.000 | 2.2200 |
| 82.000 | 2.3600 |
| 83.000 | 2.5000 |
| 84.000 | 2.6500 |
| 85.000 | 2.8000 |

==========
==== Cross Sections ==========
==========

Name: SC-0810_W1 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE DEPRESSIONAL AREA

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 58.400 | 0.000000 |
| 11.900 | 57.800 | 0.000000 |
| 31.100 | 57.200 | 0.000000 |
| 43.400 | 57.800 | 0.000000 |
| 63.200 | 58.700 | 0.000000 |

---

Name: SC-0810_W2 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE SWALE

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 59.300 | 0.000000 |
| 30.700 | 59.000 | 0.000000 |
| 68.400 | 58.500 | 0.000000 |
| 106.100 | 58.700 | 0.000000 |
| 133.700 | 59.300 | 0.000000 |

---

Name: SC-0840_W Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 59.000 | 0.000000 |
| 6.700 | 58.000 | 0.000000 |
| 13.300 | 57.000 | 0.000000 |
| 20.000 | 56.000 | 0.000000 |
| 39.900 | 55.000 | 0.000000 |
| 91.800 | 54.000 | 0.000000 |
| 116.000 | 54.000 | 0.000000 |
| 137.600 | 54.000 | 0.000000 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | | |
|---|---|---|
| 182.000 | 55.000 | 0.000000 |
| 203.100 | 56.000 | 0.000000 |
| 218.500 | 57.000 | 0.000000 |
| 229.100 | 58.000 | 0.000000 |
| 239.500 | 59.000 | 0.000000 |

Name: SC-0875_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 36.600 | 66.000 | 0.000000 |
| 44.200 | 65.500 | 0.000000 |
| 51.800 | 66.000 | 0.000000 |
| 78.700 | 67.000 | 0.000000 |

Name: SC-0880_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA OBTAINED FROM SSMC SURVEY, DATED JULY 2013.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 63.300 | 0.000000 |
| 9.200 | 62.600 | 0.000000 |
| 24.700 | 63.400 | 0.000000 |

Name: SC-0890_W Group: Grace Lake
Encroachment: No

SURVEYED CROSS SECTION (SSMC, DATED JULY 2013).

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 70.960 | 0.000000 |
| 4.200 | 70.600 | 0.000000 |
| 26.000 | 67.700 | 0.000000 |
| 48.500 | 71.100 | 0.000000 |
| 64.600 | 79.100 | 0.000000 |
| 78.400 | 83.600 | 0.000000 |
| 82.500 | 83.400 | 0.000000 |

Name: SC-0920_W1 Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 20.300 | 66.000 | 0.000000 |
| 45.300 | 65.000 | 0.000000 |
| 53.000 | 64.000 | 0.000000 |
| 63.600 | 63.000 | 0.000000 |
| 80.700 | 62.000 | 0.000000 |
| 93.800 | 61.000 | 0.000000 |
| 106.600 | 60.000 | 0.000000 |
| 139.200 | 59.500 | 0.000000 |
| 168.200 | 60.000 | 0.000000 |
| 194.200 | 61.000 | 0.000000 |
| 206.100 | 62.000 | 0.000000 |
| 224.900 | 63.000 | 0.000000 |
| 240.600 | 64.000 | 0.000000 |
| 249.600 | 65.000 | 0.000000 |
| 258.000 | 66.000 | 0.000000 |
| 277.100 | 67.000 | 0.000000 |

Name: SC-0920_W3 Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | | |
|---|---|---|
| 0.000 | 66.900 | 0.000000 |
| 24.000 | 66.800 | 0.000000 |
| 47.000 | 67.100 | 0.000000 |

---

Name: SC-0930_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan3DS.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 64.000 | 0.011000 |
| 0.320 | 63.600 | 0.011000 |
| 1.550 | 63.000 | 0.011000 |
| 2.250 | 62.600 | 0.011000 |
| 4.340 | 62.700 | 0.011000 |
| 5.150 | 63.000 | 0.011000 |
| 6.110 | 63.400 | 0.011000 |
| 8.310 | 64.000 | 0.011000 |

---

Name: SC-0940_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan2DS3US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 65.700 | 0.150000 |
| 2.240 | 65.000 | 0.150000 |
| 5.290 | 64.000 | 0.150000 |
| 8.190 | 63.100 | 0.150000 |
| 9.050 | 63.000 | 0.150000 |
| 11.130 | 62.900 | 0.150000 |
| 12.170 | 63.000 | 0.150000 |
| 19.550 | 64.000 | 0.150000 |
| 26.880 | 65.000 | 0.150000 |

---

Name: SC-0950_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan1DS2US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.980 | 0.150000 |
| 9.010 | 66.700 | 0.150000 |
| 15.920 | 66.000 | 0.150000 |
| 17.990 | 65.800 | 0.150000 |
| 20.380 | 65.700 | 0.150000 |
| 22.200 | 66.000 | 0.150000 |
| 23.200 | 66.300 | 0.150000 |
| 27.190 | 66.500 | 0.150000 |
| 30.370 | 67.000 | 0.150000 |
| 40.400 | 68.000 | 0.150000 |
| 48.060 | 68.700 | 0.150000 |

---

Name: SC-0950_US Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan1_US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.000 | 0.150000 |
| 1.190 | 70.000 | 0.150000 |
| 2.360 | 69.000 | 0.150000 |
| 3.560 | 68.000 | 0.150000 |
| 4.580 | 67.000 | 0.150000 |
| 5.300 | 66.200 | 0.150000 |
| 11.970 | 67.000 | 0.150000 |
| 12.060 | 68.000 | 0.150000 |
| 12.060 | 69.000 | 0.150000 |
| 12.060 | 69.700 | 0.150000 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0960_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION EEW I-4 Chan DS.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.230 | 0.011000 |
| 0.610 | 71.000 | 0.011000 |
| 2.090 | 70.000 | 0.011000 |
| 3.570 | 69.000 | 0.011000 |
| 3.800 | 68.640 | 0.011000 |
| 8.900 | 68.640 | 0.011000 |
| 9.240 | 69.000 | 0.011000 |
| 10.080 | 70.000 | 0.011000 |

---

Name: SC-0960_US Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION EEW I-4 Chan US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.000 | 0.011000 |
| 0.960 | 70.000 | 0.011000 |
| 1.930 | 69.000 | 0.011000 |
| 7.640 | 68.860 | 0.011000 |
| 7.810 | 69.000 | 0.011000 |
| 8.830 | 70.000 | 0.011000 |
| 9.880 | 71.000 | 0.011000 |
| 10.790 | 72.000 | 0.011000 |

==========

==== Pipes ====

==========

Name: SC-0760-P From Node: SC-0760 Length(ft): 534.00
Group: Grace Lake To Node: SC-0750 Count: 1
Friction Equation: Automatic

| | UPSTREAM | DOWNSTREAM | |
|---|---|---|---|
| Geometry: | Circular | Circular | Solution Algorithm: Most Restrictive |
| Span(in): | 36.00 | 36.00 | Flow: Both |
| Rise(in): | 36.00 | 36.00 | Entrance Loss Coef: 0.00 |
| Invert(ft): | 53.080 | 48.960 | Exit Loss Coef: 1.00 |
| Manning's N: | 0.012000 | 0.012000 | Bend Loss Coef: 0.00 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| | | | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY DATA BY SSMC, DATED DEC. 2007.

---

Name: SC-0790-P From Node: SC-0790 Length(ft): 30.00
Group: Grace Lake To Node: SC-0780 Count: 1
Friction Equation: Automatic

| | UPSTREAM | DOWNSTREAM | |
|---|---|---|---|
| Geometry: | Circular | Circular | Solution Algorithm: Most Restrictive |
| Span(in): | 18.00 | 18.00 | Flow: Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: 0.50 |
| Invert(ft): | 64.050 | 64.240 | Exit Loss Coef: 0.00 |
| Manning's N: | 0.013000 | 0.013000 | Bend Loss Coef: 0.00 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| | | | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

PIPE DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILTS (DATED 05/19/1985).
ORIGINAL PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND HAD TO BE CONVERTED TO THE NAVD VERTICAL DATUM.
ELEVATIONS SHOWN CORRESPOND TO THE NAVD DATUM.

| | | | |
|---|---|---|---|
| Name: SC-0815-P | | From Node: SC-0815 | Length(ft): 412.00 |
| Group: Grace Lake | | To Node: SC-0810 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 18.00 | 18.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 18.00 | 18.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 55.000 | 53.520 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

UPSTREAM INVERT OBTAINED FROM THE PROPOSED ICPR MODEL, PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008).
DOWNSTREAM INVERT WAS OBTAINED FROM THE SSMC SURVEY, DATED JULY 2013.

| | | | |
|---|---|---|---|
| Name: SC-0830-P | | From Node: SC-0830 | Length(ft): 227.00 |
| Group: Grace Lake | | To Node: SC-0810 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 54.00 | 54.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 54.00 | 54.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 51.520 | 52.330 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (NORTH CROSSING)
UPSTREAM (WEST END) INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.
DOWNSTREAM (EAST END) INVERT ELEVATION WAS REVISED BASED ON SURVEY PERFORMED BY SSMC, DATED JULY 2013.

| | | | |
|---|---|---|---|
| Name: SC-0850-P | | From Node: SC-0850 | Length(ft): 66.00 |
| Group: Grace Lake | | To Node: SC-0840 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 36.00 | 36.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 56.690 | 56.270 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

| | | | |
|---|---|---|---|
| Name: SC-0860-P | | From Node: SC-0860 | Length(ft): 62.00 |
| Group: Grace Lake | | To Node: SC-0850 | Count: 1 |
| | | | Friction Equation: Automatic |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | Flow: | Both |
| Span(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 36.00 | 36.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 56.920 | 56.650 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | |
|---|---|---|---|
| Name: | SC-0870-P | From Node: SC-0870 | Length(ft): 499.00 |
| Group: | Grace Lake | To Node: SC-0860 | Count: 1 |
| | | | Friction Equation: Automatic |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | Flow: | Both |
| Span(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 36.00 | 36.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 59.620 | 57.050 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | |
|---|---|---|---|
| Name: | SC-0875-P | From Node: SC-0875 | Length(ft): 47.00 |
| Group: | Grace Lake | To Node: SC-0870 | Count: 1 |
| | | | Friction Equation: Automatic |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | Flow: | Both |
| Span(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 36.00 | 36.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 59.710 | 59.650 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | |
|---|---|---|---|
| Name: | SC-0890-P | From Node: SC-0890 | Length(ft): 220.00 |
| Group: | Grace Lake | To Node: SC-0880 | Count: 1 |
| | | | Friction Equation: Automatic |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | Flow: | Both |
| Span(in): | 48.00 | 48.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 48.00 | 48.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 58.430 | 57.840 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (SOUTH CROSSING)
INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0970-P | From Node: | SC-0970 | Length(ft): | 200.00 |
| Group: | Grace Lake | To Node: | SC-0940 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 30.00 | 30.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 30.00 | 30.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 65.780 | 65.700 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008)

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0980-P1 | From Node: | SC-0980 | Length(ft): | 165.00 |
| Group: | Grace Lake | To Node: | SC-0970 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 30.00 | 30.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 30.00 | 30.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 68.100 | 66.070 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO HDR PIPE LINK I-4_30Inch.
SURVEY DATA PROVIDED BY SSMC (DATED DEC. 2007)

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0980-P2 | From Node: | SC-0980 | Length(ft): | 135.00 |
| Group: | Grace Lake | To Node: | SC-0960 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 24.00 | 24.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 24.00 | 24.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 69.830 | 68.780 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR PIPE LINK EEWilliams_24.
SURVEY DATA PROVIDED BY SSMC (DATED DEC. 2007)

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| | | | | |
|---|---|---|---|---|
| Name: SC-0985-P | | From Node: SC-0985 | Length(ft): 230.00 | |
| Group: Grace Lake | | To Node: SC-0980 | Count: 1 | |
| | | | Friction Equation: Automatic | |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive | |
| Geometry: | Circular | Circular | Flow: Both | |
| Span(in): | 42.00 | 42.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 42.00 | 42.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 67.000 | 67.000 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE SIZE AND INVERT DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR, IN
SUPPORT OF THE GRACE LAKE SINKHOLE ANALYSIS REPORT (DATED APRIL 2008).
IT APPEARS THAT THIS PIPE SEGMENT WAS NOT SURVEYED
PIPE LENGTH WAS ADJUSTED TO MATCH FIELD OBSERVATIONS

| | | | | |
|---|---|---|---|---|
| Name: SC-0990-P | | From Node: SC-0990 | Length(ft): 219.00 | |
| Group: Grace Lake | | To Node: SC-0920 | Count: 1 | |
| | | | Friction Equation: Automatic | |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive | |
| Geometry: | Circular | Circular | Flow: Both | |
| Span(in): | 15.00 | 15.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 15.00 | 15.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 71.000 | 52.000 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE (FINAL PIPE SEGMENT).
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM. ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DA

| | | | | |
|---|---|---|---|---|
| Name: SC-1000-P | | From Node: SC-1000 | Length(ft): 112.00 | |
| Group: Grace Lake | | To Node: SC-0985 | Count: 1 | |
| | | | Friction Equation: Automatic | |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive | |
| Geometry: | Arch | Arch | Flow: Both | |
| Span(in): | 95.00 | 95.00 | Entrance Loss Coef: | 0.50 |
| Rise(in): | 67.00 | 67.00 | Exit Loss Coef: | 0.00 |
| Invert(ft): | 68.620 | 68.070 | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.024000 | 0.024000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

Downstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

CULVERT CROSSING HICKORY DITCH ROAD
INVERT DATA OBTAINED FROM THE CITY OF LONGWOOD STORMWATER MASTERPLAN
PIPE SIZE WAS ADJUSTED TO REFLECT THE NEAREST STANDARD SIZE FOR AN ARCH PIPE BASED ON SURVEYED DIMENSIONS

==========
==== Channels ==========
==========

Name: SC-0930-C From Node: SC-0930 Length(ft): 106.00

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Group: Grace Lake To Node: SC-0920 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Irregular | Irregular | Friction Equation: | Automatic |
| Invert(ft): | 62.900 | 62.600 | Solution Algorithm: | Automatic |
| TClpInitZ(ft): | 9999.000 | 9999.000 | Flow: | Both |
| Manning's N: | | | Contraction Coef: | 0.100 |
| Top Clip(ft): | | | Expansion Coef: | 0.300 |
| Bot Clip(ft): | | | Entrance Loss Coef: | 0.000 |
| Main XSec: | SC-0940_DS | SC-0930_DS | Exit Loss Coef: | 0.000 |
| AuxElev1(ft): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Aux XSec1: | | | Inlet Ctrl Spec: | Use dc |
| AuxElev2(ft): | 0.000 | 0.000 | Stabilizer Option: | None |
| Aux XSec2: | | | | |
| Top Width(ft): | | | | |
| Depth(ft): | | | | |
| Bot Width(ft): | | | | |
| LtSdSlp(h/v): | | | | |
| RtSdSlp(h/v): | | | | |

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 3 AND CROSS SECTIONS I-4 Chan2DS3US (UPSTREAM) AND I-4 Chan3DS (DOWNSTREAM)

---

Name: SC-0940-C From Node: SC-0940 Length(ft): 496.00
Group: Grace Lake To Node: SC-0930 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Irregular | Irregular | Friction Equation: | Automatic |
| Invert(ft): | 65.700 | 62.900 | Solution Algorithm: | Automatic |
| TClpInitZ(ft): | 9999.000 | 9999.000 | Flow: | Both |
| Manning's N: | | | Contraction Coef: | 0.100 |
| Top Clip(ft): | | | Expansion Coef: | 0.300 |
| Bot Clip(ft): | | | Entrance Loss Coef: | 0.000 |
| Main XSec: | SC-0950_DS | SC-0940_DS | Exit Loss Coef: | 0.000 |
| AuxElev1(ft): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Aux XSec1: | | | Inlet Ctrl Spec: | Use dc |
| AuxElev2(ft): | 0.000 | 0.000 | Stabilizer Option: | None |
| Aux XSec2: | | | | |
| Top Width(ft): | | | | |
| Depth(ft): | | | | |
| Bot Width(ft): | | | | |
| LtSdSlp(h/v): | | | | |
| RtSdSlp(h/v): | | | | |

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 2 AND CROSS SECTIONS I-4 Chan1DS2US (UPSTREAM) AND I-4 Chan2DS3US (DOWNSTREAM)

---

Name: SC-0950-C From Node: SC-0950 Length(ft): 66.00
Group: Grace Lake To Node: SC-0940 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Irregular | Irregular | Friction Equation: | Automatic |
| Invert(ft): | 66.200 | 65.700 | Solution Algorithm: | Automatic |
| TClpInitZ(ft): | 9999.000 | 9999.000 | Flow: | Both |
| Manning's N: | | | Contraction Coef: | 0.100 |
| Top Clip(ft): | | | Expansion Coef: | 0.300 |
| Bot Clip(ft): | | | Entrance Loss Coef: | 0.000 |
| Main XSec: | SC-0950_US | SC-0950_DS | Exit Loss Coef: | 0.000 |
| AuxElev1(ft): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Aux XSec1: | | | Inlet Ctrl Spec: | Use dc |
| AuxElev2(ft): | 0.000 | 0.000 | Stabilizer Option: | None |
| Aux XSec2: | | | | |
| Top Width(ft): | | | | |
| Depth(ft): | | | | |
| Bot Width(ft): | | | | |
| LtSdSlp(h/v): | | | | |
| RtSdSlp(h/v): | | | | |

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 1 AND CROSS SECTIONS I-4 Chan 1_US (UPSTREAM) AND I-4 Chan1DS2US (DOWNSTREAM)

---

Name: SC-0960-C From Node: SC-0960 Length(ft): 15.00
Group: Grace Lake To Node: SC-0950 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Irregular | Irregular | Friction Equation: | Automatic |
| | | | Solution Algorithm: | Automatic |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | | | | |
|---|---|---|---|---|
| Invert(ft): | 68.780 | 68.640 | Flow: | Both |
| TClpInitZ(ft): | 9999.000 | 9999.000 | Contraction Coef: | 0.100 |
| Manning's N: | | | Expansion Coef: | 0.300 |
| Top Clip(ft): | | | Entrance Loss Coef: | 0.000 |
| Bot Clip(ft): | | | Exit Loss Coef: | 0.000 |
| Main XSec: | SC-0960_US | SC-0960_DS | Outlet Ctrl Spec: | Use dc or tw |
| AuxElev1(ft): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Aux XSec1: | | | Stabilizer Option: | None |
| AuxElev2(ft): | 0.000 | 0.000 | | |
| Aux XSec2: | | | | |
| Top Width(ft): | | | | |
| Depth(ft): | | | | |
| Bot Width(ft): | | | | |
| LtSdSlp(h/v): | | | | |
| RtSdSlp(h/v): | | | | |

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK 24 Splwy Chan AND CROSS SECTIONS EEW I-4 Chan US (UPSTREAM) AND EEW I-4 Chan DS (DOWNSTREAM)

==========
==== Drop Structures ==========
==========

| | | | |
|---|---|---|---|
| Name: | SC-0770-D1 | From Node: SC-0770 | Length(ft): 17.00 |
| Group: | Grace Lake | To Node: SC-0760 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 36.00 | 36.00 | Flow: | Both |
| Rise(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 53.250 | 53.080 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DITCH BOTTOM STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY, NORTH OF NORTH RIDGE DRIVE (TRACT "C" O

*** Weir 1 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 10.20 | Invert(ft): | 57.170 |
| Rise(in): | 33.60 | Control Elev(ft): | 57.170 |

*** Weir 2 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.60 | Invert(ft): | 57.180 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.180 |

*** Weir 3 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.00 | Invert(ft): | 57.170 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.170 |

*** Weir 4 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

Span(in): 36.00 Invert(ft): 58.180
Rise(in): 54.00 Control Elev(ft): 58.180

---

Name: SC-0770-D2 From Node: SC-0770 Length(ft): 70.00
Group: Grace Lake To Node: SC-0800 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 18.00 | 18.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 18.00 | 18.00 | Flow: | Both |
| Invert(ft): | 49.660 | 49.140 | Entrance Loss Coef: | 0.500 |
| Manning's N: | 0.024000 | 0.024000 | Exit Loss Coef: | 0.000 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE LOCATED WITHIN THE NORTHRIDGE SWALE.
REFER TO SSMC SURVEY DATED DEC. 2007 AND THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985).
IT APPEARS THAT SURVEY FROM SSMC DID NOT PICK UP THE WEIR CUT-OUT (SLOT). HOWEVER, AS BUILTS PROVIDE AN INVERT ELEVATION F

*** Weir 1 of 2 for Drop Structure SC-0770-D2 ***

TABLE

Count: 1 Bottom Clip(in): 0.000
Type: Vertical: Mavis Top Clip(in): 0.000
Flow: Both Weir Disc Coef: 3.200
Geometry: Rectangular Orifice Disc Coef: 0.600

Span(in): 30.00 Invert(ft): 56.820
Rise(in): 15.50 Control Elev(ft): 56.820

*** Weir 2 of 2 for Drop Structure SC-0770-D2 ***

TABLE

Count: 1 Bottom Clip(in): 0.000
Type: Horizontal Top Clip(in): 0.000
Flow: Both Weir Disc Coef: 3.200
Geometry: Rectangular Orifice Disc Coef: 0.600

Span(in): 37.00 Invert(ft): 58.360
Rise(in): 49.00 Control Elev(ft): 58.360

---

Name: SC-0780-D From Node: SC-0780 Length(ft): 443.00
Group: Grace Lake To Node: SC-0770 Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 18.00 | 18.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 18.00 | 18.00 | Flow: | Both |
| Invert(ft): | 62.370 | 55.900 | Entrance Loss Coef: | 0.500 |
| Manning's N: | 0.013000 | 0.013000 | Exit Loss Coef: | 0.000 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DIVERSION / CONTROL STRUCTURE. DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985).
ELEVATIONS SHOWN WERE CONVERTED TO THE NAVD VERTICAL DATUM.

*** Weir 1 of 1 for Drop Structure SC-0780-D ***

TABLE

Count: 1 Bottom Clip(in): 0.000
Type: Vertical: Mavis Top Clip(in): 0.000
Flow: Both Weir Disc Coef: 3.200
Geometry: Rectangular Orifice Disc Coef: 0.600

Span(in): 50.40 Invert(ft): 65.500
Rise(in): 24.84 Control Elev(ft): 65.500

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| | | | |
|---|---|---|---|
| Name: SC-0900-D | From Node: SC-0900 | Length(ft): 164.00 | |
| Group: Grace Lake | To Node: SC-0890 | Count: 1 | |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 24.00 | 24.00 | Flow: | Both |
| Rise(in): | 24.00 | 24.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 59.500 | 58.160 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

FDOT POND E OUTFALL STRUCTURE. STRUCTURE DATA AND UPSTREAM INVERT WAS OBTAINED FROM THE FDOT CONSTUCTION PLANS (PREPARED B
IT APPEARS THAT THE FDOT PLANS ARE REFERENCED TO THE NGVD VERTICAL DATUM. THESE ELEVATIONS WERE CONVERTED TO THE NAVD DATU
DOWNSTREAM PIPE INVERT ELEVATION WAS OBTAINED FROM SURVEYED DATA, PREPARED BY SSMC (DATED DEC. 2007)

*** Weir 1 of 3 for Drop Structure SC-0900-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 63.700 |
| Rise(in): | 15.60 | Control Elev(ft): | 63.700 |

*** Weir 2 of 3 for Drop Structure SC-0900-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 37.00 | Invert(ft): | 65.000 |
| Rise(in): | 49.00 | Control Elev(ft): | 65.000 |

*** Weir 3 of 3 for Drop Structure SC-0900-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Circular | Orifice Disc Coef: | 0.600 |
| Span(in): | 2.00 | Invert(ft): | 60.000 |
| Rise(in): | 2.00 | Control Elev(ft): | 60.000 |

---

| | | | |
|---|---|---|---|
| Name: SC-0925-D | From Node: SC-0925 | Length(ft): 360.00 | |
| Group: Grace Lake | To Node: SC-0920 | Count: 1 | |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 18.00 | 18.00 | Flow: | Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 69.350 | 64.010 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE DATA WAS OBTAINED FROM THE AS-BUILT PLANS OF THE NORTHRIDGE SUBDIVISION, PREPARED BY CPH, DATED 05/19/198
CONSTRUCTION PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND CONVERTED TO THE NAVD DATUM.

*** Weir 1 of 2 for Drop Structure SC-0925-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |

```
              Span(in): 12.00                      Invert(ft): 74.020
              Rise(in): 46.70                  Control Elev(ft): 74.020

*** Weir 2 of 2 for Drop Structure SC-0925-D ***
                                                                      TABLE
                 Count: 1                      Bottom Clip(in): 0.000
                  Type: Horizontal                Top Clip(in): 0.000
                  Flow: Both                    Weir Disc Coef: 3.200
              Geometry: Rectangular           Orifice Disc Coef: 0.600

              Span(in): 36.00                      Invert(ft): 77.910
              Rise(in): 54.00                  Control Elev(ft): 77.910


-------------------------------------------------------------------------------------------------
         Name: SC-0995-D           From Node: SC-0995           Length(ft): 1211.00
        Group: Grace Lake            To Node: SC-0990                Count: 1

              UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
     Geometry: Circular       Circular                Solution Algorithm: Most Restrictive
     Span(in): 15.00          15.00                                Flow: Both
     Rise(in): 15.00          15.00                   Entrance Loss Coef: 0.500
   Invert(ft): 80.000         76.250                      Exit Loss Coef: 0.000
  Manning's N: 0.012000       0.012000                  Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                      Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                        Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW STRUCTURE AND PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE.
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DA

*** Weir 1 of 1 for Drop Structure SC-0995-D ***
                                                                      TABLE
                 Count: 1                      Bottom Clip(in): 0.000
                  Type: Horizontal                Top Clip(in): 0.000
                  Flow: Both                    Weir Disc Coef: 3.200
              Geometry: Rectangular           Orifice Disc Coef: 0.600

              Span(in): 36.00                      Invert(ft): 83.160
              Rise(in): 54.00                  Control Elev(ft): 83.160


=================================================================================================
==== Weirs ======================================================================================
=================================================================================================

         Name: SC-0770-W           From Node: SC-0770
        Group: Grace Lake            To Node: SC-0750
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 180.00
                  Rise(in): 999.00
                Invert(ft): 58.500
       Control Elevation(ft): 58.500
                                       TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------
         Name: SC-0780-W           From Node: SC-0780
        Group: Grace Lake            To Node: SC-0770
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 2400.00
                  Rise(in): 999.00
                Invert(ft): 67.900
       Control Elevation(ft): 67.900
                                       TABLE
             Bottom Clip(in): 0.000
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
               Top Clip(in): 0.000
         Weir Discharge Coef: 3.200
      Orifice Discharge Coef: 0.600

OVERLAND OVERTOPPING FROM POND TO THE NORTHRIDGE SWALE.
ELEVATION WAS OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS AND COMPARED TO THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------------
         Name: SC-0800-W1          From Node: SC-0800
        Group: Grace Lake            To Node: SC-0770
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                   Span(in): 1200.00
                   Rise(in): 999.00
                 Invert(ft): 58.000
       Control Elevation(ft): 58.000
                                       TABLE
              Bottom Clip(in): 0.000
                 Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

NORTHRIDGE DEPRESSIONAL AREA BERM OVERTOPPING
PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP AND SURVEYED DATA.

-------------------------------------------------------------------------------------------------------
         Name: SC-0800-W2          From Node: SC-0800
        Group: Grace Lake            To Node: SC-0750
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                   Span(in): 600.00
                   Rise(in): 999.00
                 Invert(ft): 58.500
       Control Elevation(ft): 58.500
                                       TABLE
              Bottom Clip(in): 0.000
                 Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------------
         Name: SC-0810-W1          From Node: SC-0810
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0810_W1
                 Invert(ft): 57.200
       Control Elevation(ft): 57.200
      Struct Opening Dim(ft): 9999.00
                                       TABLE
              Bottom Clip(ft): 0.000
                 Top Clip(ft): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------------
         Name: SC-0810-W2          From Node: SC-0810
        Group: Grace Lake            To Node: SC-0770
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0810_W2
                 Invert(ft): 58.500
       Control Elevation(ft): 58.500
      Struct Opening Dim(ft): 9999.00
                                       TABLE
              Bottom Clip(ft): 0.000
                 Top Clip(ft): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------------
         Name: SC-0820-W1          From Node: SC-0820
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
        Group: Grace Lake            To Node: SC-0815
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Trapezoidal

            Bottom Width(ft): 5.00
        Left Side Slope(h/v): 6.00
       Right Side Slope(h/v): 6.00
                  Invert(ft): 55.000
       Control Elevation(ft): 55.000
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

CONCRETE WEIR (OUTFALL)

-------------------------------------------------------------------------------------------------
         Name: SC-0820-W2          From Node: SC-0820
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 56.500
       Control Elevation(ft): 56.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

POND BERM OVERTOPPING

-------------------------------------------------------------------------------------------------
         Name: SC-0840-W           From Node: SC-0840
        Group: Grace Lake            To Node: SC-0830
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0840_W
                  Invert(ft): 54.000
       Control Elevation(ft): 54.000
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
         Name: SC-0875-W           From Node: SC-0875
        Group: Grace Lake            To Node: SC-0840
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0875_W
                  Invert(ft): 65.500
       Control Elevation(ft): 65.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERLAND OVERTOPPING

-------------------------------------------------------------------------------------------------
         Name: SC-0880-W           From Node: SC-0880
        Group: Grace Lake            To Node: SC-0875
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0880_W
                  Invert(ft): 62.600
       Control Elevation(ft): 62.600
      Struct Opening Dim(ft): 9999.00
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

TABLE
Bottom Clip(ft): 0.000
Top Clip(ft): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

---

Name: SC-0890-W From Node: SC-0890
Group: Grace Lake To Node: SC-0810
Flow: Both Count: 1
Type: Vertical: Fread Geometry: Irregular

XSec: SC-0890_W
Invert(ft): 67.700
Control Elevation(ft): 67.700
Struct Opening Dim(ft): 9999.00
TABLE
Bottom Clip(ft): 0.000
Top Clip(ft): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

OVERTOPPING OF I-4 SWALE AT HIGH POING ALONG THE EAST RIGHT-OF-WAY.
POTENTIAL INTERCONNECTION OF THE TWO (2) CULVERTS CROSSING I-4 (NORTH AND SOUTH).
CROSS SECTION DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC (DATED JULY 2013).

---

Name: SC-0900-W From Node: SC-0900
Group: Grace Lake To Node: SC-0890
Flow: Both Count: 1
Type: Vertical: Fread Geometry: Rectangular

Span(in): 120.00
Rise(in): 999.00
Invert(ft): 68.000
Control Elevation(ft): 68.000
TABLE
Bottom Clip(in): 0.000
Top Clip(in): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

ELEVATIONS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

---

Name: SC-0910-W From Node: SC-0910
Group: Grace Lake To Node: SC-0890
Flow: Both Count: 1
Type: Vertical: Fread Geometry: Rectangular

Span(in): 960.00
Rise(in): 999.00
Invert(ft): 59.500
Control Elevation(ft): 59.500
TABLE
Bottom Clip(in): 0.000
Top Clip(in): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

OVERTOPPING ELEVATION WAS ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

---

Name: SC-0920-W1 From Node: SC-0920
Group: Grace Lake To Node: SC-0910
Flow: Both Count: 1
Type: Vertical: Fread Geometry: Irregular

XSec: SC-0920_W1
Invert(ft): 59.500
Control Elevation(ft): 59.500
Struct Opening Dim(ft): 9999.00
TABLE
Bottom Clip(ft): 0.000
Top Clip(ft): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
        Name: SC-0920-W2          From Node: SC-0920
       Group: Grace Lake            To Node: SC-0890
        Flow: Both                    Count: 1
        Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 1160.00
                  Rise(in): 999.00
                Invert(ft): 62.500
     Control Elevation(ft): 62.500
                                       TABLE
           Bottom Clip(in): 0.000
              Top Clip(in): 0.000
       Weir Discharge Coef: 2.800
    Orifice Discharge Coef: 0.600
```

---

```
        Name: SC-0920-W3          From Node: SC-0920
       Group: Grace Lake            To Node: SC-0790
        Flow: Both                    Count: 1
        Type: Vertical: Fread      Geometry: Irregular

                     XSec: SC-0920_W3
                Invert(ft): 66.800
     Control Elevation(ft): 66.800
    Struct Opening Dim(ft): 9999.00
                                       TABLE
           Bottom Clip(ft): 0.000
              Top Clip(ft): 0.000
       Weir Discharge Coef: 2.800
    Orifice Discharge Coef: 0.600
```

PARAMETERS ARE BASED ON SURVEY DATA OBTAINED FROM SSMC, DATED JULY 2013.

---

```
        Name: SC-0925-W           From Node: SC-0925
       Group: Grace Lake            To Node: SC-0920
        Flow: Both                    Count: 1
        Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 680.00
                  Rise(in): 999.00
                Invert(ft): 78.700
     Control Elevation(ft): 78.700
                                       TABLE
           Bottom Clip(in): 0.000
              Top Clip(in): 0.000
       Weir Discharge Coef: 2.800
    Orifice Discharge Coef: 0.600
```

---

```
        Name: SC-0970-W           From Node: SC-0970
       Group: Grace Lake            To Node: SC-0940
        Flow: Both                    Count: 1
        Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 120.00
                  Rise(in): 999.00
                Invert(ft): 71.000
     Control Elevation(ft): 71.000
                                       TABLE
           Bottom Clip(in): 0.000
              Top Clip(in): 0.000
       Weir Discharge Coef: 2.800
    Orifice Discharge Coef: 0.600
```

---

```
        Name: SC-0985-W           From Node: SC-0985
       Group: Grace Lake            To Node: SC-0980
        Flow: Both                    Count: 1
        Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 600.00
                  Rise(in): 999.00
                Invert(ft): 73.500
     Control Elevation(ft): 73.500
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

TABLE
Bottom Clip(in): 0.000
Top Clip(in): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

PENELOPE POND OVERTOPPING
PARAMETERS WERE ESTIMATED USING THE 1-FT TOPOGRAPHIC MAPS

---

Name: SC-1000-W From Node: SC-1000
Group: Grace Lake To Node: SC-0985
Flow: Both Count: 1
Type: Vertical: Fread Geometry: Rectangular

Span(in): 600.00
Rise(in): 999.00
Invert(ft): 77.500
Control Elevation(ft): 77.500
TABLE
Bottom Clip(in): 0.000
Top Clip(in): 0.000
Weir Discharge Coef: 2.800
Orifice Discharge Coef: 0.600

OVERTOPPING HICKORY TREE ROAD

==========
==== Hydrology Simulations ====
==========

Name: 010-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\010-024.R32

Override Defaults: Yes
Storm Duration(hrs): 24.00
Rainfall File: Flmod
Rainfall Amount(in): 6.80

| Time(hrs) | Print Inc(min) |
|---|---|
| 30.000 | 5.00 |

---

Name: 025-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\025-024.R32

Override Defaults: Yes
Storm Duration(hrs): 24.00
Rainfall File: Flmod
Rainfall Amount(in): 8.50

| Time(hrs) | Print Inc(min) |
|---|---|
| 30.000 | 5.00 |

---

Name: 025-096
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\025-096.R32

Override Defaults: Yes
Storm Duration(hrs): 96.00
Rainfall File: Sjrwmd96
Rainfall Amount(in): 11.30

| Time(hrs) | Print Inc(min) |
|---|---|
| 30.000 | 5.00 |

---

Name: 100-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\100-024.R32

Override Defaults: Yes
Storm Duration(hrs): 24.00
Rainfall File: Flmod
Rainfall Amount(in): 11.40

| Time(hrs) | Print Inc(min) |
|---|---|
| 30.000 | 5.00 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: 100-096
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\100-096.R32

Override Defaults: Yes
Storm Duration(hrs): 96.00
Rainfall File: Sjrwmd96
Rainfall Amount(in): 15.00

| Time(hrs) | Print Inc(min) |
|---|---|
| 96.000 | 5.00 |

---

Name: MA-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\MA-024.R32

Override Defaults: Yes
Storm Duration(hrs): 24.00
Rainfall File: Flmod
Rainfall Amount(in): 4.40

| Time(hrs) | Print Inc(min) |
|---|---|
| 30.000 | 5.00 |

==========
==== Routing Simulations ==========
==========

Name: 010-024 Hydrology Sim: 010-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\010-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 36.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 1.0000
Boundary Stages: 010-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
10-YEAR STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 999.000 | 15.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 025-024 Hydrology Sim: 025-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\025-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 36.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 1.0000
Boundary Stages: 025-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
25-YEAR STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 999.000 | 15.000 |

| Group | Run |
|---|---|

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 025-096 Hydrology Sim: 025-096
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\025-096.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 120.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 96.000 | 15.000 |
| 120.000 | 30.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 100-024 Hydrology Sim: 100-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\100-024.I32

Execute: Yes Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 336.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
100-YEAR STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 48.000 | 15.000 |
| 336.000 | 60.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 100-096 Hydrology Sim: 100-096
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\100-096.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 180.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Time(hrs) | Print Inc(min) |
|---|---|
| 96.000 | 15.000 |
| 120.000 | 30.000 |
| 180.000 | 60.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: MA-024 Hydrology Sim: MA-024
Filename: L:\Projects_Drainage\Seminole\SMC-22014 Grace Lake\ICPR Pegasus (Sept 2013)\MA-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 36.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 1.0000
Boundary Stages: 010-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
MEAN ANNUAL STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 999.000 | 15.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

==========
==== Boundary Conditions ====
==========

Name: 010-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.400 |
| 7.500 | 50.400 |
| 8.000 | 50.400 |
| 8.500 | 50.410 |
| 8.670 | 50.410 |
| 8.830 | 50.420 |
| 9.000 | 50.420 |
| 9.170 | 50.430 |
| 9.330 | 50.430 |
| 9.500 | 50.440 |
| 9.670 | 50.440 |
| 9.830 | 50.450 |
| 10.000 | 50.460 |
| 10.170 | 50.470 |
| 10.330 | 50.470 |

| | |
|---|---|
| 10.500 | 50.480 |
| 10.670 | 50.490 |
| 10.830 | 50.510 |
| 11.000 | 50.520 |
| 11.170 | 50.530 |
| 11.330 | 50.550 |
| 11.500 | 50.570 |
| 11.670 | 50.600 |
| 11.830 | 50.650 |
| 12.000 | 50.740 |
| 12.170 | 50.840 |
| 12.330 | 50.960 |
| 12.500 | 51.080 |
| 12.670 | 51.170 |
| 12.830 | 51.250 |
| 13.000 | 51.320 |
| 13.170 | 51.370 |
| 13.330 | 51.420 |
| 13.500 | 51.460 |
| 13.670 | 51.500 |
| 13.830 | 51.540 |
| 14.000 | 51.570 |
| 14.170 | 51.600 |
| 14.330 | 51.620 |
| 14.500 | 51.650 |
| 14.670 | 51.680 |
| 14.830 | 51.700 |
| 15.000 | 51.720 |
| 15.170 | 51.750 |
| 15.330 | 51.770 |
| 15.500 | 51.790 |
| 15.670 | 51.810 |
| 15.830 | 51.830 |
| 16.000 | 51.850 |
| 16.170 | 51.870 |
| 16.670 | 51.930 |
| 17.170 | 51.980 |
| 17.670 | 52.040 |
| 18.170 | 52.090 |
| 18.670 | 52.150 |
| 19.170 | 52.200 |
| 19.670 | 52.250 |
| 20.170 | 52.300 |
| 20.670 | 52.340 |
| 21.170 | 52.390 |
| 21.670 | 52.430 |
| 22.170 | 52.470 |
| 22.670 | 52.500 |
| 23.170 | 52.540 |
| 23.670 | 52.570 |
| 24.170 | 52.600 |
| 24.670 | 52.620 |
| 25.170 | 52.640 |
| 25.670 | 52.650 |
| 26.170 | 52.660 |
| 26.670 | 52.670 |
| 27.170 | 52.670 |
| 27.670 | 52.680 |
| 28.170 | 52.680 |
| 28.670 | 52.680 |
| 29.170 | 52.690 |
| 29.670 | 52.690 |
| 30.170 | 52.680 |
| 30.670 | 52.680 |
| 31.170 | 52.680 |
| 31.670 | 52.680 |
| 32.170 | 52.670 |
| 32.670 | 52.670 |
| 33.170 | 52.660 |
| 33.670 | 52.660 |
| 34.170 | 52.650 |
| 34.670 | 52.640 |
| 35.170 | 52.640 |
| 35.670 | 52.630 |
| 36.000 | 52.620 |

Name: 010-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.150 |
| 5.500 | 42.160 |
| 6.000 | 42.160 |
| 6.500 | 42.160 |
| 7.000 | 42.170 |
| 7.500 | 42.180 |
| 8.000 | 42.190 |
| 8.500 | 42.210 |
| 8.750 | 42.220 |
| 9.000 | 42.240 |
| 9.250 | 42.250 |
| 9.500 | 42.270 |
| 9.750 | 42.280 |
| 10.000 | 42.300 |
| 10.250 | 42.310 |
| 10.500 | 42.330 |
| 10.750 | 42.350 |
| 11.000 | 42.370 |
| 11.250 | 42.390 |
| 11.500 | 42.420 |
| 11.750 | 42.470 |
| 12.000 | 42.570 |
| 12.250 | 42.700 |
| 12.500 | 42.830 |
| 12.750 | 42.910 |
| 13.000 | 42.940 |
| 13.250 | 42.950 |
| 13.500 | 42.950 |
| 13.750 | 42.940 |
| 14.000 | 42.940 |
| 14.250 | 42.930 |
| 14.500 | 42.930 |
| 14.750 | 42.930 |
| 15.000 | 42.940 |
| 15.250 | 42.970 |
| 15.500 | 43.000 |
| 15.750 | 43.020 |
| 16.000 | 43.050 |
| 16.250 | 43.080 |
| 16.750 | 43.120 |
| 17.250 | 43.160 |
| 17.750 | 43.190 |
| 18.250 | 43.220 |
| 18.750 | 43.240 |
| 19.250 | 43.250 |
| 19.750 | 43.270 |
| 20.250 | 43.280 |
| 20.750 | 43.290 |
| 21.250 | 43.300 |
| 21.750 | 43.310 |
| 22.250 | 43.320 |
| 22.750 | 43.320 |
| 23.250 | 43.330 |
| 23.750 | 43.350 |
| 24.250 | 43.370 |
| 24.750 | 43.390 |
| 25.250 | 43.410 |
| 25.750 | 43.420 |
| 26.250 | 43.430 |
| 26.750 | 43.450 |
| 27.250 | 43.460 |
| 27.750 | 43.470 |
| 28.250 | 43.470 |
| 28.750 | 43.480 |
| 29.250 | 43.480 |
| 29.750 | 43.490 |
| 30.250 | 43.490 |
| 30.750 | 43.490 |
| 31.250 | 43.490 |
| 31.750 | 43.490 |
| 32.250 | 43.490 |
| 32.750 | 43.490 |
| 33.250 | 43.490 |

| | |
|---|---|
| 33.750 | 43.490 |
| 34.250 | 43.480 |
| 34.750 | 43.480 |
| 35.250 | 43.480 |
| 35.750 | 43.470 |
| 36.250 | 43.460 |
| 36.750 | 43.460 |
| 37.250 | 43.450 |
| 37.750 | 43.440 |
| 38.250 | 43.440 |
| 38.750 | 43.430 |
| 39.250 | 43.420 |
| 39.750 | 43.410 |
| 40.250 | 43.400 |
| 40.750 | 43.390 |
| 41.250 | 43.380 |
| 41.750 | 43.370 |
| 42.250 | 43.360 |
| 42.750 | 43.350 |
| 43.250 | 43.340 |
| 43.750 | 43.330 |
| 44.250 | 43.310 |
| 44.750 | 43.300 |
| 45.250 | 43.290 |
| 45.750 | 43.280 |
| 46.250 | 43.270 |
| 46.750 | 43.250 |
| 47.250 | 43.240 |
| 47.750 | 43.230 |
| 48.000 | 43.220 |

Name: 010-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.130 |
| 8.500 | 46.130 |
| 8.750 | 46.140 |
| 9.000 | 46.140 |
| 9.250 | 46.140 |
| 9.500 | 46.140 |
| 9.750 | 46.150 |
| 10.000 | 46.150 |
| 10.250 | 46.160 |
| 10.500 | 46.160 |
| 10.750 | 46.170 |
| 11.000 | 46.180 |
| 11.250 | 46.200 |
| 11.500 | 46.220 |
| 11.750 | 46.260 |
| 12.000 | 46.330 |
| 12.250 | 46.430 |
| 12.500 | 46.530 |
| 12.750 | 46.600 |
| 13.000 | 46.650 |
| 13.250 | 46.690 |
| 13.500 | 46.720 |
| 13.750 | 46.740 |
| 14.000 | 46.770 |
| 14.250 | 46.800 |
| 14.500 | 46.820 |
| 14.750 | 46.850 |
| 15.000 | 46.870 |
| 15.250 | 46.900 |
| 15.500 | 46.920 |

| | |
|---|---|
| 15.750 | 46.950 |
| 16.000 | 46.980 |
| 16.250 | 47.000 |
| 16.750 | 47.060 |
| 17.250 | 47.120 |
| 17.750 | 47.180 |
| 18.250 | 47.240 |
| 18.750 | 47.300 |
| 19.250 | 47.350 |
| 19.750 | 47.410 |
| 20.250 | 47.460 |
| 20.750 | 47.490 |
| 21.250 | 47.520 |
| 21.750 | 47.550 |
| 22.250 | 47.580 |
| 22.750 | 47.730 |
| 23.250 | 48.070 |
| 23.750 | 48.530 |
| 24.250 | 48.700 |
| 24.750 | 48.810 |
| 25.250 | 48.880 |
| 25.750 | 48.920 |
| 26.250 | 48.950 |
| 26.750 | 48.970 |
| 27.250 | 48.980 |
| 27.750 | 48.980 |
| 28.250 | 48.980 |
| 28.750 | 48.970 |
| 29.250 | 48.960 |
| 29.750 | 48.950 |
| 30.250 | 48.940 |
| 30.750 | 48.920 |
| 31.250 | 48.910 |
| 31.750 | 48.890 |
| 32.250 | 48.870 |
| 32.750 | 48.850 |
| 33.250 | 48.830 |
| 33.750 | 48.810 |
| 34.250 | 48.790 |
| 34.750 | 48.770 |
| 35.250 | 48.750 |
| 35.750 | 48.720 |
| 36.250 | 48.700 |
| 36.750 | 48.680 |
| 37.250 | 48.660 |
| 37.750 | 48.640 |
| 38.250 | 48.620 |
| 38.750 | 48.600 |
| 39.250 | 48.580 |
| 39.750 | 48.560 |
| 40.250 | 48.540 |
| 40.750 | 48.520 |
| 41.250 | 48.510 |
| 41.750 | 48.490 |
| 42.250 | 48.470 |
| 42.750 | 48.290 |
| 43.250 | 48.270 |
| 43.750 | 48.240 |
| 44.250 | 48.220 |
| 44.750 | 48.200 |
| 45.250 | 48.170 |
| 45.750 | 48.150 |
| 46.250 | 48.130 |
| 46.750 | 48.110 |
| 47.250 | 48.090 |
| 47.750 | 48.060 |
| 48.000 | 48.050 |

Name: 010-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |

| | |
|---|---|
| 4.500 | 41.060 |
| 5.000 | 41.090 |
| 5.500 | 41.180 |
| 6.000 | 41.310 |
| 6.500 | 41.400 |
| 7.000 | 41.520 |
| 7.500 | 41.670 |
| 8.000 | 41.810 |
| 8.500 | 41.960 |
| 8.750 | 42.050 |
| 9.000 | 42.130 |
| 9.250 | 42.230 |
| 9.500 | 42.320 |
| 9.750 | 42.400 |
| 10.000 | 42.480 |
| 10.250 | 42.570 |
| 10.500 | 42.670 |
| 10.750 | 42.770 |
| 11.000 | 42.870 |
| 11.250 | 42.970 |
| 11.500 | 43.120 |
| 11.750 | 43.540 |
| 12.000 | 43.920 |
| 12.250 | 44.110 |
| 12.500 | 44.080 |
| 12.750 | 43.900 |
| 13.000 | 43.750 |
| 13.250 | 43.700 |
| 13.500 | 43.720 |
| 13.750 | 43.740 |
| 14.000 | 43.750 |
| 14.250 | 43.750 |
| 14.500 | 43.780 |
| 14.750 | 43.840 |
| 15.000 | 43.910 |
| 15.250 | 43.960 |
| 15.500 | 44.000 |
| 15.750 | 44.020 |
| 16.000 | 44.030 |
| 16.250 | 44.030 |
| 16.750 | 44.020 |
| 17.250 | 44.000 |
| 17.750 | 43.960 |
| 18.250 | 43.900 |
| 18.750 | 43.840 |
| 19.250 | 43.790 |
| 19.750 | 43.740 |
| 20.250 | 43.700 |
| 20.750 | 43.670 |
| 21.250 | 43.660 |
| 21.750 | 43.650 |
| 22.250 | 43.650 |
| 22.750 | 43.640 |
| 23.250 | 43.630 |
| 23.750 | 43.620 |
| 24.250 | 43.600 |
| 24.750 | 43.570 |
| 25.250 | 43.540 |
| 25.750 | 43.510 |
| 26.250 | 43.480 |
| 26.750 | 43.460 |
| 27.250 | 43.430 |
| 27.750 | 43.430 |
| 28.250 | 43.320 |
| 28.750 | 42.350 |
| 29.250 | 42.150 |
| 29.750 | 42.080 |
| 30.250 | 42.030 |
| 30.750 | 42.000 |
| 31.250 | 41.970 |
| 31.750 | 41.950 |
| 32.250 | 41.920 |
| 32.750 | 41.890 |
| 33.250 | 41.860 |
| 33.750 | 41.830 |
| 34.250 | 41.810 |
| 34.750 | 41.790 |
| 35.250 | 41.770 |
| 35.750 | 41.750 |
| 36.250 | 41.730 |
| 36.750 | 41.710 |
| 37.250 | 41.700 |

| | |
|---|---|
| 37.750 | 41.680 |
| 38.250 | 41.670 |
| 38.750 | 41.660 |
| 39.250 | 41.650 |
| 39.750 | 41.640 |
| 40.250 | 41.630 |
| 40.750 | 41.620 |
| 41.250 | 41.610 |
| 41.750 | 41.600 |
| 42.250 | 41.590 |
| 42.750 | 41.580 |
| 43.250 | 41.570 |
| 43.750 | 41.560 |
| 44.250 | 41.550 |
| 44.750 | 41.550 |
| 45.250 | 41.540 |
| 45.750 | 41.530 |
| 46.250 | 41.520 |
| 46.750 | 41.520 |
| 47.250 | 41.510 |
| 47.750 | 41.510 |
| 48.000 | 41.510 |

Name: 025-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.410 |
| 7.500 | 50.420 |
| 8.000 | 50.430 |
| 8.500 | 50.450 |
| 8.670 | 50.450 |
| 8.830 | 50.460 |
| 9.000 | 50.470 |
| 9.170 | 50.480 |
| 9.330 | 50.480 |
| 9.500 | 50.490 |
| 9.670 | 50.500 |
| 9.830 | 50.510 |
| 10.000 | 50.520 |
| 10.170 | 50.530 |
| 10.330 | 50.550 |
| 10.500 | 50.560 |
| 10.670 | 50.570 |
| 10.830 | 50.590 |
| 11.000 | 50.610 |
| 11.170 | 50.630 |
| 11.330 | 50.650 |
| 11.500 | 50.680 |
| 11.670 | 50.710 |
| 11.830 | 50.780 |
| 12.000 | 50.880 |
| 12.170 | 51.020 |
| 12.330 | 51.170 |
| 12.500 | 51.310 |
| 12.670 | 51.440 |
| 12.830 | 51.530 |
| 13.000 | 51.610 |
| 13.170 | 51.680 |
| 13.330 | 51.740 |
| 13.500 | 51.800 |
| 13.670 | 51.840 |
| 13.830 | 51.890 |
| 14.000 | 51.920 |
| 14.170 | 51.960 |
| 14.330 | 52.000 |
| 14.500 | 52.030 |

| | |
|---|---|
| 14.670 | 52.060 |
| 14.830 | 52.090 |
| 15.000 | 52.120 |
| 15.170 | 52.140 |
| 15.330 | 52.170 |
| 15.500 | 52.200 |
| 15.670 | 52.220 |
| 15.830 | 52.250 |
| 16.000 | 52.280 |
| 16.170 | 52.300 |
| 16.670 | 52.380 |
| 17.170 | 52.450 |
| 17.670 | 52.520 |
| 18.170 | 52.590 |
| 18.670 | 52.650 |
| 19.170 | 52.720 |
| 19.670 | 52.770 |
| 20.170 | 52.830 |
| 20.670 | 52.890 |
| 21.170 | 52.940 |
| 21.670 | 52.980 |
| 22.170 | 53.030 |
| 22.670 | 53.070 |
| 23.170 | 53.110 |
| 23.670 | 53.140 |
| 24.170 | 53.170 |
| 24.670 | 53.190 |
| 25.170 | 53.200 |
| 25.670 | 53.210 |
| 26.170 | 53.220 |
| 26.670 | 53.230 |
| 27.170 | 53.230 |
| 27.670 | 53.230 |
| 28.170 | 53.240 |
| 28.670 | 53.230 |
| 29.170 | 53.230 |
| 29.670 | 53.230 |
| 30.170 | 53.220 |
| 30.670 | 53.220 |
| 31.170 | 53.210 |
| 31.670 | 53.210 |
| 32.170 | 53.200 |
| 32.670 | 53.190 |
| 33.170 | 53.180 |
| 33.670 | 53.170 |
| 34.170 | 53.160 |
| 34.670 | 53.150 |
| 35.170 | 53.140 |
| 35.670 | 53.130 |
| 36.000 | 53.120 |

Name: 025-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.160 |
| 5.500 | 42.160 |
| 6.000 | 42.170 |
| 6.500 | 42.180 |
| 7.000 | 42.190 |
| 7.500 | 42.210 |
| 8.000 | 42.240 |
| 8.500 | 42.270 |
| 8.750 | 42.280 |
| 9.000 | 42.300 |
| 9.250 | 42.320 |
| 9.500 | 42.330 |
| 9.750 | 42.350 |
| 10.000 | 42.370 |
| 10.250 | 42.380 |
| 10.500 | 42.400 |

| | |
|---|---|
| 10.750 | 42.420 |
| 11.000 | 42.450 |
| 11.250 | 42.470 |
| 11.500 | 42.500 |
| 11.750 | 42.560 |
| 12.000 | 42.670 |
| 12.250 | 42.820 |
| 12.500 | 42.950 |
| 12.750 | 43.030 |
| 13.000 | 43.070 |
| 13.250 | 43.080 |
| 13.500 | 43.080 |
| 13.750 | 43.080 |
| 14.000 | 43.090 |
| 14.250 | 43.110 |
| 14.500 | 43.150 |
| 14.750 | 43.200 |
| 15.000 | 43.250 |
| 15.250 | 43.300 |
| 15.500 | 43.340 |
| 15.750 | 43.370 |
| 16.000 | 43.410 |
| 16.250 | 43.440 |
| 16.750 | 43.490 |
| 17.250 | 43.540 |
| 17.750 | 43.570 |
| 18.250 | 43.600 |
| 18.750 | 43.620 |
| 19.250 | 43.640 |
| 19.750 | 43.650 |
| 20.250 | 43.670 |
| 20.750 | 43.690 |
| 21.250 | 43.720 |
| 21.750 | 43.750 |
| 22.250 | 43.780 |
| 22.750 | 43.810 |
| 23.250 | 43.830 |
| 23.750 | 43.860 |
| 24.250 | 43.880 |
| 24.750 | 43.900 |
| 25.250 | 43.910 |
| 25.750 | 43.920 |
| 26.250 | 43.930 |
| 26.750 | 43.940 |
| 27.250 | 43.940 |
| 27.750 | 43.950 |
| 28.250 | 43.950 |
| 28.750 | 43.950 |
| 29.250 | 43.950 |
| 29.750 | 43.950 |
| 30.250 | 43.950 |
| 30.750 | 43.940 |
| 31.250 | 43.940 |
| 31.750 | 43.930 |
| 32.250 | 43.930 |
| 32.750 | 43.920 |
| 33.250 | 43.910 |
| 33.750 | 43.910 |
| 34.250 | 43.900 |
| 34.750 | 43.890 |
| 35.250 | 43.880 |
| 35.750 | 43.870 |
| 36.250 | 43.850 |
| 36.750 | 43.840 |
| 37.250 | 43.830 |
| 37.750 | 43.820 |
| 38.250 | 43.800 |
| 38.750 | 43.790 |
| 39.250 | 43.780 |
| 39.750 | 43.760 |
| 40.250 | 43.750 |
| 40.750 | 43.730 |
| 41.250 | 43.720 |
| 41.750 | 43.700 |
| 42.250 | 43.690 |
| 42.750 | 43.670 |
| 43.250 | 43.660 |
| 43.750 | 43.640 |
| 44.250 | 43.630 |
| 44.750 | 43.610 |
| 45.250 | 43.600 |
| 45.750 | 43.580 |

| | |
|---|---|
| 46.250 | 43.570 |
| 46.750 | 43.550 |
| 47.250 | 43.530 |
| 47.750 | 43.520 |
| 48.000 | 43.510 |

Name: 025-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.140 |
| 8.500 | 46.150 |
| 8.750 | 46.150 |
| 9.000 | 46.150 |
| 9.250 | 46.160 |
| 9.500 | 46.160 |
| 9.750 | 46.170 |
| 10.000 | 46.180 |
| 10.250 | 46.190 |
| 10.500 | 46.200 |
| 10.750 | 46.220 |
| 11.000 | 46.240 |
| 11.250 | 46.260 |
| 11.500 | 46.290 |
| 11.750 | 46.330 |
| 12.000 | 46.400 |
| 12.250 | 46.570 |
| 12.500 | 46.710 |
| 12.750 | 46.800 |
| 13.000 | 46.860 |
| 13.250 | 46.910 |
| 13.500 | 46.940 |
| 13.750 | 46.980 |
| 14.000 | 47.010 |
| 14.250 | 47.040 |
| 14.500 | 47.070 |
| 14.750 | 47.100 |
| 15.000 | 47.130 |
| 15.250 | 47.160 |
| 15.500 | 47.190 |
| 15.750 | 47.220 |
| 16.000 | 47.260 |
| 16.250 | 47.290 |
| 16.750 | 47.350 |
| 17.250 | 47.410 |
| 17.750 | 47.460 |
| 18.250 | 47.500 |
| 18.750 | 47.530 |
| 19.250 | 47.570 |
| 19.750 | 47.720 |
| 20.250 | 48.190 |
| 20.750 | 48.710 |
| 21.250 | 48.950 |
| 21.750 | 49.120 |
| 22.250 | 49.240 |
| 22.750 | 49.310 |
| 23.250 | 49.370 |
| 23.750 | 49.410 |
| 24.250 | 49.430 |
| 24.750 | 49.430 |
| 25.250 | 49.430 |
| 25.750 | 49.440 |
| 26.250 | 49.430 |
| 26.750 | 49.430 |
| 27.250 | 49.420 |

| | |
|---|---|
| 27.750 | 49.410 |
| 28.250 | 49.400 |
| 28.750 | 49.380 |
| 29.250 | 49.360 |
| 29.750 | 49.340 |
| 30.250 | 49.320 |
| 30.750 | 49.300 |
| 31.250 | 49.280 |
| 31.750 | 49.250 |
| 32.250 | 49.230 |
| 32.750 | 49.190 |
| 33.250 | 49.160 |
| 33.750 | 49.130 |
| 34.250 | 49.100 |
| 34.750 | 49.080 |
| 35.250 | 49.050 |
| 35.750 | 49.020 |
| 36.250 | 48.990 |
| 36.750 | 48.960 |
| 37.250 | 48.930 |
| 37.750 | 48.900 |
| 38.250 | 48.870 |
| 38.750 | 48.840 |
| 39.250 | 48.820 |
| 39.750 | 48.790 |
| 40.250 | 48.770 |
| 40.750 | 48.740 |
| 41.250 | 48.720 |
| 41.750 | 48.700 |
| 42.250 | 48.670 |
| 42.750 | 48.650 |
| 43.250 | 48.630 |
| 43.750 | 48.610 |
| 44.250 | 48.590 |
| 44.750 | 48.570 |
| 45.250 | 48.550 |
| 45.750 | 48.530 |
| 46.250 | 48.510 |
| 46.750 | 48.500 |
| 47.250 | 48.480 |
| 47.750 | 48.460 |
| 48.000 | 48.290 |

Name: 025-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |
| 4.500 | 41.140 |
| 5.000 | 41.280 |
| 5.500 | 41.390 |
| 6.000 | 41.510 |
| 6.500 | 41.670 |
| 7.000 | 41.830 |
| 7.500 | 42.000 |
| 8.000 | 42.170 |
| 8.500 | 42.340 |
| 8.750 | 42.420 |
| 9.000 | 42.500 |
| 9.250 | 42.580 |
| 9.500 | 42.650 |
| 9.750 | 42.730 |
| 10.000 | 42.800 |
| 10.250 | 42.870 |
| 10.500 | 42.960 |
| 10.750 | 43.070 |
| 11.000 | 43.160 |
| 11.250 | 43.240 |
| 11.500 | 43.430 |
| 11.750 | 43.690 |
| 12.000 | 44.060 |
| 12.250 | 44.120 |
| 12.500 | 44.140 |

| | |
|---|---|
| 12.750 | 44.090 |
| 13.000 | 43.950 |
| 13.250 | 43.930 |
| 13.500 | 43.870 |
| 13.750 | 43.960 |
| 14.000 | 44.130 |
| 14.250 | 44.240 |
| 14.500 | 44.340 |
| 14.750 | 44.420 |
| 15.000 | 44.490 |
| 15.250 | 44.540 |
| 15.500 | 44.570 |
| 15.750 | 44.580 |
| 16.000 | 44.580 |
| 16.250 | 44.570 |
| 16.750 | 44.520 |
| 17.250 | 44.470 |
| 17.750 | 44.410 |
| 18.250 | 44.350 |
| 18.750 | 44.290 |
| 19.250 | 44.240 |
| 19.750 | 44.180 |
| 20.250 | 44.130 |
| 20.750 | 44.070 |
| 21.250 | 43.990 |
| 21.750 | 43.910 |
| 22.250 | 43.840 |
| 22.750 | 43.770 |
| 23.250 | 43.720 |
| 23.750 | 43.690 |
| 24.250 | 43.660 |
| 24.750 | 43.630 |
| 25.250 | 43.600 |
| 25.750 | 43.570 |
| 26.250 | 43.550 |
| 26.750 | 43.530 |
| 27.250 | 43.510 |
| 27.750 | 43.480 |
| 28.250 | 43.460 |
| 28.750 | 43.440 |
| 29.250 | 43.410 |
| 29.750 | 43.400 |
| 30.250 | 42.620 |
| 30.750 | 42.160 |
| 31.250 | 42.050 |
| 31.750 | 42.010 |
| 32.250 | 41.980 |
| 32.750 | 41.960 |
| 33.250 | 41.930 |
| 33.750 | 41.910 |
| 34.250 | 41.900 |
| 34.750 | 41.890 |
| 35.250 | 41.880 |
| 35.750 | 41.860 |
| 36.250 | 41.850 |
| 36.750 | 41.840 |
| 37.250 | 41.830 |
| 37.750 | 41.820 |
| 38.250 | 41.830 |
| 38.750 | 41.810 |
| 39.250 | 41.800 |
| 39.750 | 41.790 |
| 40.250 | 41.770 |
| 40.750 | 41.760 |
| 41.250 | 41.750 |
| 41.750 | 41.730 |
| 42.250 | 41.720 |
| 42.750 | 41.710 |
| 43.250 | 41.700 |
| 43.750 | 41.680 |
| 44.250 | 41.670 |
| 44.750 | 41.660 |
| 45.250 | 41.650 |
| 45.750 | 41.640 |
| 46.250 | 41.630 |
| 46.750 | 41.620 |
| 47.250 | 41.610 |
| 47.750 | 41.600 |
| 48.000 | 41.600 |

Name: 100-024 Node: GC-1000 Type: Stage

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.410 |
| 3.500 | 50.410 |
| 4.000 | 50.410 |
| 4.500 | 50.410 |
| 5.000 | 50.420 |
| 5.500 | 50.420 |
| 6.000 | 50.440 |
| 6.500 | 50.450 |
| 7.000 | 50.460 |
| 7.500 | 50.480 |
| 8.000 | 50.510 |
| 8.500 | 50.540 |
| 8.670 | 50.550 |
| 8.830 | 50.560 |
| 9.000 | 50.570 |
| 9.170 | 50.580 |
| 9.330 | 50.600 |
| 9.500 | 50.610 |
| 9.670 | 50.630 |
| 9.830 | 50.640 |
| 10.000 | 50.660 |
| 10.170 | 50.680 |
| 10.330 | 50.700 |
| 10.500 | 50.720 |
| 10.670 | 50.740 |
| 10.830 | 50.770 |
| 11.000 | 50.790 |
| 11.170 | 50.820 |
| 11.330 | 50.850 |
| 11.500 | 50.890 |
| 11.670 | 50.950 |
| 11.830 | 51.040 |
| 12.000 | 51.170 |
| 12.170 | 51.350 |
| 12.330 | 51.560 |
| 12.500 | 51.760 |
| 12.670 | 51.940 |
| 12.830 | 52.080 |
| 13.000 | 52.200 |
| 13.170 | 52.310 |
| 13.330 | 52.410 |
| 13.500 | 52.490 |
| 13.670 | 52.570 |
| 13.830 | 52.640 |
| 14.000 | 52.710 |
| 14.170 | 52.770 |
| 14.330 | 52.830 |
| 14.500 | 52.880 |
| 14.670 | 52.930 |
| 14.830 | 52.970 |
| 15.000 | 53.010 |
| 15.170 | 53.050 |
| 15.330 | 53.080 |
| 15.500 | 53.120 |
| 15.670 | 53.150 |
| 15.830 | 53.180 |
| 16.000 | 53.210 |
| 16.170 | 53.230 |
| 16.670 | 53.310 |
| 17.170 | 53.380 |
| 17.670 | 53.440 |
| 18.170 | 53.500 |
| 18.670 | 53.560 |
| 19.170 | 53.610 |
| 19.670 | 53.660 |
| 20.170 | 53.700 |
| 20.670 | 53.740 |
| 21.170 | 53.780 |
| 21.670 | 53.820 |
| 22.170 | 53.850 |
| 22.670 | 53.880 |
| 23.170 | 53.910 |
| 23.670 | 53.940 |

| | |
|---|---|
| 24.170 | 53.970 |
| 24.670 | 53.980 |
| 25.170 | 54.000 |
| 25.670 | 54.000 |
| 26.170 | 54.010 |
| 26.670 | 54.010 |
| 27.170 | 54.010 |
| 27.670 | 54.000 |
| 28.170 | 54.000 |
| 28.670 | 54.000 |
| 29.170 | 53.990 |
| 29.670 | 53.990 |
| 30.170 | 53.980 |
| 30.670 | 53.970 |
| 31.170 | 53.970 |
| 31.670 | 53.960 |
| 32.170 | 53.950 |
| 32.670 | 53.940 |
| 33.170 | 53.920 |
| 33.670 | 53.910 |
| 34.170 | 53.900 |
| 34.670 | 53.890 |
| 35.170 | 53.870 |
| 35.670 | 53.860 |
| 36.000 | 53.850 |

Name: 100-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.160 |
| 5.000 | 42.170 |
| 5.500 | 42.180 |
| 6.000 | 42.210 |
| 6.500 | 42.230 |
| 7.000 | 42.270 |
| 7.500 | 42.300 |
| 8.000 | 42.330 |
| 8.500 | 42.370 |
| 8.750 | 42.380 |
| 9.000 | 42.400 |
| 9.250 | 42.420 |
| 9.500 | 42.440 |
| 9.750 | 42.460 |
| 10.000 | 42.470 |
| 10.250 | 42.500 |
| 10.500 | 42.520 |
| 10.750 | 42.540 |
| 11.000 | 42.570 |
| 11.250 | 42.600 |
| 11.500 | 42.630 |
| 11.750 | 42.700 |
| 12.000 | 42.830 |
| 12.250 | 42.980 |
| 12.500 | 43.130 |
| 12.750 | 43.230 |
| 13.000 | 43.300 |
| 13.250 | 43.350 |
| 13.500 | 43.390 |
| 13.750 | 43.450 |
| 14.000 | 43.540 |
| 14.250 | 43.610 |
| 14.500 | 43.690 |
| 14.750 | 43.750 |
| 15.000 | 43.810 |
| 15.250 | 43.860 |
| 15.500 | 43.910 |
| 15.750 | 43.950 |
| 16.000 | 43.990 |
| 16.250 | 44.020 |
| 16.750 | 44.090 |
| 17.250 | 44.150 |

| | |
|---|---|
| 17.750 | 44.200 |
| 18.250 | 44.250 |
| 18.750 | 44.300 |
| 19.250 | 44.350 |
| 19.750 | 44.390 |
| 20.250 | 44.430 |
| 20.750 | 44.460 |
| 21.250 | 44.490 |
| 21.750 | 44.520 |
| 22.250 | 44.550 |
| 22.750 | 44.570 |
| 23.250 | 44.600 |
| 23.750 | 44.620 |
| 24.250 | 44.640 |
| 24.750 | 44.650 |
| 25.250 | 44.660 |
| 25.750 | 44.670 |
| 26.250 | 44.670 |
| 26.750 | 44.670 |
| 27.250 | 44.670 |
| 27.750 | 44.670 |
| 28.250 | 44.670 |
| 28.750 | 44.670 |
| 29.250 | 44.670 |
| 29.750 | 44.670 |
| 30.250 | 44.670 |
| 30.750 | 44.670 |
| 31.250 | 44.660 |
| 31.750 | 44.660 |
| 32.250 | 44.650 |
| 32.750 | 44.650 |
| 33.250 | 44.640 |
| 33.750 | 44.630 |
| 34.250 | 44.620 |
| 34.750 | 44.610 |
| 35.250 | 44.600 |
| 35.750 | 44.590 |
| 36.250 | 44.570 |
| 36.750 | 44.560 |
| 37.250 | 44.540 |
| 37.750 | 44.530 |
| 38.250 | 44.510 |
| 38.750 | 44.490 |
| 39.250 | 44.470 |
| 39.750 | 44.450 |
| 40.250 | 44.430 |
| 40.750 | 44.410 |
| 41.250 | 44.390 |
| 41.750 | 44.370 |
| 42.250 | 44.350 |
| 42.750 | 44.330 |
| 43.250 | 44.300 |
| 43.750 | 44.280 |
| 44.250 | 44.260 |
| 44.750 | 44.240 |
| 45.250 | 44.210 |
| 45.750 | 44.190 |
| 46.250 | 44.170 |
| 46.750 | 44.140 |
| 47.250 | 44.120 |
| 47.750 | 44.100 |
| 48.000 | 44.070 |

Name: 100-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.140 |

| | |
|---|---|
| 7.000 | 46.150 |
| 7.500 | 46.150 |
| 8.000 | 46.170 |
| 8.500 | 46.180 |
| 8.750 | 46.190 |
| 9.000 | 46.200 |
| 9.250 | 46.220 |
| 9.500 | 46.230 |
| 9.750 | 46.250 |
| 10.000 | 46.270 |
| 10.250 | 46.290 |
| 10.500 | 46.320 |
| 10.750 | 46.330 |
| 11.000 | 46.330 |
| 11.250 | 46.340 |
| 11.500 | 46.360 |
| 11.750 | 46.440 |
| 12.000 | 46.630 |
| 12.250 | 46.860 |
| 12.500 | 47.030 |
| 12.750 | 47.140 |
| 13.000 | 47.210 |
| 13.250 | 47.270 |
| 13.500 | 47.310 |
| 13.750 | 47.350 |
| 14.000 | 47.390 |
| 14.250 | 47.430 |
| 14.500 | 47.460 |
| 14.750 | 47.480 |
| 15.000 | 47.500 |
| 15.250 | 47.520 |
| 15.500 | 47.540 |
| 15.750 | 47.560 |
| 16.000 | 47.600 |
| 16.250 | 47.750 |
| 16.750 | 48.370 |
| 17.250 | 48.910 |
| 17.750 | 49.200 |
| 18.250 | 49.380 |
| 18.750 | 49.510 |
| 19.250 | 49.610 |
| 19.750 | 49.700 |
| 20.250 | 49.770 |
| 20.750 | 49.830 |
| 21.250 | 49.890 |
| 21.750 | 49.890 |
| 22.250 | 49.910 |
| 22.750 | 49.940 |
| 23.250 | 49.950 |
| 23.750 | 49.960 |
| 24.250 | 49.970 |
| 24.750 | 49.960 |
| 25.250 | 49.950 |
| 25.750 | 49.950 |
| 26.250 | 49.950 |
| 26.750 | 49.950 |
| 27.250 | 49.950 |
| 27.750 | 49.950 |
| 28.250 | 49.940 |
| 28.750 | 49.940 |
| 29.250 | 49.940 |
| 29.750 | 49.940 |
| 30.250 | 49.940 |
| 30.750 | 49.930 |
| 31.250 | 49.920 |
| 31.750 | 49.910 |
| 32.250 | 49.900 |
| 32.750 | 49.890 |
| 33.250 | 49.890 |
| 33.750 | 49.870 |
| 34.250 | 49.840 |
| 34.750 | 49.810 |
| 35.250 | 49.770 |
| 35.750 | 49.740 |
| 36.250 | 49.700 |
| 36.750 | 49.660 |
| 37.250 | 49.620 |
| 37.750 | 49.580 |
| 38.250 | 49.530 |
| 38.750 | 49.490 |
| 39.250 | 49.450 |
| 39.750 | 49.410 |

| | |
|---|---|
| 40.250 | 49.370 |
| 40.750 | 49.340 |
| 41.250 | 49.300 |
| 41.750 | 49.260 |
| 42.250 | 49.220 |
| 42.750 | 49.180 |
| 43.250 | 49.140 |
| 43.750 | 49.100 |
| 44.250 | 49.070 |
| 44.750 | 49.040 |
| 45.250 | 49.010 |
| 45.750 | 48.980 |
| 46.250 | 48.950 |
| 46.750 | 48.920 |
| 47.250 | 48.890 |
| 47.750 | 48.870 |
| 48.000 | 48.840 |

Name: 100-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.140 |
| 4.000 | 41.280 |
| 4.500 | 41.420 |
| 5.000 | 41.600 |
| 5.500 | 41.810 |
| 6.000 | 42.000 |
| 6.500 | 42.190 |
| 7.000 | 42.380 |
| 7.500 | 42.530 |
| 8.000 | 42.680 |
| 8.500 | 42.800 |
| 8.750 | 42.870 |
| 9.000 | 42.940 |
| 9.250 | 43.020 |
| 9.500 | 43.080 |
| 9.750 | 43.140 |
| 10.000 | 43.200 |
| 10.250 | 43.370 |
| 10.500 | 43.370 |
| 10.750 | 43.430 |
| 11.000 | 43.500 |
| 11.250 | 43.540 |
| 11.500 | 43.610 |
| 11.750 | 43.920 |
| 12.000 | 44.160 |
| 12.250 | 44.250 |
| 12.500 | 44.260 |
| 12.750 | 44.220 |
| 13.000 | 44.240 |
| 13.250 | 44.400 |
| 13.500 | 44.650 |
| 13.750 | 44.870 |
| 14.000 | 45.020 |
| 14.250 | 45.170 |
| 14.500 | 45.290 |
| 14.750 | 45.370 |
| 15.000 | 45.460 |
| 15.250 | 45.500 |
| 15.500 | 45.500 |
| 15.750 | 45.470 |
| 16.000 | 45.410 |
| 16.250 | 45.350 |
| 16.750 | 45.250 |
| 17.250 | 45.140 |
| 17.750 | 45.030 |
| 18.250 | 44.910 |
| 18.750 | 44.800 |
| 19.250 | 44.690 |
| 19.750 | 44.600 |
| 20.250 | 44.510 |
| 20.750 | 44.420 |
| 21.250 | 44.350 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 21.750 | 44.280 |
| 22.250 | 44.220 |
| 22.750 | 44.170 |
| 23.250 | 44.120 |
| 23.750 | 44.050 |
| 24.250 | 43.970 |
| 24.750 | 43.860 |
| 25.250 | 43.730 |
| 25.750 | 43.640 |
| 26.250 | 43.600 |
| 26.750 | 43.580 |
| 27.250 | 43.560 |
| 27.750 | 43.540 |
| 28.250 | 43.530 |
| 28.750 | 43.510 |
| 29.250 | 43.510 |
| 29.750 | 43.510 |
| 30.250 | 43.510 |
| 30.750 | 43.490 |
| 31.250 | 43.470 |
| 31.750 | 43.450 |
| 32.250 | 43.420 |
| 32.750 | 43.420 |
| 33.250 | 43.330 |
| 33.750 | 42.350 |
| 34.250 | 42.110 |
| 34.750 | 42.050 |
| 35.250 | 42.020 |
| 35.750 | 42.000 |
| 36.250 | 41.980 |
| 36.750 | 41.960 |
| 37.250 | 41.950 |
| 37.750 | 41.930 |
| 38.250 | 41.920 |
| 38.750 | 41.910 |
| 39.250 | 41.900 |
| 39.750 | 41.890 |
| 40.250 | 41.880 |
| 40.750 | 41.870 |
| 41.250 | 41.870 |
| 41.750 | 41.860 |
| 42.250 | 41.860 |
| 42.750 | 41.850 |
| 43.250 | 41.850 |
| 43.750 | 41.840 |
| 44.250 | 41.840 |
| 44.750 | 41.840 |
| 45.250 | 41.830 |
| 45.750 | 41.830 |
| 46.250 | 41.830 |
| 46.750 | 41.830 |
| 47.250 | 41.830 |
| 47.750 | 41.820 |
| 48.000 | 41.820 |

**ST. JOHNS RIVER WATER MANAGEMENT DISTRICT (SJRWMD)**
**JOINT APPLICATION FOR INDIVIDUAL ENVIRONMENTAL RESOURCE PERMIT**

**ERP APPLICATION NO. 4-117-121387-2**
**ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE**

SEMINOLE COUNTY
FLORIDA'S NATURAL CHOICE

# TAB 4.2

UPDATED SURFACE WATER ANALYSIS

ICPR FLOOD ROUTING RESULTS FOR THE
100-YEAR, 96-HOUR STORM EVENT
(GROUP "GRACE LAKE")

INITIAL STAGE => ELEVATION 58-FT, NAVD

Pegasus ENGINEERING

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
NODE MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 58 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| SC-0750 | Grace Lake | 100-096 | 0.00 | 52.00 | 54.00 | 0.0000 | 40 | 96.00 | 48.18 | 0.00 | 0.00 |
| SC-0760 | Grace Lake | 100-096 | 96.00 | 55.87 | 58.00 | 0.0001 | 619 | 96.00 | 31.85 | 95.93 | 31.85 |
| SC-0770 | Grace Lake | 100-096 | 96.00 | 58.69 | 58.00 | -0.0004 | 44368 | 59.72 | 49.94 | 96.00 | 34.71 |
| SC-0780 | Grace Lake | 100-096 | 0.00 | 64.24 | 67.27 | 0.0000 | 114 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-0790 | Grace Lake | 100-096 | 0.00 | 64.00 | 67.00 | 0.0000 | 7842 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-0800 | Grace Lake | 100-096 | 96.00 | 58.70 | 56.00 | 0.0002 | 379104 | 61.31 | 96.79 | 96.02 | 39.83 |
| SC-0810 | Grace Lake | 100-096 | 96.00 | 58.73 | 58.00 | 0.0049 | 2421 | 61.41 | 68.15 | 61.42 | 68.15 |
| SC-0815 | Grace Lake | 100-096 | 96.00 | 58.70 | 56.00 | 0.0001 | 2500 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-0820 | Grace Lake | 100-096 | 96.00 | 58.70 | 56.00 | 0.0001 | 79554 | 60.08 | 39.78 | 61.46 | 6.73 |
| SC-0830 | Grace Lake | 100-096 | 96.00 | 59.03 | 59.00 | -0.0010 | 40264 | 61.21 | 74.77 | 61.43 | 72.31 |
| SC-0840 | Grace Lake | 100-096 | 96.00 | 59.03 | 58.00 | 0.0002 | 206982 | 60.31 | 150.90 | 61.28 | 62.39 |
| SC-0850 | Grace Lake | 100-096 | 96.00 | 60.16 | 59.50 | 0.0011 | 145 | 96.00 | 42.89 | 96.00 | 42.89 |
| SC-0860 | Grace Lake | 100-096 | 96.00 | 61.24 | 61.55 | 0.0006 | 155 | 96.00 | 42.89 | 96.00 | 42.89 |
| SC-0870 | Grace Lake | 100-096 | 96.00 | 63.86 | 66.00 | 0.0004 | 154 | 96.00 | 42.89 | 96.00 | 42.89 |
| SC-0875 | Grace Lake | 100-096 | 96.00 | 64.88 | 64.00 | 0.0006 | 439 | 96.00 | 42.89 | 96.00 | 42.89 |
| SC-0880 | Grace Lake | 100-096 | 96.00 | 64.94 | 64.00 | 0.0047 | 241109 | 60.08 | 157.25 | 96.00 | 42.89 |
| SC-0890 | Grace Lake | 100-096 | 96.74 | 65.33 | 66.00 | 0.0066 | 458 | 97.72 | 100.44 | 97.69 | 42.08 |
| SC-0900 | Grace Lake | 100-096 | 96.54 | 65.32 | 66.00 | 0.0001 | 54641 | 60.08 | 34.60 | 61.26 | 9.03 |
| SC-0910 | Grace Lake | 100-096 | 96.52 | 65.33 | 66.00 | 0.0001 | 144829 | 67.64 | 20.89 | 97.72 | 51.58 |
| SC-0920 | Grace Lake | 100-096 | 96.52 | 65.33 | 66.00 | 0.0001 | 1562098 | 60.08 | 567.06 | 97.72 | 67.27 |
| SC-0925 | Grace Lake | 100-096 | 60.56 | 78.79 | 76.00 | 0.0002 | 48853 | 60.08 | 63.78 | 60.56 | 23.84 |
| SC-0930 | Grace Lake | 100-096 | 60.25 | 65.95 | 66.00 | 0.0001 | 9594 | 60.19 | 105.55 | 60.25 | 105.16 |
| SC-0940 | Grace Lake | 100-096 | 60.19 | 69.07 | 69.00 | 0.0017 | 12328 | 60.17 | 105.66 | 60.19 | 105.55 |
| SC-0950 | Grace Lake | 100-096 | 60.25 | 69.44 | 72.00 | 0.0019 | 1139 | 60.48 | 38.86 | 60.49 | 38.89 |
| SC-0960 | Grace Lake | 100-096 | 60.44 | 70.40 | 73.00 | 0.0043 | 505 | 60.48 | 38.86 | 60.48 | 38.86 |
| SC-0970 | Grace Lake | 100-096 | 60.10 | 72.09 | 71.00 | 0.0005 | 2037 | 60.08 | 69.36 | 60.10 | 69.16 |
| SC-0980 | Grace Lake | 100-096 | 60.48 | 77.25 | 74.00 | 0.0008 | 33808 | 60.08 | 131.53 | 60.53 | 91.11 |
| SC-0985 | Grace Lake | 100-096 | 60.48 | 77.27 | 73.00 | 0.0004 | 139136 | 60.08 | 371.60 | 63.31 | 77.79 |
| SC-0990 | Grace Lake | 100-096 | 68.21 | 72.66 | 79.00 | 0.0009 | 151 | 68.20 | 5.76 | 68.21 | 5.76 |
| SC-0995 | Grace Lake | 100-096 | 68.20 | 86.23 | 84.00 | 0.0002 | 129991 | 60.08 | 167.63 | 68.20 | 5.76 |

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
LINK MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 58 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Flow hrs | Max Flow cfs | Max Delta Q cfs | Max Time US Stage hrs | Max US Stage ft | Max Time DS Stage hrs | Max DS Stage ft |
|---|---|---|---|---|---|---|---|---|---|
| SC-0760-P | Grace Lake | 100-096 | 95.93 | 31.85 | 0.003 | 96.00 | 55.87 | 0.00 | 52.00 |
| SC-0770-D1 | Grace Lake | 100-096 | 96.00 | 31.85 | 0.001 | 96.00 | 58.69 | 96.00 | 55.87 |
| SC-0770-D2 | Grace Lake | 100-096 | 60.06 | 14.66 | 0.611 | 96.00 | 58.69 | 96.00 | 58.70 |
| SC-0770-W | Grace Lake | 100-096 | 96.00 | 3.49 | -0.000 | 96.00 | 58.69 | 0.00 | 52.00 |
| SC-0780-D | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 0.00 | 64.24 | 96.00 | 58.69 |
| SC-0780-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 0.00 | 64.24 | 96.00 | 58.69 |
| SC-0790-P | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 0.00 | 64.00 | 0.00 | 64.24 |
| SC-0800-W1 | Grace Lake | 100-096 | 96.04 | 27.03 | -0.011 | 96.00 | 58.70 | 96.00 | 58.69 |
| SC-0800-W2 | Grace Lake | 100-096 | 96.00 | 12.84 | 0.000 | 96.00 | 58.70 | 0.00 | 52.00 |
| SC-0810-W1 | Grace Lake | 100-096 | 61.42 | 68.15 | -0.023 | 96.00 | 58.73 | 96.00 | 58.70 |
| SC-0810-W2 | Grace Lake | 100-096 | 96.00 | 7.40 | -0.002 | 96.00 | 58.73 | 96.00 | 58.69 |
| SC-0815-P | Grace Lake | 100-096 | 0.00 | 0.00 | -0.002 | 96.00 | 58.70 | 96.00 | 58.73 |
| SC-0820-W1 | Grace Lake | 100-096 | 0.00 | 0.00 | -0.002 | 96.00 | 58.70 | 96.00 | 58.70 |
| SC-0820-W2 | Grace Lake | 100-096 | 61.46 | 12.64 | 0.830 | 96.00 | 58.70 | 96.00 | 58.70 |
| SC-0830-P | Grace Lake | 100-096 | 61.43 | 72.31 | 4.384 | 96.00 | 59.03 | 96.00 | 58.73 |
| SC-0840-W | Grace Lake | 100-096 | 61.28 | 62.39 | 5.653 | 96.00 | 59.03 | 96.00 | 59.03 |
| SC-0850-P | Grace Lake | 100-096 | 96.00 | 42.89 | -1.869 | 96.00 | 60.16 | 61.44 | 59.02 |
| SC-0860-P | Grace Lake | 100-096 | 96.00 | 42.89 | 0.059 | 96.00 | 61.24 | 96.00 | 60.16 |
| SC-0870-P | Grace Lake | 100-096 | 96.00 | 42.89 | 0.009 | 96.00 | 63.86 | 96.00 | 61.24 |
| SC-0875-P | Grace Lake | 100-096 | 96.00 | 42.89 | -0.017 | 96.00 | 64.88 | 96.00 | 63.86 |
| SC-0875-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 96.00 | 64.88 | 96.00 | 59.03 |
| SC-0880-W | Grace Lake | 100-096 | 96.00 | 42.89 | -0.010 | 96.00 | 64.94 | 96.00 | 64.88 |
| SC-0890-P | Grace Lake | 100-096 | 97.69 | 42.08 | -12.347 | 96.74 | 65.33 | 96.00 | 64.94 |
| SC-0890-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 96.74 | 65.33 | 96.00 | 58.73 |
| SC-0900-D | Grace Lake | 100-096 | 61.26 | 9.03 | 1.109 | 96.54 | 65.32 | 96.74 | 65.33 |
| SC-0900-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 96.54 | 65.32 | 96.74 | 65.33 |
| SC-0910-W | Grace Lake | 100-096 | 97.72 | 51.58 | 37.633 | 96.52 | 65.33 | 96.74 | 65.33 |
| SC-0920-W1 | Grace Lake | 100-096 | 96.11 | 19.85 | 3.451 | 96.52 | 65.33 | 96.52 | 65.33 |
| SC-0920-W2 | Grace Lake | 100-096 | 97.72 | 47.89 | 28.679 | 96.52 | 65.33 | 96.74 | 65.33 |
| SC-0920-W3 | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 96.52 | 65.33 | 0.00 | 64.00 |
| SC-0925-D | Grace Lake | 100-096 | 60.56 | 19.84 | 0.032 | 60.56 | 78.79 | 96.52 | 65.33 |
| SC-0925-W | Grace Lake | 100-096 | 60.56 | 4.00 | 0.001 | 60.56 | 78.79 | 96.52 | 65.33 |
| SC-0930-C | Grace Lake | 100-096 | 60.25 | 105.16 | -0.436 | 60.25 | 65.95 | 96.52 | 65.33 |
| SC-0940-C | Grace Lake | 100-096 | 60.19 | 105.55 | -0.034 | 60.19 | 69.07 | 60.25 | 65.95 |
| SC-0950-C | Grace Lake | 100-096 | 60.49 | 38.89 | 0.721 | 60.25 | 69.44 | 60.19 | 69.07 |
| SC-0960-C | Grace Lake | 100-096 | 60.48 | 38.86 | -15.425 | 60.44 | 70.40 | 60.25 | 69.44 |
| SC-0970-P | Grace Lake | 100-096 | 60.09 | 37.51 | -5.134 | 60.10 | 72.09 | 60.19 | 69.07 |
| SC-0970-W | Grace Lake | 100-096 | 60.10 | 31.68 | 0.004 | 60.10 | 72.09 | 60.19 | 69.07 |
| SC-0980-P1 | Grace Lake | 100-096 | 60.57 | 52.28 | 0.003 | 60.48 | 77.25 | 60.10 | 72.09 |
| SC-0980-P2 | Grace Lake | 100-096 | 60.48 | 38.86 | 0.005 | 60.48 | 77.25 | 59.48 | 70.78 |
| SC-0985-P | Grace Lake | 100-096 | 71.34 | 47.27 | -0.050 | 60.48 | 77.27 | 60.48 | 77.25 |
| SC-0985-W | Grace Lake | 100-096 | 63.31 | 69.28 | -0.224 | 60.48 | 77.27 | 60.48 | 77.25 |
| SC-0990-P | Grace Lake | 100-096 | 68.21 | 5.76 | 0.013 | 68.21 | 72.66 | 116.99 | 64.70 |
| SC-0995-D | Grace Lake | 100-096 | 68.20 | 5.76 | 0.004 | 68.20 | 86.23 | 68.21 | 72.66 |
| SC-1000-P | Grace Lake | 100-096 | 62.34 | 182.85 | -252.066 | 60.46 | 78.05 | 60.48 | 77.27 |
| SC-1000-W | Grace Lake | 100-096 | 60.46 | 56.63 | 56.633 | 60.46 | 78.05 | 60.48 | 77.27 |

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
BASIN MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 58 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Simulation | Basin | Group | Time Max hrs | Flow Max cfs | Volume in | Volume ft3 |
|---|---|---|---|---|---|---|
| 100-096 | SC-0770 | Grace Lake | 60.04 | 92.29 | 8.835 | 577896 |
| 100-096 | SC-0800A | Grace Lake | 60.03 | 52.65 | 11.625 | 378938 |
| 100-096 | SC-0800B | Grace Lake | 60.03 | 23.17 | 10.850 | 158725 |
| 100-096 | SC-0810 | Grace Lake | 60.01 | 22.88 | 11.173 | 140732 |
| 100-096 | SC-0820A | Grace Lake | 60.03 | 19.44 | 11.164 | 130493 |
| 100-096 | SC-0820B | Grace Lake | 60.13 | 22.13 | 11.173 | 201980 |
| 100-096 | SC-0830 | Grace Lake | 60.17 | 32.41 | 9.697 | 325245 |
| 100-096 | SC-0840 | Grace Lake | 60.11 | 148.40 | 8.286 | 1249386 |
| 100-096 | SC-0880 | Grace Lake | 60.18 | 251.81 | 8.650 | 2443779 |
| 100-096 | SC-0900A | Grace Lake | 60.02 | 14.15 | 11.008 | 91507 |
| 100-096 | SC-0900B | Grace Lake | 60.22 | 22.93 | 11.170 | 224637 |
| 100-096 | SC-0910 | Grace Lake | 60.03 | 38.07 | 11.775 | 260308 |
| 100-096 | SC-0920 | Grace Lake | 60.08 | 448.71 | 10.856 | 3492417 |
| 100-096 | SC-0925 | Grace Lake | 60.03 | 64.99 | 8.656 | 416039 |
| 100-096 | SC-0970 | Grace Lake | 60.05 | 22.94 | 10.044 | 153865 |
| 100-096 | SC-0980A | Grace Lake | 60.13 | 10.05 | 8.654 | 86703 |
| 100-096 | SC-0980B | Grace Lake | 60.03 | 28.62 | 8.656 | 183195 |
| 100-096 | SC-0980C | Grace Lake | 60.09 | 54.01 | 8.656 | 386816 |
| 100-096 | SC-0985 | Grace Lake | 60.07 | 205.63 | 8.656 | 1378148 |
| 100-096 | SC-0995 | Grace Lake | 60.11 | 168.83 | 10.044 | 1315407 |

# TAB 4.7

## UPDATED SURFACE WATER ANALYSIS

ICPR FLOOD ROUTING RESULTS FOR THE
100-YEAR, 96-HOUR STORM EVENT
(GROUP "GRACE LAKE")

INITIAL STAGE => ELEVATION 62.6-FT, NAVD

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
NODE MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 62.6 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| SC-0750 | Grace Lake | 100-096 | 0.00 | 52.00 | 54.00 | 0.0000 | 40 | 72.14 | 65.02 | 0.00 | 0.00 |
| SC-0760 | Grace Lake | 100-096 | 72.12 | 56.22 | 58.00 | 0.0001 | 342 | 72.12 | 37.54 | 72.12 | 37.54 |
| SC-0770 | Grace Lake | 100-096 | 72.12 | 58.77 | 58.00 | 0.0001 | 45682 | 59.72 | 49.94 | 72.11 | 42.95 |
| SC-0780 | Grace Lake | 100-096 | 97.37 | 64.44 | 67.27 | 0.0000 | 129 | 96.85 | 0.00 | 0.00 | 0.00 |
| SC-0790 | Grace Lake | 100-096 | 97.43 | 64.44 | 67.00 | 0.0000 | 8815 | 95.56 | 0.09 | 96.85 | 0.00 |
| SC-0800 | Grace Lake | 100-096 | 72.15 | 58.79 | 56.00 | 0.0002 | 382357 | 60.08 | 164.59 | 72.42 | 48.09 |
| SC-0810 | Grace Lake | 100-096 | 72.15 | 58.82 | 58.00 | 0.0049 | 2497 | 61.08 | 95.99 | 61.09 | 95.99 |
| SC-0815 | Grace Lake | 100-096 | 72.15 | 58.79 | 56.00 | 0.0001 | 2536 | 0.00 | 0.00 | 0.00 | 0.00 |
| SC-0820 | Grace Lake | 100-096 | 72.15 | 58.79 | 56.00 | 0.0001 | 79844 | 60.08 | 39.78 | 60.59 | 19.83 |
| SC-0830 | Grace Lake | 100-096 | 61.22 | 59.85 | 59.00 | -0.0010 | 44942 | 60.67 | 102.70 | 61.23 | 99.91 |
| SC-0840 | Grace Lake | 100-096 | 61.22 | 59.86 | 58.00 | 0.0001 | 229303 | 60.08 | 188.60 | 61.19 | 87.24 |
| SC-0850 | Grace Lake | 100-096 | 61.24 | 60.96 | 59.50 | 0.0001 | 123 | 96.00 | 46.99 | 96.00 | 46.99 |
| SC-0860 | Grace Lake | 100-096 | 61.26 | 62.04 | 61.55 | 0.0003 | 155 | 96.00 | 46.99 | 96.00 | 46.99 |
| SC-0870 | Grace Lake | 100-096 | 96.00 | 64.88 | 66.00 | 0.0001 | 154 | 96.00 | 46.99 | 96.00 | 46.99 |
| SC-0875 | Grace Lake | 100-096 | 96.00 | 66.11 | 64.00 | 0.0003 | 439 | 96.00 | 57.19 | 96.00 | 57.19 |
| SC-0880 | Grace Lake | 100-096 | 96.00 | 66.17 | 64.00 | 0.0001 | 336649 | 60.17 | 208.09 | 96.00 | 57.19 |
| SC-0890 | Grace Lake | 100-096 | 95.19 | 66.84 | 66.00 | 0.0066 | 458 | 93.88 | 119.00 | 96.85 | 53.46 |
| SC-0900 | Grace Lake | 100-096 | 95.85 | 66.83 | 66.00 | 0.0001 | 65989 | 60.08 | 34.60 | 60.71 | 6.43 |
| SC-0910 | Grace Lake | 100-096 | 95.67 | 66.83 | 66.00 | 0.0000 | 158860 | 60.00 | 31.68 | 93.88 | 58.72 |
| SC-0920 | Grace Lake | 100-096 | 95.56 | 66.84 | 66.00 | 0.0000 | 1676967 | 60.08 | 567.06 | 93.88 | 83.35 |
| SC-0925 | Grace Lake | 100-096 | 60.56 | 78.79 | 76.00 | 0.0002 | 48853 | 60.08 | 63.78 | 60.56 | 23.84 |
| SC-0930 | Grace Lake | 100-096 | 94.94 | 66.87 | 66.00 | 0.0001 | 9192 | 60.19 | 105.55 | 60.25 | 105.15 |
| SC-0940 | Grace Lake | 100-096 | 60.19 | 69.07 | 69.00 | 0.0014 | 12328 | 60.17 | 105.66 | 60.19 | 105.55 |
| SC-0950 | Grace Lake | 100-096 | 60.26 | 69.44 | 72.00 | 0.0019 | 1139 | 69.31 | 41.38 | 60.50 | 38.92 |
| SC-0960 | Grace Lake | 100-096 | 60.43 | 70.40 | 73.00 | 0.0047 | 505 | 60.49 | 38.89 | 69.31 | 41.38 |
| SC-0970 | Grace Lake | 100-096 | 60.10 | 72.09 | 71.00 | 0.0003 | 2037 | 60.08 | 69.37 | 60.10 | 69.16 |
| SC-0980 | Grace Lake | 100-096 | 60.49 | 77.26 | 74.00 | 0.0005 | 33859 | 60.08 | 131.88 | 60.52 | 91.18 |
| SC-0985 | Grace Lake | 100-096 | 60.49 | 77.28 | 73.00 | 0.0002 | 139367 | 60.08 | 371.23 | 63.32 | 77.81 |
| SC-0990 | Grace Lake | 100-096 | 68.21 | 72.66 | 79.00 | 0.0009 | 151 | 68.20 | 5.76 | 68.21 | 5.76 |
| SC-0995 | Grace Lake | 100-096 | 68.20 | 86.23 | 84.00 | 0.0002 | 129991 | 60.08 | 167.63 | 68.20 | 5.76 |

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
LINK MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 62.6 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Flow hrs | Max Flow cfs | Max Delta Q cfs | Max Time US Stage hrs | Max US Stage ft | Max Time DS Stage hrs | Max DS Stage ft |
|---|---|---|---|---|---|---|---|---|---|
| SC-0760-P | Grace Lake | 100-096 | 72.12 | 37.54 | 0.004 | 72.12 | 56.22 | 0.00 | 52.00 |
| SC-0770-D1 | Grace Lake | 100-096 | 72.12 | 37.54 | 0.001 | 72.12 | 58.77 | 72.12 | 56.22 |
| SC-0770-D2 | Grace Lake | 100-096 | 59.97 | 14.25 | 0.611 | 72.12 | 58.77 | 72.15 | 58.79 |
| SC-0770-W | Grace Lake | 100-096 | 72.12 | 6.03 | -0.000 | 72.12 | 58.77 | 0.00 | 52.00 |
| SC-0780-D | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 97.37 | 64.44 | 72.12 | 58.77 |
| SC-0780-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 97.37 | 64.44 | 72.12 | 58.77 |
| SC-0790-P | Grace Lake | 100-096 | 96.85 | 0.00 | 0.003 | 97.43 | 64.44 | 97.37 | 64.44 |
| SC-0800-W1 | Grace Lake | 100-096 | 96.04 | 27.57 | 0.012 | 72.15 | 58.79 | 72.12 | 58.77 |
| SC-0800-W2 | Grace Lake | 100-096 | 72.15 | 21.45 | 0.000 | 72.15 | 58.79 | 0.00 | 52.00 |
| SC-0810-W1 | Grace Lake | 100-096 | 61.09 | 95.99 | -0.023 | 72.15 | 58.82 | 72.15 | 58.79 |
| SC-0810-W2 | Grace Lake | 100-096 | 72.20 | 14.85 | -0.003 | 72.15 | 58.82 | 72.12 | 58.77 |
| SC-0815-P | Grace Lake | 100-096 | 0.00 | 0.00 | -0.002 | 72.15 | 58.79 | 72.15 | 58.82 |
| SC-0820-W1 | Grace Lake | 100-096 | 0.00 | 0.00 | -0.002 | 72.15 | 58.79 | 72.15 | 58.79 |
| SC-0820-W2 | Grace Lake | 100-096 | 60.59 | 25.78 | 0.870 | 72.15 | 58.79 | 72.15 | 58.79 |
| SC-0830-P | Grace Lake | 100-096 | 61.23 | 99.91 | 2.172 | 61.22 | 59.85 | 72.15 | 58.82 |
| SC-0840-W | Grace Lake | 100-096 | 61.19 | 87.24 | -0.008 | 61.22 | 59.86 | 61.22 | 59.85 |
| SC-0850-P | Grace Lake | 100-096 | 96.00 | 46.99 | 0.005 | 61.24 | 60.96 | 61.22 | 59.86 |
| SC-0860-P | Grace Lake | 100-096 | 96.00 | 46.99 | 0.138 | 61.26 | 62.04 | 61.24 | 60.96 |
| SC-0870-P | Grace Lake | 100-096 | 96.00 | 46.99 | 0.005 | 96.00 | 64.88 | 61.26 | 62.04 |
| SC-0875-P | Grace Lake | 100-096 | 96.00 | 46.99 | -0.002 | 96.00 | 66.11 | 96.00 | 64.88 |
| SC-0875-W | Grace Lake | 100-096 | 96.00 | 10.19 | -0.000 | 96.00 | 66.11 | 61.22 | 59.86 |
| SC-0880-W | Grace Lake | 100-096 | 96.00 | 57.19 | -0.002 | 96.00 | 66.17 | 96.00 | 66.11 |
| SC-0890-P | Grace Lake | 100-096 | 96.85 | 53.46 | 5.223 | 95.19 | 66.84 | 96.00 | 66.17 |
| SC-0890-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 95.19 | 66.84 | 72.15 | 58.82 |
| SC-0900-D | Grace Lake | 100-096 | 60.71 | 6.43 | 1.261 | 95.85 | 66.83 | 95.19 | 66.84 |
| SC-0900-W | Grace Lake | 100-096 | 0.00 | 0.00 | 0.000 | 95.85 | 66.83 | 95.19 | 66.84 |
| SC-0910-W | Grace Lake | 100-096 | 93.88 | 58.72 | 39.647 | 95.67 | 66.83 | 95.19 | 66.84 |
| SC-0920-W1 | Grace Lake | 100-096 | 91.45 | 24.32 | 9.915 | 95.56 | 66.84 | 95.67 | 66.83 |
| SC-0920-W2 | Grace Lake | 100-096 | 93.88 | 59.18 | 33.527 | 95.56 | 66.84 | 95.19 | 66.84 |
| SC-0920-W3 | Grace Lake | 100-096 | 95.56 | 0.09 | -0.000 | 95.56 | 66.84 | 97.43 | 64.44 |
| SC-0925-D | Grace Lake | 100-096 | 60.56 | 19.84 | 0.032 | 60.56 | 78.79 | 95.56 | 66.84 |
| SC-0925-W | Grace Lake | 100-096 | 60.56 | 4.00 | 0.001 | 60.56 | 78.79 | 95.56 | 66.84 |
| SC-0930-C | Grace Lake | 100-096 | 60.25 | 105.15 | -0.436 | 94.94 | 66.87 | 95.56 | 66.84 |
| SC-0940-C | Grace Lake | 100-096 | 60.19 | 105.55 | 1.012 | 60.19 | 69.07 | 94.94 | 66.87 |
| SC-0950-C | Grace Lake | 100-096 | 60.50 | 38.92 | 0.721 | 60.26 | 69.44 | 60.19 | 69.07 |
| SC-0960-C | Grace Lake | 100-096 | 69.31 | 41.38 | -17.116 | 60.43 | 70.40 | 60.26 | 69.44 |
| SC-0970-P | Grace Lake | 100-096 | 60.09 | 37.51 | -5.134 | 60.10 | 72.09 | 60.19 | 69.07 |
| SC-0970-W | Grace Lake | 100-096 | 60.10 | 31.68 | 0.004 | 60.10 | 72.09 | 60.19 | 69.07 |
| SC-0980-P1 | Grace Lake | 100-096 | 60.53 | 52.30 | 0.003 | 60.49 | 77.26 | 60.10 | 72.09 |
| SC-0980-P2 | Grace Lake | 100-096 | 60.49 | 38.89 | 0.003 | 60.49 | 77.26 | 59.48 | 70.78 |
| SC-0985-P | Grace Lake | 100-096 | 70.90 | 48.30 | -0.051 | 60.49 | 77.28 | 60.49 | 77.26 |
| SC-0985-W | Grace Lake | 100-096 | 63.32 | 69.30 | -0.227 | 60.49 | 77.28 | 60.49 | 77.26 |
| SC-0990-P | Grace Lake | 100-096 | 68.21 | 5.76 | 0.013 | 68.21 | 72.66 | 116.84 | 65.99 |
| SC-0995-D | Grace Lake | 100-096 | 68.20 | 5.76 | 0.004 | 68.20 | 86.23 | 68.21 | 72.66 |
| SC-1000-P | Grace Lake | 100-096 | 62.20 | 182.55 | -252.336 | 60.41 | 78.07 | 60.49 | 77.28 |
| SC-1000-W | Grace Lake | 100-096 | 60.41 | 59.76 | 59.763 | 60.41 | 78.07 | 60.49 | 77.28 |

ALTERNATIVE SINKHOLE REMEDIATION PROTOCOL FOR GRACE LAKE
PROPOSED CONDITIONS ANALYSIS
BASIN MAXIMUM CONDITIONS REPORT
MARCH 2014
GRACE LAKE INITIAL STAGE = 62.6 FT, NAVD

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Simulation | Basin | Group | Time Max hrs | Flow Max cfs | Volume in | Volume ft3 |
|---|---|---|---|---|---|---|
| 100-096 | SC-0770 | Grace Lake | 60.04 | 92.29 | 8.835 | 577896 |
| 100-096 | SC-0800A | Grace Lake | 60.03 | 52.65 | 11.625 | 378938 |
| 100-096 | SC-0800B | Grace Lake | 60.03 | 23.17 | 10.850 | 158725 |
| 100-096 | SC-0810 | Grace Lake | 60.01 | 22.88 | 11.173 | 140732 |
| 100-096 | SC-0820A | Grace Lake | 60.03 | 19.44 | 11.164 | 130493 |
| 100-096 | SC-0820B | Grace Lake | 60.13 | 22.13 | 11.173 | 201980 |
| 100-096 | SC-0830 | Grace Lake | 60.17 | 32.41 | 9.697 | 325245 |
| 100-096 | SC-0840 | Grace Lake | 60.11 | 148.40 | 8.286 | 1249386 |
| 100-096 | SC-0880 | Grace Lake | 60.18 | 251.81 | 8.650 | 2443779 |
| 100-096 | SC-0900A | Grace Lake | 60.02 | 14.15 | 11.008 | 91507 |
| 100-096 | SC-0900B | Grace Lake | 60.22 | 22.93 | 11.170 | 224637 |
| 100-096 | SC-0910 | Grace Lake | 60.03 | 38.07 | 11.775 | 260308 |
| 100-096 | SC-0920 | Grace Lake | 60.08 | 448.71 | 10.856 | 3492417 |
| 100-096 | SC-0925 | Grace Lake | 60.03 | 64.99 | 8.656 | 416039 |
| 100-096 | SC-0970 | Grace Lake | 60.05 | 22.94 | 10.044 | 153865 |
| 100-096 | SC-0980A | Grace Lake | 60.13 | 10.05 | 8.654 | 86703 |
| 100-096 | SC-0980B | Grace Lake | 60.03 | 28.62 | 8.656 | 183195 |
| 100-096 | SC-0980C | Grace Lake | 60.09 | 54.01 | 8.656 | 386816 |
| 100-096 | SC-0985 | Grace Lake | 60.07 | 205.63 | 8.656 | 1378148 |
| 100-096 | SC-0995 | Grace Lake | 60.11 | 168.83 | 10.044 | 1315407 |

Existing Conditions, Grace Lake

GRACE LAKE
EXISTING CONDITIONS OUTPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs |
|---|---|---|---|---|---|---|---|---|---|---|
| SC-0750 | Grace Lake | 100-096 | 0.00 | 52.00 | 54.00 | 0.0000 | 40 | 72.14 | 62.48 | 0.00 |
| SC-0760 | Grace Lake | 100-096 | 72.11 | 56.17 | 58.00 | 0.0001 | 342 | 72.12 | 36.70 | 72.11 |
| SC-0770 | Grace Lake | 100-096 | 72.12 | 58.76 | 58.00 | -0.0004 | 45492 | 59.72 | 49.94 | 72.11 |
| SC-0780 | Grace Lake | 100-096 | 0.00 | 64.24 | 67.27 | 0.0000 | 114 | 0.00 | 0.00 | 0.00 |
| SC-0790 | Grace Lake | 100-096 | 0.00 | 64.00 | 67.00 | 0.0000 | 7842 | 0.00 | 0.00 | 0.00 |
| SC-0800 | Grace Lake | 100-096 | 72.16 | 58.77 | 59.00 | 0.0001 | 225137 | 61.52 | 108.04 | 72.35 |
| SC-0810 | Grace Lake | 100-096 | 72.17 | 58.80 | 58.00 | 0.0024 | 2038 | 61.23 | 84.96 | 61.24 |
| SC-0830 | Grace Lake | 100-096 | 61.22 | 59.61 | 59.00 | -0.0003 | 29239 | 60.94 | 91.07 | 61.22 |
| SC-0840 | Grace Lake | 100-096 | 61.22 | 59.62 | 58.00 | 0.0002 | 219543 | 60.08 | 189.65 | 61.14 |
| SC-0850 | Grace Lake | 100-096 | 61.23 | 60.69 | 59.50 | 0.0003 | 123 | 96.00 | 46.72 | 96.00 |
| SC-0860 | Grace Lake | 100-096 | 61.24 | 61.74 | 61.55 | 0.0003 | 155 | 96.00 | 46.72 | 96.00 |
| SC-0870 | Grace Lake | 100-096 | 96.00 | 64.81 | 66.00 | 0.0003 | 154 | 96.00 | 46.72 | 96.00 |
| SC-0875 | Grace Lake | 100-096 | 96.00 | 66.03 | 64.00 | 0.0003 | 439 | 96.00 | 53.55 | 96.00 |
| SC-0880 | Grace Lake | 100-096 | 96.00 | 66.08 | 64.00 | -0.0002 | 288585 | 60.17 | 166.24 | 96.00 |
| SC-0900 | Grace Lake | 100-096 | 96.00 | 66.73 | 67.00 | 0.0029 | 87002 | 60.00 | 10.65 | 150.07 |
| SC-0910 | Grace Lake | 100-096 | 96.00 | 66.73 | 66.00 | -0.0002 | 138757 | 95.93 | 50.30 | 96.88 |
| SC-0920 | Grace Lake | 100-096 | 96.00 | 66.73 | 66.00 | -0.0002 | 1612618 | 60.08 | 538.84 | 95.98 |
| SC-0925 | Grace Lake | 100-096 | 60.56 | 78.79 | 76.00 | 0.0002 | 48853 | 60.08 | 63.78 | 60.56 |
| SC-0930 | Grace Lake | 100-096 | 96.00 | 66.74 | 69.20 | 0.0050 | 12734 | 60.51 | 94.79 | 60.55 |
| SC-0940 | Grace Lake | 100-096 | 60.39 | 69.34 | 70.00 | 0.0001 | 7068 | 60.49 | 94.68 | 60.51 |
| SC-0980 | Grace Lake | 100-096 | 60.49 | 77.24 | 74.00 | 0.0007 | 33711 | 60.08 | 137.29 | 60.49 |
| SC-0985 | Grace Lake | 100-096 | 60.49 | 77.25 | 73.00 | 0.0004 | 138791 | 60.08 | 377.30 | 63.19 |
| SC-0990 | Grace Lake | 100-096 | 68.21 | 72.66 | 79.00 | 0.0009 | 151 | 68.20 | 5.76 | 68.21 |
| SC-0995 | Grace Lake | 100-096 | 68.20 | 86.23 | 84.00 | 0.0002 | 129991 | 60.08 | 167.62 | 68.20 |

Grace Lake, Existing Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0770 | 120 | A | 57 | 16.48 | 939.36 | |
| SC-0770 | 120 | D | 86 | 0.38 | 32.68 | |
| SC-0770 | 190 | A | 49 | 0.49 | 24.01 | |
| SC-0770 | 190 | D | 84 | 0.63 | 52.92 | |
| SC-0770 | 400 | A | 39 | 0.01 | 0.39 | |
| SC-0770 | 814 | D | 89 | 0.03 | 2.67 | |
| | | | Totals | 18.02 | 1052.03 | 58.38 |
| SC-0800A | 120 | A | 57 | 0.12 | 6.84 | |
| SC-0800A | 190 | A | 49 | 0.25 | 12.25 | |
| SC-0800A | 190 | D | 84 | 2.25 | 189.00 | |
| SC-0800A | 400 | A | 39 | 1.07 | 41.73 | |
| SC-0800A | 400 | D | 77 | 2.09 | 160.93 | |
| SC-0800A | 814 | A | 49 | 0.26 | 12.74 | |
| SC-0800A | 814 | D | 80 | 0.39 | 31.20 | |
| SC-0800A | 814 | - | 98 | 0.19 | 18.62 | |
| SC-0800A | 530a | D | 84 | 2.23 | 187.32 | |
| | | | Totals | 8.85 | 660.63 | 74.65 |
| SC-0800B | 120 | A | 57 | 0.92 | 52.44 | |
| SC-0800B | 120 | D | 86 | 0.05 | 4.30 | |
| SC-0800B | 400 | A | 39 | 0.28 | 10.92 | |
| SC-0800B | 400 | D | 77 | 2.78 | 214.06 | |
| | | | Totals | 4.03 | 281.72 | 69.91 |
| SC-0810 | 120 | A | 57 | 0.69 | 39.33 | |
| SC-0810 | 120 | D | 86 | 0.07 | 6.02 | |
| SC-0810 | 190 | D | 84 | 0.01 | 0.84 | |
| SC-0810 | 814 | A | 49 | 1.12 | 54.88 | |
| SC-0810 | 814 | D | 80 | 0.61 | 48.80 | |
| SC-0810 | 814 | - | 98 | 0.97 | 95.06 | |
| | | | Totals | 3.47 | 244.93 | 70.59 |
| SC-0820A | 400 | A | 39 | 0.81 | 31.59 | |
| SC-0820A | 400 | D | 80 | 0.64 | 51.20 | |
| SC-0820A | 814 | - | 98 | 0.21 | 20.58 | |
| SC-0820A | 530a | D | 84 | 1.66 | 139.44 | |
| | | | Totals | 3.32 | 242.81 | 73.14 |

Grace Lake, Existing Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0820B | 814 | A | 49 | 1.45 | 71.05 | |
| SC-0820B | 814 | D | 80 | 0.18 | 14.40 | |
| SC-0820B | 814 | - | 98 | 2.85 | 279.30 | |
| | | | Totals | 4.48 | 364.75 | 81.42 |
| | | | | | | |
| SC-0830 | 110 | A | 51 | 0 | 0.00 | |
| SC-0830 | 172 | A | 69 | 0.31 | 21.39 | |
| SC-0830 | 172 | D | 89 | 0.04 | 3.56 | |
| SC-0830 | 190 | A | 49 | 0.17 | 8.33 | |
| SC-0830 | 400 | A | 39 | 1.45 | 56.55 | |
| SC-0830 | 400 | D | 77 | 0.08 | 6.16 | |
| SC-0830 | 643 | A | 98 | 0.01 | 0.98 | |
| SC-0830 | 643 | D | 98 | 1 | 98.00 | |
| SC-0830 | 814 | A | 49 | 2.36 | 115.64 | |
| SC-0830 | 814 | D | 80 | 0.92 | 73.60 | |
| SC-0830 | 814 | - | 98 | 1.47 | 144.06 | |
| | | | Totals | 7.81 | 528.27 | 67.64 |
| | | | | | | |
| SC-0840 | 110 | A | 51 | 31.31 | 1596.81 | |
| SC-0840 | 110 | D | 84 | 0.18 | 15.12 | |
| SC-0840 | 172 | A | 69 | 0.99 | 68.31 | |
| SC-0840 | 172 | D | 89 | 0.51 | 45.39 | |
| SC-0840 | 190 | A | 49 | 1.84 | 90.16 | |
| SC-0840 | 400 | A | 39 | 3.17 | 123.63 | |
| SC-0840 | 400 | D | 77 | 4.75 | 365.75 | |
| SC-0840 | 643 | A | 98 | 0.00 | 0.04 | |
| SC-0840 | 643 | D | 98 | 0.22 | 21.56 | |
| | | | Totals | 42.97 | 2326.77 | 54.15 |
| | | | | | | |
| SC-0880 | 110 | A | 51 | 55.38 | 2824.38 | |
| SC-0880 | 110 | D | 84 | 2.2 | 184.80 | |
| SC-0880 | 140 | A | 89 | 2.37 | 210.93 | |
| SC-0880 | 172 | A | 69 | 3.54 | 244.26 | |
| SC-0880 | 190 | A | 49 | 2.7 | 132.30 | |
| SC-0880 | 190 | D | 84 | 1.05 | 88.20 | |
| SC-0880 | 400 | A | 39 | 0.9 | 35.10 | |
| SC-0880 | 814 | A | 49 | 5.70 | 279.30 | |
| SC-0880 | 814 | D | 80 | 1.27 | 101.60 | |
| SC-0880 | 814 | - | 98 | 2.72 | 266.56 | |
| | | | Totals | 77.83 | 4367.43 | 56.11 |

Grace Lake, Existing Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0900A | 814 | A | 49 | 0.95 | 46.55 | |
| SC-0900A | 814 | D | 80 | 0.72 | 57.60 | |
| SC-0900A | 814 | - | 98 | 0.45 | 44.10 | |
| SC-0900A | 530a | Water | 100 | 0.42 | 42.00 | |
| | | | Totals | 2.54 | 190.25 | 74.90 |
| | | | | | | |
| SC-0900B | 814 | A | 49 | 0.86 | 42.14 | |
| SC-0900B | 814 | D | 80 | 0.2 | 16.00 | |
| SC-0900B | 814 | - | 98 | 3.67 | 359.66 | |
| | | | Totals | 4.73 | 417.80 | 88.33 |
| | | | | | | |
| SC-0910 | 120 | A | 57 | 1.98 | 112.86 | |
| SC-0910 | 120 | D | 86 | 0.01 | 0.86 | |
| SC-0910 | 190 | D | 84 | 0.02 | 1.68 | |
| SC-0910 | 400 | A | 39 | 0.11 | 4.29 | |
| SC-0910 | 400 | D | 77 | 1.16 | 89.32 | |
| SC-0910 | 640 | A | 98 | 0.95 | 93.10 | |
| SC-0910 | 640 | D | 98 | 0.58 | 56.84 | |
| SC-0910 | 814 | A | 49 | 0.43 | 21.07 | |
| SC-0910 | 814 | D | 80 | 0.49 | 39.20 | |
| SC-0910 | 814 | - | 98 | 0.36 | 35.28 | |
| | | | Totals | 6.09 | 454.50 | 74.63 |
| | | | | | | |
| SC-0920 | 120 | A | 57 | 50.59 | 2883.63 | |
| SC-0920 | 120 | D | 86 | 0.65 | 55.90 | |
| SC-0920 | 170 | A | 69 | 0.36 | 24.84 | |
| SC-0920 | 190 | A | 49 | 0.43 | 21.07 | |
| SC-0920 | 190 | D | 84 | 0.24 | 20.16 | |
| SC-0920 | 400 | A | 39 | 5.09 | 198.51 | |
| SC-0920 | 400 | D | 77 | 1.93 | 148.61 | |
| SC-0920 | 520 | A | 100 | 0.54 | 54.00 | |
| SC-0920 | 520 | D | 100 | 21.51 | 2151.00 | |
| SC-0920 | 640 | A | 98 | 1.12 | 109.76 | |
| SC-0920 | 640 | D | 98 | 3.54 | 346.92 | |
| SC-0920 | 814 | A | 49 | 1.66 | 81.34 | |
| SC-0920 | 814 | - | 98 | 0.96 | 94.08 | |
| | | | Totals | 88.62 | 6189.82 | 69.85 |

Grace Lake, Existing Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0925 | 120 | A | 57 | 13.12 | 747.84 | |
| SC-0925 | 170 | A | 69 | 0.12 | 8.28 | |
| | | | Totals | 13.24 | 756.12 | 57.11 |
| SC-0970 | 814 | - | 98 | 0.92 | 90.16 | |
| SC-0970 | 814 | A | 49 | 2.07 | 101.43 | |
| | | | Totals | 2.99 | 191.59 | 64.08 |
| SC-0980A | 814 | A | 49 | 1.59 | 77.91 | |
| SC-0980A | 814 | - | 98 | 1.17 | 114.66 | |
| | | | Totals | 2.76 | 192.57 | 69.77 |
| SC-0980B | 120 | A | 57 | 5.83 | 332.31 | |
| SC-0980B | 814 | A | 69 | 0.00 | 0.00 | |
| | | | Totals | 5.83 | 332.31 | 57.00 |
| SC-0980C | 120 | A | 57 | 12.31 | 701.67 | |
| | | | Totals | 12.31 | 701.67 | 57.00 |
| SC-0985 | 120 | A | 57 | 45.09 | 2570.13 | |
| | | | Totals | 45.09 | 2570.13 | 57.00 |
| SC-0995 | 120 | A | 57 | 17.74 | 1011.41 | |
| SC-0995 | 170 | A | 69 | 16.01 | 1104.97 | |
| SC-0995 | 400 | A | 39 | 0.00 | 0.08 | |
| SC-0995 | 530b | A | 92 | 2.32 | 213.81 | |
| | | | Totals | 36.08 | 2330.26 | 64.58 |

| | |
|---|---|
| Total Project Area (acres) = | 391.06 |
| I-4 Pavement (acres)= | 15.94 |

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
================================================================================
==== Basins ====================================================================
================================================================================

         Name: SC-0770                 Node: SC-0770               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 14.00
              Area(ac): 18.020                Time Shift(hrs): 0.00
          Curve Number: 58.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0800A                Node: SC-0800               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                   Peaking Factor: 256.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 13.00
              Area(ac): 8.850                 Time Shift(hrs): 0.00
          Curve Number: 75.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0800B                Node: SC-0800               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                   Peaking Factor: 256.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 12.00
              Area(ac): 4.030                 Time Shift(hrs): 0.00
          Curve Number: 70.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0810                 Node: SC-0810               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 11.00
              Area(ac): 3.470                 Time Shift(hrs): 0.00
          Curve Number: 71.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0820A                Node: SC-0820               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                   Peaking Factor: 256.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 11.00
              Area(ac): 3.320                 Time Shift(hrs): 0.00
          Curve Number: 73.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00

FDOT POND F BASIN AREA

--------------------------------------------------------------------------------------------------
         Name: SC-0820B                Node: SC-0820               Status: Onsite
        Group: Grace Lake              Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File:                  Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000              Time of Conc(min): 30.00
              Area(ac): 4.480                 Time Shift(hrs): 0.00
          Curve Number: 81.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00

I-4 BASIN AREA CONTRIBUTING RUNOFF TO POND SC-0820

--------------------------------------------------------------------------------------------------
         Name: SC-0830                 Node: SC-0830               Status: Onsite
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 28.00
Area(ac): 7.810 Time Shift(hrs): 0.00
Curve Number: 68.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0840 Node: SC-0840 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 21.00
Area(ac): 42.970 Time Shift(hrs): 0.00
Curve Number: 54.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0880 Node: SC-0880 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 27.00
Area(ac): 77.830 Time Shift(hrs): 0.00
Curve Number: 56.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0900A Node: SC-0900 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 10.00
Area(ac): 2.540 Time Shift(hrs): 0.00
Curve Number: 75.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

FDOT POND E BASIN

---

Name: SC-0900B Node: SC-0900 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 32.00
Area(ac): 4.730 Time Shift(hrs): 0.00
Curve Number: 88.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

I-4 BASIN CONTRIBUTING RUNOFF TO POND E

---

Name: SC-0910 Node: SC-0910 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 11.00
Area(ac): 6.090 Time Shift(hrs): 0.00
Curve Number: 75.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0920 Node: SC-0920 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 22.00
Area(ac): 88.620 Time Shift(hrs): 0.00

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
          Curve Number: 70.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0925                 Node: SC-0925               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 15.00
             Area(ac): 13.240               Time Shift(hrs): 0.00
          Curve Number: 57.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0970                 Node: SC-0970               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 16.00
             Area(ac): 2.990                Time Shift(hrs): 0.00
          Curve Number: 64.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0980A                Node: SC-0980               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 29.00
             Area(ac): 2.760                Time Shift(hrs): 0.00
          Curve Number: 70.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0980B                Node: SC-0980               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 15.00
             Area(ac): 5.830                Time Shift(hrs): 0.00
          Curve Number: 57.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0980C                Node: SC-0980               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 20.00
             Area(ac): 12.310               Time Shift(hrs): 0.00
          Curve Number: 57.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: SC-0985                 Node: SC-0985               Status: Onsite
       Group: Grace Lake              Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                  Peaking Factor: 323.0
         Rainfall File:                 Storm Duration(hrs): 0.00
   Rainfall Amount(in): 0.000             Time of Conc(min): 17.00
             Area(ac): 45.090               Time Shift(hrs): 0.00
          Curve Number: 57.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
```

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0995 Node: SC-0995 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 23.00
Area(ac): 36.080 Time Shift(hrs): 0.00
Curve Number: 65.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

==========
==== Nodes ==========
==========

Name: SC-0750 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: Grace Lake Warn Stage(ft): 54.000
Type: Time/Stage

ASSUMED TAILWATER AT THE CROWN OF THE OUTFALL PIPE THAT DISCHARGES TO THE BOLLING FARMS SUBDIVISION WETLAND AND POND.
SURVEYED PIPE INVERT ELEVATION IS 48.96 FT, NAVD (SSMC SURVEY DATED DEC. 2007).

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 52.000 |
| 180.00 | 52.000 |

---

Name: SC-0760 Base Flow(cfs): 0.000 Init Stage(ft): 53.080
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

CURB INLET STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY.
PARAMETERS WERE OBTAINED FROM SURVEY DATA BY SSMC (DATED DEC. 2007 AND JULY 2013).

| Stage(ft) | Area(ac) |
|---|---|
| 53.080 | 0.0010 |
| 58.780 | 0.0010 |

---

Name: SC-0770 Base Flow(cfs): 0.000 Init Stage(ft): 57.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

NORTHRIDGE SWALE LOCATED SOUTH OF THE NORTHRIDGE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 55.900 | 0.0100 |
| 57.000 | 0.4100 |
| 58.000 | 0.7700 |

---

Name: SC-0780 Base Flow(cfs): 0.000 Init Stage(ft): 64.240
Group: Grace Lake Warn Stage(ft): 67.270
Type: Stage/Area

DIVERSION STRUCTURE. DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985). REFER TO STRUCTURE C-1.

| Stage(ft) | Area(ac) |
|---|---|
| 64.240 | 0.0010 |
| 67.570 | 0.0010 |

---

Name: SC-0790 Base Flow(cfs): 0.000 Init Stage(ft): 64.000
Group: Grace Lake Warn Stage(ft): 67.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED NORTH OF GRACE LAKE, SOUTH OF NORTH RIDGE DR., EAST OF GRACE VIEW CT., AND WEST OF NORTH RIDGE
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 64.000 | 0.1800 |
| 65.000 | 0.2300 |
| 66.000 | 0.2900 |
| 67.000 | 0.3900 |

---

Name: SC-0800 Base Flow(cfs): 0.000 Init Stage(ft): 47.000

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

NORTHRIDE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.9700 |
| 48.000 | 1.9200 |
| 49.000 | 2.3000 |
| 50.000 | 2.6500 |
| 51.000 | 2.9900 |
| 52.000 | 3.3100 |
| 53.000 | 3.6700 |
| 54.000 | 4.1400 |
| 55.000 | 4.9500 |
| 56.000 | 5.6900 |
| 57.000 | 6.5900 |
| 58.000 | 7.3600 |
| 59.000 | 8.1400 |

---

Name: SC-0810 Base Flow(cfs): 0.000 Init Stage(ft): 52.330
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 52.330 | 0.0010 |
| 55.000 | 0.0050 |
| 56.000 | 0.0100 |
| 57.000 | 0.0200 |
| 58.000 | 0.0400 |
| 59.000 | 0.0800 |

---

Name: SC-0815 Base Flow(cfs): 0.000 Init Stage(ft): 55.000
Group: Grace Lake Warn Stage(ft): 56.000
Type: Stage/Area

SHALLOW SWALE

| Stage(ft) | Area(ac) |
|---|---|
| 55.000 | 0.0200 |
| 56.000 | 0.0300 |
| 57.000 | 0.0800 |
| 58.000 | 0.1300 |
| 59.000 | 0.1800 |

---

Name: SC-0820 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

FDOT POND F
STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP AND COMPARED TO THE PERMITTED PARAMETERS (SJRWMD PERMIT NO. 22434

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 1.0600 |
| 53.000 | 1.1400 |
| 54.000 | 1.2200 |
| 55.000 | 1.4400 |
| 56.000 | 1.6700 |
| 57.000 | 1.7500 |
| 58.000 | 1.8500 |
| 59.000 | 1.9800 |

---

Name: SC-0830 Base Flow(cfs): 0.000 Init Stage(ft): 52.890
Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY WEST (UPSTREAM SIDE) OF THE I-4 CULVERT CROSSING (NORTH PIPE)

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 0.0010 |
| 53.000 | 0.1200 |
| 54.000 | 0.3100 |
| 55.000 | 0.5400 |

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 56.000 | 0.6800 |
| 57.000 | 0.8000 |
| 58.000 | 0.9100 |
| 59.000 | 1.1100 |
| 60.000 | 1.4200 |

---

Name: SC-0840 Base Flow(cfs): 0.000 Init Stage(ft): 50.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

DEPRESSIONAL AREA NORTH OF DIXON ROAD AND EAST OF SUNSHINE TREE BOULEVARD.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHI MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.0200 |
| 48.000 | 0.0500 |
| 49.000 | 0.0900 |
| 50.000 | 0.1200 |
| 51.000 | 0.3400 |
| 52.000 | 0.5400 |
| 53.000 | 0.7700 |
| 54.000 | 1.1800 |
| 55.000 | 1.8600 |
| 56.000 | 2.6300 |
| 57.000 | 3.2900 |
| 58.000 | 3.9900 |
| 59.000 | 4.5400 |
| 60.000 | 5.3500 |

---

Name: SC-0850 Base Flow(cfs): 0.000 Init Stage(ft): 56.690
Group: Grace Lake Warn Stage(ft): 59.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 56.650 | 0.0010 |
| 59.500 | 0.0010 |

---

Name: SC-0860 Base Flow(cfs): 0.000 Init Stage(ft): 56.920
Group: Grace Lake Warn Stage(ft): 61.550
Type: Stage/Area

DITCH BOTTOM INLET LOCATED AT THE SOUTHEAST CORNER OF THE INTERSECTION OF DIXON RD. AND SUNSHINE TREE BLVD.

| Stage(ft) | Area(ac) |
|---|---|
| 56.920 | 0.0010 |
| 62.650 | 0.0010 |

---

Name: SC-0870 Base Flow(cfs): 0.000 Init Stage(ft): 59.620
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.
CURB INLET LOCATED ALONG THE SUNSHINE TREE BLVD EAST RIGHT-OF-WAY.

| Stage(ft) | Area(ac) |
|---|---|
| 59.620 | 0.0010 |
| 67.000 | 0.0010 |

---

Name: SC-0875 Base Flow(cfs): 0.000 Init Stage(ft): 59.710
Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 59.710 | 0.0100 |
| 64.000 | 0.0100 |

---

Name: SC-0880 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

DEPRESSIONAL AREA SOUTH OF THE ONE CHURCH (SOCCER FIELDS)
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 57.260 | 0.0010 |
| 58.000 | 0.0020 |
| 59.000 | 0.0300 |
| 60.000 | 0.1000 |
| 61.000 | 0.2900 |
| 62.000 | 1.5200 |
| 63.000 | 3.1000 |
| 64.000 | 4.1400 |
| 65.000 | 5.7500 |
| 66.000 | 7.4600 |
| 67.000 | 9.2100 |

---

Name: SC-0890 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

UPSTREAM END (EAST SIDE) OF THE SOUTHERN CULVERT CROSSING I-4

| Stage(ft) | Area(ac) |
|---|---|
| 58.200 | 0.0100 |
| 66.000 | 0.0100 |

---

Name: SC-0900 Base Flow(cfs): 0.000 Init Stage(ft): 60.000
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.
FDOT POND E (REFER TO THE SJRWMD PERMIT NO. 22434-1)

| Stage(ft) | Area(ac) |
|---|---|
| 59.000 | 0.3950 |
| 60.000 | 0.5280 |
| 61.000 | 0.6600 |
| 62.000 | 0.8500 |
| 63.000 | 0.9700 |
| 63.700 | 1.0300 |
| 64.500 | 1.2000 |
| 65.000 | 1.3700 |
| 66.000 | 1.4500 |

---

Name: SC-0910 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY EAST OF THE SOUTH I-4 CROSS CULVERT, ADJACENT TO GRACE LAKE.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 55.000 | 0.1700 |
| 56.000 | 0.3000 |
| 57.000 | 0.4500 |
| 58.000 | 0.6600 |
| 59.000 | 0.9600 |
| 60.000 | 1.4200 |
| 61.000 | 1.8200 |
| 62.000 | 2.2500 |
| 63.000 | 2.6800 |
| 64.000 | 2.9600 |
| 65.000 | 3.2500 |
| 66.000 | 3.4800 |
| 67.000 | 3.6800 |

---

Name: SC-0920 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

GRACE LAKE.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 33-54 FT, NAVD, WAS OBTAINED FROM THE SURVEY PREPARED BY SSMC, DATED DEC. 2007.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 55-67, NAVD, IS BASED ON THE 1-FT TOPOGRAPHY.
INITIAL STAGE IS BASED ON THE GRACE LAKE "NORMAL" HYDROPERIOD ELEVATION BETWEEN ELEVATION 58-63 FT, NAVD
(REFER TO ENGINEERING REPORT FROM DEVO ENGINEERING).

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Stage(ft) | Area(ac) |
|---|---|
| 33.000 | 0.0000 |
| 34.000 | 0.0005 |
| 35.000 | 0.0014 |
| 36.000 | 0.0028 |
| 37.000 | 0.0053 |
| 38.000 | 0.0140 |
| 39.000 | 0.0450 |
| 40.000 | 0.0980 |
| 41.000 | 0.1830 |
| 42.000 | 0.3010 |
| 43.000 | 0.4270 |
| 44.000 | 0.5320 |
| 45.000 | 0.6430 |
| 46.000 | 0.7540 |
| 47.000 | 0.8640 |
| 48.000 | 1.1900 |
| 49.000 | 3.6300 |
| 50.000 | 5.8800 |
| 51.000 | 8.1300 |
| 52.000 | 10.5200 |
| 53.000 | 12.8800 |
| 54.000 | 14.9400 |
| 55.000 | 16.6400 |
| 56.000 | 18.3800 |
| 57.000 | 20.0700 |
| 58.000 | 22.0500 |
| 59.000 | 24.0900 |
| 60.000 | 26.0500 |
| 61.000 | 27.8500 |
| 62.000 | 29.7000 |
| 63.000 | 31.6800 |
| 64.000 | 33.6800 |
| 65.000 | 35.3300 |
| 66.000 | 36.9000 |
| 67.000 | 38.7900 |

---

Name: SC-0925 Base Flow(cfs): 0.000 Init Stage(ft): 68.000
Group: Grace Lake Warn Stage(ft): 76.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED ALONG NORTH RIDGE LAKE CIRCLE, SOUTH OF NORTH RIDGE DR.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAPS.

| Stage(ft) | Area(ac) |
|---|---|
| 68.000 | 0.0300 |
| 69.000 | 0.0800 |
| 70.000 | 0.1000 |
| 71.000 | 0.1300 |
| 72.000 | 0.1600 |
| 73.000 | 0.1800 |
| 74.000 | 0.2200 |
| 75.000 | 0.2500 |
| 76.000 | 0.2900 |
| 77.000 | 0.5100 |
| 78.000 | 0.8700 |
| 79.000 | 1.1900 |

---

Name: SC-0930 Base Flow(cfs): 0.000 Init Stage(ft): 61.000
Group: Grace Lake Warn Stage(ft): 69.200
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 3.

| Stage(ft) | Area(ac) |
|---|---|
| 61.000 | 0.0100 |
| 69.200 | 0.0100 |

---

Name: SC-0940 Base Flow(cfs): 0.000 Init Stage(ft): 64.930
Group: Grace Lake Warn Stage(ft): 69.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 2.

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| Stage(ft) | Area(ac) |
|---|---|
| 64.930 | 0.0100 |
| 69.000 | 0.0100 |

---

Name: SC-0950 Base Flow(cfs): 0.000 Init Stage(ft): 66.200
Group: Grace Lake Warn Stage(ft): 72.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 1.

| Stage(ft) | Area(ac) |
|---|---|
| 66.200 | 0.0100 |
| 72.000 | 0.0100 |

---

Name: SC-0960 Base Flow(cfs): 0.000 Init Stage(ft): 68.780
Group: Grace Lake Warn Stage(ft): 73.000
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 0.

| Stage(ft) | Area(ac) |
|---|---|
| 68.780 | 0.0100 |
| 73.000 | 0.0100 |

---

Name: SC-0970 Base Flow(cfs): 0.000 Init Stage(ft): 65.680
Group: Grace Lake Warn Stage(ft): 71.000
Type: Stage/Area

STAGE AREA ESTIMATED BASED ON THE 1-FT TOPOGRAPHY.
NODE INITIAL STAGE OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE Ghost_I-4_30in.

| Stage(ft) | Area(ac) |
|---|---|
| 65.680 | 0.0100 |
| 71.000 | 0.0400 |

---

Name: SC-0980 Base Flow(cfs): 0.000 Init Stage(ft): 68.100
Group: Grace Lake Warn Stage(ft): 74.000
Type: Stage/Area

STAGE-AREA OBTAINED FROM THE 1-FT TOPO MAPS
INITIAL STAGE IS BASED ON THE DOWNSTREAM PIPE INVERT ELEVATION

| Stage(ft) | Area(ac) |
|---|---|
| 67.000 | 0.0100 |
| 70.000 | 0.0150 |
| 71.000 | 0.0200 |
| 72.000 | 0.1000 |
| 73.000 | 0.1800 |
| 74.000 | 0.3200 |

---

Name: SC-0985 Base Flow(cfs): 0.000 Init Stage(ft): 68.100
Group: Grace Lake Warn Stage(ft): 73.000
Type: Stage/Area

PENELOPE POND (POND LOCATED EAST OF PENELOPE DR AND NORTH OF HICKORY TREE RD)
STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP
INITIAL STAGE WAS ESTIMATED BASED ON THE DOWNSTREAM PIPE INVERT JUST SOUTH OF EE WILLIAMSON RD

| Stage(ft) | Area(ac) |
|---|---|
| 66.000 | 0.1100 |
| 71.000 | 0.2200 |
| 72.000 | 0.3400 |
| 73.000 | 0.5900 |
| 74.000 | 1.2000 |

---

Name: SC-0990 Base Flow(cfs): 0.000 Init Stage(ft): 71.000
Group: Grace Lake Warn Stage(ft): 79.000
Type: Stage/Area

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

EMERGENCY OVERFLOW MANHOLE

| Stage(ft) | Area(ac) |
|---|---|
| 71.000 | 0.0010 |
| 79.000 | 0.0010 |

---

Name: SC-0995 Base Flow(cfs): 0.000 Init Stage(ft): 77.500
Group: Grace Lake Warn Stage(ft): 84.000
Type: Stage/Area

WET DETENTION POND THAT SERVES THE WOODLAND ELEMENTARY SCHOOL, THE BELLA TUSCANY SUBDIVISION AND A PORTION OF EE WILLIAMSON ROAD POND WAS EXPANDED TO PROVIDE WATER QUALITY TREATMENT AND ATTENUATION FROM THE BELLA TUSCANY SUBDIVISION (REFER TO THE SJRMD PERM STAGE-AREA RELATIONSHIP AND INITIAL STAGE WAS OBTAINED FROM THE PERMITTED PARAMETERS. ELEVATIONS SHOWN HEREIN WERE CONVERTED TO SINCE THE ORIGINAL BELLA TUSCANY SUBDIVISION PLANS ARE REFERENCED TO THE NGVD VERTICAL DATUM (CONVERSION USED: NAVD ELEV. = NGV

| Stage(ft) | Area(ac) |
|---|---|
| 77.500 | 1.8600 |
| 78.000 | 1.9300 |
| 79.000 | 2.0000 |
| 80.000 | 2.0800 |
| 81.000 | 2.2200 |
| 82.000 | 2.3600 |
| 83.000 | 2.5000 |
| 84.000 | 2.6500 |
| 85.000 | 2.8000 |

==========
==== Cross Sections ==========
==========

Name: SC-0810_W1 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE DEPRESSIONAL AREA

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 58.400 | 0.000000 |
| 11.900 | 57.800 | 0.000000 |
| 31.100 | 57.200 | 0.000000 |
| 43.400 | 57.800 | 0.000000 |
| 63.200 | 58.700 | 0.000000 |

---

Name: SC-0810_W2 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE SWALE

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 59.300 | 0.000000 |
| 30.700 | 59.000 | 0.000000 |
| 68.400 | 58.500 | 0.000000 |
| 106.100 | 58.700 | 0.000000 |
| 133.700 | 59.300 | 0.000000 |

---

Name: SC-0840_W Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 60.000 | 0.000000 |
| 12.000 | 59.000 | 0.000000 |
| 18.700 | 58.000 | 0.000000 |
| 25.300 | 57.000 | 0.000000 |
| 32.000 | 56.000 | 0.000000 |
| 51.900 | 55.000 | 0.000000 |
| 103.800 | 54.000 | 0.000000 |
| 128.000 | 54.000 | 0.000000 |
| 149.600 | 54.000 | 0.000000 |
| 194.000 | 55.000 | 0.000000 |
| 215.100 | 56.000 | 0.000000 |
| 230.500 | 57.000 | 0.000000 |
| 241.100 | 58.000 | 0.000000 |
| 251.500 | 59.000 | 0.000000 |
| 262.500 | 60.000 | 0.000000 |

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0875_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 36.600 | 66.000 | 0.000000 |
| 44.200 | 65.500 | 0.000000 |
| 51.800 | 66.000 | 0.000000 |
| 78.700 | 67.000 | 0.000000 |

Name: SC-0880_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA OBTAINED FROM SSMC SURVEY, DATED JULY 2013.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 63.300 | 0.000000 |
| 9.200 | 62.600 | 0.000000 |
| 24.700 | 63.400 | 0.000000 |

Name: SC-0890_W Group: Grace Lake
Encroachment: No

SURVEYED CROSS SECTION (SSMC, DATED JULY 2013).

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 70.960 | 0.000000 |
| 4.200 | 70.600 | 0.000000 |
| 26.000 | 68.500 | 0.000000 |
| 48.500 | 71.100 | 0.000000 |
| 64.600 | 79.100 | 0.000000 |
| 78.400 | 83.600 | 0.000000 |
| 82.500 | 83.400 | 0.000000 |

Name: SC-0920_W1 Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 20.300 | 66.000 | 0.000000 |
| 45.300 | 65.000 | 0.000000 |
| 53.000 | 64.000 | 0.000000 |
| 63.600 | 63.000 | 0.000000 |
| 80.700 | 62.000 | 0.000000 |
| 93.800 | 61.000 | 0.000000 |
| 106.600 | 60.000 | 0.000000 |
| 139.200 | 59.500 | 0.000000 |
| 168.200 | 60.000 | 0.000000 |
| 194.200 | 61.000 | 0.000000 |
| 206.100 | 62.000 | 0.000000 |
| 224.900 | 63.000 | 0.000000 |
| 240.600 | 64.000 | 0.000000 |
| 249.600 | 65.000 | 0.000000 |
| 258.000 | 66.000 | 0.000000 |
| 277.100 | 67.000 | 0.000000 |

Name: SC-0920_W3 Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 66.900 | 0.000000 |
| 24.000 | 66.800 | 0.000000 |
| 47.000 | 67.100 | 0.000000 |

Name: SC-0930_DS Group: Grace Lake
Encroachment: No

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan3DS.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 64.000 | 0.011000 |
| 28.100 | 63.000 | 0.011000 |
| 28.900 | 62.000 | 0.011000 |
| 29.500 | 61.000 | 0.011000 |
| 32.000 | 60.500 | 0.011000 |
| 38.000 | 60.500 | 0.011000 |
| 41.400 | 61.000 | 0.011000 |
| 43.200 | 62.000 | 0.011000 |
| 44.800 | 63.000 | 0.011000 |
| 77.900 | 64.000 | 0.011000 |

---
Name: SC-0940_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan2DS3US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 68.000 | 0.150000 |
| 10.100 | 67.000 | 0.150000 |
| 30.500 | 66.000 | 0.150000 |
| 45.200 | 65.000 | 0.150000 |
| 49.100 | 64.000 | 0.150000 |
| 49.500 | 63.000 | 0.150000 |
| 50.500 | 62.000 | 0.150000 |
| 52.000 | 61.000 | 0.150000 |
| 54.000 | 62.000 | 0.150000 |
| 56.000 | 63.000 | 0.150000 |
| 64.200 | 64.000 | 0.150000 |
| 79.000 | 65.000 | 0.150000 |
| 85.000 | 66.000 | 0.150000 |
| 90.000 | 67.000 | 0.150000 |

---
Name: SC-0950_DS Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan1DS2US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 69.000 | 0.150000 |
| 16.000 | 68.000 | 0.150000 |
| 42.400 | 67.000 | 0.150000 |
| 47.400 | 66.000 | 0.150000 |
| 51.600 | 65.000 | 0.150000 |
| 56.100 | 64.930 | 0.150000 |
| 60.200 | 65.000 | 0.150000 |
| 64.800 | 66.000 | 0.150000 |
| 69.300 | 67.000 | 0.150000 |
| 73.700 | 68.000 | 0.150000 |
| 78.000 | 69.000 | 0.150000 |

---
Name: SC-0950_US Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION I-4 Chan1_US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.000 | 0.150000 |
| 1.190 | 70.000 | 0.150000 |
| 2.360 | 69.000 | 0.150000 |
| 3.560 | 68.000 | 0.150000 |
| 4.580 | 67.000 | 0.150000 |
| 5.300 | 66.200 | 0.150000 |
| 11.970 | 67.000 | 0.150000 |
| 12.060 | 68.000 | 0.150000 |
| 12.060 | 69.000 | 0.150000 |
| 12.060 | 69.700 | 0.150000 |

---
Name: SC-0960_DS Group: Grace Lake
Encroachment: No

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION EEW I-4 Chan DS.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.230 | 0.011000 |
| 0.610 | 71.000 | 0.011000 |
| 2.090 | 70.000 | 0.011000 |
| 3.570 | 69.000 | 0.011000 |
| 3.800 | 68.640 | 0.011000 |
| 8.900 | 68.640 | 0.011000 |
| 9.240 | 69.000 | 0.011000 |
| 10.080 | 70.000 | 0.011000 |

---

Name: SC-0960_US Group: Grace Lake
Encroachment: No

CHANNEL CROSS SECTION DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR CROSS SECTION EEW I-4 Chan US.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 71.000 | 0.011000 |
| 0.960 | 70.000 | 0.011000 |
| 1.930 | 69.000 | 0.011000 |
| 7.640 | 68.780 | 0.011000 |
| 7.810 | 69.000 | 0.011000 |
| 8.830 | 70.000 | 0.011000 |
| 9.880 | 71.000 | 0.011000 |
| 10.790 | 72.000 | 0.011000 |

==========
==== Pipes ====
==========

Name: SC-0760-P From Node: SC-0760 Length(ft): 534.00
Group: Grace Lake To Node: SC-0750 Count: 1
Friction Equation: Automatic

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 36.00 | 36.00 | Flow: | Both |
| Rise(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.00 |
| Invert(ft): | 53.080 | 48.960 | Exit Loss Coef: | 1.00 |
| Manning's N: | 0.012000 | 0.012000 | Bend Loss Coef: | 0.00 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY DATA BY SSMC, DATED DEC. 2007.

---

Name: SC-0790-P From Node: SC-0790 Length(ft): 30.00
Group: Grace Lake To Node: SC-0780 Count: 1
Friction Equation: Automatic

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 18.00 | 18.00 | Flow: | Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: | 0.50 |
| Invert(ft): | 64.050 | 64.240 | Exit Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | Bend Loss Coef: | 0.00 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILTS (DATED 05/19/1985).
ORIGINAL PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND HAD TO BE CONVERTED TO THE NAVD VERTICAL DATUM.
ELEVATIONS SHOWN CORRESPOND TO THE NAVD DATUM.

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-----------------------------------------------------------------------------------------------
         Name: SC-0815-P           From Node: SC-0815           Length(ft): 412.00
        Group: Grace Lake            To Node: SC-0810                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 18.00          18.00                     Entrance Loss Coef: 0.50
     Rise(in): 18.00          18.00                         Exit Loss Coef: 0.00
   Invert(ft): 55.000         53.520                        Bend Loss Coef: 0.00
  Manning's N: 0.013000       0.013000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

UPSTREAM INVERT OBTAINED FROM THE PROPOSED ICPR MODEL, PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008).
DOWNSTREAM INVERT WAS OBTAINED FROM THE SSMC SURVEY, DATED JULY 2013.

```
-----------------------------------------------------------------------------------------------
         Name: SC-0830-P           From Node: SC-0830           Length(ft): 227.00
        Group: Grace Lake            To Node: SC-0810                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 54.00          54.00                     Entrance Loss Coef: 0.50
     Rise(in): 54.00          54.00                         Exit Loss Coef: 0.00
   Invert(ft): 51.520         52.330                        Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (NORTH CROSSING)
UPSTREAM (WEST END) INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.
DOWNSTREAM (EAST END) INVERT ELEVATION WAS REVISED BASED ON SURVEY PERFORMED BY SSMC, DATED JULY 2013.

```
-----------------------------------------------------------------------------------------------
         Name: SC-0850-P           From Node: SC-0850           Length(ft): 66.00
        Group: Grace Lake            To Node: SC-0840                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 36.00          36.00                     Entrance Loss Coef: 0.50
     Rise(in): 36.00          36.00                         Exit Loss Coef: 0.00
   Invert(ft): 56.690         56.270                        Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

```
-----------------------------------------------------------------------------------------------
         Name: SC-0860-P           From Node: SC-0860           Length(ft): 62.00
        Group: Grace Lake            To Node: SC-0850                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 36.00          36.00                     Entrance Loss Coef: 0.50
     Rise(in): 36.00          36.00                         Exit Loss Coef: 0.00
   Invert(ft): 56.920         56.650                        Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
 Bot Clip(in): 0.000          0.000                      Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

```
---------------------------------------------------------------------------------------------------
         Name: SC-0870-P           From Node: SC-0870            Length(ft): 499.00
        Group: Grace Lake            To Node: SC-0860                 Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                 Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                         Flow: Both
     Span(in): 36.00          36.00                      Entrance Loss Coef: 0.50
     Rise(in): 36.00          36.00                          Exit Loss Coef: 0.00
   Invert(ft): 59.620         57.050                         Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                     Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                         Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                      Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

```
---------------------------------------------------------------------------------------------------
         Name: SC-0875-P           From Node: SC-0875            Length(ft): 47.00
        Group: Grace Lake            To Node: SC-0870                 Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                 Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                         Flow: Both
     Span(in): 36.00          36.00                      Entrance Loss Coef: 0.50
     Rise(in): 36.00          36.00                          Exit Loss Coef: 0.00
   Invert(ft): 59.710         59.650                         Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                     Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                         Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                      Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

```
---------------------------------------------------------------------------------------------------
         Name: SC-0890-P           From Node: SC-0890            Length(ft): 220.00
        Group: Grace Lake            To Node: SC-0880                 Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                 Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                         Flow: Both
     Span(in): 48.00          48.00                      Entrance Loss Coef: 0.50
     Rise(in): 48.00          48.00                          Exit Loss Coef: 0.00
   Invert(ft): 57.420         57.260                         Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                     Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                         Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                      Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (SOUTH CROSSING)
INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0970-P | From Node: | SC-0970 | Length(ft): | 128.00 |
| Group: | Grace Lake | To Node: | SC-0940 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 30.00 | 30.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 30.00 | 30.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 65.680 | 64.930 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008)

---

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0980-P1 | From Node: | SC-0980 | Length(ft): | 165.00 |
| Group: | Grace Lake | To Node: | SC-0970 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 30.00 | 30.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 30.00 | 30.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 68.100 | 66.070 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO HDR PIPE LINK I-4_30Inch. SURVEY DATA PROVIDED BY SSMC (DATED DEC. 2007)

---

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0980-P2 | From Node: | SC-0980 | Length(ft): | 135.00 |
| Group: | Grace Lake | To Node: | SC-0960 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 24.00 | 24.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 24.00 | 24.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 69.830 | 68.780 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR PIPE LINK EEWilliams_24. SURVEY DATA PROVIDED BY SSMC (DATED DEC. 2007)

---

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0985-P | From Node: | SC-0985 | Length(ft): | 230.00 |
| Group: | Grace Lake | To Node: | SC-0980 | Count: | 1 |
| | | | | Friction Equation: | Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: | Most Restrictive |
| Geometry: | Circular | Circular | | Flow: | Both |
| Span(in): | 42.00 | 42.00 | | Entrance Loss Coef: | 0.50 |
| Rise(in): | 42.00 | 42.00 | | Exit Loss Coef: | 0.00 |
| Invert(ft): | 67.000 | 67.000 | | Bend Loss Coef: | 0.00 |
| Manning's N: | 0.013000 | 0.013000 | | Outlet Ctrl Spec: | Use dc or tw |

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE SIZE AND INVERT DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR, IN
SUPPORT OF THE GRACE LAKE SINKHOLE ANALYSIS REPORT (DATED APRIL 2008).
IT APPEARS THAT THIS PIPE SEGMENT WAS NOT SURVEYED
PIPE LENGTH WAS ADJUSTED TO MATCH FIELD OBSERVATIONS

```
---------------------------------------------------------------------------------------------------
         Name: SC-0990-P           From Node: SC-0990           Length(ft): 219.00
        Group: Grace Lake            To Node: SC-0920                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                         Flow: Both
     Span(in): 15.00          15.00                     Entrance Loss Coef: 0.50
     Rise(in): 15.00          15.00                        Exit Loss Coef: 0.00
   Invert(ft): 71.000         52.000                       Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE (FINAL PIPE SEGMENT).
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DATUM (

```
---------------------------------------------------------------------------------------------------
         Name: SC-1000-P           From Node: SC-1000           Length(ft): 112.00
        Group: Grace Lake            To Node: SC-0985                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Arch           Arch                             Flow: Both
     Span(in): 95.00          95.00                     Entrance Loss Coef: 0.50
     Rise(in): 67.00          67.00                        Exit Loss Coef: 0.00
   Invert(ft): 68.620         68.070                       Bend Loss Coef: 0.00
  Manning's N: 0.024000       0.024000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

Downstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

CULVERT CROSSING HICKORY DITCH ROAD
INVERT DATA OBTAINED FROM THE CITY OF LONGWOOD STORMWATER MASTERPLAN
PIPE SIZE WAS ADJUSTED TO REFLECT THE NEAREST STANDARD SIZE FOR AN ARCH PIPE BASED ON SURVEYED DIMENSIONS

```
===================================================================================
==== Channels =====================================================================
===================================================================================

          Name: SC-0930-C           From Node: SC-0930           Length(ft): 106.00
         Group: Grace Lake            To Node: SC-0920                Count: 1

                UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
      Geometry: Irregular      Irregular                 Solution Algorithm: Automatic
    Invert(ft): 61.000         60.500                           Flow: Both
 TClpInitZ(ft): 9999.000       9999.000                   Contraction Coef: 0.100
   Manning's N:                                             Expansion Coef: 0.300
  Top Clip(ft):                                         Entrance Loss Coef: 0.000
  Bot Clip(ft):                                            Exit Loss Coef: 0.000
     Main XSec: SC-0940_DS     SC-0930_DS                 Outlet Ctrl Spec: Use dc or tw
  AuxElev1(ft): 0.000          0.000                       Inlet Ctrl Spec: Use dc
     Aux XSec1:                                          Stabilizer Option: None
  AuxElev2(ft): 0.000          0.000
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
     Aux XSec2:
 Top Width(ft):
     Depth(ft):
 Bot Width(ft):
  LtSdSlp(h/v):
  RtSdSlp(h/v):
```

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 3 AND CROSS SECTIONS I-4 Chan2DS3US (UPSTREAM) AND I-4 Chan3DS (DOWNSTREAM)

```
----------------------------------------------------------------------------------------------------
          Name: SC-0940-C           From Node: SC-0940            Length(ft): 496.00
         Group: Grace Lake            To Node: SC-0930                 Count: 1

                UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
      Geometry: Irregular      Irregular                 Solution Algorithm: Automatic
    Invert(ft): 64.930         61.000                                Flow: Both
 TClpInitZ(ft): 9999.000       9999.000                   Contraction Coef: 0.100
   Manning's N:                                             Expansion Coef: 0.300
  Top Clip(ft):                                          Entrance Loss Coef: 0.000
  Bot Clip(ft):                                              Exit Loss Coef: 0.000
     Main XSec: SC-0950_DS     SC-0940_DS                  Outlet Ctrl Spec: Use dc or tw
  AuxElev1(ft): 0.000          0.000                        Inlet Ctrl Spec: Use dc
     Aux XSec1:                                           Stabilizer Option: None
  AuxElev2(ft): 0.000          0.000
     Aux XSec2:
 Top Width(ft):
     Depth(ft):
 Bot Width(ft):
  LtSdSlp(h/v):
  RtSdSlp(h/v):
```

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 2 AND CROSS SECTIONS I-4 Chan1DS2US (UPSTREAM) AND I-4 Chan2DS3US (DOWNSTREAM)

```
----------------------------------------------------------------------------------------------------
          Name: SC-0950-C           From Node: SC-0950            Length(ft): 66.00
         Group: Grace Lake            To Node: SC-0940                 Count: 1

                UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
      Geometry: Irregular      Irregular                 Solution Algorithm: Automatic
    Invert(ft): 66.200         64.930                                Flow: Both
 TClpInitZ(ft): 9999.000       9999.000                   Contraction Coef: 0.100
   Manning's N:                                             Expansion Coef: 0.300
  Top Clip(ft):                                          Entrance Loss Coef: 0.000
  Bot Clip(ft):                                              Exit Loss Coef: 0.000
     Main XSec: SC-0950_US     SC-0950_DS                  Outlet Ctrl Spec: Use dc or tw
  AuxElev1(ft): 0.000          0.000                        Inlet Ctrl Spec: Use dc
     Aux XSec1:                                           Stabilizer Option: None
  AuxElev2(ft): 0.000          0.000
     Aux XSec2:
 Top Width(ft):
     Depth(ft):
 Bot Width(ft):
  LtSdSlp(h/v):
  RtSdSlp(h/v):
```

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 1 AND CROSS SECTIONS I-4 Chan 1_US (UPSTREAM) AND I-4 Chan1DS2US (DOWNSTREAM)

```
----------------------------------------------------------------------------------------------------
          Name: SC-0960-C           From Node: SC-0960            Length(ft): 15.00
         Group: Grace Lake            To Node: SC-0950                 Count: 1

                UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
      Geometry: Irregular      Irregular                 Solution Algorithm: Automatic
    Invert(ft): 68.780         68.640                                Flow: Both
 TClpInitZ(ft): 9999.000       9999.000                   Contraction Coef: 0.100
   Manning's N:                                             Expansion Coef: 0.300
  Top Clip(ft):                                          Entrance Loss Coef: 0.000
  Bot Clip(ft):                                              Exit Loss Coef: 0.000
     Main XSec: SC-0960_US     SC-0960_DS                  Outlet Ctrl Spec: Use dc or tw
  AuxElev1(ft): 0.000          0.000                        Inlet Ctrl Spec: Use dc
     Aux XSec1:                                           Stabilizer Option: None
  AuxElev2(ft): 0.000          0.000
     Aux XSec2:
 Top Width(ft):
     Depth(ft):
 Bot Width(ft):
  LtSdSlp(h/v):
  RtSdSlp(h/v):
```

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK 24 Splwy Chan AND CROSS SECTIONS EEW I-4 Chan US (UPSTREAM) AND EEW I-4 Chan DS (DOWNSTREAM)

==========
==== Drop Structures ==========
==========

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0770-D1 | From Node: | SC-0770 | Length(ft): | 17.00 |
| Group: | Grace Lake | To Node: | SC-0760 | Count: | 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 36.00 | 36.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 36.00 | 36.00 | Flow: | Both |
| Invert(ft): | 53.250 | 53.080 | Entrance Loss Coef: | 0.500 |
| Manning's N: | 0.012000 | 0.012000 | Exit Loss Coef: | 0.000 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DITCH BOTTOM STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY, NORTH OF NORTH RIDGE DRIVE (TRACT "C" OVERFL

*** Weir 1 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 10.20 | Invert(ft): | 57.170 |
| Rise(in): | 33.60 | Control Elev(ft): | 57.170 |

*** Weir 2 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.60 | Invert(ft): | 57.180 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.180 |

*** Weir 3 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.00 | Invert(ft): | 57.170 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.170 |

*** Weir 4 of 4 for Drop Structure SC-0770-D1 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 58.180 |
| Rise(in): | 54.00 | Control Elev(ft): | 58.180 |

---

| | | | | | |
|---|---|---|---|---|---|
| Name: | SC-0770-D2 | From Node: | SC-0770 | Length(ft): | 70.00 |
| Group: | Grace Lake | To Node: | SC-0800 | Count: | 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 18.00 | 18.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 18.00 | 18.00 | Flow: | Both |
| Invert(ft): | 49.660 | 49.140 | Entrance Loss Coef: | 0.500 |
| Manning's N: | 0.024000 | 0.024000 | Exit Loss Coef: | 0.000 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE LOCATED WITHIN THE NORTHRIDGE SWALE.
REFER TO SSMC SURVEY DATED DEC. 2007 AND THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985).
IT APPEARS THAT SURVEY FROM SSMC DID NOT PICK UP THE WEIR CUT-OUT (SLOT). HOWEVER, AS BUILTS PROVIDE AN INVERT ELEVATION FOR TH

*** Weir 1 of 2 for Drop Structure SC-0770-D2 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 30.00 | Invert(ft): | 56.820 |
| Rise(in): | 15.50 | Control Elev(ft): | 56.820 |

*** Weir 2 of 2 for Drop Structure SC-0770-D2 ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 37.00 | Invert(ft): | 58.360 |
| Rise(in): | 49.00 | Control Elev(ft): | 58.360 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0780-D | From Node: SC-0780 | Length(ft): 443.00 |
| Group: | Grace Lake | To Node: SC-0770 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 18.00 | 18.00 | Flow: | Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 62.370 | 55.900 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DIVERSION / CONTROL STRUCTURE. DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985).
ELEVATIONS SHOWN WERE CONVERTED TO THE NAVD VERTICAL DATUM.

*** Weir 1 of 1 for Drop Structure SC-0780-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 50.40 | Invert(ft): | 65.500 |
| Rise(in): | 24.84 | Control Elev(ft): | 65.500 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0900-D | From Node: SC-0900 | Length(ft): 164.00 |
| Group: | Grace Lake | To Node: SC-0890 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 24.00 | 24.00 | Flow: | Both |
| Rise(in): | 24.00 | 24.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 59.300 | 58.160 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

FDOT POND E OUTFALL STRUCTURE.  STRUCTURE DATA AND UPSTREAM INVERT WAS OBTAINED FROM THE FDOT CONSTUCTION PLANS (PREPARED BY GRE
IT APPEARS THAT THE FDOT PLANS ARE REFERENCED TO THE NGVD VERTICAL DATUM.  THESE ELEVATIONS WERE CONVERTED TO THE NAVD DATUM.
DOWNSTREAM PIPE INVERT ELEVATION WAS OBTAINED FROM SURVEYED DATA, PREPARED BY SSMC (DATED DEC. 2007)

*** Weir 1 of 3 for Drop Structure SC-0900-D ***
TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 63.120 |
| Rise(in): | 18.96 | Control Elev(ft): | 63.120 |

*** Weir 2 of 3 for Drop Structure SC-0900-D ***
TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 37.00 | Invert(ft): | 64.700 |
| Rise(in): | 49.00 | Control Elev(ft): | 64.700 |

*** Weir 3 of 3 for Drop Structure SC-0900-D ***
TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Circular | Orifice Disc Coef: | 0.600 |
| Span(in): | 2.00 | Invert(ft): | 60.000 |
| Rise(in): | 2.00 | Control Elev(ft): | 60.000 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0925-D | From Node: SC-0925 | Length(ft): 360.00 |
| Group: | Grace Lake | To Node: SC-0920 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 18.00 | 18.00 | Flow: | Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 69.350 | 64.010 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE DATA WAS OBTAINED FROM THE AS-BUILT PLANS OF THE NORTHRIDGE SUBDIVISION, PREPARED BY CPH, DATED 05/19/1985.
CONSTRUCTION PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND CONVERTED TO THE NAVD DATUM.

*** Weir 1 of 2 for Drop Structure SC-0925-D ***
TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 12.00 | Invert(ft): | 74.020 |
| Rise(in): | 46.70 | Control Elev(ft): | 74.020 |

*** Weir 2 of 2 for Drop Structure SC-0925-D ***
TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 77.910 |
| Rise(in): | 54.00 | Control Elev(ft): | 77.910 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0995-D | From Node: SC-0995 | Length(ft): 1211.00 |
| Group: | Grace Lake | To Node: SC-0990 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
     Span(in): 15.00          15.00                                  Flow: Both
     Rise(in): 15.00          15.00                 Entrance Loss Coef: 0.500
   Invert(ft): 80.000         76.250                     Exit Loss Coef: 0.000
  Manning's N: 0.012000       0.012000                Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                     Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                       Solution Incs: 10
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW STRUCTURE AND PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE.
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DATUM (

*** Weir 1 of 1 for Drop Structure SC-0995-D ***

```
                                                                                TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Horizontal                Top Clip(in): 0.000
                   Flow: Both                    Weir Disc Coef: 3.200
               Geometry: Rectangular           Orifice Disc Coef: 0.600

               Span(in): 36.00                       Invert(ft): 83.160
               Rise(in): 54.00                  Control Elev(ft): 83.160
```

==========
==== Weirs ==========
==========

```
         Name: SC-0770-W          From Node: SC-0770
        Group: Grace Lake           To Node: SC-0750
         Flow: Both                   Count: 1
         Type: Vertical: Fread     Geometry: Rectangular

                    Span(in): 180.00
                    Rise(in): 999.00
                  Invert(ft): 58.500
       Control Elevation(ft): 58.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

---

```
         Name: SC-0780-W          From Node: SC-0780
        Group: Grace Lake           To Node: SC-0770
         Flow: Both                   Count: 1
         Type: Vertical: Fread     Geometry: Rectangular

                    Span(in): 2400.00
                    Rise(in): 999.00
                  Invert(ft): 67.900
       Control Elevation(ft): 67.900
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 3.200
      Orifice Discharge Coef: 0.600
```

OVERLAND OVERTOPPING FROM POND TO THE NORTHRIDGE SWALE.
ELEVATION WAS OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS AND COMPARED TO THE 1-FT TOPOGRAPHIC MAP.

---

```
         Name: SC-0800-W1         From Node: SC-0800
        Group: Grace Lake           To Node: SC-0770
         Flow: Both                   Count: 1
         Type: Vertical: Fread     Geometry: Rectangular

                    Span(in): 1200.00
                    Rise(in): 999.00
                  Invert(ft): 58.000
       Control Elevation(ft): 58.000
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

NORTHRIDGE DEPRESSIONAL AREA BERM OVERTOPPING
PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP AND SURVEYED DATA.

```
-------------------------------------------------------------------------------------------------
         Name: SC-0800-W2          From Node: SC-0800
        Group: Grace Lake            To Node: SC-0750
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 600.00
                  Rise(in): 999.00
                Invert(ft): 58.500
       Control Elevation(ft): 58.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

```
-------------------------------------------------------------------------------------------------
         Name: SC-0810-W1          From Node: SC-0810
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                       XSec: SC-0810_W1
                Invert(ft): 57.200
       Control Elevation(ft): 57.200
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
         Name: SC-0810-W2          From Node: SC-0810
        Group: Grace Lake            To Node: SC-0770
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                       XSec: SC-0810_W2
                Invert(ft): 58.500
       Control Elevation(ft): 58.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
         Name: SC-0820-W1          From Node: SC-0820
        Group: Grace Lake            To Node: SC-0815
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Trapezoidal

            Bottom Width(ft): 5.00
        Left Side Slope(h/v): 6.00
       Right Side Slope(h/v): 6.00
                Invert(ft): 55.000
       Control Elevation(ft): 55.000
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

CONCRETE WEIR (OUTFALL)

```
-------------------------------------------------------------------------------------------------
         Name: SC-0820-W2          From Node: SC-0820
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                  Span(in): 600.00
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
                  Rise(in): 999.00
                Invert(ft): 56.010
       Control Elevation(ft): 56.010
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

POND BERM OVERTOPPING

```
------------------------------------------------------------------------------------------------------
         Name: SC-0840-W           From Node: SC-0840
        Group: Grace Lake            To Node: SC-0830
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0840_W
                Invert(ft): 54.000
       Control Elevation(ft): 54.000
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



------------------------------------------------------------------------------------------------------
         Name: SC-0875-W           From Node: SC-0875
        Group: Grace Lake            To Node: SC-0840
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0875_W
                Invert(ft): 65.500
       Control Elevation(ft): 65.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

OVERLAND OVERTOPPING

```
------------------------------------------------------------------------------------------------------
         Name: SC-0880-W           From Node: SC-0880
        Group: Grace Lake            To Node: SC-0875
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0880_W
                Invert(ft): 62.600
       Control Elevation(ft): 62.600
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



------------------------------------------------------------------------------------------------------
         Name: SC-0890-W           From Node: SC-0890
        Group: Grace Lake            To Node: SC-0810
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0890_W
                Invert(ft): 68.500
       Control Elevation(ft): 68.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

OVERTOPPING OF I-4 SWALE AT HIGH POING ALONG THE EAST RIGHT-OF-WAY.
POTENTIAL INTERCONNECTION OF THE TWO (2) CULVERTS CROSSING I-4 (NORTH AND SOUTH).
CROSS SECTION DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC (DATED JULY 2013).

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-----------------------------------------------------------------------------------------------
         Name: SC-0900-W           From Node: SC-0900
        Group: Grace Lake            To Node: SC-0890
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 120.00
                    Rise(in): 999.00
                  Invert(ft): 66.010
       Control Elevation(ft): 66.010
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

ELEVATIONS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-----------------------------------------------------------------------------------------------
         Name: SC-0910-W           From Node: SC-0910
        Group: Grace Lake            To Node: SC-0890
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 960.00
                    Rise(in): 999.00
                  Invert(ft): 59.500
       Control Elevation(ft): 59.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING ELEVATION WAS ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-----------------------------------------------------------------------------------------------
         Name: SC-0920-W1          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0910
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0920_W1
                  Invert(ft): 59.500
       Control Elevation(ft): 59.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-----------------------------------------------------------------------------------------------
         Name: SC-0920-W2          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0890
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 1160.00
                    Rise(in): 999.00
                  Invert(ft): 62.500
       Control Elevation(ft): 62.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-----------------------------------------------------------------------------------------------
         Name: SC-0920-W3          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0790
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0920_W3
                  Invert(ft): 66.800
       Control Elevation(ft): 66.800
      Struct Opening Dim(ft): 9999.00
                                          TABLE
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
       Orifice Discharge Coef: 0.600

PARAMETERS ARE BASED ON SURVEY DATA OBTAINED FROM SSMC, DATED JULY 2013.

-------------------------------------------------------------------------------------------------
         Name: SC-0925-W           From Node: SC-0925
        Group: Grace Lake            To Node: SC-0920
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 680.00
                    Rise(in): 999.00
                  Invert(ft): 78.700
       Control Elevation(ft): 78.700
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
       Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
         Name: SC-0970-W           From Node: SC-0970
        Group: Grace Lake            To Node: SC-0940
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 120.00
                    Rise(in): 999.00
                  Invert(ft): 71.000
       Control Elevation(ft): 71.000
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
       Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
         Name: SC-0985-W           From Node: SC-0985
        Group: Grace Lake            To Node: SC-0980
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 73.500
       Control Elevation(ft): 73.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
       Orifice Discharge Coef: 0.600

PENELOPE POND OVERTOPPING
PARAMETERS WERE ESTIMATED USING THE 1-FT TOPOGRAPHIC MAPS

-------------------------------------------------------------------------------------------------
         Name: SC-1000-W           From Node: SC-1000
        Group: Grace Lake            To Node: SC-0985
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 77.500
       Control Elevation(ft): 77.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
       Orifice Discharge Coef: 0.600

OVERTOPPING HICKORY TREE ROAD

================================================================================
==== Hydrology Simulations =====================================================
================================================================================
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
         Name: 010-024
     Filename: C:\TEMP ICPR\010-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 6.80

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 025-024
     Filename: C:\TEMP ICPR\025-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 8.50

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 025-096
     Filename: C:\TEMP ICPR\025-096.R32

      Override Defaults: Yes
    Storm Duration(hrs): 96.00
          Rainfall File: Sjrwmd96
    Rainfall Amount(in): 11.30

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 100-024
     Filename: C:\TEMP ICPR\100-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 11.40

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 100-096
     Filename: C:\TEMP ICPR\100-096.R32

      Override Defaults: Yes
    Storm Duration(hrs): 96.00
          Rainfall File: Sjrwmd96
    Rainfall Amount(in): 15.00

Time(hrs)       Print Inc(min)
--------------- ---------------
96.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: MA-024
     Filename: C:\TEMP ICPR\MA-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 4.40

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

===============================================================================================
==== Routing Simulations ======================================================================
===============================================================================================

         Name: 010-024             Hydrology Sim: 010-024
     Filename: C:\TEMP ICPR\010-024.I32
```

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
      Execute: No          Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 36.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 1.0000
        Boundary Stages: 010-024                 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
10-YEAR STORM EVENT (24-HOUR DURATION)

Time(hrs)       Print Inc(min)
--------------- ---------------
999.000         15.000

Group           Run
--------------- -----
BASE            Yes
Cranes          Yes
Gee             Yes
Grace Lake      Yes
Soldier         Yes


-------------------------------------------------------------------------------------------------------
         Name: 025-024             Hydrology Sim: 025-024
     Filename: C:\TEMP ICPR\025-024.I32

      Execute: No          Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 36.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 1.0000
        Boundary Stages: 025-024                 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
25-YEAR STORM EVENT (24-HOUR DURATION)

Time(hrs)       Print Inc(min)
--------------- ---------------
999.000         15.000

Group           Run
--------------- -----
BASE            Yes
Cranes          Yes
Gee             Yes
Grace Lake      Yes
Soldier         Yes


-------------------------------------------------------------------------------------------------------
         Name: 025-096             Hydrology Sim: 025-096
     Filename: C:\TEMP ICPR\025-096.I32

      Execute: No          Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 120.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 60.0000
        Boundary Stages: 100-024                 Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
96.000          15.000
120.000         30.000

Group           Run
--------------- -----
BASE            Yes
Cranes          Yes
Gee             Yes
Grace Lake      Yes
Soldier         Yes
```

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-------------------------------------------------------------------------------------------------
         Name: 100-024             Hydrology Sim: 100-024
     Filename: C:\TEMP ICPR\100-024.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 336.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages: 100-024                 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
100-YEAR STORM EVENT (24-HOUR DURATION)

Time(hrs)       Print Inc(min)
--------------- ---------------
48.000          15.000
336.000         60.000

Group           Run
--------------- -----
BASE            Yes
Cranes          Yes
Gee             Yes
Grace Lake      Yes
Soldier         Yes


-------------------------------------------------------------------------------------------------
         Name: 100-096             Hydrology Sim: 100-096
     Filename: C:\TEMP ICPR\100-096.I32

      Execute: Yes         Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 180.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 60.0000
        Boundary Stages: 100-024                 Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
96.000          15.000
120.000         30.000
180.000         60.000

Group           Run
--------------- -----
BASE            Yes
Cranes          Yes
Gee             Yes
Grace Lake      Yes
Soldier         Yes


-------------------------------------------------------------------------------------------------
         Name: MA-024              Hydrology Sim: MA-024
     Filename: C:\TEMP ICPR\MA-024.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 36.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 1.0000
        Boundary Stages: 010-024                 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
MEAN ANNUAL STORM EVENT (24-HOUR DURATION)

Time(hrs)       Print Inc(min)
--------------- ---------------
999.000         15.000

Group           Run
```

---

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

==== Boundary Conditions ====

Name: 010-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.400 |
| 7.500 | 50.400 |
| 8.000 | 50.400 |
| 8.500 | 50.410 |
| 8.670 | 50.410 |
| 8.830 | 50.420 |
| 9.000 | 50.420 |
| 9.170 | 50.430 |
| 9.330 | 50.430 |
| 9.500 | 50.440 |
| 9.670 | 50.440 |
| 9.830 | 50.450 |
| 10.000 | 50.460 |
| 10.170 | 50.470 |
| 10.330 | 50.470 |
| 10.500 | 50.480 |
| 10.670 | 50.490 |
| 10.830 | 50.510 |
| 11.000 | 50.520 |
| 11.170 | 50.530 |
| 11.330 | 50.550 |
| 11.500 | 50.570 |
| 11.670 | 50.600 |
| 11.830 | 50.650 |
| 12.000 | 50.740 |
| 12.170 | 50.840 |
| 12.330 | 50.960 |
| 12.500 | 51.080 |
| 12.670 | 51.170 |
| 12.830 | 51.250 |
| 13.000 | 51.320 |
| 13.170 | 51.370 |
| 13.330 | 51.420 |
| 13.500 | 51.460 |
| 13.670 | 51.500 |
| 13.830 | 51.540 |
| 14.000 | 51.570 |
| 14.170 | 51.600 |
| 14.330 | 51.620 |
| 14.500 | 51.650 |
| 14.670 | 51.680 |
| 14.830 | 51.700 |
| 15.000 | 51.720 |
| 15.170 | 51.750 |
| 15.330 | 51.770 |
| 15.500 | 51.790 |
| 15.670 | 51.810 |
| 15.830 | 51.830 |
| 16.000 | 51.850 |
| 16.170 | 51.870 |
| 16.670 | 51.930 |
| 17.170 | 51.980 |
| 17.670 | 52.040 |
| 18.170 | 52.090 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 18.670 | 52.150 |
| 19.170 | 52.200 |
| 19.670 | 52.250 |
| 20.170 | 52.300 |
| 20.670 | 52.340 |
| 21.170 | 52.390 |
| 21.670 | 52.430 |
| 22.170 | 52.470 |
| 22.670 | 52.500 |
| 23.170 | 52.540 |
| 23.670 | 52.570 |
| 24.170 | 52.600 |
| 24.670 | 52.620 |
| 25.170 | 52.640 |
| 25.670 | 52.650 |
| 26.170 | 52.660 |
| 26.670 | 52.670 |
| 27.170 | 52.670 |
| 27.670 | 52.680 |
| 28.170 | 52.680 |
| 28.670 | 52.680 |
| 29.170 | 52.690 |
| 29.670 | 52.690 |
| 30.170 | 52.680 |
| 30.670 | 52.680 |
| 31.170 | 52.680 |
| 31.670 | 52.680 |
| 32.170 | 52.670 |
| 32.670 | 52.670 |
| 33.170 | 52.660 |
| 33.670 | 52.660 |
| 34.170 | 52.650 |
| 34.670 | 52.640 |
| 35.170 | 52.640 |
| 35.670 | 52.630 |
| 36.000 | 52.620 |

Name: 010-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.150 |
| 5.500 | 42.160 |
| 6.000 | 42.160 |
| 6.500 | 42.160 |
| 7.000 | 42.170 |
| 7.500 | 42.180 |
| 8.000 | 42.190 |
| 8.500 | 42.210 |
| 8.750 | 42.220 |
| 9.000 | 42.240 |
| 9.250 | 42.250 |
| 9.500 | 42.270 |
| 9.750 | 42.280 |
| 10.000 | 42.300 |
| 10.250 | 42.310 |
| 10.500 | 42.330 |
| 10.750 | 42.350 |
| 11.000 | 42.370 |
| 11.250 | 42.390 |
| 11.500 | 42.420 |
| 11.750 | 42.470 |
| 12.000 | 42.570 |
| 12.250 | 42.700 |
| 12.500 | 42.830 |
| 12.750 | 42.910 |
| 13.000 | 42.940 |
| 13.250 | 42.950 |
| 13.500 | 42.950 |
| 13.750 | 42.940 |
| 14.000 | 42.940 |
| 14.250 | 42.930 |
| 14.500 | 42.930 |

| | |
|---|---|
| 14.750 | 42.930 |
| 15.000 | 42.940 |
| 15.250 | 42.970 |
| 15.500 | 43.000 |
| 15.750 | 43.020 |
| 16.000 | 43.050 |
| 16.250 | 43.080 |
| 16.750 | 43.120 |
| 17.250 | 43.160 |
| 17.750 | 43.190 |
| 18.250 | 43.220 |
| 18.750 | 43.240 |
| 19.250 | 43.250 |
| 19.750 | 43.270 |
| 20.250 | 43.280 |
| 20.750 | 43.290 |
| 21.250 | 43.300 |
| 21.750 | 43.310 |
| 22.250 | 43.320 |
| 22.750 | 43.320 |
| 23.250 | 43.330 |
| 23.750 | 43.350 |
| 24.250 | 43.370 |
| 24.750 | 43.390 |
| 25.250 | 43.410 |
| 25.750 | 43.420 |
| 26.250 | 43.430 |
| 26.750 | 43.450 |
| 27.250 | 43.460 |
| 27.750 | 43.470 |
| 28.250 | 43.470 |
| 28.750 | 43.480 |
| 29.250 | 43.480 |
| 29.750 | 43.490 |
| 30.250 | 43.490 |
| 30.750 | 43.490 |
| 31.250 | 43.490 |
| 31.750 | 43.490 |
| 32.250 | 43.490 |
| 32.750 | 43.490 |
| 33.250 | 43.490 |
| 33.750 | 43.490 |
| 34.250 | 43.480 |
| 34.750 | 43.480 |
| 35.250 | 43.480 |
| 35.750 | 43.470 |
| 36.250 | 43.460 |
| 36.750 | 43.460 |
| 37.250 | 43.450 |
| 37.750 | 43.440 |
| 38.250 | 43.440 |
| 38.750 | 43.430 |
| 39.250 | 43.420 |
| 39.750 | 43.410 |
| 40.250 | 43.400 |
| 40.750 | 43.390 |
| 41.250 | 43.380 |
| 41.750 | 43.370 |
| 42.250 | 43.360 |
| 42.750 | 43.350 |
| 43.250 | 43.340 |
| 43.750 | 43.330 |
| 44.250 | 43.310 |
| 44.750 | 43.300 |
| 45.250 | 43.290 |
| 45.750 | 43.280 |
| 46.250 | 43.270 |
| 46.750 | 43.250 |
| 47.250 | 43.240 |
| 47.750 | 43.230 |
| 48.000 | 43.220 |

Name: 010-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.130 |
| 8.500 | 46.130 |
| 8.750 | 46.140 |
| 9.000 | 46.140 |
| 9.250 | 46.140 |
| 9.500 | 46.140 |
| 9.750 | 46.150 |
| 10.000 | 46.150 |
| 10.250 | 46.160 |
| 10.500 | 46.160 |
| 10.750 | 46.170 |
| 11.000 | 46.180 |
| 11.250 | 46.200 |
| 11.500 | 46.220 |
| 11.750 | 46.260 |
| 12.000 | 46.330 |
| 12.250 | 46.430 |
| 12.500 | 46.530 |
| 12.750 | 46.600 |
| 13.000 | 46.650 |
| 13.250 | 46.690 |
| 13.500 | 46.720 |
| 13.750 | 46.740 |
| 14.000 | 46.770 |
| 14.250 | 46.800 |
| 14.500 | 46.820 |
| 14.750 | 46.850 |
| 15.000 | 46.870 |
| 15.250 | 46.900 |
| 15.500 | 46.920 |
| 15.750 | 46.950 |
| 16.000 | 46.980 |
| 16.250 | 47.000 |
| 16.750 | 47.060 |
| 17.250 | 47.120 |
| 17.750 | 47.180 |
| 18.250 | 47.240 |
| 18.750 | 47.300 |
| 19.250 | 47.350 |
| 19.750 | 47.410 |
| 20.250 | 47.460 |
| 20.750 | 47.490 |
| 21.250 | 47.520 |
| 21.750 | 47.550 |
| 22.250 | 47.580 |
| 22.750 | 47.730 |
| 23.250 | 48.070 |
| 23.750 | 48.530 |
| 24.250 | 48.700 |
| 24.750 | 48.810 |
| 25.250 | 48.880 |
| 25.750 | 48.920 |
| 26.250 | 48.950 |
| 26.750 | 48.970 |
| 27.250 | 48.980 |
| 27.750 | 48.980 |
| 28.250 | 48.980 |
| 28.750 | 48.970 |
| 29.250 | 48.960 |
| 29.750 | 48.950 |
| 30.250 | 48.940 |
| 30.750 | 48.920 |
| 31.250 | 48.910 |
| 31.750 | 48.890 |
| 32.250 | 48.870 |
| 32.750 | 48.850 |
| 33.250 | 48.830 |
| 33.750 | 48.810 |
| 34.250 | 48.790 |
| 34.750 | 48.770 |
| 35.250 | 48.750 |
| 35.750 | 48.720 |
| 36.250 | 48.700 |
| 36.750 | 48.680 |
| 37.250 | 48.660 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 37.750 | 48.640 |
| 38.250 | 48.620 |
| 38.750 | 48.600 |
| 39.250 | 48.580 |
| 39.750 | 48.560 |
| 40.250 | 48.540 |
| 40.750 | 48.520 |
| 41.250 | 48.510 |
| 41.750 | 48.490 |
| 42.250 | 48.470 |
| 42.750 | 48.290 |
| 43.250 | 48.270 |
| 43.750 | 48.240 |
| 44.250 | 48.220 |
| 44.750 | 48.200 |
| 45.250 | 48.170 |
| 45.750 | 48.150 |
| 46.250 | 48.130 |
| 46.750 | 48.110 |
| 47.250 | 48.090 |
| 47.750 | 48.060 |
| 48.000 | 48.050 |

Name: 010-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |
| 4.500 | 41.060 |
| 5.000 | 41.090 |
| 5.500 | 41.180 |
| 6.000 | 41.310 |
| 6.500 | 41.400 |
| 7.000 | 41.520 |
| 7.500 | 41.670 |
| 8.000 | 41.810 |
| 8.500 | 41.960 |
| 8.750 | 42.050 |
| 9.000 | 42.130 |
| 9.250 | 42.230 |
| 9.500 | 42.320 |
| 9.750 | 42.400 |
| 10.000 | 42.480 |
| 10.250 | 42.570 |
| 10.500 | 42.670 |
| 10.750 | 42.770 |
| 11.000 | 42.870 |
| 11.250 | 42.970 |
| 11.500 | 43.120 |
| 11.750 | 43.540 |
| 12.000 | 43.920 |
| 12.250 | 44.110 |
| 12.500 | 44.080 |
| 12.750 | 43.900 |
| 13.000 | 43.750 |
| 13.250 | 43.700 |
| 13.500 | 43.720 |
| 13.750 | 43.740 |
| 14.000 | 43.750 |
| 14.250 | 43.750 |
| 14.500 | 43.780 |
| 14.750 | 43.840 |
| 15.000 | 43.910 |
| 15.250 | 43.960 |
| 15.500 | 44.000 |
| 15.750 | 44.020 |
| 16.000 | 44.030 |
| 16.250 | 44.030 |
| 16.750 | 44.020 |
| 17.250 | 44.000 |
| 17.750 | 43.960 |
| 18.250 | 43.900 |
| 18.750 | 43.840 |
| 19.250 | 43.790 |
| 19.750 | 43.740 |

| | |
|---|---|
| 20.250 | 43.700 |
| 20.750 | 43.670 |
| 21.250 | 43.660 |
| 21.750 | 43.650 |
| 22.250 | 43.650 |
| 22.750 | 43.640 |
| 23.250 | 43.630 |
| 23.750 | 43.620 |
| 24.250 | 43.600 |
| 24.750 | 43.570 |
| 25.250 | 43.540 |
| 25.750 | 43.510 |
| 26.250 | 43.480 |
| 26.750 | 43.460 |
| 27.250 | 43.430 |
| 27.750 | 43.430 |
| 28.250 | 43.320 |
| 28.750 | 42.350 |
| 29.250 | 42.150 |
| 29.750 | 42.080 |
| 30.250 | 42.030 |
| 30.750 | 42.000 |
| 31.250 | 41.970 |
| 31.750 | 41.950 |
| 32.250 | 41.920 |
| 32.750 | 41.890 |
| 33.250 | 41.860 |
| 33.750 | 41.830 |
| 34.250 | 41.810 |
| 34.750 | 41.790 |
| 35.250 | 41.770 |
| 35.750 | 41.750 |
| 36.250 | 41.730 |
| 36.750 | 41.710 |
| 37.250 | 41.700 |
| 37.750 | 41.680 |
| 38.250 | 41.670 |
| 38.750 | 41.660 |
| 39.250 | 41.650 |
| 39.750 | 41.640 |
| 40.250 | 41.630 |
| 40.750 | 41.620 |
| 41.250 | 41.610 |
| 41.750 | 41.600 |
| 42.250 | 41.590 |
| 42.750 | 41.580 |
| 43.250 | 41.570 |
| 43.750 | 41.560 |
| 44.250 | 41.550 |
| 44.750 | 41.550 |
| 45.250 | 41.540 |
| 45.750 | 41.530 |
| 46.250 | 41.520 |
| 46.750 | 41.520 |
| 47.250 | 41.510 |
| 47.750 | 41.510 |
| 48.000 | 41.510 |

Name: 025-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.410 |
| 7.500 | 50.420 |
| 8.000 | 50.430 |
| 8.500 | 50.450 |
| 8.670 | 50.450 |
| 8.830 | 50.460 |
| 9.000 | 50.470 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 9.170 | 50.480 |
| 9.330 | 50.480 |
| 9.500 | 50.490 |
| 9.670 | 50.500 |
| 9.830 | 50.510 |
| 10.000 | 50.520 |
| 10.170 | 50.530 |
| 10.330 | 50.550 |
| 10.500 | 50.560 |
| 10.670 | 50.570 |
| 10.830 | 50.590 |
| 11.000 | 50.610 |
| 11.170 | 50.630 |
| 11.330 | 50.650 |
| 11.500 | 50.680 |
| 11.670 | 50.710 |
| 11.830 | 50.780 |
| 12.000 | 50.880 |
| 12.170 | 51.020 |
| 12.330 | 51.170 |
| 12.500 | 51.310 |
| 12.670 | 51.440 |
| 12.830 | 51.530 |
| 13.000 | 51.610 |
| 13.170 | 51.680 |
| 13.330 | 51.740 |
| 13.500 | 51.800 |
| 13.670 | 51.840 |
| 13.830 | 51.890 |
| 14.000 | 51.920 |
| 14.170 | 51.960 |
| 14.330 | 52.000 |
| 14.500 | 52.030 |
| 14.670 | 52.060 |
| 14.830 | 52.090 |
| 15.000 | 52.120 |
| 15.170 | 52.140 |
| 15.330 | 52.170 |
| 15.500 | 52.200 |
| 15.670 | 52.220 |
| 15.830 | 52.250 |
| 16.000 | 52.280 |
| 16.170 | 52.300 |
| 16.670 | 52.380 |
| 17.170 | 52.450 |
| 17.670 | 52.520 |
| 18.170 | 52.590 |
| 18.670 | 52.650 |
| 19.170 | 52.720 |
| 19.670 | 52.770 |
| 20.170 | 52.830 |
| 20.670 | 52.890 |
| 21.170 | 52.940 |
| 21.670 | 52.980 |
| 22.170 | 53.030 |
| 22.670 | 53.070 |
| 23.170 | 53.110 |
| 23.670 | 53.140 |
| 24.170 | 53.170 |
| 24.670 | 53.190 |
| 25.170 | 53.200 |
| 25.670 | 53.210 |
| 26.170 | 53.220 |
| 26.670 | 53.230 |
| 27.170 | 53.230 |
| 27.670 | 53.230 |
| 28.170 | 53.240 |
| 28.670 | 53.230 |
| 29.170 | 53.230 |
| 29.670 | 53.230 |
| 30.170 | 53.220 |
| 30.670 | 53.220 |
| 31.170 | 53.210 |
| 31.670 | 53.210 |
| 32.170 | 53.200 |
| 32.670 | 53.190 |
| 33.170 | 53.180 |
| 33.670 | 53.170 |
| 34.170 | 53.160 |
| 34.670 | 53.150 |
| 35.170 | 53.140 |
| 35.670 | 53.130 |
| 36.000 | 53.120 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: 025-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.160 |
| 5.500 | 42.160 |
| 6.000 | 42.170 |
| 6.500 | 42.180 |
| 7.000 | 42.190 |
| 7.500 | 42.210 |
| 8.000 | 42.240 |
| 8.500 | 42.270 |
| 8.750 | 42.280 |
| 9.000 | 42.300 |
| 9.250 | 42.320 |
| 9.500 | 42.330 |
| 9.750 | 42.350 |
| 10.000 | 42.370 |
| 10.250 | 42.380 |
| 10.500 | 42.400 |
| 10.750 | 42.420 |
| 11.000 | 42.450 |
| 11.250 | 42.470 |
| 11.500 | 42.500 |
| 11.750 | 42.560 |
| 12.000 | 42.670 |
| 12.250 | 42.820 |
| 12.500 | 42.950 |
| 12.750 | 43.030 |
| 13.000 | 43.070 |
| 13.250 | 43.080 |
| 13.500 | 43.080 |
| 13.750 | 43.080 |
| 14.000 | 43.090 |
| 14.250 | 43.110 |
| 14.500 | 43.150 |
| 14.750 | 43.200 |
| 15.000 | 43.250 |
| 15.250 | 43.300 |
| 15.500 | 43.340 |
| 15.750 | 43.370 |
| 16.000 | 43.410 |
| 16.250 | 43.440 |
| 16.750 | 43.490 |
| 17.250 | 43.540 |
| 17.750 | 43.570 |
| 18.250 | 43.600 |
| 18.750 | 43.620 |
| 19.250 | 43.640 |
| 19.750 | 43.650 |
| 20.250 | 43.670 |
| 20.750 | 43.690 |
| 21.250 | 43.720 |
| 21.750 | 43.750 |
| 22.250 | 43.780 |
| 22.750 | 43.810 |
| 23.250 | 43.830 |
| 23.750 | 43.860 |
| 24.250 | 43.880 |
| 24.750 | 43.900 |
| 25.250 | 43.910 |
| 25.750 | 43.920 |
| 26.250 | 43.930 |
| 26.750 | 43.940 |
| 27.250 | 43.940 |
| 27.750 | 43.950 |
| 28.250 | 43.950 |
| 28.750 | 43.950 |
| 29.250 | 43.950 |
| 29.750 | 43.950 |
| 30.250 | 43.950 |
| 30.750 | 43.940 |
| 31.250 | 43.940 |

| | |
|---|---|
| 31.750 | 43.930 |
| 32.250 | 43.930 |
| 32.750 | 43.920 |
| 33.250 | 43.910 |
| 33.750 | 43.910 |
| 34.250 | 43.900 |
| 34.750 | 43.890 |
| 35.250 | 43.880 |
| 35.750 | 43.870 |
| 36.250 | 43.850 |
| 36.750 | 43.840 |
| 37.250 | 43.830 |
| 37.750 | 43.820 |
| 38.250 | 43.800 |
| 38.750 | 43.790 |
| 39.250 | 43.780 |
| 39.750 | 43.760 |
| 40.250 | 43.750 |
| 40.750 | 43.730 |
| 41.250 | 43.720 |
| 41.750 | 43.700 |
| 42.250 | 43.690 |
| 42.750 | 43.670 |
| 43.250 | 43.660 |
| 43.750 | 43.640 |
| 44.250 | 43.630 |
| 44.750 | 43.610 |
| 45.250 | 43.600 |
| 45.750 | 43.580 |
| 46.250 | 43.570 |
| 46.750 | 43.550 |
| 47.250 | 43.530 |
| 47.750 | 43.520 |
| 48.000 | 43.510 |

Name: 025-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.140 |
| 8.500 | 46.150 |
| 8.750 | 46.150 |
| 9.000 | 46.150 |
| 9.250 | 46.160 |
| 9.500 | 46.160 |
| 9.750 | 46.170 |
| 10.000 | 46.180 |
| 10.250 | 46.190 |
| 10.500 | 46.200 |
| 10.750 | 46.220 |
| 11.000 | 46.240 |
| 11.250 | 46.260 |
| 11.500 | 46.290 |
| 11.750 | 46.330 |
| 12.000 | 46.400 |
| 12.250 | 46.570 |
| 12.500 | 46.710 |
| 12.750 | 46.800 |
| 13.000 | 46.860 |
| 13.250 | 46.910 |
| 13.500 | 46.940 |
| 13.750 | 46.980 |
| 14.000 | 47.010 |
| 14.250 | 47.040 |
| 14.500 | 47.070 |
| 14.750 | 47.100 |
| 15.000 | 47.130 |

| | |
|---|---|
| 15.250 | 47.160 |
| 15.500 | 47.190 |
| 15.750 | 47.220 |
| 16.000 | 47.260 |
| 16.250 | 47.290 |
| 16.750 | 47.350 |
| 17.250 | 47.410 |
| 17.750 | 47.460 |
| 18.250 | 47.500 |
| 18.750 | 47.530 |
| 19.250 | 47.570 |
| 19.750 | 47.720 |
| 20.250 | 48.190 |
| 20.750 | 48.710 |
| 21.250 | 48.950 |
| 21.750 | 49.120 |
| 22.250 | 49.240 |
| 22.750 | 49.310 |
| 23.250 | 49.370 |
| 23.750 | 49.410 |
| 24.250 | 49.430 |
| 24.750 | 49.430 |
| 25.250 | 49.430 |
| 25.750 | 49.440 |
| 26.250 | 49.430 |
| 26.750 | 49.430 |
| 27.250 | 49.420 |
| 27.750 | 49.410 |
| 28.250 | 49.400 |
| 28.750 | 49.380 |
| 29.250 | 49.360 |
| 29.750 | 49.340 |
| 30.250 | 49.320 |
| 30.750 | 49.300 |
| 31.250 | 49.280 |
| 31.750 | 49.250 |
| 32.250 | 49.230 |
| 32.750 | 49.190 |
| 33.250 | 49.160 |
| 33.750 | 49.130 |
| 34.250 | 49.100 |
| 34.750 | 49.080 |
| 35.250 | 49.050 |
| 35.750 | 49.020 |
| 36.250 | 48.990 |
| 36.750 | 48.960 |
| 37.250 | 48.930 |
| 37.750 | 48.900 |
| 38.250 | 48.870 |
| 38.750 | 48.840 |
| 39.250 | 48.820 |
| 39.750 | 48.790 |
| 40.250 | 48.770 |
| 40.750 | 48.740 |
| 41.250 | 48.720 |
| 41.750 | 48.700 |
| 42.250 | 48.670 |
| 42.750 | 48.650 |
| 43.250 | 48.630 |
| 43.750 | 48.610 |
| 44.250 | 48.590 |
| 44.750 | 48.570 |
| 45.250 | 48.550 |
| 45.750 | 48.530 |
| 46.250 | 48.510 |
| 46.750 | 48.500 |
| 47.250 | 48.480 |
| 47.750 | 48.460 |
| 48.000 | 48.290 |

Name: 025-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 4.500 | 41.140 |
| 5.000 | 41.280 |
| 5.500 | 41.390 |
| 6.000 | 41.510 |
| 6.500 | 41.670 |
| 7.000 | 41.830 |
| 7.500 | 42.000 |
| 8.000 | 42.170 |
| 8.500 | 42.340 |
| 8.750 | 42.420 |
| 9.000 | 42.500 |
| 9.250 | 42.580 |
| 9.500 | 42.650 |
| 9.750 | 42.730 |
| 10.000 | 42.800 |
| 10.250 | 42.870 |
| 10.500 | 42.960 |
| 10.750 | 43.070 |
| 11.000 | 43.160 |
| 11.250 | 43.240 |
| 11.500 | 43.430 |
| 11.750 | 43.690 |
| 12.000 | 44.060 |
| 12.250 | 44.120 |
| 12.500 | 44.140 |
| 12.750 | 44.090 |
| 13.000 | 43.950 |
| 13.250 | 43.930 |
| 13.500 | 43.870 |
| 13.750 | 43.960 |
| 14.000 | 44.130 |
| 14.250 | 44.240 |
| 14.500 | 44.340 |
| 14.750 | 44.420 |
| 15.000 | 44.490 |
| 15.250 | 44.540 |
| 15.500 | 44.570 |
| 15.750 | 44.580 |
| 16.000 | 44.580 |
| 16.250 | 44.570 |
| 16.750 | 44.520 |
| 17.250 | 44.470 |
| 17.750 | 44.410 |
| 18.250 | 44.350 |
| 18.750 | 44.290 |
| 19.250 | 44.240 |
| 19.750 | 44.180 |
| 20.250 | 44.130 |
| 20.750 | 44.070 |
| 21.250 | 43.990 |
| 21.750 | 43.910 |
| 22.250 | 43.840 |
| 22.750 | 43.770 |
| 23.250 | 43.720 |
| 23.750 | 43.690 |
| 24.250 | 43.660 |
| 24.750 | 43.630 |
| 25.250 | 43.600 |
| 25.750 | 43.570 |
| 26.250 | 43.550 |
| 26.750 | 43.530 |
| 27.250 | 43.510 |
| 27.750 | 43.480 |
| 28.250 | 43.460 |
| 28.750 | 43.440 |
| 29.250 | 43.410 |
| 29.750 | 43.400 |
| 30.250 | 42.620 |
| 30.750 | 42.160 |
| 31.250 | 42.050 |
| 31.750 | 42.010 |
| 32.250 | 41.980 |
| 32.750 | 41.960 |
| 33.250 | 41.930 |
| 33.750 | 41.910 |
| 34.250 | 41.900 |
| 34.750 | 41.890 |
| 35.250 | 41.880 |
| 35.750 | 41.860 |
| 36.250 | 41.850 |
| 36.750 | 41.840 |
| 37.250 | 41.830 |
| 37.750 | 41.820 |
| 38.250 | 41.830 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 38.750 | 41.810 |
| 39.250 | 41.800 |
| 39.750 | 41.790 |
| 40.250 | 41.770 |
| 40.750 | 41.760 |
| 41.250 | 41.750 |
| 41.750 | 41.730 |
| 42.250 | 41.720 |
| 42.750 | 41.710 |
| 43.250 | 41.700 |
| 43.750 | 41.680 |
| 44.250 | 41.670 |
| 44.750 | 41.660 |
| 45.250 | 41.650 |
| 45.750 | 41.640 |
| 46.250 | 41.630 |
| 46.750 | 41.620 |
| 47.250 | 41.610 |
| 47.750 | 41.600 |
| 48.000 | 41.600 |

Name: 100-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.410 |
| 3.500 | 50.410 |
| 4.000 | 50.410 |
| 4.500 | 50.410 |
| 5.000 | 50.420 |
| 5.500 | 50.420 |
| 6.000 | 50.440 |
| 6.500 | 50.450 |
| 7.000 | 50.460 |
| 7.500 | 50.480 |
| 8.000 | 50.510 |
| 8.500 | 50.540 |
| 8.670 | 50.550 |
| 8.830 | 50.560 |
| 9.000 | 50.570 |
| 9.170 | 50.580 |
| 9.330 | 50.600 |
| 9.500 | 50.610 |
| 9.670 | 50.630 |
| 9.830 | 50.640 |
| 10.000 | 50.660 |
| 10.170 | 50.680 |
| 10.330 | 50.700 |
| 10.500 | 50.720 |
| 10.670 | 50.740 |
| 10.830 | 50.770 |
| 11.000 | 50.790 |
| 11.170 | 50.820 |
| 11.330 | 50.850 |
| 11.500 | 50.890 |
| 11.670 | 50.950 |
| 11.830 | 51.040 |
| 12.000 | 51.170 |
| 12.170 | 51.350 |
| 12.330 | 51.560 |
| 12.500 | 51.760 |
| 12.670 | 51.940 |
| 12.830 | 52.080 |
| 13.000 | 52.200 |
| 13.170 | 52.310 |
| 13.330 | 52.410 |
| 13.500 | 52.490 |
| 13.670 | 52.570 |
| 13.830 | 52.640 |
| 14.000 | 52.710 |
| 14.170 | 52.770 |
| 14.330 | 52.830 |
| 14.500 | 52.880 |
| 14.670 | 52.930 |
| 14.830 | 52.970 |
| 15.000 | 53.010 |
| 15.170 | 53.050 |

| | |
|---|---|
| 15.330 | 53.080 |
| 15.500 | 53.120 |
| 15.670 | 53.150 |
| 15.830 | 53.180 |
| 16.000 | 53.210 |
| 16.170 | 53.230 |
| 16.670 | 53.310 |
| 17.170 | 53.380 |
| 17.670 | 53.440 |
| 18.170 | 53.500 |
| 18.670 | 53.560 |
| 19.170 | 53.610 |
| 19.670 | 53.660 |
| 20.170 | 53.700 |
| 20.670 | 53.740 |
| 21.170 | 53.780 |
| 21.670 | 53.820 |
| 22.170 | 53.850 |
| 22.670 | 53.880 |
| 23.170 | 53.910 |
| 23.670 | 53.940 |
| 24.170 | 53.970 |
| 24.670 | 53.980 |
| 25.170 | 54.000 |
| 25.670 | 54.000 |
| 26.170 | 54.010 |
| 26.670 | 54.010 |
| 27.170 | 54.010 |
| 27.670 | 54.000 |
| 28.170 | 54.000 |
| 28.670 | 54.000 |
| 29.170 | 53.990 |
| 29.670 | 53.990 |
| 30.170 | 53.980 |
| 30.670 | 53.970 |
| 31.170 | 53.970 |
| 31.670 | 53.960 |
| 32.170 | 53.950 |
| 32.670 | 53.940 |
| 33.170 | 53.920 |
| 33.670 | 53.910 |
| 34.170 | 53.900 |
| 34.670 | 53.890 |
| 35.170 | 53.870 |
| 35.670 | 53.860 |
| 36.000 | 53.850 |

Name: 100-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.160 |
| 5.000 | 42.170 |
| 5.500 | 42.180 |
| 6.000 | 42.210 |
| 6.500 | 42.230 |
| 7.000 | 42.270 |
| 7.500 | 42.300 |
| 8.000 | 42.330 |
| 8.500 | 42.370 |
| 8.750 | 42.380 |
| 9.000 | 42.400 |
| 9.250 | 42.420 |
| 9.500 | 42.440 |
| 9.750 | 42.460 |
| 10.000 | 42.470 |
| 10.250 | 42.500 |
| 10.500 | 42.520 |
| 10.750 | 42.540 |
| 11.000 | 42.570 |
| 11.250 | 42.600 |
| 11.500 | 42.630 |
| 11.750 | 42.700 |
| 12.000 | 42.830 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 12.250 | 42.980 |
| 12.500 | 43.130 |
| 12.750 | 43.230 |
| 13.000 | 43.300 |
| 13.250 | 43.350 |
| 13.500 | 43.390 |
| 13.750 | 43.450 |
| 14.000 | 43.540 |
| 14.250 | 43.610 |
| 14.500 | 43.690 |
| 14.750 | 43.750 |
| 15.000 | 43.810 |
| 15.250 | 43.860 |
| 15.500 | 43.910 |
| 15.750 | 43.950 |
| 16.000 | 43.990 |
| 16.250 | 44.020 |
| 16.750 | 44.090 |
| 17.250 | 44.150 |
| 17.750 | 44.200 |
| 18.250 | 44.250 |
| 18.750 | 44.300 |
| 19.250 | 44.350 |
| 19.750 | 44.390 |
| 20.250 | 44.430 |
| 20.750 | 44.460 |
| 21.250 | 44.490 |
| 21.750 | 44.520 |
| 22.250 | 44.550 |
| 22.750 | 44.570 |
| 23.250 | 44.600 |
| 23.750 | 44.620 |
| 24.250 | 44.640 |
| 24.750 | 44.650 |
| 25.250 | 44.660 |
| 25.750 | 44.670 |
| 26.250 | 44.670 |
| 26.750 | 44.670 |
| 27.250 | 44.670 |
| 27.750 | 44.670 |
| 28.250 | 44.670 |
| 28.750 | 44.670 |
| 29.250 | 44.670 |
| 29.750 | 44.670 |
| 30.250 | 44.670 |
| 30.750 | 44.670 |
| 31.250 | 44.660 |
| 31.750 | 44.660 |
| 32.250 | 44.650 |
| 32.750 | 44.650 |
| 33.250 | 44.640 |
| 33.750 | 44.630 |
| 34.250 | 44.620 |
| 34.750 | 44.610 |
| 35.250 | 44.600 |
| 35.750 | 44.590 |
| 36.250 | 44.570 |
| 36.750 | 44.560 |
| 37.250 | 44.540 |
| 37.750 | 44.530 |
| 38.250 | 44.510 |
| 38.750 | 44.490 |
| 39.250 | 44.470 |
| 39.750 | 44.450 |
| 40.250 | 44.430 |
| 40.750 | 44.410 |
| 41.250 | 44.390 |
| 41.750 | 44.370 |
| 42.250 | 44.350 |
| 42.750 | 44.330 |
| 43.250 | 44.300 |
| 43.750 | 44.280 |
| 44.250 | 44.260 |
| 44.750 | 44.240 |
| 45.250 | 44.210 |
| 45.750 | 44.190 |
| 46.250 | 44.170 |
| 46.750 | 44.140 |
| 47.250 | 44.120 |
| 47.750 | 44.100 |
| 48.000 | 44.070 |

Name: 100-024 Node: SC-3010 Type: Stage

GRACE LAKE
EXISTING CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.140 |
| 7.000 | 46.150 |
| 7.500 | 46.150 |
| 8.000 | 46.170 |
| 8.500 | 46.180 |
| 8.750 | 46.190 |
| 9.000 | 46.200 |
| 9.250 | 46.220 |
| 9.500 | 46.230 |
| 9.750 | 46.250 |
| 10.000 | 46.270 |
| 10.250 | 46.290 |
| 10.500 | 46.320 |
| 10.750 | 46.330 |
| 11.000 | 46.330 |
| 11.250 | 46.340 |
| 11.500 | 46.360 |
| 11.750 | 46.440 |
| 12.000 | 46.630 |
| 12.250 | 46.860 |
| 12.500 | 47.030 |
| 12.750 | 47.140 |
| 13.000 | 47.210 |
| 13.250 | 47.270 |
| 13.500 | 47.310 |
| 13.750 | 47.350 |
| 14.000 | 47.390 |
| 14.250 | 47.430 |
| 14.500 | 47.460 |
| 14.750 | 47.480 |
| 15.000 | 47.500 |
| 15.250 | 47.520 |
| 15.500 | 47.540 |
| 15.750 | 47.560 |
| 16.000 | 47.600 |
| 16.250 | 47.750 |
| 16.750 | 48.370 |
| 17.250 | 48.910 |
| 17.750 | 49.200 |
| 18.250 | 49.380 |
| 18.750 | 49.510 |
| 19.250 | 49.610 |
| 19.750 | 49.700 |
| 20.250 | 49.770 |
| 20.750 | 49.830 |
| 21.250 | 49.890 |
| 21.750 | 49.890 |
| 22.250 | 49.910 |
| 22.750 | 49.940 |
| 23.250 | 49.950 |
| 23.750 | 49.960 |
| 24.250 | 49.970 |
| 24.750 | 49.960 |
| 25.250 | 49.950 |
| 25.750 | 49.950 |
| 26.250 | 49.950 |
| 26.750 | 49.950 |
| 27.250 | 49.950 |
| 27.750 | 49.950 |
| 28.250 | 49.940 |
| 28.750 | 49.940 |
| 29.250 | 49.940 |
| 29.750 | 49.940 |
| 30.250 | 49.940 |
| 30.750 | 49.930 |
| 31.250 | 49.920 |
| 31.750 | 49.910 |
| 32.250 | 49.900 |

| | |
|---|---|
| 32.750 | 49.890 |
| 33.250 | 49.890 |
| 33.750 | 49.870 |
| 34.250 | 49.840 |
| 34.750 | 49.810 |
| 35.250 | 49.770 |
| 35.750 | 49.740 |
| 36.250 | 49.700 |
| 36.750 | 49.660 |
| 37.250 | 49.620 |
| 37.750 | 49.580 |
| 38.250 | 49.530 |
| 38.750 | 49.490 |
| 39.250 | 49.450 |
| 39.750 | 49.410 |
| 40.250 | 49.370 |
| 40.750 | 49.340 |
| 41.250 | 49.300 |
| 41.750 | 49.260 |
| 42.250 | 49.220 |
| 42.750 | 49.180 |
| 43.250 | 49.140 |
| 43.750 | 49.100 |
| 44.250 | 49.070 |
| 44.750 | 49.040 |
| 45.250 | 49.010 |
| 45.750 | 48.980 |
| 46.250 | 48.950 |
| 46.750 | 48.920 |
| 47.250 | 48.890 |
| 47.750 | 48.870 |
| 48.000 | 48.840 |

Name: 100-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.140 |
| 4.000 | 41.280 |
| 4.500 | 41.420 |
| 5.000 | 41.600 |
| 5.500 | 41.810 |
| 6.000 | 42.000 |
| 6.500 | 42.190 |
| 7.000 | 42.380 |
| 7.500 | 42.530 |
| 8.000 | 42.680 |
| 8.500 | 42.800 |
| 8.750 | 42.870 |
| 9.000 | 42.940 |
| 9.250 | 43.020 |
| 9.500 | 43.080 |
| 9.750 | 43.140 |
| 10.000 | 43.200 |
| 10.250 | 43.370 |
| 10.500 | 43.370 |
| 10.750 | 43.430 |
| 11.000 | 43.500 |
| 11.250 | 43.540 |
| 11.500 | 43.610 |
| 11.750 | 43.920 |
| 12.000 | 44.160 |
| 12.250 | 44.250 |
| 12.500 | 44.260 |
| 12.750 | 44.220 |
| 13.000 | 44.240 |
| 13.250 | 44.400 |
| 13.500 | 44.650 |
| 13.750 | 44.870 |
| 14.000 | 45.020 |
| 14.250 | 45.170 |
| 14.500 | 45.290 |
| 14.750 | 45.370 |
| 15.000 | 45.460 |
| 15.250 | 45.500 |
| 15.500 | 45.500 |

| | |
|---|---|
| 15.750 | 45.470 |
| 16.000 | 45.410 |
| 16.250 | 45.350 |
| 16.750 | 45.250 |
| 17.250 | 45.140 |
| 17.750 | 45.030 |
| 18.250 | 44.910 |
| 18.750 | 44.800 |
| 19.250 | 44.690 |
| 19.750 | 44.600 |
| 20.250 | 44.510 |
| 20.750 | 44.420 |
| 21.250 | 44.350 |
| 21.750 | 44.280 |
| 22.250 | 44.220 |
| 22.750 | 44.170 |
| 23.250 | 44.120 |
| 23.750 | 44.050 |
| 24.250 | 43.970 |
| 24.750 | 43.860 |
| 25.250 | 43.730 |
| 25.750 | 43.640 |
| 26.250 | 43.600 |
| 26.750 | 43.580 |
| 27.250 | 43.560 |
| 27.750 | 43.540 |
| 28.250 | 43.530 |
| 28.750 | 43.510 |
| 29.250 | 43.510 |
| 29.750 | 43.510 |
| 30.250 | 43.510 |
| 30.750 | 43.490 |
| 31.250 | 43.470 |
| 31.750 | 43.450 |
| 32.250 | 43.420 |
| 32.750 | 43.420 |
| 33.250 | 43.330 |
| 33.750 | 42.350 |
| 34.250 | 42.110 |
| 34.750 | 42.050 |
| 35.250 | 42.020 |
| 35.750 | 42.000 |
| 36.250 | 41.980 |
| 36.750 | 41.960 |
| 37.250 | 41.950 |
| 37.750 | 41.930 |
| 38.250 | 41.920 |
| 38.750 | 41.910 |
| 39.250 | 41.900 |
| 39.750 | 41.890 |
| 40.250 | 41.880 |
| 40.750 | 41.870 |
| 41.250 | 41.870 |
| 41.750 | 41.860 |
| 42.250 | 41.860 |
| 42.750 | 41.850 |
| 43.250 | 41.850 |
| 43.750 | 41.840 |
| 44.250 | 41.840 |
| 44.750 | 41.840 |
| 45.250 | 41.830 |
| 45.750 | 41.830 |
| 46.250 | 41.830 |
| 46.750 | 41.830 |
| 47.250 | 41.830 |
| 47.750 | 41.820 |
| 48.000 | 41.820 |

Proposed Conditions, Grace Lake

GRACE LAKE
PROPOSED CONDITIONS OUTPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs |
|---|---|---|---|---|---|---|---|---|---|---|
| SC-0750 | Grace Lake | 100-096 | 0.00 | 52.00 | 54.00 | 0.0000 | 40 | 72.15 | 62.47 | 0.00 |
| SC-0760 | Grace Lake | 100-096 | 72.13 | 56.17 | 58.00 | 0.0001 | 342 | 72.12 | 36.70 | 72.11 |
| SC-0770 | Grace Lake | 100-096 | 72.12 | 58.76 | 58.00 | -0.0004 | 45492 | 59.72 | 49.94 | 72.11 |
| SC-0780 | Grace Lake | 100-096 | 0.00 | 64.24 | 67.27 | 0.0000 | 114 | 0.00 | 0.00 | 0.00 |
| SC-0790 | Grace Lake | 100-096 | 0.00 | 64.00 | 67.00 | 0.0000 | 7842 | 0.00 | 0.00 | 0.00 |
| SC-0800 | Grace Lake | 100-096 | 72.16 | 58.77 | 59.00 | 0.0001 | 225137 | 61.55 | 108.18 | 72.34 |
| SC-0810 | Grace Lake | 100-096 | 72.17 | 58.80 | 58.00 | 0.0024 | 2038 | 61.23 | 84.96 | 61.24 |
| SC-0830 | Grace Lake | 100-096 | 61.22 | 59.61 | 59.00 | -0.0003 | 29239 | 60.94 | 91.07 | 61.22 |
| SC-0840 | Grace Lake | 100-096 | 61.22 | 59.62 | 58.00 | 0.0002 | 219543 | 60.08 | 189.65 | 61.14 |
| SC-0850 | Grace Lake | 100-096 | 61.23 | 60.69 | 59.50 | 0.0003 | 123 | 96.00 | 46.72 | 96.00 |
| SC-0860 | Grace Lake | 100-096 | 61.24 | 61.74 | 61.55 | 0.0003 | 155 | 96.00 | 46.72 | 96.00 |
| SC-0870 | Grace Lake | 100-096 | 96.00 | 64.81 | 66.00 | 0.0003 | 154 | 96.00 | 46.72 | 96.00 |
| SC-0875 | Grace Lake | 100-096 | 96.00 | 66.03 | 64.00 | 0.0003 | 439 | 96.00 | 53.55 | 96.00 |
| SC-0880 | Grace Lake | 100-096 | 96.00 | 66.08 | 64.00 | -0.0002 | 288585 | 60.17 | 166.24 | 96.00 |
| SC-0900 | Grace Lake | 100-096 | 96.00 | 66.73 | 67.00 | 0.0029 | 87002 | 60.00 | 10.65 | 150.07 |
| SC-0910 | Grace Lake | 100-096 | 96.00 | 66.73 | 66.00 | -0.0002 | 138757 | 95.93 | 50.30 | 96.88 |
| SC-0920 | Grace Lake | 100-096 | 96.00 | 66.73 | 66.00 | -0.0002 | 1612618 | 60.08 | 538.84 | 95.98 |
| SC-0925 | Grace Lake | 100-096 | 60.56 | 78.79 | 76.00 | 0.0002 | 48853 | 60.08 | 63.78 | 60.56 |
| SC-0930 | Grace Lake | 100-096 | 96.00 | 66.74 | 69.20 | 0.0050 | 12734 | 60.51 | 94.79 | 60.55 |
| SC-0940 | Grace Lake | 100-096 | 60.39 | 69.34 | 70.00 | 0.0001 | 7068 | 60.49 | 94.68 | 60.51 |
| SC-0980 | Grace Lake | 100-096 | 60.49 | 77.24 | 74.00 | 0.0007 | 33711 | 60.08 | 137.29 | 60.49 |
| SC-0985 | Grace Lake | 100-096 | 60.49 | 77.25 | 73.00 | 0.0004 | 138791 | 60.08 | 377.30 | 63.19 |
| SC-0990 | Grace Lake | 100-096 | 68.21 | 72.66 | 79.00 | 0.0009 | 151 | 68.20 | 5.76 | 68.21 |
| SC-0995 | Grace Lake | 100-096 | 68.20 | 86.23 | 84.00 | 0.0002 | 129991 | 60.08 | 167.62 | 68.20 |
| SC-POND300 | Grace Lake | 100-096 | 72.17 | 58.78 | 59.00 | 0.0002 | 180874 | 60.17 | 143.67 | 60.90 |
| SC-POND301 | Grace Lake | 100-096 | 72.17 | 58.78 | 59.00 | 0.0001 | 180870 | 60.08 | 102.24 | 62.32 |

Grace Lake, Proposed Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0770 | 120 | A | 57 | 16.48 | 939.36 | |
| SC-0770 | 120 | D | 86 | 0.38 | 32.68 | |
| SC-0770 | 190 | A | 49 | 0.48 | 23.52 | |
| SC-0770 | 190 | D | 84 | 0.63 | 52.92 | |
| SC-0770 | 400 | A | 39 | 0.01 | 0.39 | |
| SC-0770 | 814 | D | 89 | 0.03 | 2.67 | |
| | | | Totals | 18.01 | 1051.54 | 58.39 |
| SC-0800A | 190 | A | 49 | 0.25 | 12.25 | |
| SC-0800A | 190 | D | 84 | 2.25 | 189.00 | |
| SC-0800A | 400 | A | 39 | 0.03 | 1.17 | |
| SC-0800A | 400 | D | 77 | 0.10 | 7.70 | |
| SC-0800A | 814 | D | 80 | 0.37 | 29.60 | |
| SC-0800A | 530a | D | 84 | 2.23 | 187.32 | |
| | | | Totals | 5.23 | 427.04 | 81.65 |
| SC-Pond300 | 400 | D | 80 | 3.43 | 274.40 | |
| SC-Pond300 | 110 | A | 51 | 5.59 | 285.09 | |
| SC-Pond300 | 530a | Water | 100 | 2.11 | 211.00 | |
| SC-Pond300 | 814 | A | 49 | 0.88 | 43.12 | |
| SC-Pond300 | 814 | - | 98 | 17.77 | 1741.46 | |
| | | | Totals | 29.78 | 2555.07 | 85.80 |
| SC-0810 | 120 | A | 57 | 0.69 | 39.33 | |
| SC-0810 | 120 | D | 86 | 0.07 | 6.02 | |
| SC-0810 | 190 | D | 84 | 0.01 | 0.84 | |
| SC-0810 | 814 | A | 49 | 0.29 | 14.21 | |
| SC-0810 | 814 | D | 80 | 0.16 | 12.80 | |
| | | | Totals | 1.22 | 73.20 | 60.00 |
| SC-Pond301 | 400 | A | 49 | 1.69 | 82.81 | |
| SC-Pond301 | 400 | D | 80 | 3.41 | 272.80 | |
| SC-Pond301 | 814 | - | 98 | 13.62 | 1334.76 | |
| | | | Totals | 18.72 | 1690.37 | 90.30 |

Grace Lake, Proposed Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0830 | 172 | A | 69 | 0.31 | 21.39 | |
| SC-0830 | 172 | D | 89 | 0.04 | 3.56 | |
| SC-0830 | 190 | A | 49 | 0.17 | 8.33 | |
| SC-0830 | 400 | A | 39 | 1.45 | 56.55 | |
| SC-0830 | 400 | D | 77 | 0.08 | 6.16 | |
| SC-0830 | 643 | A | 98 | 0.01 | 0.98 | |
| SC-0830 | 643 | D | 98 | 1.00 | 98.00 | |
| SC-0830 | 814 | A | 49 | 0.19 | 9.31 | |
| SC-0830 | 814 | D | 80 | 0.08 | 6.40 | |
| | | | Totals | 3.33 | 210.68 | 63.27 |
| SC-0840 | 110 | A | 51 | 31.31 | 1596.81 | |
| SC-0840 | 110 | D | 84 | 0.18 | 15.12 | |
| SC-0840 | 172 | A | 69 | 0.99 | 68.31 | |
| SC-0840 | 172 | D | 89 | 0.51 | 45.39 | |
| SC-0840 | 190 | A | 49 | 1.84 | 90.16 | |
| SC-0840 | 400 | A | 39 | 3.17 | 123.63 | |
| SC-0840 | 400 | D | 77 | 4.75 | 365.75 | |
| SC-0840 | 643 | D | 98 | 0.22 | 21.56 | |
| | | | Totals | 42.97 | 2326.73 | 54.15 |
| SC-0880 | 110 | A | 51 | 49.79 | 2539.29 | |
| SC-0880 | 110 | D | 84 | 2.2 | 184.80 | |
| SC-0880 | 140 | A | 89 | 2.37 | 210.93 | |
| SC-0880 | 172 | A | 69 | 3.54 | 244.26 | |
| SC-0880 | 190 | A | 49 | 2.78 | 136.22 | |
| SC-0880 | 190 | D | 84 | 1.05 | 88.20 | |
| SC-0880 | 400 | A | 39 | 0.9 | 35.10 | |
| SC-0880 | 814 | A | 49 | 1.90 | 93.10 | |
| SC-0880 | 814 | D | 80 | 0.42 | 33.60 | |
| | | | Totals | 64.95 | 3565.50 | 54.90 |

Grace Lake, Proposed Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0900A | 190 | A | 49 | 1.29 | 63.21 | |
| SC-0900A | 814 | D | 80 | 0.71 | 56.80 | |
| | | | Totals | 2.00 | 120.01 | 60.01 |
| | | | | | | |
| SC-0910 | 120 | A | 57 | 1.98 | 112.86 | |
| SC-0910 | 120 | D | 86 | 0.01 | 0.86 | |
| SC-0910 | 400 | A | 39 | 0.11 | 4.29 | |
| SC-0910 | 400 | D | 77 | 1.1 | 84.70 | |
| SC-0910 | 640 | A | 98 | 0.95 | 93.10 | |
| SC-0910 | 640 | D | 98 | 0.58 | 56.84 | |
| SC-0910 | 814 | A | 49 | 0.12 | 5.88 | |
| SC-0910 | 814 | D | 80 | 0.14 | 11.20 | |
| | | | Totals | 4.99 | 369.73 | 74.09 |
| | | | | | | |
| SC-0920 | 120 | A | 57 | 50.59 | 2883.63 | |
| SC-0920 | 120 | D | 86 | 0.65 | 55.90 | |
| SC-0920 | 170 | A | 69 | 0.36 | 24.84 | |
| SC-0920 | 190 | A | 49 | 0.43 | 21.07 | |
| SC-0920 | 190 | D | 84 | 0.08 | 6.72 | |
| SC-0920 | 400 | A | 39 | 4.69 | 182.91 | |
| SC-0920 | 400 | D | 77 | 1.66 | 127.82 | |
| SC-0920 | 520 | A | 100 | 0.54 | 54.00 | |
| SC-0920 | 520 | D | 100 | 21.51 | 2151.00 | |
| SC-0920 | 640 | A | 98 | 1.12 | 109.76 | |
| SC-0920 | 640 | D | 98 | 3.54 | 346.92 | |
| SC-0920 | 814 - EE W | - | 49 | 0.12 | 5.88 | |
| SC-0920 | 814 - EE W | - | 98 | 0.88 | 86.24 | |
| | | | Totals | 86.17 | 6056.69 | 70.29 |

Grace Lake, Proposed Conditions, April 2017
Summary of Computed Runoff Curve Numbers

Table No. 3.2.5

| Sub-Basin Name | FLUCCS Land Use Code | Soil HSG | Runoff CN | Acres | CN x Area | Weighted Runoff CN |
|---|---|---|---|---|---|---|
| SC-0925 | 120 | A | 57 | 13.12 | 747.84 | |
| SC-0925 | 170 | A | 69 | 0.12 | 8.28 | |
| | | | Totals | 13.24 | 756.12 | 57.11 |
| SC-0980A | 814 | A | 49 | 1.11 | 54.39 | |
| SC-0980A | 814 | - | 98 | 0.76 | 74.48 | |
| | | | Totals | 1.87 | 128.87 | 68.91 |
| SC-0980B | 120 | A | 57 | 5.83 | 332.31 | |
| | | | Totals | 5.83 | 332.31 | 57.00 |
| SC-0980C | 120 | A | 57 | 12.31 | 701.67 | |
| | | | Totals | 12.31 | 701.67 | 57.00 |
| SC-0985 | 120 | A | 57 | 45.09 | 2570.13 | |
| | | | Totals | 45.09 | 2570.13 | 57.00 |
| SC-0995 | 120 | A | 57 | 17.74 | 1011.41 | |
| SC-0995 | 170 | A | 69 | 16.01 | 1104.97 | |
| SC-0995 | 530b | A | 92 | 2.32 | 213.81 | |
| | | | Totals | 36.08 | 2330.18 | 64.58 |

| | |
|---|---|
| Total Project Area (acres) = | 391.79 |
| I-4 Pavement (acres)= | 33.03 |
| Additional Area (acres)= | 0.73 |
| New Impervious Area (acres)= | 17.09 |

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
================================================================================
==== Basins ====================================================================
================================================================================

         Name: SC-0770                Node: SC-0770               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                  Peaking Factor: 323.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 14.00
              Area(ac): 18.010              Time Shift(hrs): 0.00
          Curve Number: 58.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0800A               Node: SC-0800               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                  Peaking Factor: 256.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 13.00
              Area(ac): 5.230               Time Shift(hrs): 0.00
          Curve Number: 82.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0810                Node: SC-0810               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                  Peaking Factor: 323.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 11.00
              Area(ac): 1.220               Time Shift(hrs): 0.00
          Curve Number: 60.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0830                Node: SC-0830               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                  Peaking Factor: 256.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 20.00
              Area(ac): 3.330               Time Shift(hrs): 0.00
          Curve Number: 63.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0840                Node: SC-0840               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                  Peaking Factor: 256.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 21.00
              Area(ac): 42.970              Time Shift(hrs): 0.00
          Curve Number: 54.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0880                Node: SC-0880               Status: Onsite
        Group: Grace Lake             Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh256                  Peaking Factor: 256.0
          Rainfall File:                Storm Duration(hrs): 0.00
    Rainfall Amount(in): 0.000            Time of Conc(min): 27.00
              Area(ac): 64.950              Time Shift(hrs): 0.00
          Curve Number: 55.00           Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: SC-0900A               Node: SC-0900               Status: Onsite
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 10.00
Area(ac): 2.000 Time Shift(hrs): 0.00
Curve Number: 60.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

NEW FPC SITE

---

Name: SC-0910 Node: SC-0910 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh256 Peaking Factor: 256.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 11.00
Area(ac): 4.990 Time Shift(hrs): 0.00
Curve Number: 74.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0920 Node: SC-0920 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 22.00
Area(ac): 86.170 Time Shift(hrs): 0.00
Curve Number: 70.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0925 Node: SC-0925 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 15.00
Area(ac): 13.240 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980A Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 29.00
Area(ac): 1.870 Time Shift(hrs): 0.00
Curve Number: 69.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980B Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 15.00
Area(ac): 5.830 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0980C Node: SC-0980 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 20.00
Area(ac): 12.310 Time Shift(hrs): 0.00

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0985 Node: SC-0985 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 17.00
Area(ac): 45.090 Time Shift(hrs): 0.00
Curve Number: 57.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-0995 Node: SC-0995 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 23.00
Area(ac): 36.080 Time Shift(hrs): 0.00
Curve Number: 65.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: SC-POND300 Node: SC-POND300 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 31.00
Area(ac): 29.780 Time Shift(hrs): 0.00
Curve Number: 85.80 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

POND 300

---

Name: SC-POND301 Node: SC-POND301 Status: Onsite
Group: Grace Lake Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Storm Duration(hrs): 0.00
Rainfall Amount(in): 0.000 Time of Conc(min): 25.00
Area(ac): 18.720 Time Shift(hrs): 0.00
Curve Number: 90.30 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

POND 301

==========
==== Nodes ==========
==========

Name: SC-0750 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: Grace Lake Warn Stage(ft): 54.000
Type: Time/Stage

ASSUMED TAILWATER AT THE CROWN OF THE OUTFALL PIPE THAT DISCHARGES TO THE BOLLING FARMS SUBDIVISION WETLAND AND POND.
SURVEYED PIPE INVERT ELEVATION IS 48.96 FT, NAVD (SSMC SURVEY DATED DEC. 2007).

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 52.000 |
| 180.00 | 52.000 |

---

Name: SC-0760 Base Flow(cfs): 0.000 Init Stage(ft): 53.080
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

CURB INLET STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY.
PARAMETERS WERE OBTAINED FROM SURVEY DATA BY SSMC (DATED DEC. 2007 AND JULY 2013).

| Stage(ft) | Area(ac) |
|---|---|

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 53.080 | 0.0010 |
| 58.780 | 0.0010 |

Name: SC-0770 Base Flow(cfs): 0.000 Init Stage(ft): 57.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

NORTHRIDGE SWALE LOCATED SOUTH OF THE NORTHRIDGE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 55.900 | 0.0100 |
| 57.000 | 0.4100 |
| 58.000 | 0.7700 |

Name: SC-0780 Base Flow(cfs): 0.000 Init Stage(ft): 64.240
Group: Grace Lake Warn Stage(ft): 67.270
Type: Stage/Area

DIVERSION STRUCTURE. DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985). REFER TO STRUCTURE C-1.

| Stage(ft) | Area(ac) |
|---|---|
| 64.240 | 0.0010 |
| 67.570 | 0.0010 |

Name: SC-0790 Base Flow(cfs): 0.000 Init Stage(ft): 64.000
Group: Grace Lake Warn Stage(ft): 67.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED NORTH OF GRACE LAKE, SOUTH OF NORTH RIDGE DR., EAST OF GRACE VIEW CT., AND WEST OF NORTH RIDGE
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 64.000 | 0.1800 |
| 65.000 | 0.2300 |
| 66.000 | 0.2900 |
| 67.000 | 0.3900 |

Name: SC-0800 Base Flow(cfs): 0.000 Init Stage(ft): 47.000
Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

NORTHRIDE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.9700 |
| 48.000 | 1.9200 |
| 49.000 | 2.3000 |
| 50.000 | 2.6300 |
| 51.000 | 2.9200 |
| 52.000 | 3.1800 |
| 53.000 | 3.4500 |
| 54.000 | 3.7300 |
| 55.000 | 4.0500 |
| 56.000 | 4.3500 |
| 57.000 | 4.6800 |
| 58.000 | 5.0600 |
| 59.000 | 5.2000 |

Name: SC-0810 Base Flow(cfs): 0.000 Init Stage(ft): 52.330
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 52.330 | 0.0010 |
| 55.000 | 0.0030 |
| 56.000 | 0.0060 |
| 57.000 | 0.0140 |
| 58.000 | 0.0300 |
| 59.000 | 0.0500 |

Name: SC-0830 Base Flow(cfs): 0.000 Init Stage(ft): 52.890

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY WEST (UPSTREAM SIDE) OF THE I-4 CULVERT CROSSING (NORTH PIPE)

| Stage(ft) | Area(ac) |
|---|---|
| 51.400 | 0.0010 |
| 53.000 | 0.0800 |
| 54.000 | 0.2300 |
| 55.000 | 0.4000 |
| 56.000 | 0.4900 |
| 57.000 | 0.5500 |
| 58.000 | 0.6000 |
| 59.000 | 0.6400 |
| 60.000 | 0.6900 |

---

Name: SC-0840 Base Flow(cfs): 0.000 Init Stage(ft): 50.000
Group: Grace Lake Warn Stage(ft): 58.000
Type: Stage/Area

DEPRESSIONAL AREA NORTH OF DIXON ROAD AND EAST OF SUNSHINE TREE BOULEVARD.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHI MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 47.000 | 0.0200 |
| 48.000 | 0.0500 |
| 49.000 | 0.0900 |
| 50.000 | 0.1200 |
| 51.000 | 0.3400 |
| 52.000 | 0.5400 |
| 53.000 | 0.7700 |
| 54.000 | 1.1800 |
| 55.000 | 1.8600 |
| 56.000 | 2.6300 |
| 57.000 | 3.2900 |
| 58.000 | 3.9900 |
| 59.000 | 4.5400 |
| 60.000 | 5.3500 |

---

Name: SC-0850 Base Flow(cfs): 0.000 Init Stage(ft): 56.690
Group: Grace Lake Warn Stage(ft): 59.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 56.650 | 0.0010 |
| 59.500 | 0.0010 |

---

Name: SC-0860 Base Flow(cfs): 0.000 Init Stage(ft): 56.920
Group: Grace Lake Warn Stage(ft): 61.550
Type: Stage/Area

DITCH BOTTOM INLET LOCATED AT THE SOUTHEAST CORNER OF THE INTERSECTION OF DIXON RD. AND SUNSHINE TREE BLVD.

| Stage(ft) | Area(ac) |
|---|---|
| 56.920 | 0.0010 |
| 62.650 | 0.0010 |

---

Name: SC-0870 Base Flow(cfs): 0.000 Init Stage(ft): 59.620
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.
CURB INLET LOCATED ALONG THE SUNSHINE TREE BLVD EAST RIGHT-OF-WAY.

| Stage(ft) | Area(ac) |
|---|---|
| 59.620 | 0.0010 |
| 67.000 | 0.0010 |

---

Name: SC-0875 Base Flow(cfs): 0.000 Init Stage(ft): 59.710
Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| Stage(ft) | Area(ac) |
|---|---|
| 59.710 | 0.0100 |
| 64.000 | 0.0100 |

Name: SC-0880 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 64.000
Type: Stage/Area

DEPRESSIONAL AREA SOUTH OF THE ONE CHURCH (SOCCER FIELDS)
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 57.100 | 0.0010 |
| 58.000 | 0.0020 |
| 59.000 | 0.0110 |
| 60.000 | 0.0400 |
| 61.000 | 0.1700 |
| 62.000 | 1.3100 |
| 63.000 | 2.7800 |
| 64.000 | 3.6800 |
| 65.000 | 5.1500 |
| 66.000 | 6.5300 |
| 67.000 | 7.7500 |

Name: SC-0900 Base Flow(cfs): 0.000 Init Stage(ft): 61.000
Group: Grace Lake Warn Stage(ft): 67.000
Type: Stage/Area

NEW FPC SITE

| Stage(ft) | Area(ac) |
|---|---|
| 61.000 | 1.8100 |
| 62.000 | 1.8900 |
| 63.000 | 1.9500 |
| 64.000 | 1.9700 |
| 65.000 | 1.9800 |
| 66.000 | 1.9900 |
| 67.000 | 2.0000 |

Name: SC-0910 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

DEPRESSIONAL AREA IMMEDIATELY EAST OF THE SOUTH I-4 CROSS CULVERT, ADJACENT TO GRACE LAKE.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP.

| Stage(ft) | Area(ac) |
|---|---|
| 55.000 | 0.1700 |
| 56.000 | 0.3000 |
| 57.000 | 0.4500 |
| 58.000 | 0.6600 |
| 59.000 | 0.9600 |
| 60.000 | 1.4100 |
| 61.000 | 1.7800 |
| 62.000 | 2.1200 |
| 63.000 | 2.4800 |
| 64.000 | 2.6900 |
| 65.000 | 2.9200 |
| 66.000 | 3.0900 |
| 67.000 | 3.2200 |

Name: SC-0920 Base Flow(cfs): 0.000 Init Stage(ft): 62.600
Group: Grace Lake Warn Stage(ft): 66.000
Type: Stage/Area

GRACE LAKE.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 33-54 FT, NAVD, WAS OBTAINED FROM THE SURVEY PREPARED BY SSMC, DATED DEC. 2007.
STAGE-AREA RELATIONSHIP BETWEEN ELEVATIONS 55-67, NAVD, IS BASED ON THE 1-FT TOPOGRAPHY.
INITIAL STAGE IS BASED ON THE GRACE LAKE "NORMAL" HYDROPERIOD ELEVATION BETWEEN ELEVATION 58-63 FT, NAVD
(REFER TO ENGINEERING REPORT FROM DEVO ENGINEERING).

| Stage(ft) | Area(ac) |
|---|---|

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 33.000 | 0.0000 |
| 34.000 | 0.0005 |
| 35.000 | 0.0014 |
| 36.000 | 0.0028 |
| 37.000 | 0.0053 |
| 38.000 | 0.0140 |
| 39.000 | 0.0450 |
| 40.000 | 0.0980 |
| 41.000 | 0.1830 |
| 42.000 | 0.3010 |
| 43.000 | 0.4270 |
| 44.000 | 0.5320 |
| 45.000 | 0.6430 |
| 46.000 | 0.7540 |
| 47.000 | 0.8640 |
| 48.000 | 1.1900 |
| 49.000 | 3.6300 |
| 50.000 | 5.8800 |
| 51.000 | 8.1300 |
| 52.000 | 10.5200 |
| 53.000 | 12.8800 |
| 54.000 | 14.9400 |
| 55.000 | 16.6400 |
| 56.000 | 18.3800 |
| 57.000 | 20.0700 |
| 58.000 | 22.0500 |
| 59.000 | 24.0900 |
| 60.000 | 26.0500 |
| 61.000 | 27.8500 |
| 62.000 | 29.5900 |
| 63.000 | 31.4200 |
| 64.000 | 33.1400 |
| 65.000 | 34.4100 |
| 66.000 | 35.7500 |
| 67.000 | 37.3700 |

---

Name: SC-0925 Base Flow(cfs): 0.000 Init Stage(ft): 68.000
Group: Grace Lake Warn Stage(ft): 76.000
Type: Stage/Area

SMALL DRY RETENTION POND LOCATED ALONG NORTH RIDGE LAKE CIRCLE, SOUTH OF NORTH RIDGE DR.
STAGE-AREA RELATIONSHIP WAS OBTAINED FROM THE 1-FT TOPOGRAPHIC MAPS.

| Stage(ft) | Area(ac) |
|---|---|
| 68.000 | 0.0300 |
| 69.000 | 0.0800 |
| 70.000 | 0.1000 |
| 71.000 | 0.1300 |
| 72.000 | 0.1600 |
| 73.000 | 0.1800 |
| 74.000 | 0.2200 |
| 75.000 | 0.2500 |
| 76.000 | 0.2900 |
| 77.000 | 0.5100 |
| 78.000 | 0.8700 |
| 79.000 | 1.1900 |

---

Name: SC-0930 Base Flow(cfs): 0.000 Init Stage(ft): 61.000
Group: Grace Lake Warn Stage(ft): 69.200
Type: Stage/Area

NODE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO NODE GHOST 3.

| Stage(ft) | Area(ac) |
|---|---|
| 61.000 | 0.0100 |
| 69.200 | 0.0100 |

---

Name: SC-0940 Base Flow(cfs): 0.000 Init Stage(ft): 66.500
Group: Grace Lake Warn Stage(ft): 70.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 66.500 | 0.0100 |
| 70.000 | 0.0100 |

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-------------------------------------------------------------------------------------------
      Name: SC-0980             Base Flow(cfs): 0.000          Init Stage(ft): 68.100
     Group: Grace Lake                                       Warn Stage(ft): 74.000
      Type: Stage/Area
```

STAGE-AREA OBTAINED FROM THE 1-FT TOPO MAPS
INITIAL STAGE IS BASED ON THE DOWNSTREAM PIPE INVERT ELEVATION

| Stage(ft) | Area(ac) |
|---|---|
| 67.000 | 0.0100 |
| 70.000 | 0.0150 |
| 71.000 | 0.0200 |
| 72.000 | 0.1000 |
| 73.000 | 0.1800 |
| 74.000 | 0.3200 |

```
-------------------------------------------------------------------------------------------
      Name: SC-0985             Base Flow(cfs): 0.000          Init Stage(ft): 68.100
     Group: Grace Lake                                       Warn Stage(ft): 73.000
      Type: Stage/Area
```

PENELOPE POND (POND LOCATED EAST OF PENELOPE DR AND NORTH OF HICKORY TREE RD)
STAGE-AREA RELATIONSHIP OBTAINED FROM THE 1-FT TOPOGRAPHIC MAP
INITIAL STAGE WAS ESTIMATED BASED ON THE DOWNSTREAM PIPE INVERT JUST SOUTH OF EE WILLIAMSON RD

| Stage(ft) | Area(ac) |
|---|---|
| 66.000 | 0.1100 |
| 71.000 | 0.2200 |
| 72.000 | 0.3400 |
| 73.000 | 0.5900 |
| 74.000 | 1.2000 |

```
-------------------------------------------------------------------------------------------
      Name: SC-0990             Base Flow(cfs): 0.000          Init Stage(ft): 71.000
     Group: Grace Lake                                       Warn Stage(ft): 79.000
      Type: Stage/Area
```

EMERGENCY OVERFLOW MANHOLE

| Stage(ft) | Area(ac) |
|---|---|
| 71.000 | 0.0010 |
| 79.000 | 0.0010 |

```
-------------------------------------------------------------------------------------------
      Name: SC-0995             Base Flow(cfs): 0.000          Init Stage(ft): 77.500
     Group: Grace Lake                                       Warn Stage(ft): 84.000
      Type: Stage/Area
```

WET DETENTION POND THAT SERVES THE WOODLAND ELEMENTARY SCHOOL, THE BELLA TUSCANY SUBDIVISION AND A PORTION OF EE WILLIAMSON ROAD
POND WAS EXPANDED TO PROVIDE WATER QUALITY TREATMENT AND ATTENUATION FROM THE BELLA TUSCANY SUBDIVISION (REFER TO THE SJRMD PERM
STAGE-AREA RELATIONSHIP AND INITIAL STAGE WAS OBTAINED FROM THE PERMITTED PARAMETERS.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO
SINCE THE ORIGINAL BELLA TUSCANY SUBDIVISION PLANS ARE REFERENCED TO THE NGVD VERTICAL DATUM (CONVERSION USED:  NAVD ELEV. = NGV

| Stage(ft) | Area(ac) |
|---|---|
| 77.500 | 1.8600 |
| 78.000 | 1.9300 |
| 79.000 | 2.0000 |
| 80.000 | 2.0800 |
| 81.000 | 2.2200 |
| 82.000 | 2.3600 |
| 83.000 | 2.5000 |
| 84.000 | 2.6500 |
| 85.000 | 2.8000 |

```
-------------------------------------------------------------------------------------------
      Name: SC-POND300          Base Flow(cfs): 0.000          Init Stage(ft): 49.000
     Group: Grace Lake                                       Warn Stage(ft): 59.000
      Type: Stage/Area
```

NORTHRIDE DEPRESSIONAL AREA

| Stage(ft) | Area(ac) |
|---|---|
| 49.000 | 2.1100 |
| 57.000 | 3.1100 |
| 57.010 | 3.5700 |
| 58.000 | 3.8800 |
| 59.000 | 4.2300 |

```
-------------------------------------------------------------------------------------------
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-POND301 Base Flow(cfs): 0.000 Init Stage(ft): 52.000
Group: Grace Lake Warn Stage(ft): 59.000
Type: Stage/Area

POND 301

| Stage(ft) | Area(ac) |
|---|---|
| 52.000 | 2.8300 |
| 57.000 | 3.5300 |
| 57.010 | 4.0200 |
| 58.000 | 4.0900 |
| 59.000 | 4.1700 |

==========
==== Cross Sections ==========
==========

Name: SC-0810_W1 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE DEPRESSIONAL AREA

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 58.400 | 0.000000 |
| 11.900 | 57.800 | 0.000000 |
| 31.100 | 57.200 | 0.000000 |
| 43.400 | 57.800 | 0.000000 |
| 63.200 | 58.700 | 0.000000 |

---

Name: SC-0810_W2 Group: Grace Lake
Encroachment: No

OVERLAND OVERTOPPING CROSS SECTION FROM I-4 CULVERT CROSSING (NORTH PIPE) TO THE NORTHRIDGE SWALE

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 59.300 | 0.000000 |
| 30.700 | 59.000 | 0.000000 |
| 68.400 | 58.500 | 0.000000 |
| 106.100 | 58.700 | 0.000000 |
| 133.700 | 59.300 | 0.000000 |

---

Name: SC-0840_W Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 60.000 | 0.000000 |
| 12.000 | 59.000 | 0.000000 |
| 18.700 | 58.000 | 0.000000 |
| 25.300 | 57.000 | 0.000000 |
| 32.000 | 56.000 | 0.000000 |
| 51.900 | 55.000 | 0.000000 |
| 103.800 | 54.000 | 0.000000 |
| 128.000 | 54.000 | 0.000000 |
| 149.600 | 54.000 | 0.000000 |
| 194.000 | 55.000 | 0.000000 |
| 215.100 | 56.000 | 0.000000 |
| 230.500 | 57.000 | 0.000000 |
| 241.100 | 58.000 | 0.000000 |
| 251.500 | 59.000 | 0.000000 |
| 262.500 | 60.000 | 0.000000 |

---

Name: SC-0875_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 36.600 | 66.000 | 0.000000 |
| 44.200 | 65.500 | 0.000000 |
| 51.800 | 66.000 | 0.000000 |
| 78.700 | 67.000 | 0.000000 |

---

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Name: SC-0880_W Group: Grace Lake
Encroachment: No

CROSS SECTION DATA OBTAINED FROM SSMC SURVEY, DATED JULY 2013.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 63.300 | 0.000000 |
| 9.200 | 62.600 | 0.000000 |
| 24.700 | 63.400 | 0.000000 |

---

Name: SC-0920_W1 Group: Grace Lake
Encroachment: No

CROSS SECTION DATA ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 67.000 | 0.000000 |
| 20.300 | 66.000 | 0.000000 |
| 45.300 | 65.000 | 0.000000 |
| 53.000 | 64.000 | 0.000000 |
| 63.600 | 63.000 | 0.000000 |
| 80.700 | 62.000 | 0.000000 |
| 93.800 | 61.000 | 0.000000 |
| 106.600 | 60.000 | 0.000000 |
| 139.200 | 59.500 | 0.000000 |
| 168.200 | 60.000 | 0.000000 |
| 194.200 | 61.000 | 0.000000 |
| 206.100 | 62.000 | 0.000000 |
| 224.900 | 63.000 | 0.000000 |
| 240.600 | 64.000 | 0.000000 |
| 249.600 | 65.000 | 0.000000 |
| 258.000 | 66.000 | 0.000000 |
| 277.100 | 67.000 | 0.000000 |

---

Name: SC-0920_W3 Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 66.900 | 0.000000 |
| 24.000 | 66.800 | 0.000000 |
| 47.000 | 67.100 | 0.000000 |

---

Name: SC-0930_DS Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 64.000 | 0.011000 |
| 28.100 | 63.000 | 0.011000 |
| 28.900 | 62.000 | 0.011000 |
| 29.500 | 61.000 | 0.011000 |
| 32.000 | 60.500 | 0.011000 |
| 38.000 | 60.500 | 0.011000 |
| 41.400 | 61.000 | 0.011000 |
| 43.200 | 62.000 | 0.011000 |
| 44.800 | 63.000 | 0.011000 |
| 77.900 | 64.000 | 0.011000 |

---

Name: SC-0940_DS Group: Grace Lake
Encroachment: No

| Station(ft) | Elevation(ft) | Manning's N |
|---|---|---|
| 0.000 | 69.200 | 0.100000 |
| 0.100 | 64.500 | 0.100000 |
| 2.100 | 64.500 | 0.100000 |
| 12.600 | 61.000 | 0.100000 |
| 17.600 | 61.000 | 0.100000 |
| 27.800 | 64.400 | 0.100000 |
| 40.800 | 66.000 | 0.100000 |

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-----------------------------------------------------------------
             Name: SC-0980_DS                  Group: Grace Lake
      Encroachment: No


    Station(ft)   Elevation(ft)     Manning's N
--------------- --------------- ---------------
          0.000          70.050        0.100000
          2.000          70.050        0.100000
         12.650          66.500        0.100000
         17.650          66.500        0.100000
         32.650          71.500        0.100000

================================================================================================
==== Pipes =====================================================================================
================================================================================================

         Name: SC-0760-P           From Node: SC-0760           Length(ft): 534.00
        Group: Grace Lake            To Node: SC-0750                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 36.00          36.00                     Entrance Loss Coef: 0.00
     Rise(in): 36.00          36.00                         Exit Loss Coef: 1.00
   Invert(ft): 53.080         48.960                        Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None


Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY DATA BY SSMC, DATED DEC. 2007.

-------------------------------------------------------------------------------------------------
         Name: SC-0790-P           From Node: SC-0790           Length(ft): 30.00
        Group: Grace Lake            To Node: SC-0780                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 18.00          18.00                     Entrance Loss Coef: 0.50
     Rise(in): 18.00          18.00                         Exit Loss Coef: 0.00
   Invert(ft): 64.050         64.240                        Bend Loss Coef: 0.00
  Manning's N: 0.013000       0.013000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None


Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILTS (DATED 05/19/1985).
ORIGINAL PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND HAD TO BE CONVERTED TO THE NAVD VERTICAL DATUM.
ELEVATIONS SHOWN CORRESPOND TO THE NAVD DATUM.

-------------------------------------------------------------------------------------------------
         Name: SC-0830-P           From Node: SC-0830           Length(ft): 273.00
        Group: Grace Lake            To Node: SC-0810                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                             Flow: Both
     Span(in): 54.00          54.00                     Entrance Loss Coef: 0.50
     Rise(in): 54.00          54.00                         Exit Loss Coef: 0.00
   Invert(ft): 51.400         52.330                        Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                     Stabilizer Option: None


Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (NORTH CROSSING)
UPSTREAM (WEST END) INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.
DOWNSTREAM (EAST END) INVERT ELEVATION WAS REVISED BASED ON SURVEY PERFORMED BY SSMC, DATED JULY 2013.

---

| | | | | |
|---|---|---|---|---|
| Name: | SC-0850-P | From Node: | SC-0850 | Length(ft): 66.00 |
| Group: | Grace Lake | To Node: | SC-0840 | Count: 1 |
| | | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | | Flow: Both |
| Span(in): | 36.00 | 36.00 | | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | | Exit Loss Coef: 0.00 |
| Invert(ft): | 56.690 | 56.270 | | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | | |
|---|---|---|---|---|
| Name: | SC-0860-P | From Node: | SC-0860 | Length(ft): 62.00 |
| Group: | Grace Lake | To Node: | SC-0850 | Count: 1 |
| | | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | | Flow: Both |
| Span(in): | 36.00 | 36.00 | | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | | Exit Loss Coef: 0.00 |
| Invert(ft): | 56.920 | 56.650 | | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | | |
|---|---|---|---|---|
| Name: | SC-0870-P | From Node: | SC-0870 | Length(ft): 499.00 |
| Group: | Grace Lake | To Node: | SC-0860 | Count: 1 |
| | | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | | Flow: Both |
| Span(in): | 36.00 | 36.00 | | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | | Exit Loss Coef: 0.00 |
| Invert(ft): | 59.620 | 57.050 | | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

---

| | | | | |
|---|---|---|---|---|
| Name: | SC-0875-P | From Node: | SC-0875 | Length(ft): 47.00 |
| Group: | Grace Lake | To Node: | SC-0870 | Count: 1 |
| | | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | | Flow: Both |
| Span(in): | 36.00 | 36.00 | | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | | Exit Loss Coef: 0.00 |
| Invert(ft): | 59.710 | 59.650 | | Bend Loss Coef: 0.00 |

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | | | |
|---|---|---|---|
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PARAMETERS OBTAINED FROM SURVEY FROM SSMC, DATED JULY 2013.

| | | | |
|---|---|---|---|
| Name: | SC-0910-P | From Node: SC-0910 | Length(ft): 272.00 |
| Group: | Grace Lake | To Node: SC-0880 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 48.00 | 48.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 48.00 | 48.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 57.420 | 57.100 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CULVERT CROSSING I-4 (SOUTH CROSSING)
INVERT DATA WAS OBTAINED FROM SURVEY PERFORMED BY SSMC, DATED DEC. 2007.

| | | | |
|---|---|---|---|
| Name: | SC-0980-P2 | From Node: SC-0980 | Length(ft): 181.00 |
| Group: | Grace Lake | To Node: SC-0940 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 36.00 | 36.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 36.00 | 36.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 68.100 | 66.500 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

PIPE DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER HDR PIPE LINK EEWilliams_24.
SURVEY DATA PROVIDED BY SSMC (DATED DEC. 2007)

| | | | |
|---|---|---|---|
| Name: | SC-0985-P | From Node: SC-0985 | Length(ft): 230.00 |
| Group: | Grace Lake | To Node: SC-0980 | Count: 1 |
| | | | Friction Equation: Automatic |
| | UPSTREAM | DOWNSTREAM | Solution Algorithm: Most Restrictive |
| Geometry: | Circular | Circular | Flow: Both |
| Span(in): | 42.00 | 42.00 | Entrance Loss Coef: 0.50 |
| Rise(in): | 42.00 | 42.00 | Exit Loss Coef: 0.00 |
| Invert(ft): | 67.000 | 67.000 | Bend Loss Coef: 0.00 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Stabilizer Option: None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

PIPE SIZE AND INVERT DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR, IN
SUPPORT OF THE GRACE LAKE SINKHOLE ANALYSIS REPORT (DATED APRIL 2008).
IT APPEARS THAT THIS PIPE SEGMENT WAS NOT SURVEYED
PIPE LENGTH WAS ADJUSTED TO MATCH FIELD OBSERVATIONS

```
-------------------------------------------------------------------------------------------------
         Name: SC-0990-P           From Node: SC-0990           Length(ft): 219.00
        Group: Grace Lake            To Node: SC-0920                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                 Solution Algorithm: Most Restrictive
     Geometry: Circular       Circular                          Flow: Both
     Span(in): 15.00          15.00                      Entrance Loss Coef: 0.50
     Rise(in): 15.00          15.00                          Exit Loss Coef: 0.00
   Invert(ft): 71.000         52.000                         Bend Loss Coef: 0.00
  Manning's N: 0.012000       0.012000                     Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                          Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                       Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE (FINAL PIPE SEGMENT).
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DATUM (

```
-------------------------------------------------------------------------------------------------
         Name: SC-1000-P           From Node: SC-1000           Length(ft): 112.00
        Group: Grace Lake            To Node: SC-0985                Count: 1
                                                          Friction Equation: Automatic
               UPSTREAM       DOWNSTREAM                 Solution Algorithm: Most Restrictive
     Geometry: Arch           Arch                              Flow: Both
     Span(in): 95.00          95.00                      Entrance Loss Coef: 0.50
     Rise(in): 67.00          67.00                          Exit Loss Coef: 0.00
   Invert(ft): 68.620         68.070                         Bend Loss Coef: 0.00
  Manning's N: 0.024000       0.024000                     Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                          Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                       Stabilizer Option: None
```

Upstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

Downstream FHWA Inlet Edge Description:
Pipe Arch 18" Corner Radius CM: 90° headwall

CULVERT CROSSING HICKORY DITCH ROAD
INVERT DATA OBTAINED FROM THE CITY OF LONGWOOD STORMWATER MASTERPLAN
PIPE SIZE WAS ADJUSTED TO REFLECT THE NEAREST STANDARD SIZE FOR AN ARCH PIPE BASED ON SURVEYED DIMENSIONS

```
================================================================================
==== Channels ==================================================================
================================================================================

          Name: SC-0930-C           From Node: SC-0930           Length(ft): 106.00
         Group: Grace Lake            To Node: SC-0920                Count: 1

                UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
      Geometry: Irregular      Irregular                 Solution Algorithm: Automatic
    Invert(ft): 61.000         60.500                          Flow: Both
 TClpInitZ(ft): 9999.000       9999.000                  Contraction Coef: 0.100
   Manning's N:                                             Expansion Coef: 0.300
  Top Clip(ft):                                         Entrance Loss Coef: 0.000
  Bot Clip(ft):                                             Exit Loss Coef: 0.000
     Main XSec: SC-0940_DS     SC-0930_DS                 Outlet Ctrl Spec: Use dc or tw
  AuxElev1(ft): 0.000          0.000                       Inlet Ctrl Spec: Use dc
     Aux XSec1:                                          Stabilizer Option: None
  AuxElev2(ft): 0.000          0.000
     Aux XSec2:
 Top Width(ft):
     Depth(ft):
 Bot Width(ft):
  LtSdSlp(h/v):
  RtSdSlp(h/v):
```

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE
LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 3 AND
CROSS SECTIONS I-4 Chan2DS3US (UPSTREAM) AND I-4 Chan3DS (DOWNSTREAM)

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
-------------------------------------------------------------------------------------------------
         Name: SC-0940-C           From Node: SC-0940           Length(ft): 550.00
        Group: Grace Lake            To Node: SC-0930                Count: 1

               UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
     Geometry: Irregular      Irregular                Solution Algorithm: Automatic
   Invert(ft): 66.500         61.000                                Flow: Both
TClpInitZ(ft): 9999.000       9999.000                Contraction Coef: 0.100
  Manning's N:                                            Expansion Coef: 0.300
 Top Clip(ft):                                        Entrance Loss Coef: 0.000
 Bot Clip(ft):                                            Exit Loss Coef: 0.000
    Main XSec: SC-0980_DS     SC-0940_DS               Outlet Ctrl Spec: Use dc or tw
 AuxElev1(ft): 0.000          0.000                     Inlet Ctrl Spec: Use dc
    Aux XSec1:                                         Stabilizer Option: None
 AuxElev2(ft): 0.000          0.000
    Aux XSec2:
Top Width(ft):
    Depth(ft):
Bot Width(ft):
 LtSdSlp(h/v):
 RtSdSlp(h/v):
```

CHANNEL DATA WAS OBTAINED FROM THE PROPOSED CONDITIONS ICPR MODEL PREPARED BY HDR IN SUPPORT OF THE LAKE GRACE SINKHOLE REPAIR ANALYSIS REPORT (DATED APRIL 2008). REFER TO CHANNEL LINK I-4 Channel 2 AND CROSS SECTIONS I-4 Chan1DS2US (UPSTREAM) AND I-4 Chan2DS3US (DOWNSTREAM)

==========
==== Drop Structures ==========
==========

```
        Name: S-O300              From Node: SC-POND300         Length(ft): 351.00
       Group: Grace Lake            To Node: SC-0800                Count: 1

              UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
    Geometry: Circular       Circular                 Solution Algorithm: Most Restrictive
    Span(in): 18.00          18.00                                 Flow: Both
    Rise(in): 18.00          18.00                    Entrance Loss Coef: 0.500
  Invert(ft): 49.000         48.700                       Exit Loss Coef: 0.000
 Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
Top Clip(in): 0.000          0.000                       Inlet Ctrl Spec: Use dc
Bot Clip(in): 0.000          0.000                         Solution Incs: 10
```

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

POND 300 OUTFALL

```
*** Weir 1 of 2 for Drop Structure S-O300 ***
                                                                                    TABLE
                 Count: 1                       Bottom Clip(in): 0.000
                  Type: Vertical: Mavis            Top Clip(in): 0.000
                  Flow: Both                    Weir Disc Coef: 3.200
             Geometry: Rectangular           Orifice Disc Coef: 0.600

             Span(in): 2.00                        Invert(ft): 50.670
             Rise(in): 63.96                Control Elev(ft): 50.670

*** Weir 2 of 2 for Drop Structure S-O300 ***
                                                                                    TABLE
                 Count: 1                       Bottom Clip(in): 0.000
                  Type: Vertical: Mavis            Top Clip(in): 0.000
                  Flow: Both                    Weir Disc Coef: 3.200
             Geometry: Circular              Orifice Disc Coef: 0.600

             Span(in): 5.25                        Invert(ft): 49.000
             Rise(in): 5.25                 Control Elev(ft): 49.000


-------------------------------------------------------------------------------------------------
        Name: S-O301              From Node: SC-POND301         Length(ft): 380.00
       Group: Grace Lake            To Node: SC-0810                Count: 1

              UPSTREAM       DOWNSTREAM                Friction Equation: Automatic
    Geometry: Circular       Circular                 Solution Algorithm: Most Restrictive
    Span(in): 18.00          18.00                                 Flow: Both
    Rise(in): 18.00          18.00                    Entrance Loss Coef: 0.500
  Invert(ft): 53.900         53.680                       Exit Loss Coef: 0.000
 Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
Top Clip(in): 0.000          0.000                       Inlet Ctrl Spec: Use dc
Bot Clip(in): 0.000          0.000                         Solution Incs: 10
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

POND 300 OUTFALL

*** Weir 1 of 1 for Drop Structure S-O301 ***

| | | | |
|---|---|---|---|
| | | | TABLE |
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 49.00 | Invert(ft): | 55.980 |
| Rise(in): | 37.00 | Control Elev(ft): | 55.980 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0770-D1 | From Node: SC-0770 | Length(ft): 17.00 |
| Group: | Grace Lake | To Node: SC-0760 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 36.00 | 36.00 | Flow: | Both |
| Rise(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 53.250 | 53.080 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DITCH BOTTOM STRUCTURE LOCATED ALONG THE NORTH RIDGE LAKE CIRCLE WEST RIGHT-OF-WAY, NORTH OF NORTH RIDGE DRIVE (TRACT "C" OVERFL

*** Weir 1 of 4 for Drop Structure SC-0770-D1 ***

| | | | |
|---|---|---|---|
| | | | TABLE |
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 10.20 | Invert(ft): | 57.170 |
| Rise(in): | 33.60 | Control Elev(ft): | 57.170 |

*** Weir 2 of 4 for Drop Structure SC-0770-D1 ***

| | | | |
|---|---|---|---|
| | | | TABLE |
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.60 | Invert(ft): | 57.180 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.180 |

*** Weir 3 of 4 for Drop Structure SC-0770-D1 ***

| | | | |
|---|---|---|---|
| | | | TABLE |
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 9.00 | Invert(ft): | 57.170 |
| Rise(in): | 34.80 | Control Elev(ft): | 57.170 |

*** Weir 4 of 4 for Drop Structure SC-0770-D1 ***

| | | | |
|---|---|---|---|
| | | | TABLE |
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 58.180 |
| Rise(in): | 54.00 | Control Elev(ft): | 58.180 |

---

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
         Name: SC-0770-D2          From Node: SC-0770           Length(ft): 70.00
        Group: Grace Lake            To Node: SC-0800                Count: 1

               UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                  Solution Algorithm: Most Restrictive
     Span(in): 18.00          18.00                                Flow: Both
     Rise(in): 18.00          18.00                     Entrance Loss Coef: 0.500
   Invert(ft): 49.660         49.140                        Exit Loss Coef: 0.000
  Manning's N: 0.024000       0.024000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                          Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE LOCATED WITHIN THE NORTHRIDGE SWALE.
REFER TO SSMC SURVEY DATED DEC. 2007 AND THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED  05/19/1985).
IT APPEARS THAT SURVEY FROM SSMC DID NOT PICK UP THE WEIR CUT-OUT (SLOT).  HOWEVER, AS BUILTS PROVIDE AN INVERT ELEVATION FOR TH

*** Weir 1 of 2 for Drop Structure SC-0770-D2 ***
                                                                                TABLE
                  Count: 1                       Bottom Clip(in): 0.000
                   Type: Vertical: Mavis            Top Clip(in): 0.000
                   Flow: Both                     Weir Disc Coef: 3.200
               Geometry: Rectangular            Orifice Disc Coef: 0.600

               Span(in): 30.00                        Invert(ft): 56.820
               Rise(in): 15.50                   Control Elev(ft): 56.820

*** Weir 2 of 2 for Drop Structure SC-0770-D2 ***
                                                                                TABLE
                  Count: 1                       Bottom Clip(in): 0.000
                   Type: Horizontal                 Top Clip(in): 0.000
                   Flow: Both                     Weir Disc Coef: 3.200
               Geometry: Rectangular            Orifice Disc Coef: 0.600

               Span(in): 37.00                        Invert(ft): 58.360
               Rise(in): 49.00                   Control Elev(ft): 58.360


-------------------------------------------------------------------------------------------------
         Name: SC-0780-D           From Node: SC-0780           Length(ft): 443.00
        Group: Grace Lake            To Node: SC-0770                Count: 1

               UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                  Solution Algorithm: Most Restrictive
     Span(in): 18.00          18.00                                Flow: Both
     Rise(in): 18.00          18.00                     Entrance Loss Coef: 0.500
   Invert(ft): 62.370         55.900                        Exit Loss Coef: 0.000
  Manning's N: 0.013000       0.013000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                          Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

DIVERSION / CONTROL STRUCTURE.  DATA OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS (DATED 05/19/1985).
ELEVATIONS SHOWN WERE CONVERTED TO THE NAVD VERTICAL DATUM.

*** Weir 1 of 1 for Drop Structure SC-0780-D ***
                                                                                TABLE
                  Count: 1                       Bottom Clip(in): 0.000
                   Type: Vertical: Mavis            Top Clip(in): 0.000
                   Flow: Both                     Weir Disc Coef: 3.200
               Geometry: Rectangular            Orifice Disc Coef: 0.600

               Span(in): 50.40                        Invert(ft): 65.500
               Rise(in): 24.84                   Control Elev(ft): 65.500


-------------------------------------------------------------------------------------------------
         Name: SC-0925-D           From Node: SC-0925           Length(ft): 360.00
        Group: Grace Lake            To Node: SC-0920                Count: 1

               UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                  Solution Algorithm: Most Restrictive
     Span(in): 18.00          18.00                                Flow: Both
     Rise(in): 18.00          18.00                     Entrance Loss Coef: 0.500
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| | | | |
|---|---|---|---|
| Invert(ft): | 69.350 | 64.010 | Exit Loss Coef: 0.000 |
| Manning's N: | 0.013000 | 0.013000 | Outlet Ctrl Spec: Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

CONTROL STRUCTURE DATA WAS OBTAINED FROM THE AS-BUILT PLANS OF THE NORTHRIDGE SUBDIVISION, PREPARED BY CPH, DATED 05/19/1985.
CONSTRUCTION PLANS WERE REFERENCED TO THE NGVD VERTICAL DATUM AND CONVERTED TO THE NAVD DATUM.

*** Weir 1 of 2 for Drop Structure SC-0925-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 12.00 | Invert(ft): | 74.020 |
| Rise(in): | 46.70 | Control Elev(ft): | 74.020 |

*** Weir 2 of 2 for Drop Structure SC-0925-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 77.910 |
| Rise(in): | 54.00 | Control Elev(ft): | 77.910 |

---

| | | | |
|---|---|---|---|
| Name: | SC-0995-D | From Node: SC-0995 | Length(ft): 1211.00 |
| Group: | Grace Lake | To Node: SC-0990 | Count: 1 |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 15.00 | 15.00 | Flow: | Both |
| Rise(in): | 15.00 | 15.00 | Entrance Loss Coef: | 0.500 |
| Invert(ft): | 80.000 | 76.250 | Exit Loss Coef: | 0.000 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

EMERGENCY OVERFLOW STRUCTURE AND PIPE FROM THE WOODLAND ELEMENTARY POND TO GRACE LAKE.
PARAMETERS WERE OBTAINED FROM PERMITTED PLANS (REFER TO THE SJRWMD PERMIT NO. 49356-3, DATED 11/21/2007).
NOTE THAT ORIGINAL PLANS WERE REFERENCED TO THE NGVD DATUM.  ELEVATIONS SHOWN HEREIN WERE CONVERTED TO THE NAVD VERTICAL DATUM (

*** Weir 1 of 1 for Drop Structure SC-0995-D ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 36.00 | Invert(ft): | 83.160 |
| Rise(in): | 54.00 | Control Elev(ft): | 83.160 |

==========
==== Weirs ==========
==========

| | | | |
|---|---|---|---|
| Name: | SC-0770-W | From Node: | SC-0770 |
| Group: | Grace Lake | To Node: | SC-0750 |
| Flow: | Both | Count: | 1 |
| Type: | Vertical: Fread | Geometry: | Rectangular |
| Span(in): | 180.00 | | |
| Rise(in): | 999.00 | | |
| Invert(ft): | 58.500 | | |
| Control Elevation(ft): | 58.500 | | |

TABLE

Bottom Clip(in): 0.000

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
               Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------
          Name: SC-0780-W           From Node: SC-0780
         Group: Grace Lake            To Node: SC-0770
          Flow: Both                    Count: 1
          Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 2400.00
                    Rise(in): 999.00
                  Invert(ft): 67.900
       Control Elevation(ft): 67.900
                                         TABLE
               Bottom Clip(in): 0.000
                  Top Clip(in): 0.000
         Weir Discharge Coef: 3.200
      Orifice Discharge Coef: 0.600

OVERLAND OVERTOPPING FROM POND TO THE NORTHRIDGE SWALE.
ELEVATION WAS OBTAINED FROM THE NORTHRIDGE SUBDIVISION AS-BUILT PLANS AND COMPARED TO THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------
          Name: SC-0800-W1          From Node: SC-0800
         Group: Grace Lake            To Node: SC-0770
          Flow: Both                    Count: 1
          Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 1200.00
                    Rise(in): 999.00
                  Invert(ft): 58.000
       Control Elevation(ft): 58.000
                                         TABLE
               Bottom Clip(in): 0.000
                  Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

NORTHRIDGE DEPRESSIONAL AREA BERM OVERTOPPING
PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP AND SURVEYED DATA.

-------------------------------------------------------------------------------------------------
          Name: SC-0800-W2          From Node: SC-0800
         Group: Grace Lake            To Node: SC-0750
          Flow: Both                    Count: 1
          Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 58.500
       Control Elevation(ft): 58.500
                                         TABLE
               Bottom Clip(in): 0.000
                  Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING WEIR.  PARAMETERS WERE ESTIMATED BASED ON THE 1-FT TOPOGRAPHIC MAP.

-------------------------------------------------------------------------------------------------
          Name: SC-0810-W1          From Node: SC-0810
         Group: Grace Lake            To Node: SC-0800
          Flow: Both                    Count: 1
          Type: Vertical: Fread      Geometry: Irregular

                         XSec: SC-0810_W1
                  Invert(ft): 57.200
       Control Elevation(ft): 57.200
      Struct Opening Dim(ft): 9999.00
                                         TABLE
               Bottom Clip(ft): 0.000
                  Top Clip(ft): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------
          Name: SC-0810-W2          From Node: SC-0810
         Group: Grace Lake            To Node: SC-0770
          Flow: Both                    Count: 1
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

```
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0810_W2
                  Invert(ft): 58.500
       Control Elevation(ft): 58.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------------
         Name: SC-0840-W           From Node: SC-0840
        Group: Grace Lake            To Node: SC-0830
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0840_W
                  Invert(ft): 54.000
       Control Elevation(ft): 54.000
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------------
         Name: SC-0875-W           From Node: SC-0875
        Group: Grace Lake            To Node: SC-0840
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0875_W
                  Invert(ft): 65.500
       Control Elevation(ft): 65.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERLAND OVERTOPPING

-------------------------------------------------------------------------------------------------------
         Name: SC-0880-W           From Node: SC-0880
        Group: Grace Lake            To Node: SC-0875
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0880_W
                  Invert(ft): 62.600
       Control Elevation(ft): 62.600
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



-------------------------------------------------------------------------------------------------------
         Name: SC-0900-W           From Node: SC-0900
        Group: Grace Lake            To Node: SC-0910
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                      Span(in): 40.00
                      Rise(in): 999.00
                  Invert(ft): 61.000
       Control Elevation(ft): 61.000
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
          Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600
```

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
------------------------------------------------------------------------------------------------------
         Name: SC-0920-W1          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0910
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0920_W1
                  Invert(ft): 59.500
       Control Elevation(ft): 59.500
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
           Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



------------------------------------------------------------------------------------------------------
         Name: SC-0920-W2          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0910
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 1160.00
                    Rise(in): 999.00
                  Invert(ft): 62.500
       Control Elevation(ft): 62.500
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
           Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



------------------------------------------------------------------------------------------------------
         Name: SC-0920-W3          From Node: SC-0920
        Group: Grace Lake            To Node: SC-0790
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Irregular

                        XSec: SC-0920_W3
                  Invert(ft): 66.800
       Control Elevation(ft): 66.800
      Struct Opening Dim(ft): 9999.00
                                          TABLE
             Bottom Clip(ft): 0.000
                Top Clip(ft): 0.000
           Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

PARAMETERS ARE BASED ON SURVEY DATA OBTAINED FROM SSMC, DATED JULY 2013.

------------------------------------------------------------------------------------------------------
         Name: SC-0925-W           From Node: SC-0925
        Group: Grace Lake            To Node: SC-0920
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 680.00
                    Rise(in): 999.00
                  Invert(ft): 78.700
       Control Elevation(ft): 78.700
                                          TABLE
             Bottom Clip(in): 0.000
                Top Clip(in): 0.000
           Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600



------------------------------------------------------------------------------------------------------
         Name: SC-0985-W           From Node: SC-0985
        Group: Grace Lake            To Node: SC-0980
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 73.500
       Control Elevation(ft): 73.500
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
                                          TABLE
            Bottom Clip(in): 0.000
               Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

PENELOPE POND OVERTOPPING
PARAMETERS WERE ESTIMATED USING THE 1-FT TOPOGRAPHIC MAPS

-------------------------------------------------------------------------------------------------
         Name: SC-1000-W           From Node: SC-1000
        Group: Grace Lake            To Node: SC-0985
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 600.00
                    Rise(in): 999.00
                  Invert(ft): 77.500
       Control Elevation(ft): 77.500
                                          TABLE
            Bottom Clip(in): 0.000
               Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

OVERTOPPING HICKORY TREE ROAD

-------------------------------------------------------------------------------------------------
         Name: SC-POND300-W1       From Node: SC-POND300
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 336.00
                    Rise(in): 999.00
                  Invert(ft): 57.010
       Control Elevation(ft): 57.010
                                          TABLE
            Bottom Clip(in): 0.000
               Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

POND BERM OVERTOPPING

-------------------------------------------------------------------------------------------------
         Name: SC-POND301-W1       From Node: SC-POND301
        Group: Grace Lake            To Node: SC-0800
         Flow: Both                    Count: 1
         Type: Vertical: Fread      Geometry: Rectangular

                    Span(in): 355.00
                    Rise(in): 999.00
                  Invert(ft): 57.010
       Control Elevation(ft): 57.010
                                          TABLE
            Bottom Clip(in): 0.000
               Top Clip(in): 0.000
         Weir Discharge Coef: 2.800
      Orifice Discharge Coef: 0.600

POND BERM OVERTOP

=================================================================================================
==== Hydrology Simulations ======================================================================
=================================================================================================

         Name: 010-024
     Filename: C:\TEMP ICPR\010-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 6.80

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------
         Name: 025-024
     Filename: C:\TEMP ICPR\025-024.R32

      Override Defaults: Yes
```

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

```
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 8.50

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 025-096
     Filename: C:\TEMP ICPR\025-096.R32

      Override Defaults: Yes
    Storm Duration(hrs): 96.00
          Rainfall File: Sjrwmd96
    Rainfall Amount(in): 11.30

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 100-024
     Filename: C:\TEMP ICPR\100-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 11.40

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: 100-096
     Filename: C:\TEMP ICPR\100-096.R32

      Override Defaults: Yes
    Storm Duration(hrs): 96.00
          Rainfall File: Sjrwmd96
    Rainfall Amount(in): 15.00

Time(hrs)       Print Inc(min)
--------------- ---------------
96.000          5.00

-------------------------------------------------------------------------------------------------------
         Name: MA-024
     Filename: C:\TEMP ICPR\MA-024.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Flmod
    Rainfall Amount(in): 4.40

Time(hrs)       Print Inc(min)
--------------- ---------------
30.000          5.00

===============================================================================================
==== Routing Simulations ======================================================================
===============================================================================================

         Name: 010-024             Hydrology Sim: 010-024
     Filename: C:\TEMP ICPR\010-024.I32

      Execute: No          Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 36.00
     Min Calc Time(sec): 0.1000              Max Calc Time(sec): 1.0000
       Boundary Stages: 010-024                Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
10-YEAR STORM EVENT (24-HOUR DURATION)

Time(hrs)       Print Inc(min)
--------------- ---------------
999.000         15.000
```

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 025-024 Hydrology Sim: 025-024
Filename: C:\TEMP ICPR\025-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 36.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 1.0000
Boundary Stages: 025-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
25-YEAR STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 999.000 | 15.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 025-096 Hydrology Sim: 025-096
Filename: C:\TEMP ICPR\025-096.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 120.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 96.000 | 15.000 |
| 120.000 | 30.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 100-024 Hydrology Sim: 100-024
Filename: C:\TEMP ICPR\100-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 336.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
100-YEAR STORM EVENT (24-HOUR DURATION)

---

GRACE LAKE
PROPOSED CONDITIONS INPUT
JUNE 2017

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

---

| Time(hrs) | Print Inc(min) |
|---|---|
| 48.000 | 15.000 |
| 336.000 | 60.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: 100-096 Hydrology Sim: 100-096
Filename: C:\TEMP ICPR\100-096.I32

Execute: Yes Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 180.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 60.0000
Boundary Stages: 100-024 Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 96.000 | 15.000 |
| 120.000 | 30.000 |
| 180.000 | 60.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

---

Name: MA-024 Hydrology Sim: MA-024
Filename: C:\TEMP ICPR\MA-024.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 36.00
Min Calc Time(sec): 0.1000 Max Calc Time(sec): 1.0000
Boundary Stages: 010-024 Boundary Flows:

GRACE LAKE SINKHOLE REMEDIATION
PROPOSED CONDITIONS ANALYSIS
MEAN ANNUAL STORM EVENT (24-HOUR DURATION)

| Time(hrs) | Print Inc(min) |
|---|---|
| 999.000 | 15.000 |

| Group | Run |
|---|---|
| BASE | Yes |
| Cranes | Yes |
| Gee | Yes |
| Grace Lake | Yes |
| Soldier | Yes |

==========
==== Boundary Conditions ====
==========

Name: 010-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |

---

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.400 |
| 7.500 | 50.400 |
| 8.000 | 50.400 |
| 8.500 | 50.410 |
| 8.670 | 50.410 |
| 8.830 | 50.420 |
| 9.000 | 50.420 |
| 9.170 | 50.430 |
| 9.330 | 50.430 |
| 9.500 | 50.440 |
| 9.670 | 50.440 |
| 9.830 | 50.450 |
| 10.000 | 50.460 |
| 10.170 | 50.470 |
| 10.330 | 50.470 |
| 10.500 | 50.480 |
| 10.670 | 50.490 |
| 10.830 | 50.510 |
| 11.000 | 50.520 |
| 11.170 | 50.530 |
| 11.330 | 50.550 |
| 11.500 | 50.570 |
| 11.670 | 50.600 |
| 11.830 | 50.650 |
| 12.000 | 50.740 |
| 12.170 | 50.840 |
| 12.330 | 50.960 |
| 12.500 | 51.080 |
| 12.670 | 51.170 |
| 12.830 | 51.250 |
| 13.000 | 51.320 |
| 13.170 | 51.370 |
| 13.330 | 51.420 |
| 13.500 | 51.460 |
| 13.670 | 51.500 |
| 13.830 | 51.540 |
| 14.000 | 51.570 |
| 14.170 | 51.600 |
| 14.330 | 51.620 |
| 14.500 | 51.650 |
| 14.670 | 51.680 |
| 14.830 | 51.700 |
| 15.000 | 51.720 |
| 15.170 | 51.750 |
| 15.330 | 51.770 |
| 15.500 | 51.790 |
| 15.670 | 51.810 |
| 15.830 | 51.830 |
| 16.000 | 51.850 |
| 16.170 | 51.870 |
| 16.670 | 51.930 |
| 17.170 | 51.980 |
| 17.670 | 52.040 |
| 18.170 | 52.090 |
| 18.670 | 52.150 |
| 19.170 | 52.200 |
| 19.670 | 52.250 |
| 20.170 | 52.300 |
| 20.670 | 52.340 |
| 21.170 | 52.390 |
| 21.670 | 52.430 |
| 22.170 | 52.470 |
| 22.670 | 52.500 |
| 23.170 | 52.540 |
| 23.670 | 52.570 |
| 24.170 | 52.600 |
| 24.670 | 52.620 |
| 25.170 | 52.640 |
| 25.670 | 52.650 |
| 26.170 | 52.660 |
| 26.670 | 52.670 |

| | |
|---|---|
| 27.170 | 52.670 |
| 27.670 | 52.680 |
| 28.170 | 52.680 |
| 28.670 | 52.680 |
| 29.170 | 52.690 |
| 29.670 | 52.690 |
| 30.170 | 52.680 |
| 30.670 | 52.680 |
| 31.170 | 52.680 |
| 31.670 | 52.680 |
| 32.170 | 52.670 |
| 32.670 | 52.670 |
| 33.170 | 52.660 |
| 33.670 | 52.660 |
| 34.170 | 52.650 |
| 34.670 | 52.640 |
| 35.170 | 52.640 |
| 35.670 | 52.630 |
| 36.000 | 52.620 |

Name: 010-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.150 |
| 5.500 | 42.160 |
| 6.000 | 42.160 |
| 6.500 | 42.160 |
| 7.000 | 42.170 |
| 7.500 | 42.180 |
| 8.000 | 42.190 |
| 8.500 | 42.210 |
| 8.750 | 42.220 |
| 9.000 | 42.240 |
| 9.250 | 42.250 |
| 9.500 | 42.270 |
| 9.750 | 42.280 |
| 10.000 | 42.300 |
| 10.250 | 42.310 |
| 10.500 | 42.330 |
| 10.750 | 42.350 |
| 11.000 | 42.370 |
| 11.250 | 42.390 |
| 11.500 | 42.420 |
| 11.750 | 42.470 |
| 12.000 | 42.570 |
| 12.250 | 42.700 |
| 12.500 | 42.830 |
| 12.750 | 42.910 |
| 13.000 | 42.940 |
| 13.250 | 42.950 |
| 13.500 | 42.950 |
| 13.750 | 42.940 |
| 14.000 | 42.940 |
| 14.250 | 42.930 |
| 14.500 | 42.930 |
| 14.750 | 42.930 |
| 15.000 | 42.940 |
| 15.250 | 42.970 |
| 15.500 | 43.000 |
| 15.750 | 43.020 |
| 16.000 | 43.050 |
| 16.250 | 43.080 |
| 16.750 | 43.120 |
| 17.250 | 43.160 |
| 17.750 | 43.190 |
| 18.250 | 43.220 |
| 18.750 | 43.240 |
| 19.250 | 43.250 |
| 19.750 | 43.270 |
| 20.250 | 43.280 |
| 20.750 | 43.290 |
| 21.250 | 43.300 |

| | |
|---|---|
| 21.750 | 43.310 |
| 22.250 | 43.320 |
| 22.750 | 43.320 |
| 23.250 | 43.330 |
| 23.750 | 43.350 |
| 24.250 | 43.370 |
| 24.750 | 43.390 |
| 25.250 | 43.410 |
| 25.750 | 43.420 |
| 26.250 | 43.430 |
| 26.750 | 43.450 |
| 27.250 | 43.460 |
| 27.750 | 43.470 |
| 28.250 | 43.470 |
| 28.750 | 43.480 |
| 29.250 | 43.480 |
| 29.750 | 43.490 |
| 30.250 | 43.490 |
| 30.750 | 43.490 |
| 31.250 | 43.490 |
| 31.750 | 43.490 |
| 32.250 | 43.490 |
| 32.750 | 43.490 |
| 33.250 | 43.490 |
| 33.750 | 43.490 |
| 34.250 | 43.480 |
| 34.750 | 43.480 |
| 35.250 | 43.480 |
| 35.750 | 43.470 |
| 36.250 | 43.460 |
| 36.750 | 43.460 |
| 37.250 | 43.450 |
| 37.750 | 43.440 |
| 38.250 | 43.440 |
| 38.750 | 43.430 |
| 39.250 | 43.420 |
| 39.750 | 43.410 |
| 40.250 | 43.400 |
| 40.750 | 43.390 |
| 41.250 | 43.380 |
| 41.750 | 43.370 |
| 42.250 | 43.360 |
| 42.750 | 43.350 |
| 43.250 | 43.340 |
| 43.750 | 43.330 |
| 44.250 | 43.310 |
| 44.750 | 43.300 |
| 45.250 | 43.290 |
| 45.750 | 43.280 |
| 46.250 | 43.270 |
| 46.750 | 43.250 |
| 47.250 | 43.240 |
| 47.750 | 43.230 |
| 48.000 | 43.220 |

Name: 010-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.130 |
| 8.500 | 46.130 |
| 8.750 | 46.140 |
| 9.000 | 46.140 |
| 9.250 | 46.140 |
| 9.500 | 46.140 |
| 9.750 | 46.150 |
| 10.000 | 46.150 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 10.250 | 46.160 |
| 10.500 | 46.160 |
| 10.750 | 46.170 |
| 11.000 | 46.180 |
| 11.250 | 46.200 |
| 11.500 | 46.220 |
| 11.750 | 46.260 |
| 12.000 | 46.330 |
| 12.250 | 46.430 |
| 12.500 | 46.530 |
| 12.750 | 46.600 |
| 13.000 | 46.650 |
| 13.250 | 46.690 |
| 13.500 | 46.720 |
| 13.750 | 46.740 |
| 14.000 | 46.770 |
| 14.250 | 46.800 |
| 14.500 | 46.820 |
| 14.750 | 46.850 |
| 15.000 | 46.870 |
| 15.250 | 46.900 |
| 15.500 | 46.920 |
| 15.750 | 46.950 |
| 16.000 | 46.980 |
| 16.250 | 47.000 |
| 16.750 | 47.060 |
| 17.250 | 47.120 |
| 17.750 | 47.180 |
| 18.250 | 47.240 |
| 18.750 | 47.300 |
| 19.250 | 47.350 |
| 19.750 | 47.410 |
| 20.250 | 47.460 |
| 20.750 | 47.490 |
| 21.250 | 47.520 |
| 21.750 | 47.550 |
| 22.250 | 47.580 |
| 22.750 | 47.730 |
| 23.250 | 48.070 |
| 23.750 | 48.530 |
| 24.250 | 48.700 |
| 24.750 | 48.810 |
| 25.250 | 48.880 |
| 25.750 | 48.920 |
| 26.250 | 48.950 |
| 26.750 | 48.970 |
| 27.250 | 48.980 |
| 27.750 | 48.980 |
| 28.250 | 48.980 |
| 28.750 | 48.970 |
| 29.250 | 48.960 |
| 29.750 | 48.950 |
| 30.250 | 48.940 |
| 30.750 | 48.920 |
| 31.250 | 48.910 |
| 31.750 | 48.890 |
| 32.250 | 48.870 |
| 32.750 | 48.850 |
| 33.250 | 48.830 |
| 33.750 | 48.810 |
| 34.250 | 48.790 |
| 34.750 | 48.770 |
| 35.250 | 48.750 |
| 35.750 | 48.720 |
| 36.250 | 48.700 |
| 36.750 | 48.680 |
| 37.250 | 48.660 |
| 37.750 | 48.640 |
| 38.250 | 48.620 |
| 38.750 | 48.600 |
| 39.250 | 48.580 |
| 39.750 | 48.560 |
| 40.250 | 48.540 |
| 40.750 | 48.520 |
| 41.250 | 48.510 |
| 41.750 | 48.490 |
| 42.250 | 48.470 |
| 42.750 | 48.290 |
| 43.250 | 48.270 |
| 43.750 | 48.240 |
| 44.250 | 48.220 |
| 44.750 | 48.200 |
| 45.250 | 48.170 |
| 45.750 | 48.150 |

| | |
|---|---|
| 46.250 | 48.130 |
| 46.750 | 48.110 |
| 47.250 | 48.090 |
| 47.750 | 48.060 |
| 48.000 | 48.050 |

Name: 010-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |
| 4.500 | 41.060 |
| 5.000 | 41.090 |
| 5.500 | 41.180 |
| 6.000 | 41.310 |
| 6.500 | 41.400 |
| 7.000 | 41.520 |
| 7.500 | 41.670 |
| 8.000 | 41.810 |
| 8.500 | 41.960 |
| 8.750 | 42.050 |
| 9.000 | 42.130 |
| 9.250 | 42.230 |
| 9.500 | 42.320 |
| 9.750 | 42.400 |
| 10.000 | 42.480 |
| 10.250 | 42.570 |
| 10.500 | 42.670 |
| 10.750 | 42.770 |
| 11.000 | 42.870 |
| 11.250 | 42.970 |
| 11.500 | 43.120 |
| 11.750 | 43.540 |
| 12.000 | 43.920 |
| 12.250 | 44.110 |
| 12.500 | 44.080 |
| 12.750 | 43.900 |
| 13.000 | 43.750 |
| 13.250 | 43.700 |
| 13.500 | 43.720 |
| 13.750 | 43.740 |
| 14.000 | 43.750 |
| 14.250 | 43.750 |
| 14.500 | 43.780 |
| 14.750 | 43.840 |
| 15.000 | 43.910 |
| 15.250 | 43.960 |
| 15.500 | 44.000 |
| 15.750 | 44.020 |
| 16.000 | 44.030 |
| 16.250 | 44.030 |
| 16.750 | 44.020 |
| 17.250 | 44.000 |
| 17.750 | 43.960 |
| 18.250 | 43.900 |
| 18.750 | 43.840 |
| 19.250 | 43.790 |
| 19.750 | 43.740 |
| 20.250 | 43.700 |
| 20.750 | 43.670 |
| 21.250 | 43.660 |
| 21.750 | 43.650 |
| 22.250 | 43.650 |
| 22.750 | 43.640 |
| 23.250 | 43.630 |
| 23.750 | 43.620 |
| 24.250 | 43.600 |
| 24.750 | 43.570 |
| 25.250 | 43.540 |
| 25.750 | 43.510 |
| 26.250 | 43.480 |
| 26.750 | 43.460 |
| 27.250 | 43.430 |
| 27.750 | 43.430 |
| 28.250 | 43.320 |

| | |
|---|---|
| 28.750 | 42.350 |
| 29.250 | 42.150 |
| 29.750 | 42.080 |
| 30.250 | 42.030 |
| 30.750 | 42.000 |
| 31.250 | 41.970 |
| 31.750 | 41.950 |
| 32.250 | 41.920 |
| 32.750 | 41.890 |
| 33.250 | 41.860 |
| 33.750 | 41.830 |
| 34.250 | 41.810 |
| 34.750 | 41.790 |
| 35.250 | 41.770 |
| 35.750 | 41.750 |
| 36.250 | 41.730 |
| 36.750 | 41.710 |
| 37.250 | 41.700 |
| 37.750 | 41.680 |
| 38.250 | 41.670 |
| 38.750 | 41.660 |
| 39.250 | 41.650 |
| 39.750 | 41.640 |
| 40.250 | 41.630 |
| 40.750 | 41.620 |
| 41.250 | 41.610 |
| 41.750 | 41.600 |
| 42.250 | 41.590 |
| 42.750 | 41.580 |
| 43.250 | 41.570 |
| 43.750 | 41.560 |
| 44.250 | 41.550 |
| 44.750 | 41.550 |
| 45.250 | 41.540 |
| 45.750 | 41.530 |
| 46.250 | 41.520 |
| 46.750 | 41.520 |
| 47.250 | 41.510 |
| 47.750 | 41.510 |
| 48.000 | 41.510 |

Name: 025-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.400 |
| 3.500 | 50.400 |
| 4.000 | 50.400 |
| 4.500 | 50.400 |
| 5.000 | 50.400 |
| 5.500 | 50.400 |
| 6.000 | 50.400 |
| 6.500 | 50.400 |
| 7.000 | 50.410 |
| 7.500 | 50.420 |
| 8.000 | 50.430 |
| 8.500 | 50.450 |
| 8.670 | 50.450 |
| 8.830 | 50.460 |
| 9.000 | 50.470 |
| 9.170 | 50.480 |
| 9.330 | 50.480 |
| 9.500 | 50.490 |
| 9.670 | 50.500 |
| 9.830 | 50.510 |
| 10.000 | 50.520 |
| 10.170 | 50.530 |
| 10.330 | 50.550 |
| 10.500 | 50.560 |
| 10.670 | 50.570 |
| 10.830 | 50.590 |
| 11.000 | 50.610 |
| 11.170 | 50.630 |
| 11.330 | 50.650 |
| 11.500 | 50.680 |
| 11.670 | 50.710 |
| 11.830 | 50.780 |

| | |
|---|---|
| 12.000 | 50.880 |
| 12.170 | 51.020 |
| 12.330 | 51.170 |
| 12.500 | 51.310 |
| 12.670 | 51.440 |
| 12.830 | 51.530 |
| 13.000 | 51.610 |
| 13.170 | 51.680 |
| 13.330 | 51.740 |
| 13.500 | 51.800 |
| 13.670 | 51.840 |
| 13.830 | 51.890 |
| 14.000 | 51.920 |
| 14.170 | 51.960 |
| 14.330 | 52.000 |
| 14.500 | 52.030 |
| 14.670 | 52.060 |
| 14.830 | 52.090 |
| 15.000 | 52.120 |
| 15.170 | 52.140 |
| 15.330 | 52.170 |
| 15.500 | 52.200 |
| 15.670 | 52.220 |
| 15.830 | 52.250 |
| 16.000 | 52.280 |
| 16.170 | 52.300 |
| 16.670 | 52.380 |
| 17.170 | 52.450 |
| 17.670 | 52.520 |
| 18.170 | 52.590 |
| 18.670 | 52.650 |
| 19.170 | 52.720 |
| 19.670 | 52.770 |
| 20.170 | 52.830 |
| 20.670 | 52.890 |
| 21.170 | 52.940 |
| 21.670 | 52.980 |
| 22.170 | 53.030 |
| 22.670 | 53.070 |
| 23.170 | 53.110 |
| 23.670 | 53.140 |
| 24.170 | 53.170 |
| 24.670 | 53.190 |
| 25.170 | 53.200 |
| 25.670 | 53.210 |
| 26.170 | 53.220 |
| 26.670 | 53.230 |
| 27.170 | 53.230 |
| 27.670 | 53.230 |
| 28.170 | 53.240 |
| 28.670 | 53.230 |
| 29.170 | 53.230 |
| 29.670 | 53.230 |
| 30.170 | 53.220 |
| 30.670 | 53.220 |
| 31.170 | 53.210 |
| 31.670 | 53.210 |
| 32.170 | 53.200 |
| 32.670 | 53.190 |
| 33.170 | 53.180 |
| 33.670 | 53.170 |
| 34.170 | 53.160 |
| 34.670 | 53.150 |
| 35.170 | 53.140 |
| 35.670 | 53.130 |
| 36.000 | 53.120 |

Name: 025-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.150 |
| 5.000 | 42.160 |
| 5.500 | 42.160 |

| | |
|---|---|
| 6.000 | 42.170 |
| 6.500 | 42.180 |
| 7.000 | 42.190 |
| 7.500 | 42.210 |
| 8.000 | 42.240 |
| 8.500 | 42.270 |
| 8.750 | 42.280 |
| 9.000 | 42.300 |
| 9.250 | 42.320 |
| 9.500 | 42.330 |
| 9.750 | 42.350 |
| 10.000 | 42.370 |
| 10.250 | 42.380 |
| 10.500 | 42.400 |
| 10.750 | 42.420 |
| 11.000 | 42.450 |
| 11.250 | 42.470 |
| 11.500 | 42.500 |
| 11.750 | 42.560 |
| 12.000 | 42.670 |
| 12.250 | 42.820 |
| 12.500 | 42.950 |
| 12.750 | 43.030 |
| 13.000 | 43.070 |
| 13.250 | 43.080 |
| 13.500 | 43.080 |
| 13.750 | 43.080 |
| 14.000 | 43.090 |
| 14.250 | 43.110 |
| 14.500 | 43.150 |
| 14.750 | 43.200 |
| 15.000 | 43.250 |
| 15.250 | 43.300 |
| 15.500 | 43.340 |
| 15.750 | 43.370 |
| 16.000 | 43.410 |
| 16.250 | 43.440 |
| 16.750 | 43.490 |
| 17.250 | 43.540 |
| 17.750 | 43.570 |
| 18.250 | 43.600 |
| 18.750 | 43.620 |
| 19.250 | 43.640 |
| 19.750 | 43.650 |
| 20.250 | 43.670 |
| 20.750 | 43.690 |
| 21.250 | 43.720 |
| 21.750 | 43.750 |
| 22.250 | 43.780 |
| 22.750 | 43.810 |
| 23.250 | 43.830 |
| 23.750 | 43.860 |
| 24.250 | 43.880 |
| 24.750 | 43.900 |
| 25.250 | 43.910 |
| 25.750 | 43.920 |
| 26.250 | 43.930 |
| 26.750 | 43.940 |
| 27.250 | 43.940 |
| 27.750 | 43.950 |
| 28.250 | 43.950 |
| 28.750 | 43.950 |
| 29.250 | 43.950 |
| 29.750 | 43.950 |
| 30.250 | 43.950 |
| 30.750 | 43.940 |
| 31.250 | 43.940 |
| 31.750 | 43.930 |
| 32.250 | 43.930 |
| 32.750 | 43.920 |
| 33.250 | 43.910 |
| 33.750 | 43.910 |
| 34.250 | 43.900 |
| 34.750 | 43.890 |
| 35.250 | 43.880 |
| 35.750 | 43.870 |
| 36.250 | 43.850 |
| 36.750 | 43.840 |
| 37.250 | 43.830 |
| 37.750 | 43.820 |
| 38.250 | 43.800 |
| 38.750 | 43.790 |
| 39.250 | 43.780 |
| 39.750 | 43.760 |

| | |
|---|---|
| 40.250 | 43.750 |
| 40.750 | 43.730 |
| 41.250 | 43.720 |
| 41.750 | 43.700 |
| 42.250 | 43.690 |
| 42.750 | 43.670 |
| 43.250 | 43.660 |
| 43.750 | 43.640 |
| 44.250 | 43.630 |
| 44.750 | 43.610 |
| 45.250 | 43.600 |
| 45.750 | 43.580 |
| 46.250 | 43.570 |
| 46.750 | 43.550 |
| 47.250 | 43.530 |
| 47.750 | 43.520 |
| 48.000 | 43.510 |

Name: 025-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.130 |
| 7.000 | 46.130 |
| 7.500 | 46.130 |
| 8.000 | 46.140 |
| 8.500 | 46.150 |
| 8.750 | 46.150 |
| 9.000 | 46.150 |
| 9.250 | 46.160 |
| 9.500 | 46.160 |
| 9.750 | 46.170 |
| 10.000 | 46.180 |
| 10.250 | 46.190 |
| 10.500 | 46.200 |
| 10.750 | 46.220 |
| 11.000 | 46.240 |
| 11.250 | 46.260 |
| 11.500 | 46.290 |
| 11.750 | 46.330 |
| 12.000 | 46.400 |
| 12.250 | 46.570 |
| 12.500 | 46.710 |
| 12.750 | 46.800 |
| 13.000 | 46.860 |
| 13.250 | 46.910 |
| 13.500 | 46.940 |
| 13.750 | 46.980 |
| 14.000 | 47.010 |
| 14.250 | 47.040 |
| 14.500 | 47.070 |
| 14.750 | 47.100 |
| 15.000 | 47.130 |
| 15.250 | 47.160 |
| 15.500 | 47.190 |
| 15.750 | 47.220 |
| 16.000 | 47.260 |
| 16.250 | 47.290 |
| 16.750 | 47.350 |
| 17.250 | 47.410 |
| 17.750 | 47.460 |
| 18.250 | 47.500 |
| 18.750 | 47.530 |
| 19.250 | 47.570 |
| 19.750 | 47.720 |
| 20.250 | 48.190 |
| 20.750 | 48.710 |
| 21.250 | 48.950 |
| 21.750 | 49.120 |
| 22.250 | 49.240 |

| | |
|---|---|
| 22.750 | 49.310 |
| 23.250 | 49.370 |
| 23.750 | 49.410 |
| 24.250 | 49.430 |
| 24.750 | 49.430 |
| 25.250 | 49.430 |
| 25.750 | 49.440 |
| 26.250 | 49.430 |
| 26.750 | 49.430 |
| 27.250 | 49.420 |
| 27.750 | 49.410 |
| 28.250 | 49.400 |
| 28.750 | 49.380 |
| 29.250 | 49.360 |
| 29.750 | 49.340 |
| 30.250 | 49.320 |
| 30.750 | 49.300 |
| 31.250 | 49.280 |
| 31.750 | 49.250 |
| 32.250 | 49.230 |
| 32.750 | 49.190 |
| 33.250 | 49.160 |
| 33.750 | 49.130 |
| 34.250 | 49.100 |
| 34.750 | 49.080 |
| 35.250 | 49.050 |
| 35.750 | 49.020 |
| 36.250 | 48.990 |
| 36.750 | 48.960 |
| 37.250 | 48.930 |
| 37.750 | 48.900 |
| 38.250 | 48.870 |
| 38.750 | 48.840 |
| 39.250 | 48.820 |
| 39.750 | 48.790 |
| 40.250 | 48.770 |
| 40.750 | 48.740 |
| 41.250 | 48.720 |
| 41.750 | 48.700 |
| 42.250 | 48.670 |
| 42.750 | 48.650 |
| 43.250 | 48.630 |
| 43.750 | 48.610 |
| 44.250 | 48.590 |
| 44.750 | 48.570 |
| 45.250 | 48.550 |
| 45.750 | 48.530 |
| 46.250 | 48.510 |
| 46.750 | 48.500 |
| 47.250 | 48.480 |
| 47.750 | 48.460 |
| 48.000 | 48.290 |

Name: 025-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.060 |
| 4.000 | 41.060 |
| 4.500 | 41.140 |
| 5.000 | 41.280 |
| 5.500 | 41.390 |
| 6.000 | 41.510 |
| 6.500 | 41.670 |
| 7.000 | 41.830 |
| 7.500 | 42.000 |
| 8.000 | 42.170 |
| 8.500 | 42.340 |
| 8.750 | 42.420 |
| 9.000 | 42.500 |
| 9.250 | 42.580 |
| 9.500 | 42.650 |
| 9.750 | 42.730 |
| 10.000 | 42.800 |
| 10.250 | 42.870 |
| 10.500 | 42.960 |

| | |
|---|---|
| 10.750 | 43.070 |
| 11.000 | 43.160 |
| 11.250 | 43.240 |
| 11.500 | 43.430 |
| 11.750 | 43.690 |
| 12.000 | 44.060 |
| 12.250 | 44.120 |
| 12.500 | 44.140 |
| 12.750 | 44.090 |
| 13.000 | 43.950 |
| 13.250 | 43.930 |
| 13.500 | 43.870 |
| 13.750 | 43.960 |
| 14.000 | 44.130 |
| 14.250 | 44.240 |
| 14.500 | 44.340 |
| 14.750 | 44.420 |
| 15.000 | 44.490 |
| 15.250 | 44.540 |
| 15.500 | 44.570 |
| 15.750 | 44.580 |
| 16.000 | 44.580 |
| 16.250 | 44.570 |
| 16.750 | 44.520 |
| 17.250 | 44.470 |
| 17.750 | 44.410 |
| 18.250 | 44.350 |
| 18.750 | 44.290 |
| 19.250 | 44.240 |
| 19.750 | 44.180 |
| 20.250 | 44.130 |
| 20.750 | 44.070 |
| 21.250 | 43.990 |
| 21.750 | 43.910 |
| 22.250 | 43.840 |
| 22.750 | 43.770 |
| 23.250 | 43.720 |
| 23.750 | 43.690 |
| 24.250 | 43.660 |
| 24.750 | 43.630 |
| 25.250 | 43.600 |
| 25.750 | 43.570 |
| 26.250 | 43.550 |
| 26.750 | 43.530 |
| 27.250 | 43.510 |
| 27.750 | 43.480 |
| 28.250 | 43.460 |
| 28.750 | 43.440 |
| 29.250 | 43.410 |
| 29.750 | 43.400 |
| 30.250 | 42.620 |
| 30.750 | 42.160 |
| 31.250 | 42.050 |
| 31.750 | 42.010 |
| 32.250 | 41.980 |
| 32.750 | 41.960 |
| 33.250 | 41.930 |
| 33.750 | 41.910 |
| 34.250 | 41.900 |
| 34.750 | 41.890 |
| 35.250 | 41.880 |
| 35.750 | 41.860 |
| 36.250 | 41.850 |
| 36.750 | 41.840 |
| 37.250 | 41.830 |
| 37.750 | 41.820 |
| 38.250 | 41.830 |
| 38.750 | 41.810 |
| 39.250 | 41.800 |
| 39.750 | 41.790 |
| 40.250 | 41.770 |
| 40.750 | 41.760 |
| 41.250 | 41.750 |
| 41.750 | 41.730 |
| 42.250 | 41.720 |
| 42.750 | 41.710 |
| 43.250 | 41.700 |
| 43.750 | 41.680 |
| 44.250 | 41.670 |
| 44.750 | 41.660 |
| 45.250 | 41.650 |
| 45.750 | 41.640 |
| 46.250 | 41.630 |
| 46.750 | 41.620 |

| | |
|---|---|
| 47.250 | 41.610 |
| 47.750 | 41.600 |
| 48.000 | 41.600 |

Name: 100-024 Node: GC-1000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 50.400 |
| 0.500 | 50.400 |
| 1.000 | 50.400 |
| 1.500 | 50.400 |
| 2.000 | 50.400 |
| 2.500 | 50.400 |
| 3.000 | 50.410 |
| 3.500 | 50.410 |
| 4.000 | 50.410 |
| 4.500 | 50.410 |
| 5.000 | 50.420 |
| 5.500 | 50.420 |
| 6.000 | 50.440 |
| 6.500 | 50.450 |
| 7.000 | 50.460 |
| 7.500 | 50.480 |
| 8.000 | 50.510 |
| 8.500 | 50.540 |
| 8.670 | 50.550 |
| 8.830 | 50.560 |
| 9.000 | 50.570 |
| 9.170 | 50.580 |
| 9.330 | 50.600 |
| 9.500 | 50.610 |
| 9.670 | 50.630 |
| 9.830 | 50.640 |
| 10.000 | 50.660 |
| 10.170 | 50.680 |
| 10.330 | 50.700 |
| 10.500 | 50.720 |
| 10.670 | 50.740 |
| 10.830 | 50.770 |
| 11.000 | 50.790 |
| 11.170 | 50.820 |
| 11.330 | 50.850 |
| 11.500 | 50.890 |
| 11.670 | 50.950 |
| 11.830 | 51.040 |
| 12.000 | 51.170 |
| 12.170 | 51.350 |
| 12.330 | 51.560 |
| 12.500 | 51.760 |
| 12.670 | 51.940 |
| 12.830 | 52.080 |
| 13.000 | 52.200 |
| 13.170 | 52.310 |
| 13.330 | 52.410 |
| 13.500 | 52.490 |
| 13.670 | 52.570 |
| 13.830 | 52.640 |
| 14.000 | 52.710 |
| 14.170 | 52.770 |
| 14.330 | 52.830 |
| 14.500 | 52.880 |
| 14.670 | 52.930 |
| 14.830 | 52.970 |
| 15.000 | 53.010 |
| 15.170 | 53.050 |
| 15.330 | 53.080 |
| 15.500 | 53.120 |
| 15.670 | 53.150 |
| 15.830 | 53.180 |
| 16.000 | 53.210 |
| 16.170 | 53.230 |
| 16.670 | 53.310 |
| 17.170 | 53.380 |
| 17.670 | 53.440 |
| 18.170 | 53.500 |
| 18.670 | 53.560 |
| 19.170 | 53.610 |
| 19.670 | 53.660 |
| 20.170 | 53.700 |
| 20.670 | 53.740 |
| 21.170 | 53.780 |
| 21.670 | 53.820 |

| | |
|---|---|
| 22.170 | 53.850 |
| 22.670 | 53.880 |
| 23.170 | 53.910 |
| 23.670 | 53.940 |
| 24.170 | 53.970 |
| 24.670 | 53.980 |
| 25.170 | 54.000 |
| 25.670 | 54.000 |
| 26.170 | 54.010 |
| 26.670 | 54.010 |
| 27.170 | 54.010 |
| 27.670 | 54.000 |
| 28.170 | 54.000 |
| 28.670 | 54.000 |
| 29.170 | 53.990 |
| 29.670 | 53.990 |
| 30.170 | 53.980 |
| 30.670 | 53.970 |
| 31.170 | 53.970 |
| 31.670 | 53.960 |
| 32.170 | 53.950 |
| 32.670 | 53.940 |
| 33.170 | 53.920 |
| 33.670 | 53.910 |
| 34.170 | 53.900 |
| 34.670 | 53.890 |
| 35.170 | 53.870 |
| 35.670 | 53.860 |
| 36.000 | 53.850 |

Name: 100-024 Node: SC-3000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 42.140 |
| 0.500 | 42.140 |
| 1.000 | 42.140 |
| 1.500 | 42.140 |
| 2.000 | 42.140 |
| 2.500 | 42.140 |
| 3.000 | 42.150 |
| 3.500 | 42.150 |
| 4.000 | 42.150 |
| 4.500 | 42.160 |
| 5.000 | 42.170 |
| 5.500 | 42.180 |
| 6.000 | 42.210 |
| 6.500 | 42.230 |
| 7.000 | 42.270 |
| 7.500 | 42.300 |
| 8.000 | 42.330 |
| 8.500 | 42.370 |
| 8.750 | 42.380 |
| 9.000 | 42.400 |
| 9.250 | 42.420 |
| 9.500 | 42.440 |
| 9.750 | 42.460 |
| 10.000 | 42.470 |
| 10.250 | 42.500 |
| 10.500 | 42.520 |
| 10.750 | 42.540 |
| 11.000 | 42.570 |
| 11.250 | 42.600 |
| 11.500 | 42.630 |
| 11.750 | 42.700 |
| 12.000 | 42.830 |
| 12.250 | 42.980 |
| 12.500 | 43.130 |
| 12.750 | 43.230 |
| 13.000 | 43.300 |
| 13.250 | 43.350 |
| 13.500 | 43.390 |
| 13.750 | 43.450 |
| 14.000 | 43.540 |
| 14.250 | 43.610 |
| 14.500 | 43.690 |
| 14.750 | 43.750 |
| 15.000 | 43.810 |
| 15.250 | 43.860 |
| 15.500 | 43.910 |
| 15.750 | 43.950 |
| 16.000 | 43.990 |
| 16.250 | 44.020 |

| | |
|---|---|
| 16.750 | 44.090 |
| 17.250 | 44.150 |
| 17.750 | 44.200 |
| 18.250 | 44.250 |
| 18.750 | 44.300 |
| 19.250 | 44.350 |
| 19.750 | 44.390 |
| 20.250 | 44.430 |
| 20.750 | 44.460 |
| 21.250 | 44.490 |
| 21.750 | 44.520 |
| 22.250 | 44.550 |
| 22.750 | 44.570 |
| 23.250 | 44.600 |
| 23.750 | 44.620 |
| 24.250 | 44.640 |
| 24.750 | 44.650 |
| 25.250 | 44.660 |
| 25.750 | 44.670 |
| 26.250 | 44.670 |
| 26.750 | 44.670 |
| 27.250 | 44.670 |
| 27.750 | 44.670 |
| 28.250 | 44.670 |
| 28.750 | 44.670 |
| 29.250 | 44.670 |
| 29.750 | 44.670 |
| 30.250 | 44.670 |
| 30.750 | 44.670 |
| 31.250 | 44.660 |
| 31.750 | 44.660 |
| 32.250 | 44.650 |
| 32.750 | 44.650 |
| 33.250 | 44.640 |
| 33.750 | 44.630 |
| 34.250 | 44.620 |
| 34.750 | 44.610 |
| 35.250 | 44.600 |
| 35.750 | 44.590 |
| 36.250 | 44.570 |
| 36.750 | 44.560 |
| 37.250 | 44.540 |
| 37.750 | 44.530 |
| 38.250 | 44.510 |
| 38.750 | 44.490 |
| 39.250 | 44.470 |
| 39.750 | 44.450 |
| 40.250 | 44.430 |
| 40.750 | 44.410 |
| 41.250 | 44.390 |
| 41.750 | 44.370 |
| 42.250 | 44.350 |
| 42.750 | 44.330 |
| 43.250 | 44.300 |
| 43.750 | 44.280 |
| 44.250 | 44.260 |
| 44.750 | 44.240 |
| 45.250 | 44.210 |
| 45.750 | 44.190 |
| 46.250 | 44.170 |
| 46.750 | 44.140 |
| 47.250 | 44.120 |
| 47.750 | 44.100 |
| 48.000 | 44.070 |

Name: 100-024 Node: SC-3010 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 45.860 |
| 0.500 | 46.020 |
| 1.000 | 46.080 |
| 1.500 | 46.090 |
| 2.000 | 46.100 |
| 2.500 | 46.110 |
| 3.000 | 46.110 |
| 3.500 | 46.120 |
| 4.000 | 46.120 |
| 4.500 | 46.120 |
| 5.000 | 46.130 |
| 5.500 | 46.130 |
| 6.000 | 46.130 |
| 6.500 | 46.140 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 7.000 | 46.150 |
| 7.500 | 46.150 |
| 8.000 | 46.170 |
| 8.500 | 46.180 |
| 8.750 | 46.190 |
| 9.000 | 46.200 |
| 9.250 | 46.220 |
| 9.500 | 46.230 |
| 9.750 | 46.250 |
| 10.000 | 46.270 |
| 10.250 | 46.290 |
| 10.500 | 46.320 |
| 10.750 | 46.330 |
| 11.000 | 46.330 |
| 11.250 | 46.340 |
| 11.500 | 46.360 |
| 11.750 | 46.440 |
| 12.000 | 46.630 |
| 12.250 | 46.860 |
| 12.500 | 47.030 |
| 12.750 | 47.140 |
| 13.000 | 47.210 |
| 13.250 | 47.270 |
| 13.500 | 47.310 |
| 13.750 | 47.350 |
| 14.000 | 47.390 |
| 14.250 | 47.430 |
| 14.500 | 47.460 |
| 14.750 | 47.480 |
| 15.000 | 47.500 |
| 15.250 | 47.520 |
| 15.500 | 47.540 |
| 15.750 | 47.560 |
| 16.000 | 47.600 |
| 16.250 | 47.750 |
| 16.750 | 48.370 |
| 17.250 | 48.910 |
| 17.750 | 49.200 |
| 18.250 | 49.380 |
| 18.750 | 49.510 |
| 19.250 | 49.610 |
| 19.750 | 49.700 |
| 20.250 | 49.770 |
| 20.750 | 49.830 |
| 21.250 | 49.890 |
| 21.750 | 49.890 |
| 22.250 | 49.910 |
| 22.750 | 49.940 |
| 23.250 | 49.950 |
| 23.750 | 49.960 |
| 24.250 | 49.970 |
| 24.750 | 49.960 |
| 25.250 | 49.950 |
| 25.750 | 49.950 |
| 26.250 | 49.950 |
| 26.750 | 49.950 |
| 27.250 | 49.950 |
| 27.750 | 49.950 |
| 28.250 | 49.940 |
| 28.750 | 49.940 |
| 29.250 | 49.940 |
| 29.750 | 49.940 |
| 30.250 | 49.940 |
| 30.750 | 49.930 |
| 31.250 | 49.920 |
| 31.750 | 49.910 |
| 32.250 | 49.900 |
| 32.750 | 49.890 |
| 33.250 | 49.890 |
| 33.750 | 49.870 |
| 34.250 | 49.840 |
| 34.750 | 49.810 |
| 35.250 | 49.770 |
| 35.750 | 49.740 |
| 36.250 | 49.700 |
| 36.750 | 49.660 |
| 37.250 | 49.620 |
| 37.750 | 49.580 |
| 38.250 | 49.530 |
| 38.750 | 49.490 |
| 39.250 | 49.450 |
| 39.750 | 49.410 |
| 40.250 | 49.370 |
| 40.750 | 49.340 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 41.250 | 49.300 |
| 41.750 | 49.260 |
| 42.250 | 49.220 |
| 42.750 | 49.180 |
| 43.250 | 49.140 |
| 43.750 | 49.100 |
| 44.250 | 49.070 |
| 44.750 | 49.040 |
| 45.250 | 49.010 |
| 45.750 | 48.980 |
| 46.250 | 48.950 |
| 46.750 | 48.920 |
| 47.250 | 48.890 |
| 47.750 | 48.870 |
| 48.000 | 48.840 |

Name: 100-024 Node: SC-5000 Type: Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.000 | 41.060 |
| 0.500 | 41.060 |
| 1.000 | 41.060 |
| 1.500 | 41.060 |
| 2.000 | 41.060 |
| 2.500 | 41.060 |
| 3.000 | 41.060 |
| 3.500 | 41.140 |
| 4.000 | 41.280 |
| 4.500 | 41.420 |
| 5.000 | 41.600 |
| 5.500 | 41.810 |
| 6.000 | 42.000 |
| 6.500 | 42.190 |
| 7.000 | 42.380 |
| 7.500 | 42.530 |
| 8.000 | 42.680 |
| 8.500 | 42.800 |
| 8.750 | 42.870 |
| 9.000 | 42.940 |
| 9.250 | 43.020 |
| 9.500 | 43.080 |
| 9.750 | 43.140 |
| 10.000 | 43.200 |
| 10.250 | 43.370 |
| 10.500 | 43.370 |
| 10.750 | 43.430 |
| 11.000 | 43.500 |
| 11.250 | 43.540 |
| 11.500 | 43.610 |
| 11.750 | 43.920 |
| 12.000 | 44.160 |
| 12.250 | 44.250 |
| 12.500 | 44.260 |
| 12.750 | 44.220 |
| 13.000 | 44.240 |
| 13.250 | 44.400 |
| 13.500 | 44.650 |
| 13.750 | 44.870 |
| 14.000 | 45.020 |
| 14.250 | 45.170 |
| 14.500 | 45.290 |
| 14.750 | 45.370 |
| 15.000 | 45.460 |
| 15.250 | 45.500 |
| 15.500 | 45.500 |
| 15.750 | 45.470 |
| 16.000 | 45.410 |
| 16.250 | 45.350 |
| 16.750 | 45.250 |
| 17.250 | 45.140 |
| 17.750 | 45.030 |
| 18.250 | 44.910 |
| 18.750 | 44.800 |
| 19.250 | 44.690 |
| 19.750 | 44.600 |
| 20.250 | 44.510 |
| 20.750 | 44.420 |
| 21.250 | 44.350 |
| 21.750 | 44.280 |
| 22.250 | 44.220 |
| 22.750 | 44.170 |
| 23.250 | 44.120 |

** ALL ELEVATIONS ARE REFERENCED TO THE NAVD VERTICAL DATUM**

| | |
|---|---|
| 23.750 | 44.050 |
| 24.250 | 43.970 |
| 24.750 | 43.860 |
| 25.250 | 43.730 |
| 25.750 | 43.640 |
| 26.250 | 43.600 |
| 26.750 | 43.580 |
| 27.250 | 43.560 |
| 27.750 | 43.540 |
| 28.250 | 43.530 |
| 28.750 | 43.510 |
| 29.250 | 43.510 |
| 29.750 | 43.510 |
| 30.250 | 43.510 |
| 30.750 | 43.490 |
| 31.250 | 43.470 |
| 31.750 | 43.450 |
| 32.250 | 43.420 |
| 32.750 | 43.420 |
| 33.250 | 43.330 |
| 33.750 | 42.350 |
| 34.250 | 42.110 |
| 34.750 | 42.050 |
| 35.250 | 42.020 |
| 35.750 | 42.000 |
| 36.250 | 41.980 |
| 36.750 | 41.960 |
| 37.250 | 41.950 |
| 37.750 | 41.930 |
| 38.250 | 41.920 |
| 38.750 | 41.910 |
| 39.250 | 41.900 |
| 39.750 | 41.890 |
| 40.250 | 41.880 |
| 40.750 | 41.870 |
| 41.250 | 41.870 |
| 41.750 | 41.860 |
| 42.250 | 41.860 |
| 42.750 | 41.850 |
| 43.250 | 41.850 |
| 43.750 | 41.840 |
| 44.250 | 41.840 |
| 44.750 | 41.840 |
| 45.250 | 41.830 |
| 45.750 | 41.830 |
| 46.250 | 41.830 |
| 46.750 | 41.830 |
| 47.250 | 41.830 |
| 47.750 | 41.820 |
| 48.000 | 41.820 |

# Summary of ICPR Flood Routing Results for the 100-Year / 96-Hour Storm Event (Group "Grace Lake") Initial Stage => Elevation 62.6-FT, NAVD

| Node Name | SJRWMD ERP 3/14 Model Max Stage (ft) (1) | Updated Existing Model Max Stage (ft) (2) | Delta (2) - (1) | Proposed Model Max Stage (ft) (3) | Delta (3) - (2) |
|---|---|---|---|---|---|
| SC-0750 | 52 | 52 | 0 | 52.00 | 0.00 |
| SC-0760 | 56.22 | 56.21 | -0.01 | 56.17 | -0.04 |
| SC-0770 | 58.77 | 58.77 | 0 | 58.76 | -0.01 |
| SC-0780 | 64.44 | 64.24 | -0.2 | 64.24 | 0.00 |
| SC-0790 | 64.44 | 64.11 | -0.33 | 64.00 | -0.11 |
| SC-0800 | 58.79 | 58.78 | -0.01 | 58.77 | -0.01 |
| SC-0810 | 58.82 | 58.82 | 0 | 58.80 | -0.02 |
| SC-0815 | 58.79 | 58.78 | -0.01 | | - |
| SC-0820 | 58.79 | 58.78 | -0.01 | | - |
| SC-0830 | 59.85 | 59.81 | -0.04 | 59.61 | -0.20 |
| SC-0840 | 59.86 | 59.82 | -0.04 | 59.62 | -0.20 |
| SC-0850 | 60.96 | 60.91 | -0.05 | 60.69 | -0.22 |
| SC-0860 | 62.04 | 61.99 | -0.05 | 61.74 | -0.25 |
| SC-0870 | 64.88 | 64.88 | 0 | 64.81 | -0.07 |
| SC-0875 | 66.11 | 66.11 | 0 | 66.03 | -0.08 |
| SC-0880 | 66.17 | 66.16 | -0.01 | 66.08 | -0.08 |
| SC-0890 | 66.84 | 66.83 | -0.01 | | - |
| SC-0900 | 66.83 | 66.82 | -0.01 | 66.73 | -0.09 |
| SC-0910 | 66.83 | 66.82 | -0.01 | 66.73 | -0.09 |
| SC-0920 | 66.84 | 66.83 | -0.01 | 66.73 | -0.10 |
| SC-0925 | 78.79 | 78.79 | 0 | 78.79 | 0.00 |
| SC-0930 | 66.87 | 66.84 | -0.03 | 66.74 | -0.10 |
| SC-0940 *** | 69.07 | 68.61 | -0.46 | 69.34 | 0.73 |
| SC-0950 | 69.44 | 69.16 | -0.28 | | - |
| SC-0960 | 70.4 | 70.38 | -0.02 | | - |
| SC-0970 | 72.09 | 71.82 | -0.27 | | - |
| SC-0980 | 77.26 | 77.28 | 0.02 | 77.24 | -0.04 |
| SC-0985 | 77.28 | 77.29 | 0.01 | 77.25 | -0.04 |
| SC-0990 | 72.66 | 72.66 | 0 | 72.66 | 0.00 |
| SC-0995 | 86.23 | 86.23 | 0 | 86.23 | 0.00 |
| SC-POND300 | ** | ** | ** | 58.78 | - |
| SC-POND301 | ** | ** | ** | 58.78 | - |

* This Node was removed in the proposed model.

** This Node was added in the proposed model.

*** Node SC0940 is increased in the proposed condition, however this increase is contained within the FDOT R/W.


Existing Permits


ERP # 22434-1

Datum = NGVD 29

RECEIVED
JUN 15 1994
4/17039806
RECORDS
ORLANDO

| STATE PROJ. NO. | SHEET NO. |
|---|---|
| 77160-3601 | 3 |




## DRAINAGE STRUCTURES

| STRUCTURE NO. | SUB-BASIN AREA (Ac.) |
|---|---|
| B-1 | 1.53 |
| B-2 | 0.24 |
| B-3 | 3.14 |
| B-4 | 0.16 |
| B-5 | 0.36 |
| B-7 | 0.32 |
| B-8 | 0.27 |
| B-9 | 0.37 |
| B-10 | 0.37 |
| B-11 | 5.06 |
| B-12 | 0.32 |
| B-13 | 0.32 |
| B-14 | 0.30 |
| B-15 | 1.43 |
| B-20 | 9.32 |
| C-1 | 2.69 |
| C-2 | 0.56 |
| C-3 | 0.16 |
| C-4 | 5.89 |
| C-5 | 1.90 |
| C-6 | 5.12 |
| C-7 | 0.38 |
| C-8 | 5.44 |
| C-9 | 0.34 |
| C-11 | 1.47 |
| E-1 | 1.27 |

| REVISIONS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |
| | | | | | | | | |

| AERIAL PHOTOGRAPHY DATA | |
|---|---|
| FLOWN BY | F.D.O.T. |
| PHOTO DATE | 2-13-93 |
| PHOTO ID. NO. | P.D. 4125 3-08 |

| | NAME | DATE | | NAME | DATE |
|---|---|---|---|---|---|
| DESIGNED BY | MAJ | 7/93 | DRAWN BY | GIY | 7/93 |
| CHECKED BY | BAK | 7/93 | CHECKED BY | BAK | 7/93 |

SUPERVISED BY : KENNETH A CARPER, PE

FLORIDA DEPARTMENT OF TRANSPORTATION

APPROVED BY :


DATE :

# DRAINAGE MAP

Datum = NGVD 29

| STATE PROJ. NO. | SHEET |
|---|---|
| 77160-3601 | 4 |

| STRUCTURE NO. | DESIGN FLOOD STAGE | DESIGN FLOOD DISCHARGE | BASE FLOOD STAGE | BASE FLOOD DISCHARGE | OVERTOPPING FLOOD STAGE | OVERTOPPING FLOOD DISCHARGE | GREATEST FLOOD STAGE | GREATEST FLOOD DISCHARGE | GREATEST FLOOD VEL. | GREATEST FLOOD FREQ. |
|---|---|---|---|---|---|---|---|---|---|---|
| (88) | 65.30 | 65.07 | 80.80 | 68.92 | | | 137.40 | 76.44 | 0.2 | 500 |
| (91) | 108.10 | 58.88 | 133.60 | 59.75 | | | 227.1 | 65.03 | 0.2 | 500 |





**DEFINITIONS**

DESIGN FLOOD: THE FLOOD SELECTED BY THE F.D.O.T. TO BE UTILIZED TO ASSURE A STANDARD LEVEL OF HYDRAULIC PERFORMANCE.

BASE FLOOD: THE FLOOD HAVING A 1% CHANCE OF BEING EXCEEDED IN ANY YEAR (100-YEAR FREQUENCY).

OVERTOPPING FLOOD: THE FLOOD WHERE FLOOD OCCURS OVER THE HIGHWAY, OVER A WATERSHED DIVIDE OR THRU EMERGENCY RELIEF STRUCTURES.

GREATEST FLOOD: THE MOST SEVERE FLOOD WHICH CAN BE PREDICTED WHERE OVERTOPPING IS NOT PRACTICABLE. NORMALLY ONE WITH A 0.2% CHANCE OF BEING EXCEEDED IN ANY YEAR (500-YEAR FREQUENCY).




| REVISIONS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |
| | | | | | | | | |

| AERIAL PHOTOGRAPHY DATA | |
|---|---|
| FLOWN BY | F.D.O.T. |
| PHOTO DATE | 2-13-93 |
| PHOTO ID. NO. | P.D. 4125 3-08 |

| | NAME | DATE | | NAME | DATE |
|---|---|---|---|---|---|
| DESIGNED BY | MAJ | 7/93 | DRAWN BY | GIY | 7/93 |
| CHECKED BY | BAK | 7/93 | CHECKED BY | BAK | 7/93 |

SUPERVISED BY : KENNETH A. CARPER, PE

FLORIDA DEPARTMENT OF TRANSPORTATION

APPROVED BY :


DATE :


# DRAINAGE MAP

| STATE PROJ. NO. | SHEET NO. |
|---|---|
| 77160-3601 | 51 |

4-117-0398AG X


Datum = NGVD 29








E-9


PLAN VIEW
TYPE D SPECIAL
N.T.S.





SECTION A-A
N.T.S.




SECTION B-B
N.T.S.




POND E TYPICAL SECTION A-A





POND E TYPICAL SECTION B-B

E.S.H.W. 55.50 TO 59.00

NOTES:

1. MINIMUM RADIUS FOR CURVES IS 5 FEET. CURVES BELOW TOP OF BERM CONTOUR ARE CONCENTRIC.
2. SKIMMERS SHALL BE CONSTRUCTED OF 3/16" FIBERGLASS, STAINLESS STEEL TUBING, REINFORCED PLASTIC PLATES AND ANGLES, CONNECTED BY EPOXY BONDING AND NON-METALLIC RIVETS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. PLASTIC ANGLES SHALL BE ATTACHED TO THE CONCRETE WITH STAINLESS STEEL BOLTS. ALL WORK SHALL CONFORM TO THE SPECIAL SPECIFICATIONS.
3. SKIMMER SHALL EXTEND FROM 6" BELOW WEIR CREST TO 6" TOP OF STRUCTURE
4. SKIMMER BLADE, WEIR, ORIFICE, CONCRETE PAD ETC. TO BE INCLUDED IN CONTRACT UNIT PRICE FOR CONTROL STRUCTURE.

Robert C. Alderman
12-7-94




| REFERENCE POINT | ℄ I-4 (SR 400) STATION | OFFSET |
|---|---|---|
| 1 | 283+29.85 | 100.00'RT. |
| 2 | 288+26.85 | 100.00'RT. |
| 3 | 288+48.75 | 167.25'RT. |
| 4 | 287+64.10 | 213.78'RT. |
| 5 | 287+10.70 | 210.00'RT. |
| 6 | 285+82.30 | 220.31'RT. |
| 7 | 285+40.65 | 249.13'RT. |
| 8 | 284+17.95 | 250.00'RT. |
| 9 | 284+00.95 | 244.70'RT. |
| 10 | 283+83.70 | 232.83'RT. |
| 11 | 283+76.70 | 226.09'RT. |
| 12 | 283+09.15 | 139.14'RT. |

H:\VOIDS\VOIDS VETAROOS.DGN
DGN Jun. 23, 1993 08:32:43
MS/PC 4.0.3.1

F:\...\Proj (1-74)20.07 1994
H:\VOIDS\Voids Vetaroos.dgn
H:\VOIDS\Voids Vetaroos.prf
F:\USABLE\spenfont.rbl

| REVISIONS | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |
| | | | | | | | | | | | |

| | NAME | DATE | | NAME | DATE |
|---|---|---|---|---|---|
| DESIGNED BY | R.C.A. | 8/94 | DRAWN BY | R.T.M. | 8/94 |
| CHECKED BY | R.D.M. | 8/94 | CHECKED BY | R.C.A. | 8/94 |

SUPERVISED BY : KENNETH A. CARPER, P.E.


FLORIDA DEPARTMENT OF TRANSPORTATION
APPROVED BY :
DATE :

Greiner

POND E DETAIL


| STATE PROJ. NO. | SHEET NO. |
|---|---|
| 77160-3601 | 52 |

NOTES:
1. MINIMUM RADIUS FOR CURVES IS 5 FEET. CURVES BELOW TOP OF BERM CONTOUR ARE CONCENTRIC.
2. MAINTENANCE ACCESS AND MAINTENANCE BERM SHALL BE SOD ON 12" STABILIZED SUBGRADE TYPE "B" (LBR 40).
3. SKIMMERS SHALL BE CONSTRUCTED OF 3/16" FIBERGLASS, STAINLESS STEEL TUBING, REINFORCED PLASTIC PLATES AND ANGLES, CONNECTED BY EPOXY BONDING AND NON-METALLIC RIVETS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. PLASTIC ANGLES SHALL BE ATTACHED TO THE CONCRETE WITH STAINLESS STEEL BOLTS. ALL WORK SHALL CONFORM TO THE SPECIAL SPECIFICATIONS.
4. SKIMMER BLADE, WEIR, ORIFICE, CONCRETE PAD ETC. TO BE INCLUDED IN CONTRACT UNIT PRICE FOR CONTROL STRUCTURE.





PLAN


POND F OUTFALL WEIR DETAIL




SECTION A-A




POND F TYPICAL SECTION




Robert C. Alderman
12-9-94

| REFERENCE POINT | ℄ POND F STATION | OFFSET |
|---|---|---|
| 1 | 1+80.00 | 308.50'LT. |
| 2 | 3+38.00 | 318.50'LT. |
| 3 | 3+69.50 | 298.00'LT. |
| 4 | 4+39.50 | 103.00'LT. |
| 5 | 3+93.00 | 36.00'LT. |
| 6 | 2+15.50 | 36.50'LT. |
| 7 | 1+64.50 | 86.50'LT. |
| 8 | 1+66.00 | 148.50'LT. |
| 9 | 1+58.50 | 161.50'LT. |
| 10 | 1+22.50 | 202.00'LT. |
| 11 | 1+17.50 | 250.00'LT. |
| 12 | 1+39.00 | 282.00'LT. |

RECEIVED
DEC 07 1994
4-117-0398 AG
RECORDS
ORLANDO

| REVISIONS | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |
| | | | | | | | | | | | |

| | NAME | DATE | | NAME | DATE |
|---|---|---|---|---|---|
| DESIGNED BY | R.C.A. | 8/94 | DRAWN BY | R.T.M. | 8/94 |
| CHECKED BY | R.D.M. | 8/94 | CHECKED BY | R.C.A. | 8/94 |

SUPERVISED BY : KENNETH A. CARPER, P.E.

FLORIDA DEPARTMENT OF TRANSPORTATION
APPROVED BY :
DATE :

Greiner

# POND F DETAIL

Mon Nov 14 08:41:17 1994
H:\VOL80\PONDS\VETAROOK.DGN
DGN Jul. 28, 1993 10:06:16
MS/PC 4.0.3.1
H:\VOL80\PONDS\VETAROOK.dgn
H:\VOL80\ponds\vetarook.prt
H:\VOL80\ponds\vetarook.plt
H:\TABLE\support.tbl

RECEIVED
JUN 15 1994
4-117-0398 AC
RECORDS
ORLANDO

# INTERSTATE 4 WIDENING
## (S.R. 434 to Lake Mary Boulevard)
## State Project No. 77160-3601
## W.P.I. Number 5148825

Datum = NGVD 29

## VOLUME I
## Individual MSSW Permit Calculations

Seminole County, Florida

June, 1994

Datum = NGVD 29

## INTRODUCTION

The Florida Department of Transportation has retained the Orlando office of Greiner, Inc. to design and prepare construction plans for the widening of Interstate 4 from four (4) lanes to six (6) lanes beginning at S.R. 434 and ending at Lake Mary Boulevard, a distance of 3.98 miles. A key component of this project is the design of stormwater management facilities to serve the proposed improvements. There are eight water retention areas required for this project. Currently the Department owns two of the eight sites; therefore, six sites will require the purchase of additional right-of-way.

The purpose of this report is to present the design concepts and calculations to support a pre-development and post-development analysis of each basin. This report will enable the reviewer to examine the construction plans and determine the stormwater criteria has been satisfied.

Information utilized in the analysis included As-Built Plans for Interstate 4 (1961); St. Johns River Water Management District (SJRWMD) contour aerial photographs; the FDOT Location Hydraulics Report (March 1992) prepared for this project; USGS Quadrangle Maps; USDA Soil Conservation Service Soil Survey of Seminole County, Florida; FEMA Flood Insurance Rate Maps for Seminole County, Florida (Unincorporated Areas); and numerous field investigations.

## STORMWATER MANAGEMENT CRITERIA

Datum = NGVD 29

The project corridor is in west Seminole County, and it lies within the jurisdiction of the St. Johns River Water Management District (SJRWMD). The majority of the project lies within Most Effective Recharge Areas of the Wekiva River Hydrologic Basin, as defined by SJRWMD. Runoff from the southern portion of the roadway (S.R. 434 to 1,110 ft. south of E.E. Williamson Road) flows via existing ditch and/or storm sewer systems to the Little Wekiva River, which has been designated as an Outstanding Florida Water (O.F.W.) per Chapter 17-302.700(9)(i) F.A.C. Runoff from the remainder of the project flows to either a land-locked lake (ie: Grace Lake, Lake Myrtle) or an isolated depression with no positive outfall.

The stormwater management facilities for this project will be designed in conformance with the latest requirements of SJRWMD. In addition, the facilities must meet the requirements of Chapter 14-86 F.A.C. as established by FDOT.

A summary of the Stormwater Management Criteria applicable to the two (2) types of basins encountered in the project corridor is presented on the following pages.

# STORMWATER MANAGEMENT CRITERIA
# FOR
# SYSTEMS DISCHARGING TO
# OUTSTANDING FLORIDA WATERS (O.F.W'S)

Datum = NGVD 29

## A. WATER QUALITY - Basins A, B, and C

1. On-line retention systems discharging to an O.F.W. shall provide:
   a. Retention of 1.5 inches of runoff; or
   b. Retention of 2.625 inches of runoff from directly connected impervious areas; or
   c. Retention of runoff from a 3-year/1-hour storm;

   whichever is greater. Retention systems shall provide the capacity for the given volume of stormwater within 72 hours following the storm event assuming average antecedent conditions.

## B. RECHARGE

1. Retention systems in Most Effective Recharge Areas shall:
   a. Provide retention of 3.0 inches of runoff from the directly connected impervious areas; or
   b. Demonstrate that the post-development recharge will be equal to the pre-development recharge.

   Stormwater that is retained must be infiltrated into the soil or evaporated such that the storage volume is recovered within 14 days following a storm event.

## C. RUNOFF CONTROL VOLUME

Not applicable for systems with positive outfalls.

Datum = NGVD 29

## D. PEAK DISCHARGE

1. The post-development peak rate of discharge must not exceed the pre-development peak rate of discharge for the following events:
   a. 25-hear/24-hour storm; and
   b. Critical Duration (1-hour thru 10 day) storm for all frequencies (2-year thru 100-year); and
   c. Mean Annual, 24-hour storm IF the facility serves an area greater than 50% impervious surface (excluding water bodies).

Datum = NGVD 29

# STORMWATER MANAGEMENT CRITERIA
# FOR
# SYSTEMS DISCHARGING TO
# LAND-LOCKED BASINS

## A. WATER QUALITY - Basins F, G, I, and J

1. On-line retention systems shall provide:
   a. Retention of 1.0 inches of runoff; or
   b. Retention of 1.75 inches of runoff from the directly connected impervious areas;

   whichever is greater. Retention systems shall provide the capacity for the given volume of stormwater within 72 hours following the storm event assuming average antecedent conditions.

**Basin E**

2. Wet detention systems shall provide:
   a. Treatment for 1.0 inches of runoff; or
   b. Treatment for 2.5 inches of runoff from the impervious areas;

   whichever is greater. The outfall structure shall be designed to bleed down one-half the given volume of stormwater within 48-60 hours following a storm event, but no more than one-half of this volume will be discharged within the first 48 hours. Wet detention systems shall provide a 14 day residence time during the wet season (June-October), and at least 30% of the surface area shall be the littoral zone (6:1 or flatter).

## B. RECHARGE

1. Retention systems in Most Effective Recharge Areas shall:
   a. Provide retention of 3.0 inches of runoff from the directly connected impervious areas; or

Datum = NGVD 29

b. Demonstrate that the post-development recharge will be equal to the pre-development recharge.

Stormwater that is retained must be infiltrated into the soil or evaporated such that the storage volume is recovered within 14 days following a storm event.

## C. RUNOFF CONTROL VOLUME

1. The post-development volume of direct runoff must not exceed the pre-development volume of direct runoff for the following events:
   a. 25-year/96-hour storm; or P=12.96 inches
   b. 100-year, Critical Duration (1-hour thru 10-day) storm;

   whichever is greater. The retention volume must recover at a rate such that one-half of the volume is available within 7 days with the total volume available in 14 days.

## D. PEAK DISCHARGE

1. The post-development peak rate of discharge must not exceed the pre-development peak rate of discharge for the following events:
   a. 25-year/24-hour storm; and P=8.2 inches
   b. Critical Duration (1-hour thru 10 day) storm for all frequencies (2-year thru 100-year); and
   c. Mean Annual, 24-hour storm IF the facility serves an area with greater than 50% impervious surface (excluding water bodies).

Datum = NGVD 29

# TABLE 2

## SUMMARY OF PRE-DEVELOPMENT HYDROLOGIC PARAMETERS

| POST-DEV BASIN DESIGNATION | PRE-DEV BASIN DESIGNATION | BASIN AREA (ac) | CURVE NUMBER | TIME OF CONC. (min) | DISCHARGE 25-YR/24-HR (cfs) | DISCHARGE 25-YR/24-HR (cfs) |
|---|---|---|---|---|---|---|
| A | BASIN A | 13.89 | 59.60 | 30.00 | 25.28 | N/A |
| A | POND A | 1.18 | 30.00 | 23.18 | .013 | N/A |
| B | B - 201 | 10.33 | 74.40 | 22.20 | 35.31 | N/A |
| C | B - 208 | 7.94 | 53.10 | 42.40 | 8.45 | N/A |
| C | B - 210 | 20.18 | 47.40 | 61.20 | 11.79 | N/A |
| E | BASIN E | 6.20 | 54.50 | 31.60 | 10.79 | 16.28 |
| F | BASIN F | 5.89 | 48.20 | 34.00 | 6.94 | 12.39 |
| G | BASIN G | 19.45 | 51.81 | 29.30 | 31.30 | 49.60 |
| I | BASIN I | 18.07 | 53.50 | 34.00 | 28.14 | 44.21 |
| J | BASIN J | 23.96 | 47.70 | 73.70 | 15.43 | 29.64 |
| TOTALS | | 127.09 | | | | |

# TABLE 3

Datum = NGVD 29

## SUMMARY OF POST-DEVELOPMENT HYDROLOGIC PARAMETERS

| BASIN DESIGNATION | BASIN AREA (ac) | IMP. AREA (ac) | % IMP. AREA | CURVE NUMBER (cn) | TIME OF CONC. (min) | DISCHARGE 25-YR/24-HR (cfs) | DISCHARGE 25-YR/96-HR (cfs) |
|---|---|---|---|---|---|---|---|
| A | 15.91 | 7.62 | 47.9 | 67.30 | 26.33 | 49.35 | N/A |
| B | 25.95 | 10.95 | 42.2 | 63.90 | 32.83 | 62.59 | N/A |
| C | 20.80 | 8.22 | 39.5 | 62.30 | 49.80 | 35.04 | N/A |
| E | 6.20 | 3.59 | 57.9 | 77.30 | 31.60 | 21.48 | 23.73 |
| F | 5.89 | 2.71 | 46.0 | 66.10 | 34.00 | 14.83 | 18.75 |
| G | 19.89 | 6.55 | 32.9 | 58.40 | 29.30 | 42.66 | 59.64 |
| I | 18.08 | 6.35 | 35.1 | 59.70 | 34.00 | 36.92 | 51.31 |
| J | 29.92 | 7.80 | 26.1 | 54.40 | 73.70 | 27.56 | 45.30 |

[V018010.TABLE]

# TABLE 4

Datum = NGVD 29

## PEAK CONDITIONS HYDROGRAPH

| POST-DEV BASIN DESIGNATION | POST-DEV BASIN DESIGNATION | PRE-DEVELOPMENT | | POST-DEVELOPMENT | |
|---|---|---|---|---|---|
| | | DISCHARGE 25 yr/24 hr (cfs) | DISCHARGE(1) 25 yr/96 hr (cfs) | DISCHARGE 25 yr/24 hr (cfs) | DISCHARGE(1) 25 yr/96 hr (cfs) |
| A | BASIN A | 25.28 | N/A | N/A | N/A |
| A | POND A | 0.13 | N/A | N/A | N/A |
| B | B - 201 | 35.31 | N/A | 62.59 | N/A |
| C | B - 208 | 8.45 | N/A | 35.04 | N/A |
| C | B - 210 | 11.79 | N/A | N/A | N/A |
| E | (1) E | 10.79 | 16.28 | 21.48 | 23.73 |
| F | (1) F | 6.94 | 12.39 | 14.83 | 18.75 |
| G | (1) G | 31.30 | 49.60 | 42.66 | 59.64 |
| I | (1) I | 28.14 | 44.21 | 36.92 | 51.31 |
| J | (1) J | 15.43 | 29.64 | 27.56 | 45.30 |

# TABLE 5

Datum = NGVD 29

## PRE VS. POST ROUTING DISCHARGE DATA

| BASIN DESIGNATION | PRE-DEVELOPMENT | | POST-DEVELOPMENT | |
|---|---|---|---|---|
| | DISCHARGE 25 yr/96 hr (cfs) | DISCHARGE 25 yr/96 hr (cfs) | DISCHARGE 25 yr/24 hr (cfs) | DISCHARGE 25 yr/96 hr (cfs) |
| A | 49.26 | N/A | 40.14 | N/A |
| B | 16.90 | N/A | 11.17 | N/A |
| C | 14.66 | N/A | 12.70 | N/A |
| E | 10.79 | 16.28 | .20 | 1.85 |
| F | 6.94 | 12.39 | .41 | 1.67 |
| G | 31.30 | 49.60 | 2.01 | 14.53 |
| I | 28.14 | 44.21 | 2.70 | 15.94 |
| J | 15.43 | 29.64 | 0.00 | 0.00 |

# TABLE 6

Datum = NGVD 29

## SUMMARY OF REQUIRED RETENTION VOLUMES

| BASIN DESIGNATION | CRITERIA | POND TYPE WET/DRY | BASIN AREA (ac) | IMPERVIOUS AREA (ac) | OFW* | | | LANDLOCKED** | | | | VOLUME PROVIDED (ac-ft) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | 1.5 in | 2.625 in | 3.0 in *** | 1.0 in | 1.75 in | 2.5 in | 3.0 in *** | |
| A | OFW | DRY | 15.91 | 7.62 | 1.99 | 1.67 | 1.91 | | | | | 2.00 |
| B | OFW | DRY | 25.95 | 10.95 | 3.24 | 2.40 | 2.74 | | | | | 3.56 |
| C | OFW | DRY | 20.80 | 8.22 | 1.73 | 1.80 | 2.06 | | | | | 2.06 |
| E | LANDLOCKED | WET | 6.20 | 3.59 | | | | 0.53 | | 0.75 | | 0.77 |
| F | LANDLOCKED | DRY | 5.89 | 2.71 | | | | 0.49 | 0.40 | | 0.68 | 0.72 |
| G | LANDLOCKED | DRY | 19.89 | 6.55 | | | | 1.66 | 0.95 | | 1.64 | 3.40 |
| I | LANDLOCKED | DRY | 18.08 | 6.35 | | | | 1.51 | 0.93 | | 1.59 | 1.62 |
| J | LANDLOCKED | DRY | 29.93 | 7.8 | | | | 2.49 | 1.14 | | 1.95 | 2.08 |

* OFW - OUTSTANDING FLORIDA WATER
** LANDLOCKED - LANDLOCKED BASIN
*** RECHARGE VOLUME: 3.0"X DCIA

# TABLE 7

Datum = NGVD 29

## SUMMARY OF PRIMARY WATER CONTROL STRUCTURES

| POND | STRUCTURE TYPE (1) | WEIR ELEV. | WEIR LENGTH | METHOD OF RECOVERY | POND BOTTOM / CONTROL ELEV. |
|---|---|---|---|---|---|
| A | SCW | 55.80 | 3.00 | PERCOLATION | 51.00 |
| B | SCW | 53.50 | 3.00 | PERCOLATION | 51.00 |
| C | SCW | 63.00 | 3.00 | PERCOLATION | 60.00 |
| E | SCW | 64.70 | 3.00 | (qty = 1) 2* ORIFICE | 61.00 |
| F | BCW | 56.00 | 3.00 | PERCOLATION | 53.00 |
| G | SCW | 55.00 | 3.00 | PERCOLATION | 50.00 |
| I | SCW | 60.23 | 3.00 | PERCOLATION | 56.00 |
| J | SCW | 63.50 | 3.00 | PERCOLATION | 56.00 |

# TABLE 8

Datum = NGVD 29

## SUMMARY OF RETENTION VOLUME DRAWDOWN

| POND | DRAINAGE BASIN AREA (ac) | TREATMENT VOLUME REQUIRED (ac-ft) | TREATMENT VOLUME PROVIDED (ac-ft) | RECOVERY DURATION (hours) |
|---|---|---|---|---|
| A | 15.91 | 1.99 | 2.00 | 68.50 |
| B | 25.95 | 3.24 | 3.56 | 42.00 |
| C | 20.80 | 2.06 | 2.08 | 67.50 |
| E | 6.20 | 0.75 | 0.77 | 48.00 (1) |
| F | 5.89 | 0.68 | 0.72 | 2.00 |
| G | 19.89 | 1.66 | 3.40 | 4.50 |
| I | 18.08 | 4.59 | 1.62 | 70.50 |
| J | 24.07 | 2.49 | | 8.00 |

(1) BLEED DOWN ONE-HALF THE REQUIRED TREATMENT VOLUME IN 48 HOURS.

## BASIN E

Datum = NGVD 29

Basin E extends from Sta. 261+00 to Sta. 293+00. There is approximately 6.20 acres in the post-development drainage basin. The stormwater runoff is conveyed to Pond E via median ditch bottom inlets and storm sewer pipe. All widening is to be accomplished in the median with the cross slope of the proposed pavement toward the center line of I-4. No work is planned for the roadside ditches in this basin. Only proposed impervious areas in the basin will be treated in Pond E. The existing four lane section of I-4 will continue to drain to the outside roadway ditches and be carried away from I-4.

The location for Pond E is a heavily wooded parcel within the floodplain of Grace Lake, adjacent to the right (east) side of Interstate 4 (Sta. 284+00 to Sta. 289+00). The SCS Soil Survey indicates that Myakka and Eau Gallie fine sands are present at this location. These soils are classified in Hydrologic Soil Group B/D, and in their undrained condition exhibit groundwater levels at or near the surface. Pond E is be a wet detention system with a maintained water elevation equal to the normal water level of Grace Lake. Discharge from the pond will be dependent upon the level of Grace Lake. Pond E will serve as an extension of Grace Lake, providing additional floodplain storage to compensate for the new impervious areas and any existing storage that may be eliminated by placement of fill. According to the FEMA Maps in the vicinity of the pond location, the 100-year floodplain elevation is 66.00. The pond maintenance berm will displace approximately 388 cubic-feet of volume. However, Pond E will provide greater than 388 cubic-feet of compensating volume.

In order to maximize the flow-path through the pond and eliminate problems with short-circuiting, the pond is designed so that runoff enters from the south and discharges to the north. Pond E is designed in conformance with the Land-Locked Basin Criteria.

Pond E has a meandering shape due to an effort to save many of the native mature hardwood trees. These trees act as a visual and sound buffer for the Northridge and Northcove subdivision homeowners. See Table 8 in Section 2 for a summary of required retention volumes and drawdown results.

Datum = NGVD 29

# GREINER INC: WATER RESOURCES GROUP
## CURVE NUMBER AND RUNOFF VOLUME WORKSHEET

| | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I-4 WIDENING | FILENAME: | CNPR-PDE.WK3 | |
| PROJECT NUMBER: | V0187.10 | SCALE (1" = ) | 0 | DATE |
| BASIN DESIGNATION: | POND E | MADE BY: | MJJ | 28-Apr-94 |
| BASIN ANALYSIS (PRE/POST): | PRE | CHECKED BY: | RCG | [illegible] |

## SUB-BASIN ANALYSIS

1) BASIN / STUDY DATA

| | |
|---|---|
| PLANIMETERED BASIN AREA (in^2) | 0.00 |
| COMPUTED BASIN AREA (Ac) | 6.20 |
| RAINFALL (inches) - P | 18.84 |

## DETERMINE BASIN RUNOFFF CURVE NUMBER - CN

| LAND-USE DESCRIPTION | SOIL NAME | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|---|
| RANGE / GRASS BASIN I-4 | | | 39 | 4.11 | 160.29 |
| WOODS POND SITE | | | 80 | 1.50 | 120.00 |
| | | | | | |
| PAVEMENT BASIN I-4 | | | 98 | 0.59 | 57.82 |
| | | | | | |
| | | | | | |
| | | | TOTALS | 6.20 | 338.11 |

| | |
|---|---|
| COMPOSITE CN | 54.5 |

## ESTIMATE OF RUNOFF VOLUME

1) DETERMINE SOIL STORAGE - S

S = ( 1000 / CN ) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 8.34 |

2) DETERMINE RUNOFF - R

R = ( P - 0.2*S )^2 / ( P + 0.8*S)

| | | |
|---|---|---|
| RUNOFF (inches) | R | 11.56 |

3) DETERMINE RUNOFF VOLUME - V(R)

V(R) = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (Ac-ft) | V(R) | 5.97 |

Greiner

Datum = NGVD 29

Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Pond E Pre-development Time of Concentration | Computed By RCA | Date 6/94

Checked By ____ | Date ____

## Pre-dev. time of concentration

Due to the proposed widening to the inside, the pre-dev. $T_c$ is similar to the post-dev. $T_c$. The drainage patterns and basins are not altered due to the construction.

Due to the median ditch flow $T_c$ = 26.6 min

\+ 1100 LF of pipe flow = 5 min

31.6 min. ←

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

SJRWMD 25 YR \ 96 HR RAINFALL EVENT -- PRE-DEVELOPMENT--
12-16-93

Datum = NGVD 29

| | |
|---|---|
| BASIN NAME | BASINE |
| NODE NAME | PONDE |
| UNIT HYDROGRAPH | UH323 |
| PEAKING FACTOR | 323. |
| RAINFALL FILE | SJRWMD96 |
| RAIN AMOUNT (in) | 12.96 |
| STORM DURATION (hrs) | 96.00 |
| AREA (ac) | 6.20 |
| CURVE NUMBER | 54.50 |
| DCIA (%) | .00 |
| TC (mins) | 31.60 |
| LAG TIME (hrs) | .00 |
| BASIN STATUS | ONSITE |

| BASIN | QMX (cfs) | TMX (hrs) | VOL (in) | NOTES |
|---|---|---|---|---|
| BASINE | 16.28 | 60.18 | 6.49 | POND E BASIN PRE-DEVELOPMENT |


Greiner

Datum = NGVD 29

Job _____ Project No. _____ Sheet _____ of _____


Description _____ Computed By _____ Date _____

_____ Checked By _____ Date _____





Basin Characteristics:
Drainage Area = 6.20 ac.
CN = 77.3
$T_c$ = 31.6 min

Direct




Reach → E1

Drop Structure:
Weir 64.70 Pipe Length 168'
Length 3' U.S. Inv 60.5
Orifice 61.0 D.S. Inv 58.8
Dia. 2" Dia. 24




Post-Development Nodal Diagram

6-21

Datum = NGVD 29

# GREINER INC: WATER RESOURCES GROUP
## CURVE NUMBER AND RUNOFF VOLUME WORKSHEET

| | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I-4 WIDENING | FILENAME: | CN-PONDE.WK3 | |
| PROJECT NUMBER: | V0187.10 | SCALE (1" = _) | 0 | DATE |
| BASIN DESIGNATION: | POND E | MADE BY: | MJJ | 28-Apr-94 |
| BASIN ANALYSIS (PRE/POST): | POST | CHECKED BY: | ACC | [illegible] |

## SUB-BASIN ANALYSIS

1) BASIN / STUDY DATA

| | |
|---|---|
| PLANIMETERED BASIN AREA (in^2) | 0.00 |
| COMPUTED BASIN AREA (Ac) | 6.20 |
| RAINFALL (inches) - P | 18.84 |

## DETERMINE BASIN RUNOFFF CURVE NUMBER - CN

| LAND-USE | DESCRIPTION | SOIL NAME | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|---|---|
| RANGE / GRASS | BASIN I-4 | | | 39 | ✓1.11 | 43.29 |
| | POND SITE | | | 39 | ✓1.08 | 42.12 |
| | | | | | | |
| PAVEMENT | BASIN I-4 | | | 98 | ✓3.59 | 351.82 |
| | POND SITE | | | 98 | 0 | 0.00 |
| WATER | POND SITE | | | 100 | ✓0.42 | 42.00 |
| | | | | TOTALS | ✓6.20 | 479.23 |

| | |
|---|---|
| COMPOSITE CN | 77.3 |

## ESTIMATE OF RUNOFF VOLUME

1) DETERMINE SOIL STORAGE - S

S = ( 1000 / CN ) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 2.94 |

2) DETERMINE RUNOFF - R

R = ( P - 0.2*S )^2 / ( P + 0.8*S)

| | | |
|---|---|---|
| RUNOFF (inches) | R | 15.72 |

3) DETERMINE RUNOFF VOLUME - V(R)

V(R) = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (Ac-ft) | V(R) | ✓8.12 |

Datum = NGVD 29

# ST JOHN'S RIVER WATER MANAGEMENT DISTRICT

## POLLUTION ABATEMENT VOLUME REQUIREMENT

## OFFLINE RETENTION

## POND E

| POST DEVELOPMENT LAND USE | |
|---|---|
| 1) IMPERVIOUS AREA (Ac.) | 3.59 |
| 2) PERVIOUS AREA (Ac.) | 2.61 |
| 3) TOTAL AREA (Ac.) | 6.20 |

| POLLUTION ABATEMENT VOLUME (REQUIRED) | | (Ac-ft) |
|---|---|---|
| 1) 1.0 inch OF RUNOFF OVER ENTIRE AREA | 1.0" / (12" / 1 ft) * (TOTAL AREA) = | 0.52 |
| 2) 2.5 inches OVER THE IMPERVIOUS AREA | 2.5" / (12" / 1 ft) * (IMP. AREA) = | 0.75 |
| 3) 3 year / 1 Hour STORM EVENT RUNOFF | SEE CURVE NUMBER SHEET | N/A |
| 4) POLLUTION ABATEMENT VOLUME (REQUIRED) | | 0.75 |

| RECHARGE VOLUME (REQUIRED) | | (Ac-ft) |
|---|---|---|
| 1) POST-DEVELOPMENT IMPERVIOUS AREA | | 3.59 |
| 2) PRE-DEVELOPMENT IMPERVIOUS AREA | | 0.59 |
| 4) RECHARGE VOLUME (REQUIRED) | (3.0 " / (12" / 1 FT) * (IMP. DELTA) | 0.90 |

| GREINER INC: WATER RESOURCES GROUP<br>POLLUTION ABATEMENT/ RECHARGE VOLUME CALCULATIONS | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I - 4 WIDENING | FILENAME: | PAVPONDE.WK3 | |
| PROJECT NUMBER: | V0180.10 | SCALE (1" = _) | 200 | DATE |
| BASIN DESIGNATION: | POND E | MADE BY: | MJJ | 29-Apr-94 |
| ANALYSIS (PRE/POST): | POST | CHECKED BY: | RCG | 1-29-94 |

Datum = NGVD 29

GREINER INC: WATER RESOURCES GROUP

POND STAGE STORAGE CALCULATIONS – POND E

| | | | | | |
|---|---|---|---|---|---|
| PROJECT TITLE: | I – 4 WIDENING | FILENAME: | SSPONDE.WK3 | | |
| PROJECT NUMBER: | V0180.10 | SCALE (1" =__) | 200 | DATE | |
| BASIN DESIGNATION: | POND E | MADE BY: | MJJ | 09–Jun–94 | |
| BASIN ANALYSIS (PRE/POST): | POST | CHECKED BY: | | | |

| ELEV. | PLAN. VALUE 1 (si) | PLAN. VALUE 2 (si) | AREA (ac) | AVE. AREA (ac) | DELTA D (ft) | DELTA STORAGE (ac–ft) | STORAGE P.A.V.* (ac–ft) | ATTENUATION OF PEAK DISCHARGE (ac–ft) |
|---|---|---|---|---|---|---|---|---|
| 53.00 | 0.104 | 0.081 | 0.085 | | | | 0 | 0 |
| | | | | 0.17 | 6 | 1.04 | | |
| 59.00 | 0.283 | 0.286 | 0.261 | | | | 1.04 | 1.04 |
| | | | | 0.33 | 1 | 0.33 | | |
| 60.00 | | | 0.395 | | | | 1.37 | 1.37 |
| | | | | 0.46 | 1 | 0.46 | | |
| 61.00 | 0.569 | 0.579 | 0.527 | | | | 1.83 | *** 1.83 |
| | | | | 0.59 | 1 | 0.59 | | |
| 62.00 | | | 0.660 | | | | 0.59 | 0.59 |
| | | | | 0.69 | 0.5 | 0.35 | | |
| 62.50 | 0.789 | 0.796 | 0.728 | | | | 0.94 | 0.94 |
| | | | | 0.79 | 0.5 | 0.39 | | |
| 63.00 | | | 0.851 | | | | 1.34 | 1.34 |
| | | | | 0.91 | 1 | 0.91 | | |
| 64.00 | | | 0.973 | | | | 2.25 | 2.25 |
| | | | | 1.00 | 0.7 | 0.70 | | |
| 64.70 | | | 1.034 | | | | 2.95 | ** 2.95 |
| | | | | 1.12 | 0.8 | 0.89 | | |
| 65.50 | 1.302 | 1.313 | 1.201 | | | | 3.84 | 3.84 |
| | | | | 1.28 | 0.5 | 0.64 | | |
| 66.00 | | | 1.368 | | | | 4.49 | 4.49 |
| | | | | 1.41 | 1 | 1.41 | | |
| 67.00 | 1.589 | 1.572 | 1.451 | | | | 5.89 | 5.90 |
| | | | | | | | | |

* P.A.V. = POLLUTION ABATEMENT VOLUME.
** VOLUME IS BASED ON POLLUTION ABATEMENT AND LANDLOCKED CONTROL VOLUME.
*** PERMANENT POOL VOLUME.

Greiner

Datum = NGVD 29

Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Pond E Tailwater Info | Computed By RCA | Date 6/94

Checked By ____ | Date ____


Pond E discharges to Grace Lake. Grace Lake is located in a land-locked basin and Pond E is located with sufficient vertical clearance from Grace Lake that Grace Lake has no effect on the tailwater associated with Pond E.

**Greiner**

Datum = NGVD 29

Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Pond E Control Structure | Computed By RCG | Date 12-14-93 | Checked By MJS | Date 12-93





Treatment Volume = 0.75 ac-ft  Treatment Volume depth = 1.25'

Criteria:

Bleed down ½ the pollution abatement volume with in 48 to 60 hours but no more than ½ of this volume with in the first 48 hrs.

one-half × pollution abatement volume = ½ × 0.75 = 0.38 ac-ft




$\bar{H} = (64.70 + 61.083)/2 = 62.89 - 61.083 = 1.809'$

$t = 48 \text{ hours} \times 3600 \frac{\text{sec}}{\text{hr}} = 172{,}800 \text{ sec}$

$Q = \frac{0.38 \text{ ac-ft} \times 43{,}560}{172{,}800 \text{ sec.}} = 0.0958 \text{ cfs}$

Orifice eq'n:

$Q = C A \sqrt{2gH}$

$A = \frac{0.0958}{0.6\sqrt{2(32.2)(1.809)}} = 0.0148 \text{ ft}^2$  .026

the diameter of an orifice

$A = \frac{\pi d^2}{4} = 0.0148 \text{ ft}^2$

$d = 1.65 \text{ in}$  dia. ⇒ 2.0"

Greiner

Datum = NGVD 29


Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Pond E Control Structure | Computed By RCA | Date 12-14-93

Checked By MAJ | Date 12-93

Check computer model Adicpr for recovery data on Pond E

Recover 0.38 ac-ft in 48 hours:




recovery clock begins @ hour 29.75 during the storm
add 48 hours and check volume remaining in Pond E

Check ADICPR output → 29.75 + 48.00 = 77.75 hour Stage = 61.64 Volume = 0.38 ac-ft

**Greiner**

Datum = NGVD 29

Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Pond E Control Structure | Computed By RCQ | Date 12-14-93 | Checked By MJJ | Date 12-93

Check permanent pool volume:

Calculate runoff coefficient:

Sta. 261+50 to Sta. 293+60 ⟹ 3150 LF

| | | C | |
|---|---|---|---|
| 49' pav't | × 3150 = 3.54 ac. × | 0.95 | 3.36 |
| 15' grass | × 3150 = 1.08 ac. × | 0.30 | 0.32 |
| water El. 61.0 | = 0.53 ac. × | 1.00 | 0.53 |
| Berm pond E @ 67.0 | = 0.92 ac. × | 0.30 | 0.28 |
| | Σ 6.10 ac. | | Σ = 4.49 |

weighted $\bar{C} = \frac{C \times A}{A}$

$= \frac{4.49}{6.10} = 0.74$

2 week residence time during the wet season = 14 days / 153 days

Min. permanent pool volume $= \frac{(6.20 \text{ ac.})(0.74)(32 \text{ in})(14/153)}{12 \text{ in/ft}} = 1.12 \text{ ac-ft}$ ←

Pond E volume below an elevation of 61.0 feet is:

| El. | Area | Vol ac-ft |
|---|---|---|
| 53.0 | 0.085 | 1.04 |
| 59.0 | 0.261 | 0.79 |
| 61.0 | 0.529 | |
| | | 1.83 ac-ft ← |

Perm. Pool Req'd = 1.12 ac-ft << Perm. Pool Avail. = 1.83 ac-ft ✓

| JOB: | I – 4 WIDENING | PROJECT NO.: | V0180.10 | | |
|---|---|---|---|---|---|
| DESCRIPTION: | POST DEVELOPMENT CALCULATIONS AND | COMPUTED BY: | MJJ | DATE: | 09–Dec–93 |
| | DITCH PROFILES FOR POND "E" | CHECKED BY: | | DATE: | |

| | |
|---|---|
| Right Side | |
| Median | XX |
| Left Side | |

Overall Basin Length: 261 + 00 to 293 + 00
Sub–Basin 1: 261 + 00 to 287 + 50
Sub–Basin 2: 293 + 00 to 287 + 50

| | |
|---|---|
| Rainfall Zone: | 7 |
| Frequency: | 25 |

Datum = NGVD 29

| SECTION INFORMATION | | | | | DITCH GEOMETRY | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Station to Station | | | Length | Slope | TOTAL (CA) | Time of Conc. | Inten–sity | Flow Q | Front Slope | Bottom Width | Back Slope | *** n | Depth | Calc'd Vel. | Section Flow Time | Lining | Remarks |
| Begin | | End | (ft) | % | (Ac) | (min) | (in/hr) | (CFS) | (ft/ft) | (ft) | (ft/ft) | | (ft) | (ft/sec) | (min) | (Y/N) | |
| 261 | | 262 | 100 | 0.30 | 0.117 | 10.00 | 8.26 | 0.97 | 6 | | 10 | 0.060 | 0.48 | 0.52 | 3.2 | | |
| 262 | | 264 | 200 | 0.90 | 0.352 | 13.21 | 7.54 | 2.65 | 6 | | 10 | 0.060 | 0.57 | 1.01 | 3.3 | | |
| 264 | | 266 | 200 | 1.55 | 0.586 | 16.51 | 6.95 | 4.07 | 6 | | 10 | 0.060 | 0.60 | 1.38 | 2.4 | | |
| 266 | | 268 | 200 | 1.55 | 0.820 | 18.92 | 6.59 | 5.41 | 6 | | 10 | 0.060 | 0.67 | 1.48 | 2.3 | | |
| 268 | | 270 | 200 | 1.55 | 1.055 | 21.17 | 6.30 | 6.65 | 6 | | 10 | 0.042 | 0.63 | 2.04 | 1.6 | | |
| 270 | | 272 | 200 | 1.55 | 1.289 | 22.81 | 6.11 | 7.87 | 6 | | 10 | 0.042 | 0.67 | 2.13 | 1.6 | | |
| 272 | | 274 | 200 | 0.55 | 1.524 | 24.37 | 5.93 | 9.04 | 6 | | 10 | 0.042 | 0.86 | 1.50 | 2.2 | | |
| | | | | | | 26.59 | 5.71 | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| 274 | | 276 | 200 | 0.55 | 0.234 | 10.00 | 8.26 | 1.94 | 6 | | 10 | 0.060 | 0.55 | 0.78 | 4.3 | | |
| 276 | | 278 | 200 | 0.55 | 0.469 | 14.27 | 7.33 | 3.44 | 6 | | 10 | 0.060 | 0.69 | 0.90 | 3.7 | | |
| | | | | | | 17.98 | 6.73 | | | | | | | | | | |

*** If the calculated value D < 0.7 ft., use Manning's n = 0.06
If the calculated value D >= 0.7 ft., use Manning's n = 0.042

6-29

Basin E $T_c$ = 26.6 min + 1100 LF of pipe to Pond E (5 min) = 31.6 min

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

25YR-96HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

| | |
|---|---|
| BASIN NAME | BASINE |
| NODE NAME | PONDE |
| UNIT HYDROGRAPH | UH323 |
| PEAKING FACTOR | 323. |
| RAINFALL FILE | SCSII-24 |
| RAIN AMOUNT (in) | 12.20 |
| STORM DURATION (hrs) | 96.00 |
| AREA (ac) | 6.20 |
| CURVE NUMBER | 77.30 |
| DCIA (%) | .00 |
| TC (mins) | 31.60 |
| LAG TIME (hrs) | .00 |
| BASIN STATUS | ONSITE |

| BASIN | QMX (cfs) | TMX (hrs) | VOL (in) | NOTES |
|---|---|---|---|---|
| BASINE | 16.74 | 48.10 | 9.27 | POND E POST-DEVELOPMENT |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

25YR-96HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

NODAL MIN/MAX/TIME CONDITIONS REPORT

| NODE ID | PARAMETER | MINIMUMS VALUE | MINIMUMS TIME (hr) | MAXIMUMS VALUE | MAXIMUMS TIME (hr) |
|---|---|---|---|---|---|
| PONDE | STAGE (ft): | 61.00 | 7.25 | 64.92 | 52.75 |
| | VOLUME (af): | .00 | 7.25 | 3.16 | 52.75 |
| | RUNOFF (cfs): | .00 | 16.00 | 16.49 | 48.00 |
| | OFFSITE (cfs): | .00 | 96.00 | .00 | 96.00 |
| | OTHER (cfs): | .00 | 96.00 | .00 | 96.00 |
| | OUTFLOW (cfs): | -.12 | 13.75 | 1.17 | 52.75 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

| NODE NAME | NODE TYPE | INI STAGE (ft) | X-COOR (ft) | Y-COOR (ft) | LENGTH (ft) | STAGE (ft) | AR/TM/STR (ac/hr/af) |
|---|---|---|---|---|---|---|---|
| PONDB | AREA | 51.000 | .000 | .000 | .000 | 51.000 | 1.320 |
| | | | | | | 52.000 | 1.400 |
| | | | | | | 53.000 | 1.480 |
| | | | | | | 54.000 | 1.560 |
| | | | | | | 55.000 | 1.640 |
| | | | | | | 55.500 | 1.680 |
| | | | | | | 56.000 | 1.850 |
| | | | | | | 57.000 | 2.180 |
| PONDC | AREA | 60.000 | .000 | .000 | .000 | 60.000 | .520 |
| | | | | | | 61.000 | .640 |
| | | | | | | 62.000 | .750 |
| | | | | | | 63.000 | .860 |
| | | | | | | 64.000 | .980 |
| | | | | | | 65.000 | 1.090 |
| | | | | | | 66.000 | 1.210 |
| | | | | | | 67.000 | 1.320 |
| | | | | | | 67.500 | 1.380 |
| | | | | | | 69.000 | 1.850 |
| PONDE | AREA | 61.000 | .000 | .000 | .000 | 61.000 | .528 |
| | | | | | | 62.000 | .660 |
| | | | | | | 62.500 | .730 |
| | | | | | | 63.000 | .850 |
| | | | | | | 64.000 | .970 |
| | | | | | | 65.000 | 1.030 |
| | | | | | | 65.500 | 1.200 |
| | | | | | | 66.000 | 1.370 |
| | | | | | | 67.000 | 1.450 |
| PONDF | AREA | 53.000 | .000 | .000 | .000 | 53.000 | 1.060 |
| | | | | | | 54.000 | 1.140 |
| | | | | | | 55.000 | 1.220 |
| | | | | | | 56.000 | 1.440 |
| | | | | | | 57.000 | 1.670 |
| PONDG | AREA | 50.000 | .000 | .000 | .000 | 50.000 | .701 |
| | | | | | | 51.000 | .776 |
| | | | | | | 52.000 | .851 |
| | | | | | | 53.000 | .926 |
| | | | | | | 54.000 | 1.000 |
| | | | | | | 55.000 | 1.080 |
| | | | | | | 56.000 | 1.190 |
| | | | | | | 57.000 | 1.370 |
| | | | | | | 58.000 | 1.590 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

| NODE NAME | NODE TYPE | INI STAGE (ft) | X-COOR (ft) | Y-COOR (ft) | LENGTH (ft) | STAGE (ft) | AR/TM/STR (ac/hr/af) |
|---|---|---|---|---|---|---|---|
| PONDI | AREA | 56.000 | .000 | .000 | .000 | 56.000 | .648 |
| | | | | | | 57.000 | .742 |
| | | | | | | 58.000 | .837 |
| | | | | | | 59.000 | .931 |
| | | | | | | 60.000 | 1.025 |
| | | | | | | 61.000 | 1.120 |
| | | | | | | 62.000 | 1.380 |
| | | | | | | 63.000 | 1.650 |
| PONDJ | AREA | 56.000 | .000 | .000 | .000 | 56.000 | 1.300 |
| | | | | | | 57.000 | 1.480 |
| | | | | | | 58.000 | 1.650 |
| | | | | | | 59.000 | 1.830 |
| | | | | | | 60.000 | 2.000 |
| | | | | | | 61.000 | 2.180 |
| | | | | | | 62.000 | 2.360 |
| | | | | | | 63.000 | 2.530 |
| | | | | | | 64.000 | 2.710 |
| | | | | | | 65.000 | 2.890 |
| OUTFALLB | TIME | 47.470 | .000 | .000 | .000 | 47.470 | .000 |
| | | | | | | 50.470 | 11.000 |
| | | | | | | 50.470 | 16.000 |
| | | | | | | 47.470 | 24.000 |
| OUTFALLC | TIME | 50.000 | .000 | .000 | .000 | 50.000 | .000 |
| | | | | | | 50.000 | 24.000 |
| OUTFALLE | TIME | 58.300 | .000 | .000 | .000 | 58.300 | .000 |
| | | | | | | 62.300 | 11.000 |
| | | | | | | 62.300 | 16.000 |
| | | | | | | 58.300 | 24.000 |
| OUTFALLF | TIME | 53.540 | .000 | .000 | .000 | 53.540 | .000 |
| | | | | | | 55.790 | 11.000 |
| | | | | | | 55.790 | 16.000 |
| | | | | | | 53.540 | 24.000 |
| OUTFALLG | TIME | 54.000 | .000 | .000 | .000 | 54.000 | .000 |
| | | | | | | 54.000 | 24.000 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

```
>>REACH NAME       : E1
  FROM NODE        : PONDE
  TO NODE          : OUTFALLE
  REACH TYPE       : DROP STRUCTURE w/ CIRC. CULVERT
  FLOW DIRECTION   : POSITIVE AND NEGATIVE FLOWS ALLOWED
  TURBO SWITCH     : OFF

  CULVERT DATA     :
        SPAN (in):   24.000       RISE (in):   24.000     LENGTH (ft):  168.000
   U/S INVERT (ft):  60.500 D/S INVERT (ft):   58.800       MANNING N:     .012
      ENTRNC LOSS:    .500   # OF CULVERTS:    1.000

  POSITION A       : CIRCULAR RISER SLOT
    INVERT EL. (ft):  61.000       SPAN (in):    2.000       RISE (in):    2.000
        WEIR COEF.:   3.200     GATE COEF.:      .600 NUMBER OF ELEM.:    1.000

  POSITION B       : RECTANGULAR RISER SLOT
     CREST EL. (ft):  64.700  CREST LN. (ft):    3.000    OPENING (ft):  999.000
        WEIR COEF.:   3.200     GATE COEF.:      .600 NUMBER OF ELEM.:    1.000

              NOTE: POND E OUTFALL STR.

>>REACH NAME       : G1
  FROM NODE        : PONDG
  TO NODE          : OUTFALLG
  REACH TYPE       : DROP STRUCTURE w/ CIRC. CULVERT
  FLOW DIRECTION   : POSITIVE AND NEGATIVE FLOWS ALLOWED
  TURBO SWITCH     : OFF

  CULVERT DATA     :
        SPAN (in):   24.000       RISE (in):   24.000     LENGTH (ft):   58.000
   U/S INVERT (ft):  52.500 D/S INVERT (ft):   52.000       MANNING N:     .012
      ENTRNC LOSS:    .500   # OF CULVERTS:    1.000

  POSITION A       : RECTANGULAR RISER SLOT
     CREST EL. (ft):  55.000  CREST LN. (ft):    3.000    OPENING (ft):    1.000
        WEIR COEF.:   3.200     GATE COEF.:      .600 NUMBER OF ELEM.:    1.000

  POSITION B       : RECTANGULAR RISER SLOT
     CREST EL. (ft):  57.000  CREST LN. (ft):   15.000    OPENING (ft):  999.000
        WEIR COEF.:   3.200     GATE COEF.:      .600 NUMBER OF ELEM.:    1.000

              NOTE: POND G OUTFALL STR.
```

Datum = NGVD 29

## BASIN F

Basin F extends from Sta. 293+00 to Sta. 312+00. There is approximately 5.89 acres in the post-development drainage basin. The stormwater runoff is conveyed to Pond F via median ditch bottom inlets and storm sewer pipe. All widening is to be accomplished in the median with the cross slope of the proposed pavement toward the center line of I-4. No work is planned for the roadside ditches in this basin. Only proposed impervious areas in the basin will be treated in Pond F and a small basin draining to the gore area of the eastbound rest area and I-4. The existing four lane section of I-4 will continue to drain to the outside roadway ditches and be carried away from I-4.

The location of Pond F is within the southwest corner of the existing eastbound Rest Area. It is within right-of-way currently owned by FDOT. The site is bounded on the south by an existing water retention area that serves the Northridge Subdivision. The outfall for Pond F will be to an existing isolated depression on the left (west) side of Interstate 4 via an existing 54" cross drain at Sta. 302±00. This depression currently receives runoff from Interstate 4, as well as from a large portion of the residential area to the west. Pond F is designed in conformance with the Land-Locked Basin Criteria, as the depression has no positive outfall.

Pond F is proposed as a dry facility with a bond bottom located at elevation 53.00. Pond F discharges via an overflow weir constructed into the maintenance berm of the pond. The discharge from Pond F is contained within a ditch inside FDOT right-of-way. Pond F recovers the required pollution abatement volume within 2.0 hours. See attached L. J. Nodarse & Associates, Inc. geotechnical report. See Table 8 in Section 2 for a summary of required retention volumes and drawdown analysis.

| GREINER INC: WATER RESOURCES GROUP<br>CURVE NUMBER AND RUNOFF VOLUME WORKSHEET | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I-4 WIDENING | FILENAME: | CNPR-PDF.WK3 | |
| PROJECT NUMBER: | V0187.10 | SCALE (1" = __) | 0 | DATE |
| BASIN DESIGNATION: | POND F | MADE BY: | MJJ | 28-Apr-94 |
| BASIN ANALYSIS (PRE/POST): | PRE | CHECKED BY: | RCB | |

Datum = NGVD 29

## SUB-BASIN ANALYSIS

1) BASIN / STUDY DATA

| | |
|---|---|
| PLANIMETERIED BASIN AREA (in^2) | 0.00 |
| COMPUTED BASIN AREA (Ac) | 5.89 |
| RAINFALL (inches) -- P | 18.84 |

## DETERMINE BASIN RUNOFFF CURVE NUMBER -- CN

| LAND-USE | DESCRIPTION | SOIL NAME | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|---|---|
| RANGE / GRASS | BASIN I-4 | | | 39 | 2.44 | 95.16 |
| RANGE / GRASS | GORE AREA | | | 39 | 0.85 | 33.15 |
| RANGE / GRASS | POND SITE | | | 39 | 1.68 | 65.52 |
| | | | | | | |
| PAVEMENT | BASIN I-4 | | | 98 | 0.35 | 34.30 |
| PAVEMENT | POND SITE | | | 98 | 0.57 | 55.86 |
| | | | | TOTALS | 5.89 | 283.99 |

| | |
|---|---|
| COMPOSITE CN | 48.2 |

## ESTIMATE OF RUNOFF VOLUME

1) DETERMINE SOIL STORAGE -- S

S = ( 1000 / CN ) -- 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 10.74 |

2) DETERMINE RUNOFF -- R

R = ( P -- 0.2*S )^2 / ( P + 0.8*S)

| | | |
|---|---|---|
| RUNOFF (inches) | R | 10.16 |

3) DETERMINE RUNOFF VOLUME -- V(R)

V(R) = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (Ac-ft) | V(R) | 4.99 |

Greiner

Datum = NGVD 29

Job I-4 Widening Project No. V0130.10 Sheet ____ of ____

Description Pond F Pre-development Time of Concentration Computed By RCA Date 6/94

Checked By ____ Date ____

Pre-dev. time of concentration

Due to the proposed widening to the inside, the pre-dev $T_c$ is similar to the post-dev $T_c$. The drainage patterns and basins are not altered due to the construction.

Due to the median ditch flow $T_c$ = 34.0 min ←

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

SJRWMD 25 YR \ 96 HR RAINFALL EVENT -- PRE-DEVELOPMENT--
12-16-93

Datum = NGVD 29

| | |
|---|---|
| BASIN NAME | BASINF |
| NODE NAME | PONDF |
| UNIT HYDROGRAPH | UH323 |
| PEAKING FACTOR | 323. |
| RAINFALL FILE | SJRWMD96 |
| RAIN AMOUNT (in) | 12.96 |
| STORM DURATION (hrs) | 96.00 |
| AREA (ac) | 5.89 |
| CURVE NUMBER | 48.20 |
| DCIA (%) | .00 |
| TC (mins) | 34.00 |
| LAG TIME (hrs) | .00 |
| BASIN STATUS | ONSITE |

| BASIN | QMX (cfs) | TMX (hrs) | VOL (in) | NOTES |
|---|---|---|---|---|
| BASINF | 12.39 | 60.22 | 5.42 | POND F BASIN PRE-DEVELOPMENT |


Greiner

Job _____ Project No. _____ Sheet _____ of _____

Description _____ Computed By _____ Date _____

_____ Checked By _____ Date _____

Datum = NGVD 29




Post-Development Nodal Diagram

7-21

| GREINER INC: WATER RESOURCES GROUP<br>CURVE NUMBER AND RUNOFF VOLUME WORKSHEET | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I-4 WIDENING | FILENAME: | CN-PONDF.WK3 | |
| PROJECT NUMBER: | V0187.10 | SCALE (1" = __) | 0 | DATE |
| BASIN DESIGNATION: | POND F | MADE BY: | MJJ | 28-Apr-94 |
| BASIN ANALYSIS (PRE/POST): | POST | CHECKED BY: | RCa | |

Datum = NGVD 29

## SUB-BASIN ANALYSIS

1) BASIN / STUDY DATA

| | |
|---|---|
| PLANIMETERED BASIN AREA (in^2) | 0.00 |
| COMPUTED BASIN AREA (Ac) | 5.89 |
| RAINFALL (inches) - P | 18.84 |

## DETERMINE BASIN RUNOFFF CURVE NUMBER - CN

| LAND-USE DESCRIPTION | SOIL NAME | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|---|
| RANGE / GRASS BASIN I-4 | | | 39 | ✓ 0.65 | 25.35 |
| RANGE / GRASS GORE AREA | | | 39 | ✓ 0.85 | 33.15 |
| RANGE / GRASS POND SITE | | | 39 | ✓ 1.68 | 65.52 |
| | | | | | |
| PAVEMENT BASIN I-4 | | | 98 | ✓ 2.14 | 209.72 |
| PAVEMENT POND SITE | | | 98 | ✓ 0.57 | 55.86 |
| | | | TOTALS | 5.89 | 389.60 |

| | |
|---|---|
| COMPOSITE CN | ✓ 66.1 |

## ESTIMATE OF RUNOFF VOLUME

1) DETERMINE SOIL STORAGE - S

S = ( 1000 / CN ) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 5.12 |

2) DETERMINE RUNOFF - R

R = ( P - 0.2*S )^2 / ( P + 0.8*S)

| | | |
|---|---|---|
| RUNOFF (inches) | R | 13.84 |

3) DETERMINE RUNOFF VOLUME - V(R)

V(R) = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (Ac-ft) | V(R) | ✓ 6.79 |

# ST JOHN'S RIVER WATER MANAGEMENT DISTRICT

## POLLUTION ABATEMENT VOLUME REQUIREMENT

## OFFLINE RETENTION

Datum = NGVD 29

## POND F

| POST DEVELOPMENT LAND USE | |
|---|---|
| 1) IMPERVIOUS AREA (Ac.) | 2.71 |
| 2) PERVIOUS AREA (Ac.) | 3.18 |
| 3) TOTAL AREA (Ac.) | 5.89 |

| POLLUTION ABATEMENT VOLUME (REQUIRED) | | (Ac–ft) |
|---|---|---|
| 1) 1.0 inch OF RUNOFF OVER ENTIRE AREA | 1.0" / (12" / 1 ft) * (TOTAL AREA) = | 0.49 |
| 2) 1.75 inches OVER THE IMPERVIOUS AREA | 1.75" / (12" / 1 ft) * (IMP. AREA) = | 0.40 |
| 3) 3 year / 1 Hour STORM EVENT RUNOFF | SEE CURVE NUMBER SHEET | N/A |
| 4) POLLUTION ABATEMENT VOLUME (REQUIRED) | | 0.49 |

| RECHARGE VOLUME (REQUIRED) | (Ac–ft) |
|---|---|
| 1) POST–DEVELOPMENT IMPERVIOUS AREA | 2.71 |
| 2) PRE–DEVELOPMENT IMPERVIOUS AREA | 0.92 |
| 3) RECHARGE VOLUME (BASIN F) ---- (3.0 " / (12" / 1 FT) * (IMP. DELTA) | 0.45 |
| 4) ADD'L RECHARGE VOL. (BASIN E) ---- (3.0 " / (12" / 1') * (3.59 Ac – 0.59 Ac) | 0.75 |
| 5) TOTAL RECHARGE VOLUME – (BASIN E + BASIN F) | 1.20 |

| GREINER INC: WATER RESOURCES GROUP<br>POLLUTION ABATEMENT/ RECHARGE VOLUME CALCULATIONS | | | | |
|---|---|---|---|---|
| PROJECT TITLE: | I – 4 WIDENING | FILENAME: | PAVPONDF.WK3 | |
| PROJECT NUMBER: | V0180.10 | SCALE (1" = _) | 200 | DATE |
| BASIN DESIGNATION: | POND F | MADE BY: | MJJ | 14–Nov–94 |
| ANALYSIS (PRE/POST): | POST | CHECKED BY: | ACD | 11/14/94 |

Greiner

Datum = NGVD 29

Job I-4 Widening | Project No. V0180.10 | Sheet ____ of ____

Description Question No. 4 | Computed By RCA | Date 11/8/94

Checked By MJJ | Date 11/14/94

## Basin E

Impervious Area:

Pre-dev. = 0.59 acres

Post-dev. = 3.59 acres

$\Delta$ = 3.59 - 0.59 = 3.00 acres of add'l impervious in Basin E

Recharge Volume 3" x Add'l Imp.

$\frac{3"}{12'} \times 3.00 \text{ acres} = \boxed{0.75 \text{ ac-ft}}$ ✓ (A)


Add recharge volume to Basin F and provide recharge volume in Pond F which is in adjacent land locked basin.

Pond F required volume: $(2.71 - 0.92) \times \frac{3 in}{12} = \boxed{0.45 \text{ ac-ft}}$ ✓ (B)

Post-Dev. Imp. = 2.71 acres

Pre-Dev. Imp. = 0.92 acres

0.45 ac-ft + 0.75 ac-ft = $\boxed{1.20 \text{ ac-ft}}$ ✓ ← (A) + (B)




Volume Provided = 3.62 ac-ft

Volume between Pond bottom 53.0 and Weir EL. 56.0

See stage/storage on sheet 7-24 Received on June 15, 2004

Datum = NGVD 29

GREINER INC: WATER RESOURCES GROUP

POND STAGE STORAGE CALCULATIONS – POND F

| | | | | | |
|---|---|---|---|---|---|
| PROJECT TITLE: | I – 4 WIDENING | FILENAME: | SSPONDF.WK3 | | |
| PROJECT NUMBER: | V0180.10 | SCALE (1" = __) | 200 | DATE | |
| BASIN DESIGNATION: | POND F | MADE BY: | MJJ | 09–Jun–94 | |
| BASIN ANALYSIS (PRE/POST): | POST | CHECKED BY: | RCO | | |

| ELEV. | PLAN. VALUE 1 (si) | PLAN. VALUE 2 (si) | AREA (ac) | AVE. AREA (ac) | DELTA D (ft) | DELTA STORAGE (ac–ft) | STORAGE P.A.V.* (ac–ft) | ATTENUATION OF PEAK DISCHARGE (ac–ft) |
|---|---|---|---|---|---|---|---|---|
| 53.00 | 1.145 | 1.171 | 1.063 | | | | 0 | 0 |
| | | | | 1.09 | 0.62 | 0.67 | | |
| 53.62 | | | 1.113 | | | | 0.67 | 0.67 |
| | | | | 1.13 | 0.38 | 0.43 | | |
| 54.00 | | | 1.143 | | | | 1.10 | 1.10 |
| | | | | 1.16 | 0.5 | 0.58 | | |
| 54.50 | | | 1.184 | | | | 1.69 | 1.69 |
| | | | | 1.20 | 0.5 | 0.60 | | |
| 55.00 | 1.364 | 1.301 | 1.224 | | | | 2.29 | 2.29 |
| | | | | 1.33 | 1 | 1.33 | | |
| 56.00 | | | 1.445 | | | | 3.62 | ** 3.62 |
| | | | | 1.56 | 1 | 1.56 | | |
| 57.00 | 1.79 | 1.84 | 1.667 | | | | 5.18 | 5.18 |
| | | | | | | | | |

* P.A.V. = POLLUTION ABATEMENT VOLUME.

** VOLUME IS BASED ON POLLUTION ABATEMENT AND LANDLOCKED CONTROL VOLUME.

Greiner

Datum = NGVD 29

Job I-4 Widening Project No. V0180.10 Sheet ____ of ____

Description Pond F Tailwater Info Computed By RCA Date 6/94

Checked By ____ Date ____

Pond F is located in and discharges to a land-locked depressional area. The depressional area offers no effect on the tailwater for Pond F.

| JOB: | I – 4 WIDENING | PROJECT NO.: | V0180.10 | | |
|---|---|---|---|---|---|
| DESCRIPTION: | POST DEVELOPMENT CALCULATIONS AND | COMPUTED BY: | MJJ | DATE: | 09–Dec–93 |
| | DITCH PROFILES FOR POND "F" | CHECKED BY: | | DATE: | |

| | |
|---|---|
| Right Side | |
| Median | XX |
| Left Side | |

| | | | |
|---|---|---|---|
| Overall Basin Length: | 293 + 00 | to | 312 + 00 |
| Sub–Basin 1: | 293 + 00 | to | 312 + 00 |
| Sub–Basin 2: | 0 | to | 0 |

| | |
|---|---|
| Rainfall Zone: | 7 |
| Frequency: | 25 |

Datum = NGVD 29

| SECTION INFORMATION | | | | | | DITCH GEOMETRY | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Station to Station | | | | Length | Slope | TOTAL (CA) | Time of Conc. | Inten–sity | Flow Q | Front Slope | Bottom Width | Back Slope | *** n | Depth | Calc'd Vel. | Section Flow Time | Lining | Remarks |
| Begin | | End | | (ft) | % | (Ac) | (min) | (in/hr) | (CFS) | (ft/ft) | (ft) | (ft/ft) | | (ft) | (ft/sec) | (min) | (Y/N) | |
| 293 | | 296 | | 300 | 0.70 | 0.352 | 10.00 | 8.26 | 2.90 | 6 | | 10 | 0.060 | 0.61 | 0.94 | 5.3 | | |
| 296 | | 298 | | 200 | 0.70 | 0.586 | 15.32 | 7.15 | 4.19 | 6 | | 10 | 0.042 | 0.62 | 1.35 | 2.5 | | |
| 298 | | 300 | | 200 | 0.70 | 0.820 | 17.79 | 6.76 | 5.54 | 6 | 2.00 | 10 | 0.060 | 0.67 | 1.10 | 3.0 | | |
| 300 | | 302 | | 200 | 0.70 | 1.055 | 20.82 | 6.34 | 6.69 | 6 | 7.00 | 10 | 0.060 | 0.53 | 1.10 | 3.0 | | |
| 302 | | 304 | | 200 | 0.70 | 1.289 | 23.85 | 5.99 | 7.72 | 6 | 4.00 | 10 | 0.060 | 0.68 | 1.18 | 2.8 | | |
| 304 | | 306 | | 200 | 0.26 | 1.524 | 26.67 | 5.70 | 8.69 | 6 | 1.00 | 10 | 0.042 | 0.92 | 1.11 | 3.0 | | |
| 306 | | 309 | | 300 | 0.25 | 1.875 | 29.68 | 5.43 | 10.18 | 6 | | 10 | 0.042 | 1.05 | 1.15 | 4.3 | | |
| | | | | | | | 34.02 | 5.08 | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 309 | | 312 | | 300 | 0.11 | 0.352 | 10.00 | 8.26 | 2.90 | 6 | 2.00 | 10 | 0.042 | 0.65 | 0.61 | 8.2 | | |
| 312 | | 309 | 58 | 242 | 0.66 | 0.651 | 18.20 | 6.70 | 4.36 | 6 | 5.00 | 4 | 0.060 | 0.53 | 1.07 | 3.8 | | |
| | | | | | | | 21.97 | 6.20 | | | | | | | | | | |

*** If the calculated value D < 0.7 ft., use Manning's n = 0.06
If the calculated value D >= 0.7 ft., use Manning's n = 0.042

72-2

Basin F $T_c$

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

25YR-96HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94 (REVISED RAI NO.1) 11-08-94

Datum = NGVD 29

| | |
|---|---|
| BASIN NAME | BASINF |
| NODE NAME | PONDF |
| UNIT HYDROGRAPH | UH323 |
| PEAKING FACTOR | 323. |
| RAINFALL FILE | SJRWMD96 |
| RAIN AMOUNT (in) | 12.96 |
| STORM DURATION (hrs) | 96.00 |
| AREA (ac) | 5.89 |
| CURVE NUMBER | 66.10 |
| DCIA (%) | .00 |
| TC (mins) | 34.00 |
| LAG TIME (hrs) | .00 |
| BASIN STATUS | ONSITE |

| BASIN | QMX (cfs) | TMX (hrs) | VOL (in) | NOTES |
|---|---|---|---|---|
| BASINF | 18.75 | 60.22 | 8.35 | POND F POST - DEVELOPMENT |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

25YR-96HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94 (REVISED RAI NO.1) 11-08-94

Datum = NGVD 29

NODAL MIN/MAX/TIME CONDITIONS REPORT

| NODE ID | PARAMETER | <-- MINIMUMS --> VALUE | TIME (hr) | <-- MAXIMUMS --> VALUE | TIME (hr) |
|---|---|---|---|---|---|
| PONDF | STAGE (ft): | 53.00 | 7.25 | 55.81 | 63.00 |
| | VOLUME (af): | .00 | 7.00 | 3.36 | 63.00 |
| | RUNOFF (cfs): | .00 | 27.50 | 18.35 | 60.25 |
| | OFFSITE (cfs): | .00 | 96.00 | .00 | 96.00 |
| | OTHER (cfs): | .00 | 96.00 | .00 | 96.00 |
| | OUTFLOW (cfs): | -1.31 | 16.00 | 1.67 | 63.00 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

| NODE NAME | NODE TYPE | INI STAGE (ft) | X-COOR (ft) | Y-COOR (ft) | LENGTH (ft) | STAGE (ft) | AR/TM/STR (ac/hr/af) |
|---|---|---|---|---|---|---|---|
| PONDB | AREA | 51.000 | .000 | .000 | .000 | 51.000 | 1.320 |
| | | | | | | 52.000 | 1.400 |
| | | | | | | 53.000 | 1.480 |
| | | | | | | 54.000 | 1.560 |
| | | | | | | 55.000 | 1.640 |
| | | | | | | 55.500 | 1.680 |
| | | | | | | 56.000 | 1.850 |
| | | | | | | 57.000 | 2.180 |
| PONDC | AREA | 60.000 | .000 | .000 | .000 | 60.000 | .520 |
| | | | | | | 61.000 | .640 |
| | | | | | | 62.000 | .750 |
| | | | | | | 63.000 | .860 |
| | | | | | | 64.000 | .980 |
| | | | | | | 65.000 | 1.090 |
| | | | | | | 66.000 | 1.210 |
| | | | | | | 67.000 | 1.320 |
| | | | | | | 67.500 | 1.380 |
| | | | | | | 69.000 | 1.850 |
| PONDE | AREA | 61.000 | .000 | .000 | .000 | 61.000 | .528 |
| | | | | | | 62.000 | .660 |
| | | | | | | 62.500 | .730 |
| | | | | | | 63.000 | .850 |
| | | | | | | 64.000 | .970 |
| | | | | | | 65.000 | 1.030 |
| | | | | | | 65.500 | 1.200 |
| | | | | | | 66.000 | 1.370 |
| | | | | | | 67.000 | 1.450 |
| PONDF | AREA | 53.000 | .000 | .000 | .000 | 53.000 | 1.060 |
| | | | | | | 54.000 | 1.140 |
| | | | | | | 55.000 | 1.220 |
| | | | | | | 56.000 | 1.440 |
| | | | | | | 57.000 | 1.670 |
| PONDG | AREA | 50.000 | .000 | .000 | .000 | 50.000 | .701 |
| | | | | | | 51.000 | .776 |
| | | | | | | 52.000 | .851 |
| | | | | | | 53.000 | .926 |
| | | | | | | 54.000 | 1.000 |
| | | | | | | 55.000 | 1.080 |
| | | | | | | 56.000 | 1.190 |
| | | | | | | 57.000 | 1.370 |
| | | | | | | 58.000 | 1.590 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

| NODE NAME | NODE TYPE | INI STAGE (ft) | X-COOR (ft) | Y-COOR (ft) | LENGTH (ft) | STAGE (ft) | AR/TM/STR (ac/hr/af) |
|---|---|---|---|---|---|---|---|
| PONDI | AREA | 56.000 | .000 | .000 | .000 | 56.000 | .648 |
| | | | | | | 57.000 | .742 |
| | | | | | | 58.000 | .837 |
| | | | | | | 59.000 | .931 |
| | | | | | | 60.000 | 1.025 |
| | | | | | | 61.000 | 1.120 |
| | | | | | | 62.000 | 1.380 |
| | | | | | | 63.000 | 1.650 |
| PONDJ | AREA | 56.000 | .000 | .000 | .000 | 56.000 | 1.300 |
| | | | | | | 57.000 | 1.480 |
| | | | | | | 58.000 | 1.650 |
| | | | | | | 59.000 | 1.830 |
| | | | | | | 60.000 | 2.000 |
| | | | | | | 61.000 | 2.180 |
| | | | | | | 62.000 | 2.360 |
| | | | | | | 63.000 | 2.530 |
| | | | | | | 64.000 | 2.710 |
| | | | | | | 65.000 | 2.890 |
| OUTFALLB | TIME | 47.470 | .000 | .000 | .000 | 47.470 | .000 |
| | | | | | | 50.470 | 11.000 |
| | | | | | | 50.470 | 16.000 |
| | | | | | | 47.470 | 24.000 |
| OUTFALLC | TIME | 50.000 | .000 | .000 | .000 | 50.000 | .000 |
| | | | | | | 50.000 | 24.000 |
| OUTFALLE | TIME | 58.300 | .000 | .000 | .000 | 58.300 | .000 |
| | | | | | | 62.300 | 11.000 |
| | | | | | | 62.300 | 16.000 |
| | | | | | | 58.300 | 24.000 |
| OUTFALLF | TIME | 53.540 | .000 | .000 | .000 | 53.540 | .000 |
| | | | | | | 55.790 | 11.000 |
| | | | | | | 55.790 | 16.000 |
| | | | | | | 53.540 | 24.000 |
| OUTFALLG | TIME | 54.000 | .000 | .000 | .000 | 54.000 | .000 |
| | | | | | | 54.000 | 24.000 |

Advanced Interconnected Channel & Pond Routing (adICPR Ver 1.40)
Copyright 1989, Streamline Technologies, Inc.

25YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94 (REVISED RAI NO.1) 11-08-94

Datum = NGVD 29

```
>>REACH NAME       : F1
  FROM NODE        : PONDF
  TO NODE          : OUTFALLF
  REACH TYPE       : TRAPEZOIDAL WEIR/GATE/ORIFICE, MAVIS EQ.
  FLOW DIRECTION   : POSITIVE AND NEGATIVE FLOWS ALLOWED
    CREST EL. (ft):  56.000 BTM. WIDTH (ft):   5.000   LEFT SS (h/v):  6.000
     RGHT SS (h/v):   6.000   OPENING (ft): 999.000      WEIR COEF.:  3.130
        GATE COEF.:    .600 NUMBER OF ELEM.:   1.000
              NOTE:
```

Advanced Interconnected Channel & Pond Routing (adICPR Ver 2.10)
Copyright 1989, Streamline Technologies, Inc.

10YR-24HR POST-DEVELOPMENT BASINS B,C,E,F,G,I,&J
05-02-94

Datum = NGVD 29

>>REACH NAME : F2
FROM NODE : PONDF
TO NODE : OUTFALLF
REACH TYPE : CULVERT, CIRCULAR w/ ROADWAY
FLOW DIRECTION : POSITIVE AND NEGATIVE FLOWS ALLOWED
TURBO SWITCH : OFF

CULVERT DATA :

| | | | | | |
|---|---|---|---|---|---|
| SPAN (in): | 18.000 | RISE (in): | 18.000 | LENGTH (ft): | 42[illegible].000 |
| U/S INVERT (ft): | 55.000 | D/S INVERT (ft): | 54.500 | MANNING N: | .013 |
| ENTRNC LOSS: | .500 | # OF CULVERTS: | 1.000 | | |

POSITION A : NOT USED

POSITION B : NOT USED

NOTE:

Datum = NGVD 29

## SEASONAL HIGH GROUNDWATER LEVELS

| Pond | Estimated Seasonal High Groundwater Elevation (Ft., NGVD) | Seasonal High Used in PONDFLOW Model (Ft., NGVD) |
|---|---|---|
| A | +33.7 to +45.5 | +49.1, (+46.1)* |
| B | +44.3 to +48.0 | +48.1, (+45.6)* |
| C | +50.0 | -55.1 |
| E | +55.5 to +59.0 | Wet Pond |
| F | +49.0 | +46.0 |
| G | +42.0 to +42.5 | +43.1 |
| I | +44.7 to +46.1 | +52.1, (+51.0)* |
| J | +46.0 | +46.0 |

* The seasonal high estimated based on recommended over excavation.


Table 2
Summary of Groundwater Level
and Estimated Seasonal High for Ponds
S.R. 400 (I-4) Improvements
State Project No. 77160-1601
LJN Project No. 92-0393

Datum = NGVD 29

| Boring No. | Station | Offset | Approximate Ground Surface Elevation (ft. NGVD) | Encountered Groundwater Elevation (ft. NGVD) | Estimated Seasonal High Elevation (ft. NGVD) |
|---|---|---|---|---|---|
| A-1 | 195+00 | 150' LT | +53.7 | GNE | +33.7 |
| A-2 | 197+00 | 200' LT | +57.0 | GNE | +37.0 |
| A-3 | 198+00 | 250' LT | +55.0 | GNE | +35.0 |
| A-4 | 198+00 | 150' LT | +61.0 | GNE | +41.0 |
| A-5 | 200+00 | 250' LT | +61.0 | GNE | +41.0 |
| A-6 | 200+00 | 150' LT | +65.5 | GNE | +45.5 |
| A-7 | 198+00 | 200' LT | +52.5 | GNE | ** |
| B-1 | 216+00 | 220' RT | +64.3 | GNE | +46.3 |
| B-2 | 217+00 | 250' RT | +53.2 | +44.2 | +46.7 |
| B-3 | 219+00 | 220' RT | +57.0 | +44.0 | +48.0 |
| B-4 | 221+00 | 250' RT | +50.3 | +38.1 | +44.3 |
| C-1 | 232+00 | 375' LT | +66.0 | GNE | +50.0 |
| C-2 | 234+00 | 325' LT | +66.0 | GNE | +50.0 |
| C-3 | 236+00 | 275' LT | +66.0 | GNE | +50.0 |
| E-1 | 283+00 | 200' RT | +67.0 | +55.5 | +59.0 |
| E-2 | 286+00 | 200' RT | +65.0 | +51.3 | +55.5 |
| F-1 | 1+30* | 80' LT | +57.0 | +45.5 | +49.0 |
| F-2 | 2+50* | 200' RT | +55.5 | +43.4 | +49.0 |
| F-3 | 3+50* | 100' RT | +52.5 | +45.1 | +49.0 |
| F-4 | 3+00* | 250' LT | +56.5 | +43.8 | +49.0 |
| F-5 | 4+00* | 100' LT | +54.0 | +44.7 | +49.0 |

Basin 308 & 308A

- Drainage Maps
- Basin and Pond Calculations
- Basin and Pond Routing (ICPR)
  - Pre-Development
  - Post-Development
- Existing Permits (Supporting Documentation)




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# EXISTING BASIN 308 & 308A

SHEET NO. 1

0 100 400
Feet

Basin 308-1 - 0.72 Ac.

Basin 308A - 20.40 Ac.

FLOOD PLAIN

FLOOD PLAIN

FLOOD PLAIN

INTERNATIONAL PKWY.

INTERNATIONAL PKWY.

CROSS SEMINOLE TRAIL

EXIST. LA R/W LINE

℄ CONST. I-4

I-4 WB GUL

I-4 WB EXPRESS LANES

I-4 EB EXPRESS LANES

I-4 EB GUL

℄ WB I-4

℄ EB I-4

PROP. LA R/W LINE

EXIST. LA R/W LINE

EXIST. LA R/W LINE

P308-1

P308-2

P308-3

P308-4

POND 308

P308-5

P308-8

P308-7

P308-6

P308-9

WETLAND LINE

SURFACE WATER

EXIST. EASEMENT

Basin 308 - 27.27 Ac.

Basin 308-2 - 5.16 Ac.

Basin 308A

P308A-1

POND 308A

P308A-2

LOW AREA

PROP. EASEMENT

DRY POND

PROP. LA R/W LINE

DRY POND

EXIST. LA R/W LINE

21ST CENTURY INSURANCE

RINEHART RIDGE IV
660 CENTURY POINT

CROSS SEMINOLE TRAIL

BASIN 308

BASIN 308A

FLIGHT DATE: 2015

| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# PROPOSED BASIN 308-308A

SHEET NO. 2


Littlec 7/18/2017 11:33:18 AM T:\Sys\Projects\24259245201\drainage\REPORT\DRMP_Basin308_Prop.dgn

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308 | **CHECKED BY:** | JLL |

I ***PRE DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308***

***Pond 3***

COMPUTED BASIN AREA (Ac) 29.43

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 9.22 | 903.56 |
| | | | | |
| | | | | |
| Sub-total for Impervious Land Uses | | | 9.22 | 903.56 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 12.25 | 600.25 |
| Open Space, Fair Condition - (Tavares) | A | 49 | 3.82 | 187.18 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 16.07 | 787.43 |
| Pond | | | | |
| Exist. Pond Site Area | A | 49 | 4.14 | 202.86 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 4.14 | 202.86 |
| | | TOTAL | 29.43 | 1893.85 |

**COMPOSITE CN** **64.4**

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 5.54 | 6.52 | 15.98 |
| 100 yr / 10-day | FDOT | 18.50 | 5.54 | 13.19 | 32.35 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 5.54 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 13.19 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 32.35 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308 | **CHECKED BY:** | JLL |

II ***POST DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308***

***Pond 308***

COMPUTED BASIN AREA (Ac) 27.27

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 20.78 | 2036.44 |
| | | | | |
| | | | | |
| Sub-total for Impervious Land Uses | | | 20.78 | 2036.44 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 1.88 | 92.12 |
| Open Space, Fair Condition - (Tavares) | A | 49 | 0.47 | 23.03 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 2.35 | 115.15 |
| Pond | | | | |
| Exist. Pond Site Area | A | 49 | 4.14 | 202.86 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 4.14 | 202.86 |
| | | TOTAL | 27.27 | 2354.45 |

**COMPOSITE CN** **86.3**

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 1.58 | 9.50 | 21.59 |
| 100 yr / 10-day | FDOT | 18.50 | 1.58 | 16.73 | 38.01 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 1.58 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 16.73 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 38.01 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308 | **CHECKED BY:** | JLL |

III ***GEOTECHNICAL INFORMATION***

| **Estimated Seasonal High Water Table (SHWT)** | |
|---|---|
| | **Estimated SHWT (Ft)** |
| Permit No. 22124-2 | 48.20 |
| Pond Borings (Avg. Boring P308-1 to P308-4) | 43.10 |
| | |
| **Estimated SHWT** | 43.10 |

IV ***SUMMARY OF REQUIRED ATTENUTION AND TREATMENT VOLUME***

***Basin 308***

***Pond 308***

**REQUIRED ATTENUTATION CACULATION**

| **PRE-DEVELOPED CONDITION** | | **POST-DEVELOPED CONDITION** | |
|---|---|---|---|
| AREA (AC): | 29.43 | AREA (AC): | 27.27 |
| CN: | 64.4 | CN: | 86.3 |
| IMPERVIOUS AREA (AC): | 9.22 | IMPERVIOUS AREA (AC): | 20.78 |
| PERVIOUS AREA (AC): | 20.21 | PERVIOUS AREA (AC): | 6.49 |
| | | NEW IMPERVIOUS AREA (AC): | 11.56 |

**SUMMARY OF ATTENUATION ESTIMATES**

| AGENCY | DESIGN STORM | RUNOFF VOLUME V[R] PRE [ AC-FT ] | POST [ AC-FT ] | TOTAL RETENTION [ AC-FT ] |
|---|---|---|---|---|
| SJRWMD | 25 yr / 96 hr | 15.98 | 21.59 | **5.61** |
| FDOT | 100 yr / 10-day | 32.35 | 38.01 | **5.67** |

| **REQUIRED TREATMENT VOLUME CALCULATION** | | AC-FT | Basin Area | |
|---|---|---|---|---|
| Dry Retention Treatment Requirement = | 1" x Basin Area | 1.93 | 23.13 | |
| or | 1.25" x Impervious Area + 0.5" x Basin Area | 3.13 | | ***Controls*** |

| **Wekiva Basin Most Effective Recharge Area** | **AC** | **AC-FT** | |
|---|---|---|---|
| Pre Devp. Impervious Area on A Soils (West of I-4 CL) = | 6.98 | | |
| Post Devp. Impervious Area on A Soils (West of I-4 CL) = | 14.67 | | |
| Post Devp. Impervious Area - Pre Devp. Impervious Area = | 7.69 | | |
| Impevious Area added to prevous project (West of I-4 CL) = | 0 | | Permit No. 22124-2 |
| Sum of Current and prevous project Impervous Area = | 7.69 | | |
| 3" x Total Impervous Area on A Soils (West of I-4 CL) = | - | 1.92 | |

| **SJRWMD Closed Basin Volume** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 15.98 | |
| Post Devp. Runoff Volume | 21.59 | |
| Current Project Delta | 5.61 | |
| Previous Project Required Volume (60% of 4.92 ac-ft) | 2.95 | Permit No. 22124-2 (SJRWMD 25-yr / 96-hr) |
| Current Project Delta + Prevous Project Required Volume | 8.57 | ***Controls All*** |

| **FDOT Closed Basin Volume** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 32.35 | |
| Post Devp. Runoff Volume | 38.01 | |
| Current Project Delta | 5.66 | |
| Previous Project Required Volume (60% of 7.33 ac-ft) | 4.40 | Permit No. 22124-2 (FDOT 100-yr / 10-day) |
| Current Project Delta + Prevous Project Required Volume | 10.06 | ***Controls All*** |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308 | **CHECKED BY:** | JLL |

V ***PROVIDED TREATMENT & ATTENUATION VOLUME CALCULATIONS***

***Basin 308***

| **POND STAGE, AREA & STORAGE** | | | |
|---|---|---|---|
| **DESCRIPTION** | **STAGE (FT)** | **AREA (AC)** | **CUMMULATIVE STORAGE (AC-FT)** |
| Pond Bottom | 51.20 | 2.29 | 0.00 |
| Wekiva Requirement | 52.01 | 2.45 | 1.92 |
| Treatment | 52.50 | 2.55 | 3.14 |
| 1/2 Closed Basin Volume (FDOT) | 53.23 | 2.69 | 5.06 |
| SJRWMD Closed Basin Volume | 54.48 | 2.94 | 8.58 |
| **FDOT Closed Basin Volume** | 54.98 | 3.04 | 10.07 |
| Top of Bank Elevation | 56.60 | 3.36 | 15.26 |
| Top of Berm | 58.10 | 4.14 | 20.88 |

| **PROVIDED TREATMENT VOLUME** | AC-FT |
|---|---|
| Treatment Volume Provided = Volume between Pond Bottom and Weir Crest Elevation | 3.14 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308-1 | **CHECKED BY:** | JLL |

I ***PRE DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308-1***

COMPUTED BASIN AREA (Ac) 1.89

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 0.00 | 0.00 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 0.00 | 0.00 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 1.89 | 92.61 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 1.89 | 92.61 |
| | | TOTAL | 1.89 | 92.61 |

**COMPOSITE CN** **49.0**

II ***POST DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308-1***

COMPUTED BASIN AREA (Ac) 0.72

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 0.00 | 0.00 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 0.00 | 0.00 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 0.72 | 35.28 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 0.72 | 35.28 |
| | | TOTAL | 0.72 | 35.28 |

**COMPOSITE CN** **49.0**

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308-2 | **CHECKED BY:** | JLL |

I ***POST DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308-2***

COMPUTED BASIN AREA (Ac) 5.16

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 0.00 | 0.00 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 0.00 | 0.00 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 5.16 | 252.84 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 5.16 | 252.84 |
| | | TOTAL | 5.16 | 252.84 |

**COMPOSITE CN** **49.0**

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308A | **CHECKED BY:** | MB |

I ***PRE DEVELOPMENT***

***RUNOFF CURVE NUMBER (CN) CALCULATIONS***

***Basin 308A***

***Pond: 308A***

COMPUTED BASIN AREA (Ac) 20.73

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 5.91 | 579.18 |
| | | | | |
| | | | | |
| Sub-total for Impervious Land Uses | | | 5.91 | 579.18 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 9.20 | 450.80 |
| Open Space, Fair Condition - (Tavares) | A | 49 | 3.05 | 149.45 |
| | | | | |
| | | | | |
| Sub-total for Pervious Land Uses | | | 12.25 | 600.25 |
| Pond | | | | |
| Pond Site Area | A | 49 | 2.57 | 125.93 |
| | | | | |
| | | | | |
| Sub-total for Pervious Land Uses | | | 2.57 | 125.93 |
| | | TOTAL | 20.73 | 1305.36 |

**COMPOSITE CN** **63.0**

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 5.88 | 6.32 | 10.91 |
| 100 yr / 10-day | FDOT | 18.50 | 5.88 | 12.93 | 22.34 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 5.88 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 12.93 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 22.34 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308A | **CHECKED BY:** | MB |

II ***POST DEVELOPMENT***
***RUNOFF CURVE NUMBER (CN) CALCULATIONS***
***Basin 308A***
***Pond: 308A***

COMPUTED BASIN AREA (Ac) 20.40

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 11.27 | 1104.46 |
| | | | | |
| | | | | |
| Sub-total for Impervious Land Uses | | | 11.27 | 1104.46 |
| Pervious | | | | |
| Open Space, Fair Condition - (Astatula) | A | 49 | 4.92 | 241.08 |
| Open Space, Fair Condition - (Tavares) | A | 49 | 1.64 | 80.36 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 6.56 | 321.44 |
| Pond | | | | |
| Pond Site Area | A | 49 | 2.57 | 125.93 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 2.57 | 125.93 |
| | | TOTAL | 20.40 | 1551.83 |

**COMPOSITE CN** **76.1**

**ESTIMATED RUNOFF VOLUME**

SUMMARY TABLE:

| DESIGN STORM | Agency | P [in] | S [in] | R [in] | V[R] [ac-ft] |
|---|---|---|---|---|---|
| 25 yr / 96 hr | SJRWMD | 11.20 | 3.15 | 8.15 | 13.85 |
| 100 yr / 10-day | FDOT | 18.50 | 3.15 | 15.20 | 25.83 |

SAMPLE CALCULATION:

1) DETERMINE SOIL STORAGE - S

S= (1000/CN) - 10

| | | |
|---|---|---|
| SOIL STORAGE (inches) | S | 3.15 |

2) DETERMINE RUNOFF - R

P = 18.50

R = ( P - 0.2*S )^2 / ( P + 0.8*S )

| | | |
|---|---|---|
| RUNOFF (inches) | R | 15.20 |

3) DETERMINE RUNOFF VOLUME - V[R]

V[R] = R / 12 * AREA

| | | |
|---|---|---|
| RUNOFF (ac-ft) | V[R] | 25.83 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308A | **CHECKED BY:** | MB |

III ***GEOTECHNICAL INFORMATION***

| **Estimated Seasonal High Water Table (SHWT)** | |
|---|---|
| | **Estimated SHWT (Ft)** |
| Pond Borings (Avg. Boring P308A-1 7 P308A-2) | 60.30 |
| | |
| | |
| **Estimated SHWT** | 60.30 |

IV ***SUMMARY OF TREATMENT & ATTENUATION VOLUME***

***Basin 308A***

***Pond: 308A***

**REQUIRED ATTENUTATION CACULATION**

| **PRE-DEVELOPED CONDITION** | | **POST-DEVELOPED CONDITION** | |
|---|---|---|---|
| AREA (AC): | 20.73 | AREA (AC): | 20.40 |
| CN: | 63.0 | CN: | 76.1 |
| IMPERVIOUS AREA (AC): | 5.91 | IMPERVIOUS AREA (AC): | 11.27 |
| PERVIOUS AREA (AC): | 14.82 | PERVIOUS AREA (AC): | 9.13 |
| | | NEW IMPERVIOUS AREA (AC): | 5.36 |

**SUMMARY OF WATER MANAGEMENT DISTRICT ATTENUATION ESTIMATES**

| AGENCY | DESIGN STORM | RUNOFF VOLUME V[R] PRE [ AC-FT ] | POST [ AC-FT ] | TOTAL RETENTION [ AC-FT ] |
|---|---|---|---|---|
| SJRWMD | 25 yr / 96 hr | 10.91 | 13.85 | **2.94** |
| FDOT | 100 yr / 10-day | 22.34 | 25.83 | **3.49** |

| **REQUIRED TREATMENT VOLUME CALCULATION** | | AC-FT | Basin Area | |
|---|---|---|---|---|
| Dry Retention Treatment Requirement = | 1" x Basin Area | 1.70 | 20.40 | |
| or | 1.25" x Impervious Area + 0.5" x Basin Area | 2.02 | | ***Controls*** |

| **SJRWMD Closed Basin Volume** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 10.91 | |
| Post Devp. Runoff Volume | 13.85 | |
| Current Project Delta | 2.94 | |
| Previous Project Required Volume (40% of 4.92 ac-ft) | 1.97 | Permit No. 22124-2 (SJRWMD 25-yr / 96-hr) |
| Current Project Delta + Prevous Project Required Volume | 4.91 | |

| **FDOT Closed Basin Volume** | **AC-FT** | |
|---|---|---|
| Pre Devp. Runoff Volume | 22.34 | |
| Post Devp. Runoff Volume | 25.83 | |
| Current Project Delta | 3.49 | |
| Previous Project Required Volume (40% of 7.33 ac-ft) | 2.93 | Permit No. 22124-2 (FDOT 100-yr / 10-day) |
| Current Project Delta + Prevous Project Required Volume | 6.42 | ***Controls All*** |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BTU Segment 3 | **DATE:** | Apr-17 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | TDA |
| **BASIN DESIGNATION:** | Basin 308A | **CHECKED BY:** | MB |

V ***PROVIDED TREATMENT & ATTENUATION VOLUME CALCULATIONS***


***Basin 308A***

Basin 308A

| **POND STAGE, AREA & STORAGE** | | | |
|---|---|---|---|
| **DESCRIPTION** | **STAGE (FT)** | **AREA (AC)** | **CUMMULATIVE STORAGE (AC-FT)** |
| Pond Bottom | 69.10 | 1.99 | 0.00 |
| Treatment | 70.09 | 2.11 | 2.03 |
| 1/2 Closed Basin Volume (FDOT) | 70.65 | 2.17 | 3.22 |
| SJRWMD Closed Basin Volume | 71.41 | 2.26 | 4.91 |
| **FDOT Closed Basin Volume** | 72.07 | 2.34 | 6.43 |
| | 73.98 | 2.56 | 11.10 |
| Top of Bank Elevation (Inside) | 74.00 | 2.57 | 11.15 |

| **PROVIDED TREATMENT VOLUME** | AC-FT |
|---|---|
| Treatment Volume Provided = Pond Bottom and Weir Crest Elevation | 2.03 |

Pre Development




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM
# EXISTING BASIN 308

SHEET NO.
N/A

BASIN 308
Existing Conditions Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GRND 308 | BASIN308 | 100Y240H | 0.00 | 43.10 | 43.10 | 0.00 | 0 | 40.17 | 9.08 | 0.00 | 0.00 |
| OUT 308 | BASIN308 | 100Y240H | 0.00 | 49.95 | 49.95 | 0.00 | 0 | 184.00 | 22.53 | 0.00 | 0.00 |
| Pond 3 | BASIN308 | 100Y240H | 184.77 | 55.65 | 57.75 | 0.00 | 151413 | 184.00 | 29.14 | 184.69 | 23.93 |
| GRND 308 | BASIN308 | SJRWMD | 0.00 | 43.10 | 43.10 | 0.00 | 0 | 62.65 | 15.76 | 0.00 | 0.00 |
| OUT 308 | BASIN308 | SJRWMD | 0.00 | 49.95 | 49.95 | 0.00 | 0 | 64.90 | 7.57 | 0.00 | 0.00 |
| Pond 3 | BASIN308 | SJRWMD | 64.90 | 54.25 | 57.75 | 0.00 | 139022 | 60.67 | 73.28 | 62.65 | 20.14 |

Existing Discharge Rates:
Basin 308
Q-FDOT (100-yr/240-hr)= 22.53 cfs
Q-SJRWMD (25-yr/96-hr)= 7.57 cfs

==========
==== Basins ==========
==========

Name: Basin 308 Node: Pond 3 Status: Onsite
Group: BASIN308 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 77.00
Area(ac): 29.430 Time Shift(hrs): 0.00
Curve Number: 64.40 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

Used Post Development time of concentration from Permit No. 22124-2.

---

Name: Basin 308-1 Node: OUT 308 Status: Onsite
Group: BASIN308 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 10.00
Area(ac): 1.890 Time Shift(hrs): 0.00
Curve Number: 49.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

---

Name: Basin 308A Node: Pond 3 Status: Onsite
Group: BASIN308 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Sjrwmd96 Storm Duration(hrs): 96.00
Rainfall Amount(in): 11.200 Time of Conc(min): 77.00
Area(ac): 20.730 Time Shift(hrs): 0.00
Curve Number: 63.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

Used Post Development time of concentration from Permit No. 22124-2.

==========
==== Nodes ==========
==========

Name: GRND 308 Base Flow(cfs): 0.000 Init Stage(ft): 43.100
Group: BASIN308 Warn Stage(ft): 43.100
Type: Time/Stage

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 43.100 |
| 336.00 | 43.100 |

---

Name: OUT 308 Base Flow(cfs): 0.000 Init Stage(ft): 49.950
Group: BASIN308 Warn Stage(ft): 49.950
Type: Time/Stage

Used Boundary Conditon developed in previous project (Permit No. 22124-2).

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 49.950 |
| 336.00 | 49.950 |

---

Name: Pond 3 Base Flow(cfs): 0.000 Init Stage(ft): 51.200
Group: BASIN308 Warn Stage(ft): 57.750
Type: Stage/Area

Used stage/storage from Permit No. 22124-2.

| Stage(ft) | Area(ac) |
|---|---|
| 51.200 | 2.5700 |
| 56.600 | 3.6700 |
| 58.100 | 4.4700 |

==========

==== Drop Structures ================================================================
================================================================================

```
         Name: DS-E308             From Node: Pond 3             Length(ft): 310.00
        Group: BASIN308              To Node: OUT 308                 Count: 1

               UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                  Solution Algorithm: Most Restrictive
     Span(in): 30.00          30.00                                Flow: Both
     Rise(in): 30.00          30.00                     Entrance Loss Coef: 1.000
   Invert(ft): 51.180         50.520                        Exit Loss Coef: 0.500
  Manning's N: 0.012000       0.012000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                          Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Control Strcuture based on pervious permit for Post Develoment (Permit No. 22124-2).

*** Weir 1 of 2 for Drop Structure DS-E308 ***
                                                                                TABLE
                  Count: 1                       Bottom Clip(in): 0.000
                   Type: Horizontal                 Top Clip(in): 0.000
                   Flow: Both                    Weir Disc Coef: 3.200
               Geometry: Rectangular           Orifice Disc Coef: 0.600

               Span(in): 37.00                       Invert(ft): 56.750
               Rise(in): 49.00                  Control Elev(ft): 56.750

*** Weir 2 of 2 for Drop Structure DS-E308 ***
                                                                                TABLE
                  Count: 1                       Bottom Clip(in): 0.000
                   Type: Vertical: Mavis            Top Clip(in): 0.000
                   Flow: Both                    Weir Disc Coef: 3.200
               Geometry: Rectangular           Orifice Disc Coef: 0.600

               Span(in): 24.00                       Invert(ft): 53.150
               Rise(in): 43.20                  Control Elev(ft): 53.150
```

================================================================================
==== Percolation Links ==========================================================
================================================================================

```
         Name: PERC E308           From Node: Pond 3                  Flow: Both
        Group: BASIN308              To Node: GRND 308               Count: 1

          Surface Area Option: Vary based on Stage/Area Table
   Vertical Flow Termination: Horizontal Flow Algorithm
       Aquifer Base Elev(ft): 35.330                      Perimeter 1(ft): 2300.000
       Water Table Elev(ft): 43.100                       Perimeter 2(ft): 2615.000
 ***************************-9999.000                    Perimeter 3(ft): 5200.000
  Horiz Conductivity(ft/day): 20.000                  Distance 1 to 2(ft): 50.000
   Vert Conductivity(ft/day): 10.000                  Distance 2 to 3(ft): 450.000
     Effective Porosity(dec): 0.250                      Num Cells 1 to 2: 10
            Suction Head(in): 4.000                      Num Cells 2 to 3: 45
         Layer Thickness(ft): 8.100
```

================================================================================
==== Hydrology Simulations ======================================================
================================================================================

```
         Name: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\100Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 18.50

Time(hrs)       Print Inc(min)
--------------- ---------------
336.000         5.00

--------------------------------------------------------------------------------------------------------
         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.R32
```

Override Defaults: No

| Time(hrs) | Print Inc(min) |
|---|---|
| 6.000 | 5.00 |
| 14.000 | 1.00 |
| 96.000 | 5.00 |

==========
==== Routing Simulations ==========
==========

Name: 100Y240H Hydrology Sim: 100Y240H
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\100Y240H.I32

Execute: Yes Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 336.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 336.000 | 15.000 |

| Group | Run |
|---|---|
| BASIN308 | Yes |

---

Name: SJRWMD Hydrology Sim: SJRWMD
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.I32


Execute: Yes Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 120.00
Min Calc Time(sec): 0.0100 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 6.000 | 5.000 |
| 14.000 | 1.000 |
| 96.000 | 5.000 |
| 120.000 | 5.000 |

| Group | Run |
|---|---|
| BASIN308 | Yes |

Post Development




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM
# PROPOSED BASIN 308

SHEET NO.
N/A

Synychak 6/2/2017 9:07:24 AM T:\Sys\Projects\24259245201\drainage\REPORT\ICPR Link_Node\Prop_Link Node.dgn

Basin 308
Proposed Conditions Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GRND 308 | BASIN308 | 100Y240H | 0.00 | 43.10 | 43.10 | 0.0000 | 0 | 38.51 | 9.86 | 0.00 | 0.00 |
| GRND 308 | BASIN308 | SJRWMD | 0.00 | 43.10 | 43.10 | 0.0000 | 0 | 57.78 | 12.52 | 0.00 | 0.00 |
| OUT 308 | BASIN308 | 100Y240H | 0.00 | 49.95 | 49.95 | 0.0000 | 0 | 184.35 | 20.51 | 0.00 | 0.00 |
| OUT 308 | BASIN308 | SJRWMD | 0.00 | 49.95 | 49.95 | 0.0000 | 0 | 68.08 | 2.86 | 0.00 | 0.00 |
| Pond 308 | BASIN308 | 100Y240H | 184.38 | 56.99 | 57.10 | 0.0033 | 155106 | 184.00 | 31.93 | 184.31 | 22.84 |
| Pond 308 | BASIN308 | SJRWMD | 68.25 | 55.50 | 57.10 | 0.0025 | 136898 | 60.08 | 124.51 | 57.06 | 11.55 |
| Pond 308A | BASIN308 | 100Y240H | 184.09 | 72.99 | 73.00 | 0.0026 | 106528 | 184.00 | 12.67 | 184.09 | 12.21 |
| Pond 308A | BASIN308 | SJRWMD | 62.39 | 72.43 | 73.00 | 0.0019 | 103732 | 60.08 | 78.75 | 62.39 | 5.62 |

Proposed Discharge Rates:
Basin 308
Q-FDOT (100-yr/240-hr)= 20.51 cfs
Q-SJRWMD (25-yr/96-hr)= 2.86 cfs

```
================================================================================
==== Basins ====================================================================
================================================================================

        Name: Basin 308               Node: Pond 308              Status: Onsite
       Group: BASIN308                Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                   Peaking Factor: 323.0
         Rainfall File: Sjrwmd96          Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200              Time of Conc(min): 23.00
            Area(ac): 27.270                Time Shift(hrs): 0.00
        Curve Number: 86.30             Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: Basin 308-1             Node: OUT 308               Status: Onsite
       Group: BASIN308                Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                   Peaking Factor: 323.0
         Rainfall File: Sjrwmd96          Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200              Time of Conc(min): 10.00
            Area(ac): 0.720                 Time Shift(hrs): 0.00
        Curve Number: 49.00             Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: Basin 308-2             Node: Pond 308              Status: Onsite
       Group: BASIN308                Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                   Peaking Factor: 323.0
         Rainfall File: Sjrwmd96          Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200              Time of Conc(min): 14.20
            Area(ac): 5.160                 Time Shift(hrs): 0.00
        Curve Number: 49.00             Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
        Name: Basin 308A              Node: Pond 308A             Status: Onsite
       Group: BASIN308                Type: SCS Unit Hydrograph CN

       Unit Hydrograph: Uh323                   Peaking Factor: 323.0
         Rainfall File: Sjrwmd96          Storm Duration(hrs): 96.00
   Rainfall Amount(in): 11.200              Time of Conc(min): 21.00
            Area(ac): 20.400                Time Shift(hrs): 0.00
        Curve Number: 76.10             Max Allowable Q(cfs): 999999.000
             DCIA(%): 0.00



================================================================================
==== Nodes =====================================================================
================================================================================

     Name: GRND 308           Base Flow(cfs): 0.000          Init Stage(ft): 43.100
    Group: BASIN308                                         Warn Stage(ft): 43.100
     Type: Time/Stage


     Time(hrs)       Stage(ft)
-------------- ---------------
          0.00          43.100
        336.00          43.100

--------------------------------------------------------------------------------------------------
     Name: OUT 308            Base Flow(cfs): 0.000          Init Stage(ft): 49.950
    Group: BASIN308                                         Warn Stage(ft): 49.950
     Type: Time/Stage


     Time(hrs)       Stage(ft)
-------------- ---------------
          0.00          49.950
        336.00          49.950

--------------------------------------------------------------------------------------------------
     Name: Pond 308           Base Flow(cfs): 0.000          Init Stage(ft): 51.200
    Group: BASIN308                                         Warn Stage(ft): 57.100
     Type: Stage/Area
```

| Stage(ft) | Area(ac) |
|---|---|
| 51.200 | 2.2900 |
| 52.010 | 2.4500 |
| 52.500 | 2.5500 |
| 53.230 | 2.6900 |
| 54.480 | 2.9400 |
| 54.980 | 3.0400 |
| 56.600 | 3.3600 |
| 58.100 | 4.1400 |

Name: Pond 308A  Base Flow(cfs): 0.000  Init Stage(ft): 69.100
Group: BASIN308  Warn Stage(ft): 73.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 69.100 | 1.9900 |
| 70.050 | 2.1000 |
| 70.650 | 2.1700 |
| 71.410 | 2.2600 |
| 72.070 | 2.3400 |
| 73.980 | 2.5600 |
| 74.000 | 2.5700 |

## Drop Structures

Name: S-O308  From Node: Pond 308  Length(ft): 310.00
Group: BASIN308  To Node: OUT 308  Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 30.00 | 30.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 30.00 | 30.00 | Flow: | Both |
| Invert(ft): | 51.180 | 50.520 | Entrance Loss Coef: | 1.000 |
| Manning's N: | 0.012000 | 0.012000 | Exit Loss Coef: | 0.500 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

*** Weir 1 of 2 for Drop Structure S-O308 ***

TABLE

Count: 1  Bottom Clip(in): 0.000
Type: Vertical: Mavis  Top Clip(in): 0.000
Flow: Both  Weir Disc Coef: 3.200
Geometry: Rectangular  Orifice Disc Coef: 0.600

Span(in): 28.00  Invert(ft): 54.980
Rise(in): 20.40  Control Elev(ft): 54.980

*** Weir 2 of 2 for Drop Structure S-O308 ***

TABLE

Count: 1  Bottom Clip(in): 0.000
Type: Horizontal  Top Clip(in): 0.000
Flow: Both  Weir Disc Coef: 3.200
Geometry: Rectangular  Orifice Disc Coef: 0.600

Span(in): 37.00  Invert(ft): 57.100
Rise(in): 49.00  Control Elev(ft): 57.100

Name: S-O308A  From Node: Pond 308A  Length(ft): 1800.00
Group: BASIN308  To Node: Pond 308  Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 24.00 | 24.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 24.00 | 24.00 | Flow: | Both |
| Invert(ft): | 67.810 | 51.200 | Entrance Loss Coef: | 1.000 |
| Manning's N: | 0.012000 | 0.012000 | Exit Loss Coef: | 0.500 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

*** Weir 1 of 2 for Drop Structure S-O308A ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 78.00 | Invert(ft): | 72.070 |
| Rise(in): | 4.92 | Control Elev(ft): | 72.070 |

*** Weir 2 of 2 for Drop Structure S-O308A ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 37.00 | Invert(ft): | 72.900 |
| Rise(in): | 49.00 | Control Elev(ft): | 72.900 |

==========
==== Percolation Links ====
==========

| | | | |
|---|---|---|---|
| Name: | PERC 308 | From Node: | Pond 308 |
| Group: | BASIN308 | To Node: | GRND 308 |
| Flow: | Both | | |
| Count: | 1 | | |

Surface Area Option: Vary based on Stage/Area Table
Vertical Flow Termination: Horizontal Flow Algorithm

| | | | |
|---|---|---|---|
| Aquifer Base Elev(ft): | 35.330 | Perimeter 1(ft): | 2300.000 |
| Water Table Elev(ft): | 43.100 | Perimeter 2(ft): | 2615.000 |
| **********: | -9999.000 | Perimeter 3(ft): | 5200.000 |
| Horiz Conductivity(ft/day): | 20.000 | Distance 1 to 2(ft): | 50.000 |
| Vert Conductivity(ft/day): | 10.000 | Distance 2 to 3(ft): | 450.000 |
| Effective Porosity(dec): | 0.250 | Num Cells 1 to 2: | 10 |
| Suction Head(in): | 4.000 | Num Cells 2 to 3: | 45 |
| Layer Thickness(ft): | 8.100 | | |

---

| | | | |
|---|---|---|---|
| Name: | PERC 308A | From Node: | Pond 308A |
| Group: | BASIN308 | To Node: | GRND 308 |
| Flow: | Both | | |
| Count: | 1 | | |

Surface Area Option: Vary based on Stage/Area Table
Vertical Flow Termination: Horizontal Flow Algorithm

| | | | |
|---|---|---|---|
| Aquifer Base Elev(ft): | 56.500 | Perimeter 1(ft): | 1331.000 |
| Water Table Elev(ft): | 60.300 | Perimeter 2(ft): | 1645.000 |
| **********: | -9999.000 | Perimeter 3(ft): | 4472.000 |
| Horiz Conductivity(ft/day): | 1.900 | Distance 1 to 2(ft): | 50.000 |
| Vert Conductivity(ft/day): | 0.950 | Distance 2 to 3(ft): | 450.000 |
| Effective Porosity(dec): | 0.250 | Num Cells 1 to 2: | 10 |
| Suction Head(in): | 4.000 | Num Cells 2 to 3: | 45 |
| Layer Thickness(ft): | 8.800 | | |

==========
==== Hydrology Simulations ====
==========

Name: 010Y240H
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.R32

Override Defaults: Yes
Storm Duration(hrs): 240.00
Rainfall File: Fdot-240
Rainfall Amount(in): 13.50

| Time(hrs) | Print Inc(min) |
|---|---|
| 240.000 | 5.00 |

---

Name: 050Y240H
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.R32

```
      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 17.50

Time(hrs)       Print Inc(min)
--------------- ---------------
250.000         5.00

------------------------------------------------------------------------------------------------
         Name: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 18.50

Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.00

------------------------------------------------------------------------------------------------
         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.R32

      Override Defaults: No

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
96.000          5.00

================================================================================
==== Routing Simulations ======================================================
================================================================================

         Name: 010Y240H            Hydrology Sim: 010Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.I32

      Execute: Yes         Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 240.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:



Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.000

Group           Run
--------------- -----
BASIN308        Yes


------------------------------------------------------------------------------------------------
         Name: 050Y240H            Hydrology Sim: 050Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.I32

      Execute: Yes         Restart: No            Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 240.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:



Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.000

Group           Run
--------------- -----
BASIN308        Yes


------------------------------------------------------------------------------------------------
         Name: 100Y240H            Hydrology Sim: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.I32
```

```
     Execute: Yes         Restart: No           Patch: No
  Alternative: No

       Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
       Start Time(hrs): 0.000                    End Time(hrs): 336.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
       Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
336.000         15.000

Group           Run
--------------- -----
BASIN308        Yes


-------------------------------------------------------------------------------------------------------
         Name: PERC               Hydrology Sim:
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\PERC.I32

     Execute: Yes         Restart: No           Patch: No
  Alternative: No

       Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
       Start Time(hrs): 0.000                    End Time(hrs): 720.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
       Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
720.000         1.000

Group           Run
--------------- -----
BASIN308        Yes


-------------------------------------------------------------------------------------------------------
         Name: SJRWMD             Hydrology Sim: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.I32

     Execute: Yes         Restart: No           Patch: No
  Alternative: No

       Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
       Start Time(hrs): 0.000                    End Time(hrs): 120.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
       Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.000
16.000          1.000
96.000          5.000
120.000         5.000

Group           Run
--------------- -----
BASIN308        Yes
```

Basin 308
SJRWMD Wekiva Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 0.00 | 52.01 | 57.10 | 106722 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308 | BASIN308 | 0.02 | 52.00 | 57.10 | 106677 | 0.00 | 12.35 | 0.00 | 0.01 |
| PERC | Pond 308 | BASIN308 | 0.03 | 52.00 | 57.10 | 106617 | 0.00 | 12.34 | 0.00 | 0.03 |
| PERC | Pond 308 | BASIN308 | 0.05 | 51.99 | 57.10 | 106556 | 0.00 | 12.33 | 0.00 | 0.04 |
| PERC | Pond 308 | BASIN308 | 0.07 | 51.98 | 57.10 | 106496 | 0.00 | 12.33 | 0.00 | 0.06 |
| PERC | Pond 308 | BASIN308 | 0.08 | 51.98 | 57.10 | 106436 | 0.00 | 12.32 | 0.00 | 0.08 |
| PERC | Pond 308 | BASIN308 | 0.10 | 51.97 | 57.10 | 106376 | 0.00 | 12.31 | 0.00 | 0.09 |
| PERC | Pond 308 | BASIN308 | 0.12 | 51.96 | 57.10 | 106315 | 0.00 | 12.31 | 0.00 | 0.11 |
| PERC | Pond 308 | BASIN308 | 0.13 | 51.96 | 57.10 | 106255 | 0.00 | 12.30 | 0.00 | 0.13 |
| PERC | Pond 308 | BASIN308 | 0.15 | 51.95 | 57.10 | 106195 | 0.00 | 12.29 | 0.00 | 0.15 |
| PERC | Pond 308 | BASIN308 | 0.17 | 51.94 | 57.10 | 106135 | 0.00 | 12.28 | 0.00 | 0.16 |
| PERC | Pond 308 | BASIN308 | 0.18 | 51.93 | 57.10 | 106074 | 0.00 | 12.28 | 0.00 | 0.18 |
| PERC | Pond 308 | BASIN308 | 0.20 | 51.93 | 57.10 | 106014 | 0.00 | 12.27 | 0.00 | 0.20 |
| PERC | Pond 308 | BASIN308 | 0.22 | 51.92 | 57.10 | 105954 | 0.00 | 12.26 | 0.00 | 0.21 |
| PERC | Pond 308 | BASIN308 | 0.24 | 51.91 | 57.10 | 105894 | 0.00 | 12.26 | 0.00 | 0.23 |
| PERC | Pond 308 | BASIN308 | 0.25 | 51.91 | 57.10 | 105833 | 0.00 | 12.25 | 0.00 | 0.25 |
| PERC | Pond 308 | BASIN308 | 0.27 | 51.90 | 57.10 | 105773 | 0.00 | 12.24 | 0.00 | 0.26 |
| PERC | Pond 308 | BASIN308 | 0.29 | 51.89 | 57.10 | 105713 | 0.00 | 12.24 | 0.00 | 0.28 |
| PERC | Pond 308 | BASIN308 | 0.30 | 51.89 | 57.10 | 105653 | 0.00 | 12.23 | 0.00 | 0.30 |
| PERC | Pond 308 | BASIN308 | 0.32 | 51.88 | 57.10 | 105592 | 0.00 | 12.22 | 0.00 | 0.32 |
| PERC | Pond 308 | BASIN308 | 0.34 | 51.87 | 57.10 | 105532 | 0.00 | 12.21 | 0.00 | 0.33 |
| PERC | Pond 308 | BASIN308 | 0.35 | 51.86 | 57.10 | 105472 | 0.00 | 12.21 | 0.00 | 0.35 |
| PERC | Pond 308 | BASIN308 | 0.37 | 51.86 | 57.10 | 105412 | 0.00 | 12.20 | 0.00 | 0.37 |
| PERC | Pond 308 | BASIN308 | 0.39 | 51.85 | 57.10 | 105351 | 0.00 | 12.19 | 0.00 | 0.38 |
| PERC | Pond 308 | BASIN308 | 0.40 | 51.84 | 57.10 | 105291 | 0.00 | 12.19 | 0.00 | 0.40 |
| PERC | Pond 308 | BASIN308 | 0.42 | 51.84 | 57.10 | 105231 | 0.00 | 12.18 | 0.00 | 0.42 |
| PERC | Pond 308 | BASIN308 | 0.44 | 51.83 | 57.10 | 105171 | 0.00 | 12.17 | 0.00 | 0.43 |
| PERC | Pond 308 | BASIN308 | 0.45 | 51.82 | 57.10 | 105110 | 0.00 | 12.17 | 0.00 | 0.45 |
| PERC | Pond 308 | BASIN308 | 0.47 | 51.82 | 57.10 | 105050 | 0.00 | 12.16 | 0.00 | 0.47 |
| PERC | Pond 308 | BASIN308 | 0.49 | 51.81 | 57.10 | 104990 | 0.00 | 12.15 | 0.00 | 0.48 |
| PERC | Pond 308 | BASIN308 | 0.50 | 51.80 | 57.10 | 104930 | 0.00 | 12.14 | 0.00 | 0.50 |
| PERC | Pond 308 | BASIN308 | 0.52 | 51.79 | 57.10 | 104869 | 0.00 | 12.14 | 0.00 | 0.52 |
| PERC | Pond 308 | BASIN308 | 0.54 | 51.79 | 57.10 | 104809 | 0.00 | 12.13 | 0.00 | 0.54 |
| PERC | Pond 308 | BASIN308 | 0.55 | 51.78 | 57.10 | 104749 | 0.00 | 12.12 | 0.00 | 0.55 |
| PERC | Pond 308 | BASIN308 | 0.57 | 51.77 | 57.10 | 104689 | 0.00 | 12.12 | 0.00 | 0.57 |
| PERC | Pond 308 | BASIN308 | 0.59 | 51.77 | 57.10 | 104628 | 0.00 | 12.11 | 0.00 | 0.59 |
| PERC | Pond 308 | BASIN308 | 0.61 | 51.76 | 57.10 | 104568 | 0.00 | 12.10 | 0.00 | 0.60 |
| PERC | Pond 308 | BASIN308 | 0.62 | 51.75 | 57.10 | 104508 | 0.00 | 12.10 | 0.00 | 0.62 |
| PERC | Pond 308 | BASIN308 | 0.64 | 51.75 | 57.10 | 104448 | 0.00 | 12.09 | 0.00 | 0.64 |
| PERC | Pond 308 | BASIN308 | 0.66 | 51.74 | 57.10 | 104387 | 0.00 | 12.08 | 0.00 | 0.65 |
| PERC | Pond 308 | BASIN308 | 0.67 | 51.73 | 57.10 | 104327 | 0.00 | 12.07 | 0.00 | 0.67 |
| PERC | Pond 308 | BASIN308 | 0.69 | 51.72 | 57.10 | 104267 | 0.00 | 12.07 | 0.00 | 0.69 |
| PERC | Pond 308 | BASIN308 | 0.71 | 51.72 | 57.10 | 104207 | 0.00 | 12.06 | 0.00 | 0.70 |
| PERC | Pond 308 | BASIN308 | 0.72 | 51.71 | 57.10 | 104146 | 0.00 | 12.05 | 0.00 | 0.72 |
| PERC | Pond 308 | BASIN308 | 0.74 | 51.70 | 57.10 | 104086 | 0.00 | 12.05 | 0.00 | 0.74 |
| PERC | Pond 308 | BASIN308 | 0.76 | 51.70 | 57.10 | 104026 | 0.00 | 12.04 | 0.00 | 0.75 |
| PERC | Pond 308 | BASIN308 | 0.77 | 51.69 | 57.10 | 103966 | 0.00 | 12.03 | 0.00 | 0.77 |
| PERC | Pond 308 | BASIN308 | 0.79 | 51.68 | 57.10 | 103905 | 0.00 | 12.03 | 0.00 | 0.79 |
| PERC | Pond 308 | BASIN308 | 0.81 | 51.68 | 57.10 | 103845 | 0.00 | 12.02 | 0.00 | 0.80 |
| PERC | Pond 308 | BASIN308 | 0.82 | 51.67 | 57.10 | 103785 | 0.00 | 12.01 | 0.00 | 0.82 |
| PERC | Pond 308 | BASIN308 | 0.84 | 51.66 | 57.10 | 103725 | 0.00 | 12.01 | 0.00 | 0.84 |
| PERC | Pond 308 | BASIN308 | 0.86 | 51.65 | 57.10 | 103664 | 0.00 | 12.00 | 0.00 | 0.85 |
| PERC | Pond 308 | BASIN308 | 0.87 | 51.65 | 57.10 | 103604 | 0.00 | 11.99 | 0.00 | 0.87 |
| PERC | Pond 308 | BASIN308 | 0.89 | 51.64 | 57.10 | 103544 | 0.00 | 11.98 | 0.00 | 0.89 |
| PERC | Pond 308 | BASIN308 | 0.91 | 51.63 | 57.10 | 103484 | 0.00 | 11.98 | 0.00 | 0.90 |
| PERC | Pond 308 | BASIN308 | 0.92 | 51.63 | 57.10 | 103423 | 0.00 | 11.97 | 0.00 | 0.92 |
| PERC | Pond 308 | BASIN308 | 0.94 | 51.62 | 57.10 | 103363 | 0.00 | 11.96 | 0.00 | 0.94 |
| PERC | Pond 308 | BASIN308 | 0.96 | 51.61 | 57.10 | 103303 | 0.00 | 11.96 | 0.00 | 0.95 |
| PERC | Pond 308 | BASIN308 | 0.97 | 51.61 | 57.10 | 103243 | 0.00 | 11.95 | 0.00 | 0.97 |
| PERC | Pond 308 | BASIN308 | 0.99 | 51.60 | 57.10 | 103182 | 0.00 | 11.94 | 0.00 | 0.99 |
| PERC | Pond 308 | BASIN308 | 1.01 | 51.59 | 57.10 | 103122 | 0.00 | 11.94 | 0.00 | 1.00 |
| PERC | Pond 308 | BASIN308 | 1.02 | 51.59 | 57.10 | 103092 | 0.00 | 11.93 | 0.00 | 1.01 |
| PERC | Pond 308 | BASIN308 | 1.03 | 51.58 | 57.10 | 103032 | 0.00 | 11.92 | 0.00 | 1.03 |
| PERC | Pond 308 | BASIN308 | 1.05 | 51.57 | 57.10 | 102971 | 0.00 | 11.92 | 0.00 | 1.04 |
| PERC | Pond 308 | BASIN308 | 1.07 | 51.57 | 57.10 | 102911 | 0.00 | 11.91 | 0.00 | 1.06 |
| PERC | Pond 308 | BASIN308 | 1.08 | 51.56 | 57.10 | 102851 | 0.00 | 11.90 | 0.00 | 1.08 |
| PERC | Pond 308 | BASIN308 | 1.10 | 51.55 | 57.10 | 102791 | 0.00 | 11.90 | 0.00 | 1.09 |
| PERC | Pond 308 | BASIN308 | 1.12 | 51.55 | 57.10 | 102730 | 0.00 | 11.89 | 0.00 | 1.11 |
| PERC | Pond 308 | BASIN308 | 1.13 | 51.54 | 57.10 | 102670 | 0.00 | 11.88 | 0.00 | 1.13 |
| PERC | Pond 308 | BASIN308 | 1.15 | 51.53 | 57.10 | 102610 | 0.00 | 11.88 | 0.00 | 1.14 |
| PERC | Pond 308 | BASIN308 | 1.17 | 51.53 | 57.10 | 102550 | 0.00 | 11.87 | 0.00 | 1.16 |
| PERC | Pond 308 | BASIN308 | 1.18 | 51.52 | 57.10 | 102489 | 0.00 | 11.86 | 0.00 | 1.18 |
| PERC | Pond 308 | BASIN308 | 1.20 | 51.51 | 57.10 | 102429 | 0.00 | 11.86 | 0.00 | 1.19 |
| PERC | Pond 308 | BASIN308 | 1.22 | 51.50 | 57.10 | 102369 | 0.00 | 11.85 | 0.00 | 1.21 |
| PERC | Pond 308 | BASIN308 | 1.24 | 51.50 | 57.10 | 102309 | 0.00 | 11.84 | 0.00 | 1.23 |
| PERC | Pond 308 | BASIN308 | 1.25 | 51.49 | 57.10 | 102248 | 0.00 | 11.83 | 0.00 | 1.24 |
| PERC | Pond 308 | BASIN308 | 1.27 | 51.48 | 57.10 | 102188 | 0.00 | 11.83 | 0.00 | 1.26 |
| PERC | Pond 308 | BASIN308 | 1.29 | 51.48 | 57.10 | 102128 | 0.00 | 11.82 | 0.00 | 1.28 |
| PERC | Pond 308 | BASIN308 | 1.30 | 51.47 | 57.10 | 102068 | 0.00 | 11.81 | 0.00 | 1.29 |
| PERC | Pond 308 | BASIN308 | 1.32 | 51.46 | 57.10 | 102007 | 0.00 | 11.81 | 0.00 | 1.31 |
| PERC | Pond 308 | BASIN308 | 1.34 | 51.46 | 57.10 | 101947 | 0.00 | 11.80 | 0.00 | 1.32 |
| PERC | Pond 308 | BASIN308 | 1.35 | 51.45 | 57.10 | 101887 | 0.00 | 11.79 | 0.00 | 1.34 |
| PERC | Pond 308 | BASIN308 | 1.37 | 51.44 | 57.10 | 101827 | 0.00 | 11.79 | 0.00 | 1.36 |
| PERC | Pond 308 | BASIN308 | 1.39 | 51.43 | 57.10 | 101766 | 0.00 | 11.78 | 0.00 | 1.37 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 1.40 | 51.43 | 57.10 | 101706 | 0.00 | 11.77 | 0.00 | 1.39 |
| PERC | Pond 308 | BASIN308 | 1.42 | 51.42 | 57.10 | 101646 | 0.00 | 11.76 | 0.00 | 1.41 |
| PERC | Pond 308 | BASIN308 | 1.44 | 51.41 | 57.10 | 101586 | 0.00 | 11.76 | 0.00 | 1.42 |
| PERC | Pond 308 | BASIN308 | 1.45 | 51.41 | 57.10 | 101525 | 0.00 | 11.75 | 0.00 | 1.44 |
| PERC | Pond 308 | BASIN308 | 1.47 | 51.40 | 57.10 | 101465 | 0.00 | 11.74 | 0.00 | 1.46 |
| PERC | Pond 308 | BASIN308 | 1.49 | 51.39 | 57.10 | 101405 | 0.00 | 11.74 | 0.00 | 1.47 |
| PERC | Pond 308 | BASIN308 | 1.50 | 51.39 | 57.10 | 101345 | 0.00 | 11.73 | 0.00 | 1.49 |
| PERC | Pond 308 | BASIN308 | 1.52 | 51.38 | 57.10 | 101284 | 0.00 | 11.72 | 0.00 | 1.50 |
| PERC | Pond 308 | BASIN308 | 1.54 | 51.37 | 57.10 | 101224 | 0.00 | 11.72 | 0.00 | 1.52 |
| PERC | Pond 308 | BASIN308 | 1.55 | 51.36 | 57.10 | 101164 | 0.00 | 11.71 | 0.00 | 1.54 |
| PERC | Pond 308 | BASIN308 | 1.57 | 51.36 | 57.10 | 101104 | 0.00 | 11.70 | 0.00 | 1.55 |
| PERC | Pond 308 | BASIN308 | 1.59 | 51.35 | 57.10 | 101043 | 0.00 | 11.69 | 0.00 | 1.57 |
| PERC | Pond 308 | BASIN308 | 1.60 | 51.34 | 57.10 | 100983 | 0.00 | 11.69 | 0.00 | 1.59 |
| PERC | Pond 308 | BASIN308 | 1.62 | 51.34 | 57.10 | 100923 | 0.00 | 11.68 | 0.00 | 1.60 |
| PERC | Pond 308 | BASIN308 | 1.64 | 51.33 | 57.10 | 100863 | 0.00 | 11.67 | 0.00 | 1.62 |
| PERC | Pond 308 | BASIN308 | 1.66 | 51.32 | 57.10 | 100802 | 0.00 | 11.67 | 0.00 | 1.63 |
| PERC | Pond 308 | BASIN308 | 1.67 | 51.32 | 57.10 | 100742 | 0.00 | 11.66 | 0.00 | 1.65 |
| PERC | Pond 308 | BASIN308 | 1.69 | 51.31 | 57.10 | 100682 | 0.00 | 11.65 | 0.00 | 1.67 |
| PERC | Pond 308 | BASIN308 | 1.71 | 51.30 | 57.10 | 100622 | 0.00 | 11.65 | 0.00 | 1.68 |
| PERC | Pond 308 | BASIN308 | 1.72 | 51.29 | 57.10 | 100561 | 0.00 | 11.64 | 0.00 | 1.70 |
| PERC | Pond 308 | BASIN308 | 1.74 | 51.29 | 57.10 | 100501 | 0.00 | 11.63 | 0.00 | 1.72 |
| PERC | Pond 308 | BASIN308 | 1.76 | 51.28 | 57.10 | 100441 | 0.00 | 11.63 | 0.00 | 1.73 |
| PERC | Pond 308 | BASIN308 | 1.77 | 51.27 | 57.10 | 100381 | 0.00 | 11.62 | 0.00 | 1.75 |
| PERC | Pond 308 | BASIN308 | 1.79 | 51.27 | 57.10 | 100320 | 0.00 | 11.61 | 0.00 | 1.76 |
| PERC | Pond 308 | BASIN308 | 1.81 | 51.26 | 57.10 | 100260 | 0.00 | 11.60 | 0.00 | 1.78 |
| PERC | Pond 308 | BASIN308 | 1.82 | 51.25 | 57.10 | 100200 | 0.00 | 11.60 | 0.00 | 1.80 |
| PERC | Pond 308 | BASIN308 | 1.84 | 51.24 | 57.10 | 100140 | 0.00 | 11.59 | 0.00 | 1.81 |
| PERC | Pond 308 | BASIN308 | 1.86 | 51.24 | 57.10 | 100079 | 0.00 | 11.58 | 0.00 | 1.83 |
| PERC | Pond 308 | BASIN308 | 1.87 | 51.23 | 57.10 | 100019 | 0.00 | 11.58 | 0.00 | 1.84 |
| PERC | Pond 308 | BASIN308 | 1.89 | 51.22 | 57.10 | 99959 | 0.00 | 11.57 | 0.00 | 1.86 |
| PERC | Pond 308 | BASIN308 | 1.91 | 51.22 | 57.10 | 99899 | 0.00 | 11.56 | 0.00 | 1.88 |
| PERC | Pond 308 | BASIN308 | 1.92 | 51.21 | 57.10 | 99838 | 0.00 | 11.56 | 0.00 | 1.89 |
| PERC | Pond 308 | BASIN308 | 1.94 | 51.20 | 57.10 | 99778 | 0.00 | 11.55 | 0.00 | 1.91 |
| PERC | Pond 308 | BASIN308 | 1.96 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 1.97 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 1.99 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.01 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.02 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.03 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.05 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.08 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.09 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.11 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.12 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.14 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.16 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.18 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.19 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.20 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.23 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.24 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.25 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.27 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.29 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.31 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.33 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.34 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.36 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.38 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.39 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.41 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.42 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.44 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.46 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.47 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.49 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.51 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.52 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.54 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.56 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.57 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.59 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.61 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.62 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.64 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.66 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.67 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.69 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.71 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.72 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.74 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.76 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.77 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |
| PERC | Pond 308 | BASIN308 | 2.79 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 1.92 |

Basin 308
SJRWMD Treatment Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 0.00 | 52.50 | 57.10 | 111078 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308 | BASIN308 | 0.02 | 52.49 | 57.10 | 111031 | 0.00 | 12.85 | 0.00 | 0.01 |
| PERC | Pond 308 | BASIN308 | 0.03 | 52.49 | 57.10 | 110969 | 0.00 | 12.84 | 0.00 | 0.03 |
| PERC | Pond 308 | BASIN308 | 0.05 | 52.48 | 57.10 | 110907 | 0.00 | 12.84 | 0.00 | 0.04 |
| PERC | Pond 308 | BASIN308 | 0.07 | 52.47 | 57.10 | 110845 | 0.00 | 12.83 | 0.00 | 0.06 |
| PERC | Pond 308 | BASIN308 | 0.08 | 52.47 | 57.10 | 110782 | 0.00 | 12.82 | 0.00 | 0.08 |
| PERC | Pond 308 | BASIN308 | 0.10 | 52.46 | 57.10 | 110720 | 0.00 | 12.81 | 0.00 | 0.10 |
| PERC | Pond 308 | BASIN308 | 0.12 | 52.45 | 57.10 | 110658 | 0.00 | 12.81 | 0.00 | 0.12 |
| PERC | Pond 308 | BASIN308 | 0.13 | 52.45 | 57.10 | 110596 | 0.00 | 12.80 | 0.00 | 0.13 |
| PERC | Pond 308 | BASIN308 | 0.15 | 52.44 | 57.10 | 110533 | 0.00 | 12.79 | 0.00 | 0.15 |
| PERC | Pond 308 | BASIN308 | 0.17 | 52.43 | 57.10 | 110471 | 0.00 | 12.79 | 0.00 | 0.17 |
| PERC | Pond 308 | BASIN308 | 0.18 | 52.42 | 57.10 | 110409 | 0.00 | 12.78 | 0.00 | 0.19 |
| PERC | Pond 308 | BASIN308 | 0.20 | 52.42 | 57.10 | 110347 | 0.00 | 12.77 | 0.00 | 0.20 |
| PERC | Pond 308 | BASIN308 | 0.22 | 52.41 | 57.10 | 110284 | 0.00 | 12.76 | 0.00 | 0.22 |
| PERC | Pond 308 | BASIN308 | 0.24 | 52.40 | 57.10 | 110222 | 0.00 | 12.76 | 0.00 | 0.24 |
| PERC | Pond 308 | BASIN308 | 0.25 | 52.40 | 57.10 | 110160 | 0.00 | 12.75 | 0.00 | 0.26 |
| PERC | Pond 308 | BASIN308 | 0.27 | 52.39 | 57.10 | 110098 | 0.00 | 12.74 | 0.00 | 0.28 |
| PERC | Pond 308 | BASIN308 | 0.29 | 52.38 | 57.10 | 110035 | 0.00 | 12.74 | 0.00 | 0.29 |
| PERC | Pond 308 | BASIN308 | 0.30 | 52.38 | 57.10 | 109973 | 0.00 | 12.73 | 0.00 | 0.31 |
| PERC | Pond 308 | BASIN308 | 0.32 | 52.37 | 57.10 | 109911 | 0.00 | 12.72 | 0.00 | 0.33 |
| PERC | Pond 308 | BASIN308 | 0.34 | 52.36 | 57.10 | 109849 | 0.00 | 12.71 | 0.00 | 0.35 |
| PERC | Pond 308 | BASIN308 | 0.35 | 52.35 | 57.10 | 109786 | 0.00 | 12.71 | 0.00 | 0.36 |
| PERC | Pond 308 | BASIN308 | 0.37 | 52.35 | 57.10 | 109724 | 0.00 | 12.70 | 0.00 | 0.38 |
| PERC | Pond 308 | BASIN308 | 0.39 | 52.34 | 57.10 | 109662 | 0.00 | 12.69 | 0.00 | 0.40 |
| PERC | Pond 308 | BASIN308 | 0.40 | 52.33 | 57.10 | 109600 | 0.00 | 12.69 | 0.00 | 0.42 |
| PERC | Pond 308 | BASIN308 | 0.42 | 52.33 | 57.10 | 109537 | 0.00 | 12.68 | 0.00 | 0.43 |
| PERC | Pond 308 | BASIN308 | 0.44 | 52.32 | 57.10 | 109475 | 0.00 | 12.67 | 0.00 | 0.45 |
| PERC | Pond 308 | BASIN308 | 0.45 | 52.31 | 57.10 | 109413 | 0.00 | 12.66 | 0.00 | 0.47 |
| PERC | Pond 308 | BASIN308 | 0.47 | 52.31 | 57.10 | 109351 | 0.00 | 12.66 | 0.00 | 0.49 |
| PERC | Pond 308 | BASIN308 | 0.49 | 52.30 | 57.10 | 109288 | 0.00 | 12.65 | 0.00 | 0.50 |
| PERC | Pond 308 | BASIN308 | 0.50 | 52.29 | 57.10 | 109226 | 0.00 | 12.64 | 0.00 | 0.52 |
| PERC | Pond 308 | BASIN308 | 0.52 | 52.28 | 57.10 | 109164 | 0.00 | 12.63 | 0.00 | 0.54 |
| PERC | Pond 308 | BASIN308 | 0.54 | 52.28 | 57.10 | 109102 | 0.00 | 12.63 | 0.00 | 0.56 |
| PERC | Pond 308 | BASIN308 | 0.55 | 52.27 | 57.10 | 109039 | 0.00 | 12.62 | 0.00 | 0.57 |
| PERC | Pond 308 | BASIN308 | 0.57 | 52.26 | 57.10 | 108977 | 0.00 | 12.61 | 0.00 | 0.59 |
| PERC | Pond 308 | BASIN308 | 0.59 | 52.26 | 57.10 | 108915 | 0.00 | 12.61 | 0.00 | 0.61 |
| PERC | Pond 308 | BASIN308 | 0.61 | 52.25 | 57.10 | 108853 | 0.00 | 12.60 | 0.00 | 0.63 |
| PERC | Pond 308 | BASIN308 | 0.62 | 52.24 | 57.10 | 108790 | 0.00 | 12.59 | 0.00 | 0.64 |
| PERC | Pond 308 | BASIN308 | 0.64 | 52.24 | 57.10 | 108728 | 0.00 | 12.58 | 0.00 | 0.66 |
| PERC | Pond 308 | BASIN308 | 0.66 | 52.23 | 57.10 | 108666 | 0.00 | 12.58 | 0.00 | 0.68 |
| PERC | Pond 308 | BASIN308 | 0.67 | 52.22 | 57.10 | 108604 | 0.00 | 12.57 | 0.00 | 0.70 |
| PERC | Pond 308 | BASIN308 | 0.69 | 52.21 | 57.10 | 108541 | 0.00 | 12.56 | 0.00 | 0.71 |
| PERC | Pond 308 | BASIN308 | 0.71 | 52.21 | 57.10 | 108479 | 0.00 | 12.56 | 0.00 | 0.73 |
| PERC | Pond 308 | BASIN308 | 0.72 | 52.20 | 57.10 | 108417 | 0.00 | 12.55 | 0.00 | 0.75 |
| PERC | Pond 308 | BASIN308 | 0.74 | 52.19 | 57.10 | 108355 | 0.00 | 12.54 | 0.00 | 0.77 |
| PERC | Pond 308 | BASIN308 | 0.76 | 52.19 | 57.10 | 108292 | 0.00 | 12.53 | 0.00 | 0.78 |
| PERC | Pond 308 | BASIN308 | 0.77 | 52.18 | 57.10 | 108230 | 0.00 | 12.53 | 0.00 | 0.80 |
| PERC | Pond 308 | BASIN308 | 0.79 | 52.17 | 57.10 | 108168 | 0.00 | 12.52 | 0.00 | 0.82 |
| PERC | Pond 308 | BASIN308 | 0.81 | 52.17 | 57.10 | 108106 | 0.00 | 12.51 | 0.00 | 0.84 |
| PERC | Pond 308 | BASIN308 | 0.82 | 52.16 | 57.10 | 108043 | 0.00 | 12.51 | 0.00 | 0.85 |
| PERC | Pond 308 | BASIN308 | 0.84 | 52.15 | 57.10 | 107981 | 0.00 | 12.50 | 0.00 | 0.87 |
| PERC | Pond 308 | BASIN308 | 0.86 | 52.14 | 57.10 | 107919 | 0.00 | 12.49 | 0.00 | 0.89 |
| PERC | Pond 308 | BASIN308 | 0.87 | 52.14 | 57.10 | 107857 | 0.00 | 12.48 | 0.00 | 0.91 |
| PERC | Pond 308 | BASIN308 | 0.89 | 52.13 | 57.10 | 107794 | 0.00 | 12.48 | 0.00 | 0.92 |
| PERC | Pond 308 | BASIN308 | 0.91 | 52.12 | 57.10 | 107732 | 0.00 | 12.47 | 0.00 | 0.94 |
| PERC | Pond 308 | BASIN308 | 0.92 | 52.12 | 57.10 | 107670 | 0.00 | 12.46 | 0.00 | 0.96 |
| PERC | Pond 308 | BASIN308 | 0.94 | 52.11 | 57.10 | 107608 | 0.00 | 12.45 | 0.00 | 0.98 |
| PERC | Pond 308 | BASIN308 | 0.96 | 52.10 | 57.10 | 107545 | 0.00 | 12.45 | 0.00 | 0.99 |
| PERC | Pond 308 | BASIN308 | 0.97 | 52.10 | 57.10 | 107483 | 0.00 | 12.44 | 0.00 | 1.01 |
| PERC | Pond 308 | BASIN308 | 0.99 | 52.09 | 57.10 | 107421 | 0.00 | 12.43 | 0.00 | 1.03 |
| PERC | Pond 308 | BASIN308 | 1.01 | 52.08 | 57.10 | 107359 | 0.00 | 12.43 | 0.00 | 1.04 |
| PERC | Pond 308 | BASIN308 | 1.02 | 52.08 | 57.10 | 107327 | 0.00 | 12.42 | 0.00 | 1.05 |
| PERC | Pond 308 | BASIN308 | 1.03 | 52.07 | 57.10 | 107265 | 0.00 | 12.41 | 0.00 | 1.07 |
| PERC | Pond 308 | BASIN308 | 1.05 | 52.06 | 57.10 | 107203 | 0.00 | 12.41 | 0.00 | 1.09 |
| PERC | Pond 308 | BASIN308 | 1.07 | 52.06 | 57.10 | 107141 | 0.00 | 12.40 | 0.00 | 1.10 |
| PERC | Pond 308 | BASIN308 | 1.08 | 52.05 | 57.10 | 107078 | 0.00 | 12.39 | 0.00 | 1.12 |
| PERC | Pond 308 | BASIN308 | 1.10 | 52.04 | 57.10 | 107016 | 0.00 | 12.39 | 0.00 | 1.14 |
| PERC | Pond 308 | BASIN308 | 1.12 | 52.04 | 57.10 | 106954 | 0.00 | 12.38 | 0.00 | 1.16 |
| PERC | Pond 308 | BASIN308 | 1.13 | 52.03 | 57.10 | 106892 | 0.00 | 12.37 | 0.00 | 1.17 |
| PERC | Pond 308 | BASIN308 | 1.15 | 52.02 | 57.10 | 106829 | 0.00 | 12.36 | 0.00 | 1.19 |
| PERC | Pond 308 | BASIN308 | 1.17 | 52.02 | 57.10 | 106767 | 0.00 | 12.36 | 0.00 | 1.21 |
| PERC | Pond 308 | BASIN308 | 1.18 | 52.01 | 57.10 | 106706 | 0.00 | 12.35 | 0.00 | 1.23 |
| PERC | Pond 308 | BASIN308 | 1.20 | 52.00 | 57.10 | 106645 | 0.00 | 12.34 | 0.00 | 1.24 |
| PERC | Pond 308 | BASIN308 | 1.22 | 51.99 | 57.10 | 106585 | 0.00 | 12.34 | 0.00 | 1.26 |
| PERC | Pond 308 | BASIN308 | 1.24 | 51.99 | 57.10 | 106525 | 0.00 | 12.33 | 0.00 | 1.28 |
| PERC | Pond 308 | BASIN308 | 1.25 | 51.98 | 57.10 | 106465 | 0.00 | 12.32 | 0.00 | 1.29 |
| PERC | Pond 308 | BASIN308 | 1.27 | 51.97 | 57.10 | 106404 | 0.00 | 12.32 | 0.00 | 1.31 |
| PERC | Pond 308 | BASIN308 | 1.29 | 51.97 | 57.10 | 106344 | 0.00 | 12.31 | 0.00 | 1.33 |
| PERC | Pond 308 | BASIN308 | 1.30 | 51.96 | 57.10 | 106284 | 0.00 | 12.30 | 0.00 | 1.35 |
| PERC | Pond 308 | BASIN308 | 1.32 | 51.95 | 57.10 | 106224 | 0.00 | 12.29 | 0.00 | 1.36 |
| PERC | Pond 308 | BASIN308 | 1.34 | 51.95 | 57.10 | 106163 | 0.00 | 12.29 | 0.00 | 1.38 |
| PERC | Pond 308 | BASIN308 | 1.35 | 51.94 | 57.10 | 106103 | 0.00 | 12.28 | 0.00 | 1.40 |
| PERC | Pond 308 | BASIN308 | 1.37 | 51.93 | 57.10 | 106043 | 0.00 | 12.27 | 0.00 | 1.41 |
| PERC | Pond 308 | BASIN308 | 1.39 | 51.92 | 57.10 | 105983 | 0.00 | 12.27 | 0.00 | 1.43 |

Basin 308
SJRWMD Treatment Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 2.81 | 51.33 | 57.10 | 100891 | 0.00 | 11.68 | 0.00 | 2.84 |
| PERC | Pond 308 | BASIN308 | 2.82 | 51.33 | 57.10 | 100831 | 0.00 | 11.67 | 0.00 | 2.85 |
| PERC | Pond 308 | BASIN308 | 2.84 | 51.32 | 57.10 | 100771 | 0.00 | 11.66 | 0.00 | 2.87 |
| PERC | Pond 308 | BASIN308 | 2.86 | 51.31 | 57.10 | 100711 | 0.00 | 11.66 | 0.00 | 2.88 |
| PERC | Pond 308 | BASIN308 | 2.87 | 51.30 | 57.10 | 100650 | 0.00 | 11.65 | 0.00 | 2.90 |
| PERC | Pond 308 | BASIN308 | 2.89 | 51.30 | 57.10 | 100590 | 0.00 | 11.64 | 0.00 | 2.92 |
| PERC | Pond 308 | BASIN308 | 2.91 | 51.29 | 57.10 | 100530 | 0.00 | 11.64 | 0.00 | 2.93 |
| PERC | Pond 308 | BASIN308 | 2.92 | 51.28 | 57.10 | 100470 | 0.00 | 11.63 | 0.00 | 2.95 |
| PERC | Pond 308 | BASIN308 | 2.94 | 51.28 | 57.10 | 100409 | 0.00 | 11.62 | 0.00 | 2.96 |
| PERC | Pond 308 | BASIN308 | 2.96 | 51.27 | 57.10 | 100349 | 0.00 | 11.61 | 0.00 | 2.98 |
| PERC | Pond 308 | BASIN308 | 2.97 | 51.26 | 57.10 | 100289 | 0.00 | 11.61 | 0.00 | 3.00 |
| PERC | Pond 308 | BASIN308 | 2.99 | 51.26 | 57.10 | 100229 | 0.00 | 11.60 | 0.00 | 3.01 |
| PERC | Pond 308 | BASIN308 | 3.01 | 51.25 | 57.10 | 100168 | 0.00 | 11.59 | 0.00 | 3.03 |
| PERC | Pond 308 | BASIN308 | 3.03 | 51.24 | 57.10 | 100108 | 0.00 | 11.59 | 0.00 | 3.05 |
| PERC | Pond 308 | BASIN308 | 3.03 | 51.24 | 57.10 | 100078 | 0.00 | 11.58 | 0.00 | 3.05 |
| PERC | Pond 308 | BASIN308 | 3.05 | 51.23 | 57.10 | 100018 | 0.00 | 11.58 | 0.00 | 3.07 |
| PERC | Pond 308 | BASIN308 | 3.07 | 51.22 | 57.10 | 99957 | 0.00 | 11.57 | 0.00 | 3.09 |
| PERC | Pond 308 | BASIN308 | 3.08 | 51.22 | 57.10 | 99897 | 0.00 | 11.56 | 0.00 | 3.10 |
| PERC | Pond 308 | BASIN308 | 3.10 | 51.21 | 57.10 | 99837 | 0.00 | 11.56 | 0.00 | 3.12 |
| PERC | Pond 308 | BASIN308 | 3.12 | 51.20 | 57.10 | 99777 | 0.00 | 11.55 | 0.00 | 3.13 |
| PERC | Pond 308 | BASIN308 | 3.13 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.15 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.17 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.18 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.20 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.22 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.24 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.25 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.27 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.28 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.30 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.33 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.34 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.35 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.38 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.39 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.40 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.42 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.44 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.46 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.47 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.49 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.50 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.52 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.54 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.55 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.57 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.58 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.60 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.62 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.63 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.65 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.67 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.68 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.70 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.72 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.73 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.75 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.77 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.78 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.80 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.82 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.83 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.85 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.87 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.88 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.90 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.92 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.93 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.95 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.97 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 3.98 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.00 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.02 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.03 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.05 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.07 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.08 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.10 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.12 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.13 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.15 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.17 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |
| PERC | Pond 308 | BASIN308 | 4.18 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 3.14 |

Basin 308
SJRWMD Closed Basin Recovery
14-Day

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| PERC | Pond 308 | BASIN308 | 0.00 | 54.48 | 57.10 | 128066 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308 | BASIN308 | 0.02 | 54.47 | 57.10 | 128021 | 0.00 | 14.82 | 0.00 | 0.01 |
| PERC | Pond 308 | BASIN308 | 0.03 | 54.47 | 57.10 | 127960 | 0.00 | 14.81 | 0.00 | 0.03 |
| PERC | Pond 308 | BASIN308 | 0.05 | 54.46 | 57.10 | 127899 | 0.00 | 14.80 | 0.00 | 0.05 |
| PERC | Pond 308 | BASIN308 | 0.07 | 54.45 | 57.10 | 127838 | 0.00 | 14.80 | 0.00 | 0.07 |
| PERC | Pond 308 | BASIN308 | 0.08 | 54.45 | 57.10 | 127777 | 0.00 | 14.79 | 0.00 | 0.09 |
| PERC | Pond 308 | BASIN308 | 0.10 | 54.44 | 57.10 | 127716 | 0.00 | 14.78 | 0.00 | 0.11 |
| PERC | Pond 308 | BASIN308 | 0.12 | 54.43 | 57.10 | 127655 | 0.00 | 14.77 | 0.00 | 0.13 |
| PERC | Pond 308 | BASIN308 | 0.13 | 54.43 | 57.10 | 127594 | 0.00 | 14.77 | 0.00 | 0.15 |
| PERC | Pond 308 | BASIN308 | 0.15 | 54.42 | 57.10 | 127533 | 0.00 | 14.76 | 0.00 | 0.17 |
| PERC | Pond 308 | BASIN308 | 0.17 | 54.41 | 57.10 | 127472 | 0.00 | 14.75 | 0.00 | 0.20 |
| PERC | Pond 308 | BASIN308 | 0.18 | 54.40 | 57.10 | 127411 | 0.00 | 14.75 | 0.00 | 0.22 |
| PERC | Pond 308 | BASIN308 | 0.20 | 54.40 | 57.10 | 127350 | 0.00 | 14.74 | 0.00 | 0.24 |
| PERC | Pond 308 | BASIN308 | 0.22 | 54.39 | 57.10 | 127289 | 0.00 | 14.73 | 0.00 | 0.26 |
| PERC | Pond 308 | BASIN308 | 0.24 | 54.38 | 57.10 | 127228 | 0.00 | 14.73 | 0.00 | 0.28 |
| PERC | Pond 308 | BASIN308 | 0.25 | 54.38 | 57.10 | 127167 | 0.00 | 14.72 | 0.00 | 0.30 |
| PERC | Pond 308 | BASIN308 | 0.27 | 54.37 | 57.10 | 127106 | 0.00 | 14.71 | 0.00 | 0.32 |
| PERC | Pond 308 | BASIN308 | 0.29 | 54.36 | 57.10 | 127045 | 0.00 | 14.70 | 0.00 | 0.34 |
| PERC | Pond 308 | BASIN308 | 0.30 | 54.36 | 57.10 | 126984 | 0.00 | 14.70 | 0.00 | 0.36 |
| PERC | Pond 308 | BASIN308 | 0.32 | 54.35 | 57.10 | 126923 | 0.00 | 14.69 | 0.00 | 0.38 |
| PERC | Pond 308 | BASIN308 | 0.34 | 54.34 | 57.10 | 126862 | 0.00 | 14.68 | 0.00 | 0.40 |
| PERC | Pond 308 | BASIN308 | 0.35 | 54.33 | 57.10 | 126801 | 0.00 | 14.68 | 0.00 | 0.42 |
| PERC | Pond 308 | BASIN308 | 0.37 | 54.33 | 57.10 | 126740 | 0.00 | 14.67 | 0.00 | 0.44 |
| PERC | Pond 308 | BASIN308 | 0.39 | 54.32 | 57.10 | 126679 | 0.00 | 14.66 | 0.00 | 0.46 |
| PERC | Pond 308 | BASIN308 | 0.40 | 54.31 | 57.10 | 126618 | 0.00 | 14.65 | 0.00 | 0.48 |
| PERC | Pond 308 | BASIN308 | 0.42 | 54.31 | 57.10 | 126557 | 0.00 | 14.65 | 0.00 | 0.50 |
| PERC | Pond 308 | BASIN308 | 0.44 | 54.30 | 57.10 | 126496 | 0.00 | 14.64 | 0.00 | 0.52 |
| PERC | Pond 308 | BASIN308 | 0.45 | 54.29 | 57.10 | 126435 | 0.00 | 14.63 | 0.00 | 0.54 |
| PERC | Pond 308 | BASIN308 | 0.47 | 54.29 | 57.10 | 126374 | 0.00 | 14.63 | 0.00 | 0.56 |
| PERC | Pond 308 | BASIN308 | 0.49 | 54.28 | 57.10 | 126313 | 0.00 | 14.62 | 0.00 | 0.58 |
| PERC | Pond 308 | BASIN308 | 0.50 | 54.27 | 57.10 | 126252 | 0.00 | 14.61 | 0.00 | 0.60 |
| PERC | Pond 308 | BASIN308 | 0.52 | 54.26 | 57.10 | 126191 | 0.00 | 14.61 | 0.00 | 0.62 |
| PERC | Pond 308 | BASIN308 | 0.54 | 54.26 | 57.10 | 126130 | 0.00 | 14.60 | 0.00 | 0.64 |
| PERC | Pond 308 | BASIN308 | 0.55 | 54.25 | 57.10 | 126069 | 0.00 | 14.59 | 0.00 | 0.66 |
| PERC | Pond 308 | BASIN308 | 0.57 | 54.24 | 57.10 | 126008 | 0.00 | 14.58 | 0.00 | 0.68 |
| PERC | Pond 308 | BASIN308 | 0.59 | 54.24 | 57.10 | 125947 | 0.00 | 14.58 | 0.00 | 0.70 |
| PERC | Pond 308 | BASIN308 | 0.61 | 54.23 | 57.10 | 125886 | 0.00 | 14.57 | 0.00 | 0.72 |
| PERC | Pond 308 | BASIN308 | 0.62 | 54.22 | 57.10 | 125824 | 0.00 | 14.56 | 0.00 | 0.74 |
| PERC | Pond 308 | BASIN308 | 0.64 | 54.22 | 57.10 | 125763 | 0.00 | 14.56 | 0.00 | 0.77 |
| PERC | Pond 308 | BASIN308 | 0.66 | 54.21 | 57.10 | 125702 | 0.00 | 14.55 | 0.00 | 0.79 |
| PERC | Pond 308 | BASIN308 | 0.67 | 54.20 | 57.10 | 125641 | 0.00 | 14.54 | 0.00 | 0.81 |
| PERC | Pond 308 | BASIN308 | 0.69 | 54.19 | 57.10 | 125580 | 0.00 | 14.53 | 0.00 | 0.83 |
| PERC | Pond 308 | BASIN308 | 0.71 | 54.19 | 57.10 | 125519 | 0.00 | 14.53 | 0.00 | 0.85 |
| PERC | Pond 308 | BASIN308 | 0.72 | 54.18 | 57.10 | 125458 | 0.00 | 14.52 | 0.00 | 0.87 |
| PERC | Pond 308 | BASIN308 | 0.74 | 54.17 | 57.10 | 125397 | 0.00 | 14.51 | 0.00 | 0.89 |
| PERC | Pond 308 | BASIN308 | 0.76 | 54.17 | 57.10 | 125336 | 0.00 | 14.51 | 0.00 | 0.91 |
| PERC | Pond 308 | BASIN308 | 0.77 | 54.16 | 57.10 | 125275 | 0.00 | 14.50 | 0.00 | 0.93 |
| PERC | Pond 308 | BASIN308 | 0.79 | 54.15 | 57.10 | 125214 | 0.00 | 14.49 | 0.00 | 0.95 |
| PERC | Pond 308 | BASIN308 | 0.81 | 54.15 | 57.10 | 125153 | 0.00 | 14.49 | 0.00 | 0.97 |
| PERC | Pond 308 | BASIN308 | 0.82 | 54.14 | 57.10 | 125092 | 0.00 | 14.48 | 0.00 | 0.99 |
| PERC | Pond 308 | BASIN308 | 0.84 | 54.13 | 57.10 | 125031 | 0.00 | 14.47 | 0.00 | 1.01 |
| PERC | Pond 308 | BASIN308 | 0.86 | 54.12 | 57.10 | 124970 | 0.00 | 14.46 | 0.00 | 1.03 |
| PERC | Pond 308 | BASIN308 | 0.87 | 54.12 | 57.10 | 124909 | 0.00 | 14.46 | 0.00 | 1.05 |
| PERC | Pond 308 | BASIN308 | 0.89 | 54.11 | 57.10 | 124848 | 0.00 | 14.45 | 0.00 | 1.07 |
| PERC | Pond 308 | BASIN308 | 0.91 | 54.10 | 57.10 | 124787 | 0.00 | 14.44 | 0.00 | 1.09 |
| PERC | Pond 308 | BASIN308 | 0.92 | 54.10 | 57.10 | 124726 | 0.00 | 14.44 | 0.00 | 1.11 |
| PERC | Pond 308 | BASIN308 | 0.94 | 54.09 | 57.10 | 124665 | 0.00 | 14.43 | 0.00 | 1.13 |
| PERC | Pond 308 | BASIN308 | 0.96 | 54.08 | 57.10 | 124604 | 0.00 | 14.42 | 0.00 | 1.15 |
| PERC | Pond 308 | BASIN308 | 0.97 | 54.08 | 57.10 | 124543 | 0.00 | 14.41 | 0.00 | 1.17 |
| PERC | Pond 308 | BASIN308 | 0.99 | 54.07 | 57.10 | 124482 | 0.00 | 14.41 | 0.00 | 1.19 |
| PERC | Pond 308 | BASIN308 | 1.01 | 54.06 | 57.10 | 124421 | 0.00 | 14.40 | 0.00 | 1.21 |
| PERC | Pond 308 | BASIN308 | 1.02 | 54.06 | 57.10 | 124391 | 0.00 | 14.40 | 0.00 | 1.22 |
| PERC | Pond 308 | BASIN308 | 1.03 | 54.05 | 57.10 | 124330 | 0.00 | 14.39 | 0.00 | 1.24 |
| PERC | Pond 308 | BASIN308 | 1.05 | 54.04 | 57.10 | 124269 | 0.00 | 14.38 | 0.00 | 1.26 |
| PERC | Pond 308 | BASIN308 | 1.07 | 54.04 | 57.10 | 124208 | 0.00 | 14.38 | 0.00 | 1.28 |
| PERC | Pond 308 | BASIN308 | 1.08 | 54.03 | 57.10 | 124147 | 0.00 | 14.37 | 0.00 | 1.30 |
| PERC | Pond 308 | BASIN308 | 1.10 | 54.02 | 57.10 | 124086 | 0.00 | 14.36 | 0.00 | 1.32 |
| PERC | Pond 308 | BASIN308 | 1.12 | 54.02 | 57.10 | 124025 | 0.00 | 14.35 | 0.00 | 1.34 |
| PERC | Pond 308 | BASIN308 | 1.13 | 54.01 | 57.10 | 123964 | 0.00 | 14.35 | 0.00 | 1.36 |
| PERC | Pond 308 | BASIN308 | 1.15 | 54.00 | 57.10 | 123903 | 0.00 | 14.34 | 0.00 | 1.38 |
| PERC | Pond 308 | BASIN308 | 1.17 | 54.00 | 57.10 | 123842 | 0.00 | 14.33 | 0.00 | 1.40 |
| PERC | Pond 308 | BASIN308 | 1.18 | 53.99 | 57.10 | 123781 | 0.00 | 14.33 | 0.00 | 1.42 |
| PERC | Pond 308 | BASIN308 | 1.20 | 53.98 | 57.10 | 123720 | 0.00 | 14.32 | 0.00 | 1.44 |
| PERC | Pond 308 | BASIN308 | 1.22 | 53.97 | 57.10 | 123659 | 0.00 | 14.31 | 0.00 | 1.46 |
| PERC | Pond 308 | BASIN308 | 1.24 | 53.97 | 57.10 | 123598 | 0.00 | 14.31 | 0.00 | 1.48 |
| PERC | Pond 308 | BASIN308 | 1.25 | 53.96 | 57.10 | 123537 | 0.00 | 14.30 | 0.00 | 1.50 |
| PERC | Pond 308 | BASIN308 | 1.27 | 53.95 | 57.10 | 123476 | 0.00 | 14.29 | 0.00 | 1.52 |
| PERC | Pond 308 | BASIN308 | 1.29 | 53.95 | 57.10 | 123415 | 0.00 | 14.28 | 0.00 | 1.54 |
| PERC | Pond 308 | BASIN308 | 1.30 | 53.94 | 57.10 | 123354 | 0.00 | 14.28 | 0.00 | 1.56 |
| PERC | Pond 308 | BASIN308 | 1.32 | 53.93 | 57.10 | 123293 | 0.00 | 14.27 | 0.00 | 1.58 |
| PERC | Pond 308 | BASIN308 | 1.34 | 53.93 | 57.10 | 123232 | 0.00 | 14.26 | 0.00 | 1.60 |
| PERC | Pond 308 | BASIN308 | 1.35 | 53.92 | 57.10 | 123171 | 0.00 | 14.26 | 0.00 | 1.62 |
| PERC | Pond 308 | BASIN308 | 1.37 | 53.91 | 57.10 | 123110 | 0.00 | 14.25 | 0.00 | 1.64 |
| PERC | Pond 308 | BASIN308 | 1.39 | 53.90 | 57.10 | 123049 | 0.00 | 14.24 | 0.00 | 1.65 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 18.21 | 51.26 | 57.10 | 100238 | 0.00 | 1.26 | 0.00 | 8.44 |
| PERC | Pond 308 | BASIN308 | 18.23 | 51.26 | 57.10 | 100232 | 0.00 | 1.25 | 0.00 | 8.44 |
| PERC | Pond 308 | BASIN308 | 18.25 | 51.25 | 57.10 | 100225 | 0.00 | 1.25 | 0.00 | 8.44 |
| PERC | Pond 308 | BASIN308 | 18.26 | 51.25 | 57.10 | 100219 | 0.00 | 1.25 | 0.00 | 8.44 |
| PERC | Pond 308 | BASIN308 | 18.28 | 51.25 | 57.10 | 100212 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.30 | 51.25 | 57.10 | 100206 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.31 | 51.25 | 57.10 | 100199 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.33 | 51.25 | 57.10 | 100193 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.35 | 51.25 | 57.10 | 100186 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.36 | 51.25 | 57.10 | 100180 | 0.00 | 1.25 | 0.00 | 8.45 |
| PERC | Pond 308 | BASIN308 | 18.38 | 51.25 | 57.10 | 100174 | 0.00 | 1.25 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.40 | 51.25 | 57.10 | 100167 | 0.00 | 1.24 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.41 | 51.25 | 57.10 | 100161 | 0.00 | 1.24 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.43 | 51.25 | 57.10 | 100154 | 0.00 | 1.24 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.45 | 51.25 | 57.10 | 100148 | 0.00 | 1.24 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.46 | 51.25 | 57.10 | 100142 | 0.00 | 1.24 | 0.00 | 8.46 |
| PERC | Pond 308 | BASIN308 | 18.48 | 51.24 | 57.10 | 100135 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.50 | 51.24 | 57.10 | 100129 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.51 | 51.24 | 57.10 | 100122 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.53 | 51.24 | 57.10 | 100116 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.55 | 51.24 | 57.10 | 100110 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.56 | 51.24 | 57.10 | 100103 | 0.00 | 1.24 | 0.00 | 8.47 |
| PERC | Pond 308 | BASIN308 | 18.58 | 51.24 | 57.10 | 100097 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.60 | 51.24 | 57.10 | 100091 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.61 | 51.24 | 57.10 | 100084 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.63 | 51.24 | 57.10 | 100078 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.65 | 51.24 | 57.10 | 100071 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.66 | 51.24 | 57.10 | 100065 | 0.00 | 1.23 | 0.00 | 8.48 |
| PERC | Pond 308 | BASIN308 | 18.68 | 51.24 | 57.10 | 100059 | 0.00 | 1.23 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.70 | 51.23 | 57.10 | 100052 | 0.00 | 1.23 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.71 | 51.23 | 57.10 | 100046 | 0.00 | 1.23 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.73 | 51.23 | 57.10 | 100040 | 0.00 | 1.23 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.75 | 51.23 | 57.10 | 100033 | 0.00 | 1.23 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.76 | 51.23 | 57.10 | 100027 | 0.00 | 1.22 | 0.00 | 8.49 |
| PERC | Pond 308 | BASIN308 | 18.78 | 51.23 | 57.10 | 100021 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.80 | 51.23 | 57.10 | 100014 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.81 | 51.23 | 57.10 | 100008 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.83 | 51.23 | 57.10 | 100002 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.85 | 51.23 | 57.10 | 99996 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.86 | 51.23 | 57.10 | 99989 | 0.00 | 1.22 | 0.00 | 8.50 |
| PERC | Pond 308 | BASIN308 | 18.88 | 51.23 | 57.10 | 99983 | 0.00 | 1.22 | 0.00 | 8.51 |
| PERC | Pond 308 | BASIN308 | 18.90 | 51.23 | 57.10 | 99977 | 0.00 | 1.22 | 0.00 | 8.51 |
| PERC | Pond 308 | BASIN308 | 18.91 | 51.23 | 57.10 | 99970 | 0.00 | 1.22 | 0.00 | 8.51 |
| PERC | Pond 308 | BASIN308 | 18.93 | 51.22 | 57.10 | 99964 | 0.00 | 1.22 | 0.00 | 8.51 |
| PERC | Pond 308 | BASIN308 | 18.95 | 51.22 | 57.10 | 99958 | 0.00 | 1.21 | 0.00 | 8.51 |
| PERC | Pond 308 | BASIN308 | 18.96 | 51.22 | 57.10 | 99952 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 18.98 | 51.22 | 57.10 | 99945 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 19.00 | 51.22 | 57.10 | 99939 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 19.01 | 51.22 | 57.10 | 99933 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 19.03 | 51.22 | 57.10 | 99927 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 19.05 | 51.22 | 57.10 | 99920 | 0.00 | 1.21 | 0.00 | 8.52 |
| PERC | Pond 308 | BASIN308 | 19.06 | 51.22 | 57.10 | 99914 | 0.00 | 1.21 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.08 | 51.22 | 57.10 | 99908 | 0.00 | 1.21 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.10 | 51.22 | 57.10 | 99902 | 0.00 | 1.21 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.11 | 51.22 | 57.10 | 99895 | 0.00 | 1.21 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.13 | 51.22 | 57.10 | 99889 | 0.00 | 1.20 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.15 | 51.22 | 57.10 | 99883 | 0.00 | 1.20 | 0.00 | 8.53 |
| PERC | Pond 308 | BASIN308 | 19.16 | 51.21 | 57.10 | 99877 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.18 | 51.21 | 57.10 | 99870 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.20 | 51.21 | 57.10 | 99864 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.21 | 51.21 | 57.10 | 99858 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.23 | 51.21 | 57.10 | 99852 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.25 | 51.21 | 57.10 | 99846 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.26 | 51.21 | 57.10 | 99839 | 0.00 | 1.20 | 0.00 | 8.54 |
| PERC | Pond 308 | BASIN308 | 19.28 | 51.21 | 57.10 | 99833 | 0.00 | 1.20 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.30 | 51.21 | 57.10 | 99827 | 0.00 | 1.20 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.31 | 51.21 | 57.10 | 99821 | 0.00 | 1.20 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.33 | 51.21 | 57.10 | 99815 | 0.00 | 1.19 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.35 | 51.21 | 57.10 | 99808 | 0.00 | 1.19 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.36 | 51.21 | 57.10 | 99802 | 0.00 | 1.19 | 0.00 | 8.55 |
| PERC | Pond 308 | BASIN308 | 19.38 | 51.21 | 57.10 | 99796 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.40 | 51.20 | 57.10 | 99790 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.41 | 51.20 | 57.10 | 99784 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.43 | 51.20 | 57.10 | 99778 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.45 | 51.20 | 57.10 | 99772 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.46 | 51.20 | 57.10 | 99765 | 0.00 | 1.19 | 0.00 | 8.56 |
| PERC | Pond 308 | BASIN308 | 19.48 | 51.20 | 57.10 | 99759 | 0.00 | 1.19 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.50 | 51.20 | 57.10 | 99753 | 0.00 | 0.26 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.51 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.53 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.55 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.56 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.58 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |
| PERC | Pond 308 | BASIN308 | 19.60 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 8.57 |

Basin 308
FDOT Closed Basin Recovery
7-Day / 30-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 0.00 | 54.98 | 57.10 | 132422 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308 | BASIN308 | 0.02 | 54.97 | 57.10 | 132377 | 0.00 | 15.32 | 0.00 | 0.01 |
| PERC | Pond 308 | BASIN308 | 0.03 | 54.97 | 57.10 | 132316 | 0.00 | 15.31 | 0.00 | 0.03 |
| PERC | Pond 308 | BASIN308 | 0.05 | 54.96 | 57.10 | 132255 | 0.00 | 15.31 | 0.00 | 0.05 |
| PERC | Pond 308 | BASIN308 | 0.07 | 54.95 | 57.10 | 132194 | 0.00 | 15.30 | 0.00 | 0.07 |
| PERC | Pond 308 | BASIN308 | 0.08 | 54.95 | 57.10 | 132133 | 0.00 | 15.29 | 0.00 | 0.10 |
| PERC | Pond 308 | BASIN308 | 0.10 | 54.94 | 57.10 | 132072 | 0.00 | 15.29 | 0.00 | 0.12 |
| PERC | Pond 308 | BASIN308 | 0.12 | 54.93 | 57.10 | 132011 | 0.00 | 15.28 | 0.00 | 0.14 |
| PERC | Pond 308 | BASIN308 | 0.13 | 54.93 | 57.10 | 131950 | 0.00 | 15.27 | 0.00 | 0.16 |
| PERC | Pond 308 | BASIN308 | 0.15 | 54.92 | 57.10 | 131889 | 0.00 | 15.26 | 0.00 | 0.18 |
| PERC | Pond 308 | BASIN308 | 0.17 | 54.91 | 57.10 | 131828 | 0.00 | 15.26 | 0.00 | 0.20 |
| PERC | Pond 308 | BASIN308 | 0.18 | 54.90 | 57.10 | 131767 | 0.00 | 15.25 | 0.00 | 0.22 |
| PERC | Pond 308 | BASIN308 | 0.20 | 54.90 | 57.10 | 131706 | 0.00 | 15.24 | 0.00 | 0.24 |
| PERC | Pond 308 | BASIN308 | 0.22 | 54.89 | 57.10 | 131645 | 0.00 | 15.24 | 0.00 | 0.27 |
| PERC | Pond 308 | BASIN308 | 0.24 | 54.88 | 57.10 | 131584 | 0.00 | 15.23 | 0.00 | 0.29 |
| PERC | Pond 308 | BASIN308 | 0.25 | 54.88 | 57.10 | 131523 | 0.00 | 15.22 | 0.00 | 0.31 |
| PERC | Pond 308 | BASIN308 | 0.27 | 54.87 | 57.10 | 131462 | 0.00 | 15.22 | 0.00 | 0.33 |
| PERC | Pond 308 | BASIN308 | 0.29 | 54.86 | 57.10 | 131401 | 0.00 | 15.21 | 0.00 | 0.35 |
| PERC | Pond 308 | BASIN308 | 0.30 | 54.86 | 57.10 | 131340 | 0.00 | 15.20 | 0.00 | 0.37 |
| PERC | Pond 308 | BASIN308 | 0.32 | 54.85 | 57.10 | 131279 | 0.00 | 15.19 | 0.00 | 0.39 |
| PERC | Pond 308 | BASIN308 | 0.34 | 54.84 | 57.10 | 131218 | 0.00 | 15.19 | 0.00 | 0.41 |
| PERC | Pond 308 | BASIN308 | 0.35 | 54.83 | 57.10 | 131157 | 0.00 | 15.18 | 0.00 | 0.43 |
| PERC | Pond 308 | BASIN308 | 0.37 | 54.83 | 57.10 | 131096 | 0.00 | 15.17 | 0.00 | 0.46 |
| PERC | Pond 308 | BASIN308 | 0.39 | 54.82 | 57.10 | 131035 | 0.00 | 15.17 | 0.00 | 0.48 |
| PERC | Pond 308 | BASIN308 | 0.40 | 54.81 | 57.10 | 130974 | 0.00 | 15.16 | 0.00 | 0.50 |
| PERC | Pond 308 | BASIN308 | 0.42 | 54.81 | 57.10 | 130913 | 0.00 | 15.15 | 0.00 | 0.52 |
| PERC | Pond 308 | BASIN308 | 0.44 | 54.80 | 57.10 | 130852 | 0.00 | 15.14 | 0.00 | 0.54 |
| PERC | Pond 308 | BASIN308 | 0.45 | 54.79 | 57.10 | 130791 | 0.00 | 15.14 | 0.00 | 0.56 |
| PERC | Pond 308 | BASIN308 | 0.47 | 54.79 | 57.10 | 130730 | 0.00 | 15.13 | 0.00 | 0.58 |
| PERC | Pond 308 | BASIN308 | 0.49 | 54.78 | 57.10 | 130669 | 0.00 | 15.12 | 0.00 | 0.60 |
| PERC | Pond 308 | BASIN308 | 0.50 | 54.77 | 57.10 | 130608 | 0.00 | 15.12 | 0.00 | 0.62 |
| PERC | Pond 308 | BASIN308 | 0.52 | 54.76 | 57.10 | 130547 | 0.00 | 15.11 | 0.00 | 0.64 |
| PERC | Pond 308 | BASIN308 | 0.54 | 54.76 | 57.10 | 130486 | 0.00 | 15.10 | 0.00 | 0.67 |
| PERC | Pond 308 | BASIN308 | 0.55 | 54.75 | 57.10 | 130425 | 0.00 | 15.10 | 0.00 | 0.69 |
| PERC | Pond 308 | BASIN308 | 0.57 | 54.74 | 57.10 | 130364 | 0.00 | 15.09 | 0.00 | 0.71 |
| PERC | Pond 308 | BASIN308 | 0.59 | 54.74 | 57.10 | 130303 | 0.00 | 15.08 | 0.00 | 0.73 |
| PERC | Pond 308 | BASIN308 | 0.61 | 54.73 | 57.10 | 130242 | 0.00 | 15.07 | 0.00 | 0.75 |
| PERC | Pond 308 | BASIN308 | 0.62 | 54.72 | 57.10 | 130180 | 0.00 | 15.07 | 0.00 | 0.77 |
| PERC | Pond 308 | BASIN308 | 0.64 | 54.72 | 57.10 | 130119 | 0.00 | 15.06 | 0.00 | 0.79 |
| PERC | Pond 308 | BASIN308 | 0.66 | 54.71 | 57.10 | 130058 | 0.00 | 15.05 | 0.00 | 0.81 |
| PERC | Pond 308 | BASIN308 | 0.67 | 54.70 | 57.10 | 129997 | 0.00 | 15.05 | 0.00 | 0.83 |
| PERC | Pond 308 | BASIN308 | 0.69 | 54.69 | 57.10 | 129936 | 0.00 | 15.04 | 0.00 | 0.85 |
| PERC | Pond 308 | BASIN308 | 0.71 | 54.69 | 57.10 | 129875 | 0.00 | 15.03 | 0.00 | 0.87 |
| PERC | Pond 308 | BASIN308 | 0.72 | 54.68 | 57.10 | 129814 | 0.00 | 15.02 | 0.00 | 0.90 |
| PERC | Pond 308 | BASIN308 | 0.74 | 54.67 | 57.10 | 129753 | 0.00 | 15.02 | 0.00 | 0.92 |
| PERC | Pond 308 | BASIN308 | 0.76 | 54.67 | 57.10 | 129692 | 0.00 | 15.01 | 0.00 | 0.94 |
| PERC | Pond 308 | BASIN308 | 0.77 | 54.66 | 57.10 | 129631 | 0.00 | 15.00 | 0.00 | 0.96 |
| PERC | Pond 308 | BASIN308 | 0.79 | 54.65 | 57.10 | 129570 | 0.00 | 15.00 | 0.00 | 0.98 |
| PERC | Pond 308 | BASIN308 | 0.81 | 54.65 | 57.10 | 129509 | 0.00 | 14.99 | 0.00 | 1.00 |
| PERC | Pond 308 | BASIN308 | 0.82 | 54.64 | 57.10 | 129448 | 0.00 | 14.98 | 0.00 | 1.02 |
| PERC | Pond 308 | BASIN308 | 0.84 | 54.63 | 57.10 | 129387 | 0.00 | 14.98 | 0.00 | 1.04 |
| PERC | Pond 308 | BASIN308 | 0.86 | 54.62 | 57.10 | 129326 | 0.00 | 14.97 | 0.00 | 1.06 |
| PERC | Pond 308 | BASIN308 | 0.87 | 54.62 | 57.10 | 129265 | 0.00 | 14.96 | 0.00 | 1.08 |
| PERC | Pond 308 | BASIN308 | 0.89 | 54.61 | 57.10 | 129204 | 0.00 | 14.95 | 0.00 | 1.10 |
| PERC | Pond 308 | BASIN308 | 0.91 | 54.60 | 57.10 | 129143 | 0.00 | 14.95 | 0.00 | 1.12 |
| PERC | Pond 308 | BASIN308 | 0.92 | 54.60 | 57.10 | 129082 | 0.00 | 14.94 | 0.00 | 1.15 |
| PERC | Pond 308 | BASIN308 | 0.94 | 54.59 | 57.10 | 129021 | 0.00 | 14.93 | 0.00 | 1.17 |
| PERC | Pond 308 | BASIN308 | 0.96 | 54.58 | 57.10 | 128960 | 0.00 | 14.93 | 0.00 | 1.19 |
| PERC | Pond 308 | BASIN308 | 0.97 | 54.58 | 57.10 | 128899 | 0.00 | 14.92 | 0.00 | 1.21 |
| PERC | Pond 308 | BASIN308 | 0.99 | 54.57 | 57.10 | 128838 | 0.00 | 14.91 | 0.00 | 1.23 |
| PERC | Pond 308 | BASIN308 | 1.01 | 54.56 | 57.10 | 128777 | 0.00 | 14.90 | 0.00 | 1.25 |
| PERC | Pond 308 | BASIN308 | 1.02 | 54.56 | 57.10 | 128747 | 0.00 | 14.90 | 0.00 | 1.26 |
| PERC | Pond 308 | BASIN308 | 1.03 | 54.55 | 57.10 | 128686 | 0.00 | 14.89 | 0.00 | 1.28 |
| PERC | Pond 308 | BASIN308 | 1.05 | 54.54 | 57.10 | 128625 | 0.00 | 14.89 | 0.00 | 1.30 |
| PERC | Pond 308 | BASIN308 | 1.07 | 54.54 | 57.10 | 128564 | 0.00 | 14.88 | 0.00 | 1.32 |
| PERC | Pond 308 | BASIN308 | 1.08 | 54.53 | 57.10 | 128503 | 0.00 | 14.87 | 0.00 | 1.34 |
| PERC | Pond 308 | BASIN308 | 1.10 | 54.52 | 57.10 | 128442 | 0.00 | 14.87 | 0.00 | 1.36 |
| PERC | Pond 308 | BASIN308 | 1.12 | 54.52 | 57.10 | 128381 | 0.00 | 14.86 | 0.00 | 1.38 |
| PERC | Pond 308 | BASIN308 | 1.13 | 54.51 | 57.10 | 128320 | 0.00 | 14.85 | 0.00 | 1.40 |
| PERC | Pond 308 | BASIN308 | 1.15 | 54.50 | 57.10 | 128259 | 0.00 | 14.84 | 0.00 | 1.42 |
| PERC | Pond 308 | BASIN308 | 1.17 | 54.50 | 57.10 | 128198 | 0.00 | 14.84 | 0.00 | 1.45 |
| PERC | Pond 308 | BASIN308 | 1.18 | 54.49 | 57.10 | 128137 | 0.00 | 14.83 | 0.00 | 1.47 |
| PERC | Pond 308 | BASIN308 | 1.20 | 54.48 | 57.10 | 128076 | 0.00 | 14.82 | 0.00 | 1.49 |
| PERC | Pond 308 | BASIN308 | 1.22 | 54.47 | 57.10 | 128015 | 0.00 | 14.82 | 0.00 | 1.51 |
| PERC | Pond 308 | BASIN308 | 1.24 | 54.47 | 57.10 | 127954 | 0.00 | 14.81 | 0.00 | 1.53 |
| PERC | Pond 308 | BASIN308 | 1.25 | 54.46 | 57.10 | 127893 | 0.00 | 14.80 | 0.00 | 1.55 |
| PERC | Pond 308 | BASIN308 | 1.27 | 54.45 | 57.10 | 127832 | 0.00 | 14.80 | 0.00 | 1.57 |
| PERC | Pond 308 | BASIN308 | 1.29 | 54.45 | 57.10 | 127771 | 0.00 | 14.79 | 0.00 | 1.59 |
| PERC | Pond 308 | BASIN308 | 1.30 | 54.44 | 57.10 | 127710 | 0.00 | 14.78 | 0.00 | 1.61 |
| PERC | Pond 308 | BASIN308 | 1.32 | 54.43 | 57.10 | 127649 | 0.00 | 14.77 | 0.00 | 1.63 |
| PERC | Pond 308 | BASIN308 | 1.34 | 54.43 | 57.10 | 127588 | 0.00 | 14.77 | 0.00 | 1.65 |
| PERC | Pond 308 | BASIN308 | 1.35 | 54.42 | 57.10 | 127527 | 0.00 | 14.76 | 0.00 | 1.67 |
| PERC | Pond 308 | BASIN308 | 1.37 | 54.41 | 57.10 | 127466 | 0.00 | 14.75 | 0.00 | 1.69 |
| PERC | Pond 308 | BASIN308 | 1.39 | 54.40 | 57.10 | 127405 | 0.00 | 14.75 | 0.00 | 1.71 |

Basin 308
FDOT Closed Basin Recovery
7-Day / 30-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 4.20 | 53.23 | 57.10 | 117187 | 0.00 | 13.56 | 0.00 | 5.01 |
| PERC | Pond 308 | BASIN308 | 4.22 | 53.22 | 57.10 | 117128 | 0.00 | 13.56 | 0.00 | 5.02 |
| PERC | Pond 308 | BASIN308 | 4.24 | 53.22 | 57.10 | 117069 | 0.00 | 13.55 | 0.00 | 5.04 |
| PERC | Pond 308 | BASIN308 | 4.25 | 53.21 | 57.10 | 117011 | 0.00 | 13.54 | 0.00 | 5.06 |
| PERC | Pond 308 | BASIN308 | 4.27 | 53.20 | 57.10 | 116952 | 0.00 | 13.54 | 0.00 | 5.08 |
| PERC | Pond 308 | BASIN308 | 4.29 | 53.20 | 57.10 | 116894 | 0.00 | 13.53 | 0.00 | 5.10 |
| PERC | Pond 308 | BASIN308 | 4.30 | 53.19 | 57.10 | 116835 | 0.00 | 13.52 | 0.00 | 5.12 |
| PERC | Pond 308 | BASIN308 | 4.32 | 53.18 | 57.10 | 116777 | 0.00 | 13.52 | 0.00 | 5.14 |
| PERC | Pond 308 | BASIN308 | 4.34 | 53.18 | 57.10 | 116718 | 0.00 | 13.51 | 0.00 | 5.16 |
| PERC | Pond 308 | BASIN308 | 4.35 | 53.17 | 57.10 | 116660 | 0.00 | 13.50 | 0.00 | 5.17 |
| PERC | Pond 308 | BASIN308 | 4.37 | 53.16 | 57.10 | 116601 | 0.00 | 13.50 | 0.00 | 5.19 |
| PERC | Pond 308 | BASIN308 | 4.39 | 53.15 | 57.10 | 116543 | 0.00 | 13.49 | 0.00 | 5.21 |
| PERC | Pond 308 | BASIN308 | 4.40 | 53.15 | 57.10 | 116484 | 0.00 | 13.48 | 0.00 | 5.23 |
| PERC | Pond 308 | BASIN308 | 4.42 | 53.14 | 57.10 | 116426 | 0.00 | 13.48 | 0.00 | 5.25 |
| PERC | Pond 308 | BASIN308 | 4.44 | 53.13 | 57.10 | 116367 | 0.00 | 13.47 | 0.00 | 5.27 |
| PERC | Pond 308 | BASIN308 | 4.45 | 53.13 | 57.10 | 116309 | 0.00 | 13.46 | 0.00 | 5.29 |
| PERC | Pond 308 | BASIN308 | 4.47 | 53.12 | 57.10 | 116250 | 0.00 | 13.45 | 0.00 | 5.31 |
| PERC | Pond 308 | BASIN308 | 4.49 | 53.11 | 57.10 | 116192 | 0.00 | 13.45 | 0.00 | 5.32 |
| PERC | Pond 308 | BASIN308 | 4.50 | 53.11 | 57.10 | 116133 | 0.00 | 13.44 | 0.00 | 5.34 |
| PERC | Pond 308 | BASIN308 | 4.52 | 53.10 | 57.10 | 116075 | 0.00 | 13.43 | 0.00 | 5.36 |
| PERC | Pond 308 | BASIN308 | 4.54 | 53.09 | 57.10 | 116016 | 0.00 | 13.43 | 0.00 | 5.38 |
| PERC | Pond 308 | BASIN308 | 4.55 | 53.08 | 57.10 | 115958 | 0.00 | 13.42 | 0.00 | 5.40 |
| PERC | Pond 308 | BASIN308 | 4.57 | 53.08 | 57.10 | 115899 | 0.00 | 13.41 | 0.00 | 5.42 |
| PERC | Pond 308 | BASIN308 | 4.59 | 53.07 | 57.10 | 115841 | 0.00 | 13.41 | 0.00 | 5.44 |
| PERC | Pond 308 | BASIN308 | 4.60 | 53.06 | 57.10 | 115782 | 0.00 | 13.40 | 0.00 | 5.45 |
| PERC | Pond 308 | BASIN308 | 4.62 | 53.06 | 57.10 | 115724 | 0.00 | 13.39 | 0.00 | 5.47 |
| PERC | Pond 308 | BASIN308 | 4.64 | 53.05 | 57.10 | 115665 | 0.00 | 13.39 | 0.00 | 5.49 |
| PERC | Pond 308 | BASIN308 | 4.66 | 53.04 | 57.10 | 115607 | 0.00 | 13.38 | 0.00 | 5.51 |
| PERC | Pond 308 | BASIN308 | 4.67 | 53.04 | 57.10 | 115548 | 0.00 | 13.37 | 0.00 | 5.53 |
| PERC | Pond 308 | BASIN308 | 4.69 | 53.03 | 57.10 | 115490 | 0.00 | 13.37 | 0.00 | 5.55 |
| PERC | Pond 308 | BASIN308 | 4.71 | 53.02 | 57.10 | 115431 | 0.00 | 13.36 | 0.00 | 5.57 |
| PERC | Pond 308 | BASIN308 | 4.72 | 53.01 | 57.10 | 115373 | 0.00 | 13.35 | 0.00 | 5.58 |
| PERC | Pond 308 | BASIN308 | 4.74 | 53.01 | 57.10 | 115314 | 0.00 | 13.35 | 0.00 | 5.60 |
| PERC | Pond 308 | BASIN308 | 4.76 | 53.00 | 57.10 | 115256 | 0.00 | 13.34 | 0.00 | 5.62 |
| PERC | Pond 308 | BASIN308 | 4.77 | 52.99 | 57.10 | 115197 | 0.00 | 13.33 | 0.00 | 5.64 |
| PERC | Pond 308 | BASIN308 | 4.79 | 52.99 | 57.10 | 115139 | 0.00 | 13.33 | 0.00 | 5.66 |
| PERC | Pond 308 | BASIN308 | 4.81 | 52.98 | 57.10 | 115080 | 0.00 | 13.32 | 0.00 | 5.68 |
| PERC | Pond 308 | BASIN308 | 4.82 | 52.97 | 57.10 | 115022 | 0.00 | 13.31 | 0.00 | 5.70 |
| PERC | Pond 308 | BASIN308 | 4.84 | 52.97 | 57.10 | 114963 | 0.00 | 13.31 | 0.00 | 5.71 |
| PERC | Pond 308 | BASIN308 | 4.86 | 52.96 | 57.10 | 114905 | 0.00 | 13.30 | 0.00 | 5.73 |
| PERC | Pond 308 | BASIN308 | 4.87 | 52.95 | 57.10 | 114846 | 0.00 | 13.29 | 0.00 | 5.75 |
| PERC | Pond 308 | BASIN308 | 4.89 | 52.94 | 57.10 | 114788 | 0.00 | 13.29 | 0.00 | 5.77 |
| PERC | Pond 308 | BASIN308 | 4.91 | 52.94 | 57.10 | 114729 | 0.00 | 13.28 | 0.00 | 5.79 |
| PERC | Pond 308 | BASIN308 | 4.92 | 52.93 | 57.10 | 114671 | 0.00 | 13.27 | 0.00 | 5.81 |
| PERC | Pond 308 | BASIN308 | 4.94 | 52.92 | 57.10 | 114612 | 0.00 | 13.27 | 0.00 | 5.83 |
| PERC | Pond 308 | BASIN308 | 4.96 | 52.92 | 57.10 | 114554 | 0.00 | 13.26 | 0.00 | 5.84 |
| PERC | Pond 308 | BASIN308 | 4.97 | 52.91 | 57.10 | 114495 | 0.00 | 13.25 | 0.00 | 5.86 |
| PERC | Pond 308 | BASIN308 | 4.99 | 52.90 | 57.10 | 114437 | 0.00 | 13.25 | 0.00 | 5.88 |
| PERC | Pond 308 | BASIN308 | 5.01 | 52.90 | 57.10 | 114378 | 0.00 | 13.24 | 0.00 | 5.90 |
| PERC | Pond 308 | BASIN308 | 5.02 | 52.89 | 57.10 | 114320 | 0.00 | 13.23 | 0.00 | 5.92 |
| PERC | Pond 308 | BASIN308 | 5.04 | 52.88 | 57.10 | 114261 | 0.00 | 13.22 | 0.00 | 5.94 |
| PERC | Pond 308 | BASIN308 | 5.05 | 52.88 | 57.10 | 114232 | 0.00 | 13.22 | 0.00 | 5.94 |
| PERC | Pond 308 | BASIN308 | 5.07 | 52.87 | 57.10 | 114174 | 0.00 | 13.21 | 0.00 | 5.96 |
| PERC | Pond 308 | BASIN308 | 5.08 | 52.86 | 57.10 | 114115 | 0.00 | 13.21 | 0.00 | 5.98 |
| PERC | Pond 308 | BASIN308 | 5.10 | 52.86 | 57.10 | 114057 | 0.00 | 13.20 | 0.00 | 6.00 |
| PERC | Pond 308 | BASIN308 | 5.12 | 52.85 | 57.10 | 113998 | 0.00 | 13.19 | 0.00 | 6.02 |
| PERC | Pond 308 | BASIN308 | 5.13 | 52.84 | 57.10 | 113940 | 0.00 | 12.87 | 0.00 | 6.04 |
| PERC | Pond 308 | BASIN308 | 5.15 | 52.84 | 57.10 | 113884 | 0.00 | 12.37 | 0.00 | 6.05 |
| PERC | Pond 308 | BASIN308 | 5.17 | 52.83 | 57.10 | 113829 | 0.00 | 11.92 | 0.00 | 6.07 |
| PERC | Pond 308 | BASIN308 | 5.18 | 52.82 | 57.10 | 113777 | 0.00 | 11.50 | 0.00 | 6.09 |
| PERC | Pond 308 | BASIN308 | 5.20 | 52.82 | 57.10 | 113727 | 0.00 | 11.12 | 0.00 | 6.10 |
| PERC | Pond 308 | BASIN308 | 5.22 | 52.81 | 57.10 | 113678 | 0.00 | 10.78 | 0.00 | 6.12 |
| PERC | Pond 308 | BASIN308 | 5.23 | 52.81 | 57.10 | 113631 | 0.00 | 10.46 | 0.00 | 6.13 |
| PERC | Pond 308 | BASIN308 | 5.25 | 52.80 | 57.10 | 113584 | 0.00 | 10.17 | 0.00 | 6.15 |
| PERC | Pond 308 | BASIN308 | 5.27 | 52.79 | 57.10 | 113540 | 0.00 | 9.90 | 0.00 | 6.16 |
| PERC | Pond 308 | BASIN308 | 5.29 | 52.79 | 57.10 | 113496 | 0.00 | 9.64 | 0.00 | 6.17 |
| PERC | Pond 308 | BASIN308 | 5.30 | 52.78 | 57.10 | 113454 | 0.00 | 9.41 | 0.00 | 6.19 |
| PERC | Pond 308 | BASIN308 | 5.32 | 52.78 | 57.10 | 113412 | 0.00 | 9.19 | 0.00 | 6.20 |
| PERC | Pond 308 | BASIN308 | 5.34 | 52.77 | 57.10 | 113371 | 0.00 | 8.99 | 0.00 | 6.21 |
| PERC | Pond 308 | BASIN308 | 5.35 | 52.77 | 57.10 | 113332 | 0.00 | 8.80 | 0.00 | 6.23 |
| PERC | Pond 308 | BASIN308 | 5.37 | 52.77 | 57.10 | 113293 | 0.00 | 8.62 | 0.00 | 6.24 |
| PERC | Pond 308 | BASIN308 | 5.39 | 52.76 | 57.10 | 113254 | 0.00 | 8.46 | 0.00 | 6.25 |
| PERC | Pond 308 | BASIN308 | 5.41 | 52.76 | 57.10 | 113212 | 0.00 | 8.28 | 0.00 | 6.26 |
| PERC | Pond 308 | BASIN308 | 5.43 | 52.75 | 57.10 | 113166 | 0.00 | 8.10 | 0.00 | 6.28 |
| PERC | Pond 308 | BASIN308 | 5.44 | 52.75 | 57.10 | 113144 | 0.00 | 8.01 | 0.00 | 6.28 |
| PERC | Pond 308 | BASIN308 | 5.46 | 52.74 | 57.10 | 113100 | 0.00 | 7.84 | 0.00 | 6.30 |
| PERC | Pond 308 | BASIN308 | 5.47 | 52.74 | 57.10 | 113078 | 0.00 | 7.76 | 0.00 | 6.30 |
| PERC | Pond 308 | BASIN308 | 5.49 | 52.73 | 57.10 | 113035 | 0.00 | 7.61 | 0.00 | 6.32 |
| PERC | Pond 308 | BASIN308 | 5.51 | 52.73 | 57.10 | 112992 | 0.00 | 7.47 | 0.00 | 6.33 |
| PERC | Pond 308 | BASIN308 | 5.52 | 52.73 | 57.10 | 112972 | 0.00 | 7.40 | 0.00 | 6.34 |
| PERC | Pond 308 | BASIN308 | 5.54 | 52.72 | 57.10 | 112930 | 0.00 | 7.27 | 0.00 | 6.35 |
| PERC | Pond 308 | BASIN308 | 5.55 | 52.72 | 57.10 | 112910 | 0.00 | 7.21 | 0.00 | 6.36 |
| PERC | Pond 308 | BASIN308 | 5.57 | 52.71 | 57.10 | 112870 | 0.00 | 7.09 | 0.00 | 6.37 |
| PERC | Pond 308 | BASIN308 | 5.58 | 52.71 | 57.10 | 112850 | 0.00 | 7.03 | 0.00 | 6.37 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308 | BASIN308 | 30.80 | 51.23 | 57.10 | 100033 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.82 | 51.23 | 57.10 | 100029 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.84 | 51.23 | 57.10 | 100024 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.85 | 51.23 | 57.10 | 100020 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.87 | 51.23 | 57.10 | 100015 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.89 | 51.23 | 57.10 | 100011 | 0.00 | 0.87 | 0.00 | 9.99 |
| PERC | Pond 308 | BASIN308 | 30.90 | 51.23 | 57.10 | 100006 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 30.92 | 51.23 | 57.10 | 100002 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 30.94 | 51.23 | 57.10 | 99997 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 30.95 | 51.23 | 57.10 | 99993 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 30.97 | 51.23 | 57.10 | 99988 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 30.99 | 51.23 | 57.10 | 99984 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 31.00 | 51.23 | 57.10 | 99979 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 31.02 | 51.23 | 57.10 | 99975 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 31.04 | 51.23 | 57.10 | 99970 | 0.00 | 0.87 | 0.00 | 10.00 |
| PERC | Pond 308 | BASIN308 | 31.05 | 51.22 | 57.10 | 99966 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.07 | 51.22 | 57.10 | 99962 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.09 | 51.22 | 57.10 | 99957 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.10 | 51.22 | 57.10 | 99953 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.12 | 51.22 | 57.10 | 99948 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.14 | 51.22 | 57.10 | 99944 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.15 | 51.22 | 57.10 | 99939 | 0.00 | 0.87 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.17 | 51.22 | 57.10 | 99935 | 0.00 | 0.86 | 0.00 | 10.01 |
| PERC | Pond 308 | BASIN308 | 31.19 | 51.22 | 57.10 | 99930 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.20 | 51.22 | 57.10 | 99926 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.22 | 51.22 | 57.10 | 99921 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.24 | 51.22 | 57.10 | 99917 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.25 | 51.22 | 57.10 | 99912 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.27 | 51.22 | 57.10 | 99908 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.29 | 51.22 | 57.10 | 99903 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.30 | 51.22 | 57.10 | 99899 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.32 | 51.22 | 57.10 | 99895 | 0.00 | 0.86 | 0.00 | 10.02 |
| PERC | Pond 308 | BASIN308 | 31.34 | 51.22 | 57.10 | 99890 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.35 | 51.22 | 57.10 | 99886 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.37 | 51.21 | 57.10 | 99881 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.39 | 51.21 | 57.10 | 99877 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.40 | 51.21 | 57.10 | 99872 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.42 | 51.21 | 57.10 | 99868 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.44 | 51.21 | 57.10 | 99863 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.45 | 51.21 | 57.10 | 99859 | 0.00 | 0.86 | 0.00 | 10.03 |
| PERC | Pond 308 | BASIN308 | 31.47 | 51.21 | 57.10 | 99855 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.49 | 51.21 | 57.10 | 99850 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.50 | 51.21 | 57.10 | 99846 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.52 | 51.21 | 57.10 | 99841 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.54 | 51.21 | 57.10 | 99837 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.55 | 51.21 | 57.10 | 99832 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.57 | 51.21 | 57.10 | 99828 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.59 | 51.21 | 57.10 | 99824 | 0.00 | 0.86 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.60 | 51.21 | 57.10 | 99819 | 0.00 | 0.85 | 0.00 | 10.04 |
| PERC | Pond 308 | BASIN308 | 31.62 | 51.21 | 57.10 | 99815 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.64 | 51.21 | 57.10 | 99810 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.65 | 51.21 | 57.10 | 99806 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.67 | 51.21 | 57.10 | 99801 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.69 | 51.21 | 57.10 | 99797 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.70 | 51.20 | 57.10 | 99793 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.72 | 51.20 | 57.10 | 99788 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.74 | 51.20 | 57.10 | 99784 | 0.00 | 0.85 | 0.00 | 10.05 |
| PERC | Pond 308 | BASIN308 | 31.75 | 51.20 | 57.10 | 99779 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.77 | 51.20 | 57.10 | 99775 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.79 | 51.20 | 57.10 | 99771 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.80 | 51.20 | 57.10 | 99766 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.82 | 51.20 | 57.10 | 99762 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.84 | 51.20 | 57.10 | 99757 | 0.00 | 0.85 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.85 | 51.20 | 57.10 | 99753 | 0.00 | 0.22 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.87 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.89 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.90 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.92 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.94 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.95 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.97 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 31.99 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.00 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.02 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.04 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.05 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.07 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.09 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.10 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.12 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.14 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.15 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.17 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |
| PERC | Pond 308 | BASIN308 | 32.19 | 51.20 | 57.10 | 99752 | 0.00 | 0.00 | 0.00 | 10.06 |

Basin 308A
SJRWMD Treatment Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 0.00 | 70.09 | 73.00 | 91679 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.02 | 70.09 | 73.00 | 91677 | 0.00 | 1.01 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.03 | 70.09 | 73.00 | 91673 | 0.00 | 1.01 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.05 | 70.09 | 73.00 | 91670 | 0.00 | 1.01 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.07 | 70.09 | 73.00 | 91667 | 0.00 | 1.01 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.08 | 70.09 | 73.00 | 91663 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.10 | 70.09 | 73.00 | 91660 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.12 | 70.09 | 73.00 | 91656 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.13 | 70.08 | 73.00 | 91653 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.15 | 70.08 | 73.00 | 91650 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.17 | 70.08 | 73.00 | 91646 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.18 | 70.08 | 73.00 | 91643 | 0.00 | 1.01 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.20 | 70.08 | 73.00 | 91640 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.22 | 70.08 | 73.00 | 91636 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.24 | 70.08 | 73.00 | 91633 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.25 | 70.08 | 73.00 | 91629 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.27 | 70.08 | 73.00 | 91626 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.29 | 70.08 | 73.00 | 91623 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.30 | 70.08 | 73.00 | 91619 | 0.00 | 1.01 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.32 | 70.08 | 73.00 | 91616 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.34 | 70.08 | 73.00 | 91613 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.35 | 70.08 | 73.00 | 91609 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.37 | 70.08 | 73.00 | 91606 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.39 | 70.07 | 73.00 | 91602 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.40 | 70.07 | 73.00 | 91599 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.42 | 70.07 | 73.00 | 91596 | 0.00 | 1.01 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.44 | 70.07 | 73.00 | 91592 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.45 | 70.07 | 73.00 | 91589 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.47 | 70.07 | 73.00 | 91585 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.49 | 70.07 | 73.00 | 91582 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.50 | 70.07 | 73.00 | 91579 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.52 | 70.07 | 73.00 | 91575 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.54 | 70.07 | 73.00 | 91572 | 0.00 | 1.01 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.55 | 70.07 | 73.00 | 91569 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.57 | 70.07 | 73.00 | 91565 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.59 | 70.07 | 73.00 | 91562 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.61 | 70.07 | 73.00 | 91558 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.62 | 70.07 | 73.00 | 91555 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.64 | 70.06 | 73.00 | 91552 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.66 | 70.06 | 73.00 | 91548 | 0.00 | 1.01 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.67 | 70.06 | 73.00 | 91545 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.69 | 70.06 | 73.00 | 91542 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.71 | 70.06 | 73.00 | 91538 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.72 | 70.06 | 73.00 | 91535 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.74 | 70.06 | 73.00 | 91531 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.76 | 70.06 | 73.00 | 91528 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.77 | 70.06 | 73.00 | 91525 | 0.00 | 1.01 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.79 | 70.06 | 73.00 | 91521 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.81 | 70.06 | 73.00 | 91518 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.82 | 70.06 | 73.00 | 91514 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.84 | 70.06 | 73.00 | 91511 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.86 | 70.06 | 73.00 | 91508 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.87 | 70.06 | 73.00 | 91504 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.89 | 70.05 | 73.00 | 91501 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.91 | 70.05 | 73.00 | 91498 | 0.00 | 1.01 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.92 | 70.05 | 73.00 | 91494 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.94 | 70.05 | 73.00 | 91491 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.96 | 70.05 | 73.00 | 91487 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.97 | 70.05 | 73.00 | 91484 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.99 | 70.05 | 73.00 | 91481 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 1.01 | 70.05 | 73.00 | 91477 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 1.02 | 70.05 | 73.00 | 91476 | 0.00 | 1.01 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 1.03 | 70.05 | 73.00 | 91472 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.05 | 70.05 | 73.00 | 91469 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.07 | 70.05 | 73.00 | 91466 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.08 | 70.05 | 73.00 | 91462 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.10 | 70.05 | 73.00 | 91459 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.12 | 70.05 | 73.00 | 91455 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.13 | 70.05 | 73.00 | 91452 | 0.00 | 1.01 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.15 | 70.04 | 73.00 | 91449 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.17 | 70.04 | 73.00 | 91445 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.18 | 70.04 | 73.00 | 91442 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.20 | 70.04 | 73.00 | 91439 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.22 | 70.04 | 73.00 | 91435 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.24 | 70.04 | 73.00 | 91432 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.25 | 70.04 | 73.00 | 91429 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.27 | 70.04 | 73.00 | 91425 | 0.00 | 1.01 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.29 | 70.04 | 73.00 | 91422 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.30 | 70.04 | 73.00 | 91419 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.32 | 70.04 | 73.00 | 91415 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.34 | 70.04 | 73.00 | 91412 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.35 | 70.04 | 73.00 | 91408 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.37 | 70.04 | 73.00 | 91405 | 0.00 | 1.01 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.39 | 70.04 | 73.00 | 91402 | 0.00 | 1.00 | 0.00 | 0.11 |

Basin 308A
SJRWMD Treatment Recovery
3-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 23.80 | 69.15 | 73.00 | 86927 | 0.00 | 0.96 | 0.00 | 1.93 |
| PERC | Pond 308A | BASIN308 | 23.82 | 69.15 | 73.00 | 86924 | 0.00 | 0.96 | 0.00 | 1.93 |
| PERC | Pond 308A | BASIN308 | 23.83 | 69.15 | 73.00 | 86920 | 0.00 | 0.96 | 0.00 | 1.93 |
| PERC | Pond 308A | BASIN308 | 23.85 | 69.15 | 73.00 | 86917 | 0.00 | 0.96 | 0.00 | 1.93 |
| PERC | Pond 308A | BASIN308 | 23.87 | 69.15 | 73.00 | 86914 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.88 | 69.14 | 73.00 | 86910 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.90 | 69.14 | 73.00 | 86907 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.92 | 69.14 | 73.00 | 86904 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.93 | 69.14 | 73.00 | 86900 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.95 | 69.14 | 73.00 | 86897 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.97 | 69.14 | 73.00 | 86894 | 0.00 | 0.96 | 0.00 | 1.94 |
| PERC | Pond 308A | BASIN308 | 23.98 | 69.14 | 73.00 | 86890 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.00 | 69.14 | 73.00 | 86887 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.02 | 69.14 | 73.00 | 86884 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.03 | 69.14 | 73.00 | 86880 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.05 | 69.14 | 73.00 | 86877 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.07 | 69.14 | 73.00 | 86874 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.08 | 69.14 | 73.00 | 86870 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.10 | 69.14 | 73.00 | 86867 | 0.00 | 0.96 | 0.00 | 1.95 |
| PERC | Pond 308A | BASIN308 | 24.12 | 69.14 | 73.00 | 86864 | 0.00 | 0.96 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.13 | 69.13 | 73.00 | 86860 | 0.00 | 0.96 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.15 | 69.13 | 73.00 | 86857 | 0.00 | 0.96 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.17 | 69.13 | 73.00 | 86854 | 0.00 | 0.95 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.18 | 69.13 | 73.00 | 86850 | 0.00 | 0.95 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.20 | 69.13 | 73.00 | 86847 | 0.00 | 0.95 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.22 | 69.13 | 73.00 | 86844 | 0.00 | 0.95 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.23 | 69.13 | 73.00 | 86840 | 0.00 | 0.95 | 0.00 | 1.96 |
| PERC | Pond 308A | BASIN308 | 24.25 | 69.13 | 73.00 | 86837 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.27 | 69.13 | 73.00 | 86834 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.28 | 69.13 | 73.00 | 86830 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.30 | 69.13 | 73.00 | 86827 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.32 | 69.13 | 73.00 | 86824 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.33 | 69.13 | 73.00 | 86820 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.35 | 69.13 | 73.00 | 86817 | 0.00 | 0.95 | 0.00 | 1.97 |
| PERC | Pond 308A | BASIN308 | 24.37 | 69.13 | 73.00 | 86814 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.38 | 69.12 | 73.00 | 86810 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.40 | 69.12 | 73.00 | 86807 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.42 | 69.12 | 73.00 | 86804 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.43 | 69.12 | 73.00 | 86800 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.45 | 69.12 | 73.00 | 86797 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.47 | 69.12 | 73.00 | 86794 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.48 | 69.12 | 73.00 | 86790 | 0.00 | 0.95 | 0.00 | 1.98 |
| PERC | Pond 308A | BASIN308 | 24.50 | 69.12 | 73.00 | 86787 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.52 | 69.12 | 73.00 | 86784 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.53 | 69.12 | 73.00 | 86780 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.55 | 69.12 | 73.00 | 86777 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.57 | 69.12 | 73.00 | 86774 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.58 | 69.12 | 73.00 | 86770 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.60 | 69.12 | 73.00 | 86767 | 0.00 | 0.95 | 0.00 | 1.99 |
| PERC | Pond 308A | BASIN308 | 24.62 | 69.12 | 73.00 | 86764 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.63 | 69.12 | 73.00 | 86760 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.65 | 69.11 | 73.00 | 86757 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.67 | 69.11 | 73.00 | 86754 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.68 | 69.11 | 73.00 | 86750 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.70 | 69.11 | 73.00 | 86747 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.72 | 69.11 | 73.00 | 86744 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.73 | 69.11 | 73.00 | 86741 | 0.00 | 0.95 | 0.00 | 2.00 |
| PERC | Pond 308A | BASIN308 | 24.75 | 69.11 | 73.00 | 86737 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.77 | 69.11 | 73.00 | 86734 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.78 | 69.11 | 73.00 | 86731 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.80 | 69.11 | 73.00 | 86727 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.82 | 69.11 | 73.00 | 86724 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.83 | 69.11 | 73.00 | 86721 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.85 | 69.11 | 73.00 | 86717 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.87 | 69.11 | 73.00 | 86714 | 0.00 | 0.95 | 0.00 | 2.01 |
| PERC | Pond 308A | BASIN308 | 24.88 | 69.11 | 73.00 | 86711 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.90 | 69.10 | 73.00 | 86707 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.92 | 69.10 | 73.00 | 86704 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.93 | 69.10 | 73.00 | 86701 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.95 | 69.10 | 73.00 | 86697 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.97 | 69.10 | 73.00 | 86694 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 24.98 | 69.10 | 73.00 | 86691 | 0.00 | 0.95 | 0.00 | 2.02 |
| PERC | Pond 308A | BASIN308 | 25.00 | 69.10 | 73.00 | 86687 | 0.00 | 0.95 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.02 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.03 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.05 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.07 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.08 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.10 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.12 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.13 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.15 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.17 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |
| PERC | Pond 308A | BASIN308 | 25.18 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 2.03 |

Basin 308A
SJRWMD Closed Basin Recovery
14-Day

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| PERC | Pond 308A | BASIN308 | 0.00 | 71.41 | 73.00 | 98446 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.02 | 71.41 | 73.00 | 98443 | 0.00 | 1.08 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.03 | 71.41 | 73.00 | 98440 | 0.00 | 1.08 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.05 | 71.41 | 73.00 | 98436 | 0.00 | 1.08 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.07 | 71.41 | 73.00 | 98433 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.08 | 71.41 | 73.00 | 98429 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.10 | 71.41 | 73.00 | 98426 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.12 | 71.41 | 73.00 | 98422 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.13 | 71.40 | 73.00 | 98419 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.15 | 71.40 | 73.00 | 98416 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.17 | 71.40 | 73.00 | 98412 | 0.00 | 1.08 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.18 | 71.40 | 73.00 | 98409 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.20 | 71.40 | 73.00 | 98405 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.22 | 71.40 | 73.00 | 98402 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.24 | 71.40 | 73.00 | 98398 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.25 | 71.40 | 73.00 | 98395 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.27 | 71.40 | 73.00 | 98392 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.29 | 71.40 | 73.00 | 98388 | 0.00 | 1.08 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.30 | 71.40 | 73.00 | 98385 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.32 | 71.40 | 73.00 | 98381 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.34 | 71.40 | 73.00 | 98378 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.35 | 71.40 | 73.00 | 98374 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.37 | 71.40 | 73.00 | 98371 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.39 | 71.39 | 73.00 | 98368 | 0.00 | 1.08 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.40 | 71.39 | 73.00 | 98364 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.42 | 71.39 | 73.00 | 98361 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.44 | 71.39 | 73.00 | 98357 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.45 | 71.39 | 73.00 | 98354 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.47 | 71.39 | 73.00 | 98350 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.49 | 71.39 | 73.00 | 98347 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.50 | 71.39 | 73.00 | 98344 | 0.00 | 1.08 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.52 | 71.39 | 73.00 | 98340 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.54 | 71.39 | 73.00 | 98337 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.55 | 71.39 | 73.00 | 98333 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.57 | 71.39 | 73.00 | 98330 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.59 | 71.39 | 73.00 | 98326 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.61 | 71.39 | 73.00 | 98323 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.62 | 71.39 | 73.00 | 98319 | 0.00 | 1.08 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.64 | 71.38 | 73.00 | 98316 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.66 | 71.38 | 73.00 | 98313 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.67 | 71.38 | 73.00 | 98309 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.69 | 71.38 | 73.00 | 98306 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.71 | 71.38 | 73.00 | 98302 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.72 | 71.38 | 73.00 | 98299 | 0.00 | 1.08 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.74 | 71.38 | 73.00 | 98295 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.76 | 71.38 | 73.00 | 98292 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.77 | 71.38 | 73.00 | 98289 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.79 | 71.38 | 73.00 | 98285 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.81 | 71.38 | 73.00 | 98282 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.82 | 71.38 | 73.00 | 98278 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.84 | 71.38 | 73.00 | 98275 | 0.00 | 1.08 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.86 | 71.38 | 73.00 | 98271 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.87 | 71.38 | 73.00 | 98268 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.89 | 71.37 | 73.00 | 98265 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.91 | 71.37 | 73.00 | 98261 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.92 | 71.37 | 73.00 | 98258 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.94 | 71.37 | 73.00 | 98254 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.96 | 71.37 | 73.00 | 98251 | 0.00 | 1.08 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.97 | 71.37 | 73.00 | 98247 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 0.99 | 71.37 | 73.00 | 98244 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.01 | 71.37 | 73.00 | 98241 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.02 | 71.37 | 73.00 | 98239 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.03 | 71.37 | 73.00 | 98235 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.05 | 71.37 | 73.00 | 98232 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.07 | 71.37 | 73.00 | 98229 | 0.00 | 1.08 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.08 | 71.37 | 73.00 | 98225 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.10 | 71.37 | 73.00 | 98222 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.12 | 71.37 | 73.00 | 98218 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.13 | 71.37 | 73.00 | 98215 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.15 | 71.36 | 73.00 | 98211 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.17 | 71.36 | 73.00 | 98208 | 0.00 | 1.08 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.18 | 71.36 | 73.00 | 98205 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.20 | 71.36 | 73.00 | 98201 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.22 | 71.36 | 73.00 | 98198 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.24 | 71.36 | 73.00 | 98194 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.25 | 71.36 | 73.00 | 98191 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.27 | 71.36 | 73.00 | 98187 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.29 | 71.36 | 73.00 | 98184 | 0.00 | 1.08 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.30 | 71.36 | 73.00 | 98181 | 0.00 | 1.08 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.32 | 71.36 | 73.00 | 98177 | 0.00 | 1.08 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.34 | 71.36 | 73.00 | 98174 | 0.00 | 1.08 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.35 | 71.36 | 73.00 | 98170 | 0.00 | 1.08 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.37 | 71.36 | 73.00 | 98167 | 0.00 | 1.08 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.39 | 71.36 | 73.00 | 98163 | 0.00 | 1.08 | 0.00 | 0.12 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 63.01 | 69.11 | 73.00 | 86732 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.03 | 69.11 | 73.00 | 86731 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.05 | 69.11 | 73.00 | 86730 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.06 | 69.11 | 73.00 | 86729 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.08 | 69.11 | 73.00 | 86728 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.10 | 69.11 | 73.00 | 86728 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.11 | 69.11 | 73.00 | 86727 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.13 | 69.11 | 73.00 | 86726 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.15 | 69.11 | 73.00 | 86725 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.16 | 69.11 | 73.00 | 86724 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.18 | 69.11 | 73.00 | 86723 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.20 | 69.11 | 73.00 | 86722 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.21 | 69.11 | 73.00 | 86721 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.23 | 69.11 | 73.00 | 86720 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.25 | 69.11 | 73.00 | 86719 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.26 | 69.11 | 73.00 | 86718 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.28 | 69.11 | 73.00 | 86717 | 0.00 | 0.27 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.30 | 69.11 | 73.00 | 86716 | 0.00 | 0.26 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.31 | 69.11 | 73.00 | 86715 | 0.00 | 0.26 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.33 | 69.11 | 73.00 | 86715 | 0.00 | 0.26 | 0.00 | 4.89 |
| PERC | Pond 308A | BASIN308 | 63.35 | 69.11 | 73.00 | 86714 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.36 | 69.11 | 73.00 | 86713 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.38 | 69.11 | 73.00 | 86712 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.40 | 69.11 | 73.00 | 86711 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.41 | 69.11 | 73.00 | 86710 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.43 | 69.10 | 73.00 | 86709 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.45 | 69.10 | 73.00 | 86708 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.46 | 69.10 | 73.00 | 86707 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.48 | 69.10 | 73.00 | 86706 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.50 | 69.10 | 73.00 | 86705 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.51 | 69.10 | 73.00 | 86704 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.53 | 69.10 | 73.00 | 86704 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.55 | 69.10 | 73.00 | 86703 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.56 | 69.10 | 73.00 | 86702 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.58 | 69.10 | 73.00 | 86701 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.60 | 69.10 | 73.00 | 86700 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.61 | 69.10 | 73.00 | 86699 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.63 | 69.10 | 73.00 | 86698 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.65 | 69.10 | 73.00 | 86697 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.66 | 69.10 | 73.00 | 86696 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.68 | 69.10 | 73.00 | 86695 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.70 | 69.10 | 73.00 | 86694 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.71 | 69.10 | 73.00 | 86694 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.73 | 69.10 | 73.00 | 86693 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.75 | 69.10 | 73.00 | 86692 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.76 | 69.10 | 73.00 | 86691 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.78 | 69.10 | 73.00 | 86690 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.80 | 69.10 | 73.00 | 86689 | 0.00 | 0.26 | 0.00 | 4.90 |
| PERC | Pond 308A | BASIN308 | 63.81 | 69.10 | 73.00 | 86688 | 0.00 | 0.26 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.83 | 69.10 | 73.00 | 86687 | 0.00 | 0.26 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.85 | 69.10 | 73.00 | 86686 | 0.00 | 0.26 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.86 | 69.10 | 73.00 | 86685 | 0.00 | 0.26 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.88 | 69.10 | 73.00 | 86685 | 0.00 | 0.07 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.90 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.91 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.93 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.95 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.96 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 63.98 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.00 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.01 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.03 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.05 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.06 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.08 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.10 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.11 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.13 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.15 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.16 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.18 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.20 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.21 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.23 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.25 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.26 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.28 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.30 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.31 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.33 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.35 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.36 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.38 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |
| PERC | Pond 308A | BASIN308 | 64.40 | 69.10 | 73.00 | 86684 | 0.00 | 0.00 | 0.00 | 4.91 |

Basin 308A
FDOT Closed Basin Recovery
7-Day / 30-Day

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 0.00 | 72.07 | 73.00 | 101930 | 0.00 | 0.00 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.02 | 72.07 | 73.00 | 101928 | 0.00 | 1.12 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.03 | 72.07 | 73.00 | 101924 | 0.00 | 1.12 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.05 | 72.07 | 73.00 | 101921 | 0.00 | 1.12 | 0.00 | 0.00 |
| PERC | Pond 308A | BASIN308 | 0.07 | 72.07 | 73.00 | 101917 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.08 | 72.07 | 73.00 | 101914 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.10 | 72.07 | 73.00 | 101910 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.12 | 72.07 | 73.00 | 101907 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.13 | 72.06 | 73.00 | 101903 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.15 | 72.06 | 73.00 | 101900 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.17 | 72.06 | 73.00 | 101896 | 0.00 | 1.12 | 0.00 | 0.01 |
| PERC | Pond 308A | BASIN308 | 0.18 | 72.06 | 73.00 | 101893 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.20 | 72.06 | 73.00 | 101889 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.22 | 72.06 | 73.00 | 101886 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.24 | 72.06 | 73.00 | 101882 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.25 | 72.06 | 73.00 | 101879 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.27 | 72.06 | 73.00 | 101875 | 0.00 | 1.12 | 0.00 | 0.02 |
| PERC | Pond 308A | BASIN308 | 0.29 | 72.06 | 73.00 | 101872 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.30 | 72.06 | 73.00 | 101868 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.32 | 72.06 | 73.00 | 101865 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.34 | 72.06 | 73.00 | 101861 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.35 | 72.06 | 73.00 | 101858 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.37 | 72.06 | 73.00 | 101854 | 0.00 | 1.12 | 0.00 | 0.03 |
| PERC | Pond 308A | BASIN308 | 0.39 | 72.05 | 73.00 | 101850 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.40 | 72.05 | 73.00 | 101847 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.42 | 72.05 | 73.00 | 101843 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.44 | 72.05 | 73.00 | 101840 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.45 | 72.05 | 73.00 | 101836 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.47 | 72.05 | 73.00 | 101833 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.49 | 72.05 | 73.00 | 101829 | 0.00 | 1.12 | 0.00 | 0.04 |
| PERC | Pond 308A | BASIN308 | 0.50 | 72.05 | 73.00 | 101826 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.52 | 72.05 | 73.00 | 101822 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.54 | 72.05 | 73.00 | 101819 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.55 | 72.05 | 73.00 | 101815 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.57 | 72.05 | 73.00 | 101812 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.59 | 72.05 | 73.00 | 101808 | 0.00 | 1.12 | 0.00 | 0.05 |
| PERC | Pond 308A | BASIN308 | 0.61 | 72.05 | 73.00 | 101805 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.62 | 72.05 | 73.00 | 101801 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.64 | 72.04 | 73.00 | 101798 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.66 | 72.04 | 73.00 | 101794 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.67 | 72.04 | 73.00 | 101791 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.69 | 72.04 | 73.00 | 101787 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.71 | 72.04 | 73.00 | 101784 | 0.00 | 1.12 | 0.00 | 0.06 |
| PERC | Pond 308A | BASIN308 | 0.72 | 72.04 | 73.00 | 101780 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.74 | 72.04 | 73.00 | 101777 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.76 | 72.04 | 73.00 | 101773 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.77 | 72.04 | 73.00 | 101770 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.79 | 72.04 | 73.00 | 101766 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.81 | 72.04 | 73.00 | 101763 | 0.00 | 1.12 | 0.00 | 0.07 |
| PERC | Pond 308A | BASIN308 | 0.82 | 72.04 | 73.00 | 101759 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.84 | 72.04 | 73.00 | 101756 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.86 | 72.04 | 73.00 | 101752 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.87 | 72.04 | 73.00 | 101749 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.89 | 72.03 | 73.00 | 101745 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.91 | 72.03 | 73.00 | 101742 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.92 | 72.03 | 73.00 | 101738 | 0.00 | 1.12 | 0.00 | 0.08 |
| PERC | Pond 308A | BASIN308 | 0.94 | 72.03 | 73.00 | 101735 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 0.96 | 72.03 | 73.00 | 101731 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 0.97 | 72.03 | 73.00 | 101728 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 0.99 | 72.03 | 73.00 | 101724 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.01 | 72.03 | 73.00 | 101721 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.02 | 72.03 | 73.00 | 101719 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.03 | 72.03 | 73.00 | 101715 | 0.00 | 1.12 | 0.00 | 0.09 |
| PERC | Pond 308A | BASIN308 | 1.05 | 72.03 | 73.00 | 101712 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.07 | 72.03 | 73.00 | 101708 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.08 | 72.03 | 73.00 | 101705 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.10 | 72.03 | 73.00 | 101701 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.12 | 72.03 | 73.00 | 101698 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.13 | 72.03 | 73.00 | 101694 | 0.00 | 1.12 | 0.00 | 0.10 |
| PERC | Pond 308A | BASIN308 | 1.15 | 72.02 | 73.00 | 101691 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.17 | 72.02 | 73.00 | 101687 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.18 | 72.02 | 73.00 | 101684 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.20 | 72.02 | 73.00 | 101680 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.22 | 72.02 | 73.00 | 101677 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.24 | 72.02 | 73.00 | 101673 | 0.00 | 1.12 | 0.00 | 0.11 |
| PERC | Pond 308A | BASIN308 | 1.25 | 72.02 | 73.00 | 101670 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.27 | 72.02 | 73.00 | 101666 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.29 | 72.02 | 73.00 | 101663 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.30 | 72.02 | 73.00 | 101659 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.32 | 72.02 | 73.00 | 101656 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.34 | 72.02 | 73.00 | 101652 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.35 | 72.02 | 73.00 | 101649 | 0.00 | 1.12 | 0.00 | 0.12 |
| PERC | Pond 308A | BASIN308 | 1.37 | 72.02 | 73.00 | 101645 | 0.00 | 1.12 | 0.00 | 0.13 |
| PERC | Pond 308A | BASIN308 | 1.39 | 72.02 | 73.00 | 101642 | 0.00 | 1.12 | 0.00 | 0.13 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 35.00 | 70.68 | 73.00 | 94703 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.02 | 70.68 | 73.00 | 94700 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.04 | 70.68 | 73.00 | 94697 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.05 | 70.68 | 73.00 | 94693 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.07 | 70.68 | 73.00 | 94690 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.09 | 70.68 | 73.00 | 94686 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.10 | 70.68 | 73.00 | 94683 | 0.00 | 1.04 | 0.00 | 3.13 |
| PERC | Pond 308A | BASIN308 | 35.12 | 70.68 | 73.00 | 94680 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.14 | 70.68 | 73.00 | 94676 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.15 | 70.68 | 73.00 | 94673 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.17 | 70.68 | 73.00 | 94669 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.19 | 70.68 | 73.00 | 94666 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.20 | 70.68 | 73.00 | 94663 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.22 | 70.68 | 73.00 | 94659 | 0.00 | 1.04 | 0.00 | 3.14 |
| PERC | Pond 308A | BASIN308 | 35.24 | 70.68 | 73.00 | 94656 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.25 | 70.67 | 73.00 | 94652 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.27 | 70.67 | 73.00 | 94649 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.29 | 70.67 | 73.00 | 94646 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.30 | 70.67 | 73.00 | 94642 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.32 | 70.67 | 73.00 | 94639 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.34 | 70.67 | 73.00 | 94635 | 0.00 | 1.04 | 0.00 | 3.15 |
| PERC | Pond 308A | BASIN308 | 35.35 | 70.67 | 73.00 | 94632 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.37 | 70.67 | 73.00 | 94629 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.39 | 70.67 | 73.00 | 94625 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.40 | 70.67 | 73.00 | 94622 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.42 | 70.67 | 73.00 | 94618 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.44 | 70.67 | 73.00 | 94615 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.45 | 70.67 | 73.00 | 94612 | 0.00 | 1.04 | 0.00 | 3.16 |
| PERC | Pond 308A | BASIN308 | 35.47 | 70.67 | 73.00 | 94608 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.49 | 70.67 | 73.00 | 94605 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.50 | 70.66 | 73.00 | 94601 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.52 | 70.66 | 73.00 | 94598 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.54 | 70.66 | 73.00 | 94595 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.55 | 70.66 | 73.00 | 94591 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.57 | 70.66 | 73.00 | 94588 | 0.00 | 1.04 | 0.00 | 3.17 |
| PERC | Pond 308A | BASIN308 | 35.59 | 70.66 | 73.00 | 94584 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.60 | 70.66 | 73.00 | 94581 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.62 | 70.66 | 73.00 | 94578 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.64 | 70.66 | 73.00 | 94574 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.65 | 70.66 | 73.00 | 94571 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.67 | 70.66 | 73.00 | 94567 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.69 | 70.66 | 73.00 | 94564 | 0.00 | 1.04 | 0.00 | 3.18 |
| PERC | Pond 308A | BASIN308 | 35.70 | 70.66 | 73.00 | 94561 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.72 | 70.66 | 73.00 | 94557 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.74 | 70.66 | 73.00 | 94554 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.75 | 70.65 | 73.00 | 94550 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.77 | 70.65 | 73.00 | 94547 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.79 | 70.65 | 73.00 | 94544 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.80 | 70.65 | 73.00 | 94540 | 0.00 | 1.04 | 0.00 | 3.19 |
| PERC | Pond 308A | BASIN308 | 35.82 | 70.65 | 73.00 | 94537 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.84 | 70.65 | 73.00 | 94533 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.85 | 70.65 | 73.00 | 94530 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.87 | 70.65 | 73.00 | 94527 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.89 | 70.65 | 73.00 | 94523 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.90 | 70.65 | 73.00 | 94520 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.92 | 70.65 | 73.00 | 94516 | 0.00 | 1.04 | 0.00 | 3.20 |
| PERC | Pond 308A | BASIN308 | 35.94 | 70.65 | 73.00 | 94513 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 35.95 | 70.65 | 73.00 | 94510 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 35.97 | 70.65 | 73.00 | 94506 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 35.99 | 70.65 | 73.00 | 94503 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 36.00 | 70.64 | 73.00 | 94500 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 36.02 | 70.64 | 73.00 | 94496 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 36.04 | 70.64 | 73.00 | 94493 | 0.00 | 1.04 | 0.00 | 3.21 |
| PERC | Pond 308A | BASIN308 | 36.05 | 70.64 | 73.00 | 94490 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.07 | 70.64 | 73.00 | 94486 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.09 | 70.64 | 73.00 | 94483 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.10 | 70.64 | 73.00 | 94480 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.12 | 70.64 | 73.00 | 94476 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.14 | 70.64 | 73.00 | 94473 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.15 | 70.64 | 73.00 | 94469 | 0.00 | 1.04 | 0.00 | 3.22 |
| PERC | Pond 308A | BASIN308 | 36.17 | 70.64 | 73.00 | 94466 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.19 | 70.64 | 73.00 | 94463 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.20 | 70.64 | 73.00 | 94459 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.22 | 70.64 | 73.00 | 94456 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.24 | 70.64 | 73.00 | 94453 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.25 | 70.64 | 73.00 | 94449 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.27 | 70.63 | 73.00 | 94446 | 0.00 | 1.04 | 0.00 | 3.23 |
| PERC | Pond 308A | BASIN308 | 36.29 | 70.63 | 73.00 | 94443 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.30 | 70.63 | 73.00 | 94439 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.32 | 70.63 | 73.00 | 94436 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.34 | 70.63 | 73.00 | 94433 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.35 | 70.63 | 73.00 | 94429 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.37 | 70.63 | 73.00 | 94426 | 0.00 | 1.04 | 0.00 | 3.24 |
| PERC | Pond 308A | BASIN308 | 36.39 | 70.63 | 73.00 | 94423 | 0.00 | 1.04 | 0.00 | 3.24 |

| Simulation | Node | Group | Time | Stage | Warning Stage | Surface Area | Total Inflow | Total Outflow | Total Vol In | Total Vol Out |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | hrs | ft | ft | ft2 | cfs | cfs | af | af |
| PERC | Pond 308A | BASIN308 | 207.20 | 69.11 | 73.00 | 86715 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.22 | 69.11 | 73.00 | 86715 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.24 | 69.11 | 73.00 | 86714 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.25 | 69.11 | 73.00 | 86714 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.27 | 69.11 | 73.00 | 86714 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.29 | 69.11 | 73.00 | 86714 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.30 | 69.11 | 73.00 | 86713 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.32 | 69.11 | 73.00 | 86713 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.34 | 69.11 | 73.00 | 86713 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.35 | 69.11 | 73.00 | 86713 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.37 | 69.11 | 73.00 | 86712 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.39 | 69.11 | 73.00 | 86712 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.40 | 69.11 | 73.00 | 86712 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.42 | 69.11 | 73.00 | 86712 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.44 | 69.11 | 73.00 | 86712 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.45 | 69.11 | 73.00 | 86711 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.47 | 69.11 | 73.00 | 86711 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.49 | 69.11 | 73.00 | 86711 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.50 | 69.11 | 73.00 | 86711 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.52 | 69.11 | 73.00 | 86710 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.54 | 69.11 | 73.00 | 86710 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.55 | 69.11 | 73.00 | 86710 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.57 | 69.11 | 73.00 | 86710 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.59 | 69.10 | 73.00 | 86710 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.60 | 69.10 | 73.00 | 86709 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.62 | 69.10 | 73.00 | 86709 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.64 | 69.10 | 73.00 | 86709 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.65 | 69.10 | 73.00 | 86709 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.67 | 69.10 | 73.00 | 86708 | 0.00 | 0.06 | 0.00 | 6.41 |
| PERC | Pond 308A | BASIN308 | 207.69 | 69.10 | 73.00 | 86708 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.70 | 69.10 | 73.00 | 86708 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.72 | 69.10 | 73.00 | 86708 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.74 | 69.10 | 73.00 | 86708 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.75 | 69.10 | 73.00 | 86707 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.77 | 69.10 | 73.00 | 86707 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.79 | 69.10 | 73.00 | 86707 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.80 | 69.10 | 73.00 | 86707 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.82 | 69.10 | 73.00 | 86706 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.84 | 69.10 | 73.00 | 86706 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.85 | 69.10 | 73.00 | 86706 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.87 | 69.10 | 73.00 | 86706 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.89 | 69.10 | 73.00 | 86705 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.90 | 69.10 | 73.00 | 86705 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.92 | 69.10 | 73.00 | 86705 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.94 | 69.10 | 73.00 | 86705 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.95 | 69.10 | 73.00 | 86705 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.97 | 69.10 | 73.00 | 86704 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 207.99 | 69.10 | 73.00 | 86704 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.00 | 69.10 | 73.00 | 86704 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.02 | 69.10 | 73.00 | 86704 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.04 | 69.10 | 73.00 | 86703 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.05 | 69.10 | 73.00 | 86703 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.07 | 69.10 | 73.00 | 86703 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.09 | 69.10 | 73.00 | 86703 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.10 | 69.10 | 73.00 | 86703 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.12 | 69.10 | 73.00 | 86702 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.14 | 69.10 | 73.00 | 86702 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.15 | 69.10 | 73.00 | 86702 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.17 | 69.10 | 73.00 | 86702 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.19 | 69.10 | 73.00 | 86701 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.20 | 69.10 | 73.00 | 86701 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.22 | 69.10 | 73.00 | 86701 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.24 | 69.10 | 73.00 | 86701 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.25 | 69.10 | 73.00 | 86700 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.27 | 69.10 | 73.00 | 86700 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.29 | 69.10 | 73.00 | 86700 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.30 | 69.10 | 73.00 | 86700 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.32 | 69.10 | 73.00 | 86700 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.34 | 69.10 | 73.00 | 86699 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.35 | 69.10 | 73.00 | 86699 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.37 | 69.10 | 73.00 | 86699 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.39 | 69.10 | 73.00 | 86699 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.40 | 69.10 | 73.00 | 86698 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.42 | 69.10 | 73.00 | 86698 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.44 | 69.10 | 73.00 | 86698 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.45 | 69.10 | 73.00 | 86698 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.47 | 69.10 | 73.00 | 86698 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.49 | 69.10 | 73.00 | 86697 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.50 | 69.10 | 73.00 | 86697 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.52 | 69.10 | 73.00 | 86697 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.54 | 69.10 | 73.00 | 86697 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.55 | 69.10 | 73.00 | 86696 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.57 | 69.10 | 73.00 | 86696 | 0.00 | 0.06 | 0.00 | 6.42 |
| PERC | Pond 308A | BASIN308 | 208.59 | 69.10 | 73.00 | 86696 | 0.00 | 0.06 | 0.00 | 6.42 |

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **308** Designed by **TFS** Date: 7/17/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/17/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | LOWER (ft.) | FALL (ft.) | # BR / L / S | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS ZONE: 7 / FREQ. (Yrs): 10 / MANNINGS n: 0.0120 / TAILW EL (ft): 56.44 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-800** | | | 0.59 | 0.59 | 0.56 | | | | | | | | | | 59.19 | 59.17 | 0.02 | | 24.00 | 0.037 | 1.32 | | |
| | | | | BW 219 | 67.17 | 0.00 | 0.00 | 0.00 | 10.00 | 0.56 | 7.41 | 0.56 | 0.00 | **4.15** | 0.01 | 59.53 | **0.34** | 56.53 | 56.43 | | 1 | | 0.149 | | 9.46 | |
| 455+18 | 118.81 | Lt. | S-801 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 54.53 | 54.43 | 0.10 | | 24.00 | 0.102 | 3.01 | | |
| CLI4 | | | **S-801** | | | 0.93 | 1.52 | 0.88 | | | | | | | | | | 59.17 | 59.08 | 0.08 | | 30.00 | 0.098 | 2.14 | | |
| | | | | BW 217 | 84.67 | 0.00 | 0.00 | 0.00 | 10.56 | 0.66 | 7.27 | 1.44 | 0.00 | **10.50** | 0.04 | 59.97 | **0.80** | 56.27 | 56.17 | | 1 | | 0.118 | | 15.27 | |
| 455+18 | 48.39 | Lt. | S-802 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 53.77 | 53.67 | 0.10 | | 30.00 | 0.076 | 3.11 | | |
| CLI4 | | | **S-802** | | | 0.83 | 2.35 | 0.79 | | | | | | | | | | 59.08 | 58.90 | 0.18 | | 30.00 | 0.231 | 3.24 | | |
| | | | | BW 217 | 79.10 | 0.00 | 0.00 | 0.00 | 11.22 | 0.41 | 7.12 | 2.23 | 0.00 | **15.91** | 0.08 | 60.21 | **1.13** | 56.17 | 54.80 | | 1 | | 1.732 | | 58.48 | |
| 455+18 | 40.28 | Rt. | S-803 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 53.67 | 52.30 | 1.37 | | 30.00 | 0.076 | 11.91 | | |
| CLI4 | | | **S-803** | | | 0.70 | 3.05 | 0.66 | | | | | | | | | | 58.90 | 58.20 | 0.70 | | 30.00 | 0.304 | 4.15 | | |
| | | | | BW 219 | 228.25 | 0.00 | 0.00 | 0.00 | 11.63 | 0.92 | 7.04 | 2.90 | 0.00 | **20.39** | 0.21 | 59.16 | **0.26** | 54.80 | 54.30 | | 1 | | 0.219 | | 20.80 | |
| 455+18 | 122.63 | Rt. | S-804 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 52.30 | 51.80 | 0.50 | | 30.00 | 0.076 | 4.24 | | |
| CLI4 | | | **S-804** | | | 0.00 | 3.05 | 0.00 | | | | | | | | | | 58.20 | 57.92 | 0.28 | | 36.00 | 0.097 | 2.81 | | |
| | | | | MH-8J | 289.77 | 0.00 | 0.00 | 0.00 | 12.54 | 1.72 | 6.85 | 2.90 | 0.00 | **19.84** | 0.06 | 60.25 | **2.05** | 54.80 | 54.50 | | 1 | | 0.104 | | 23.25 | |
| 457+50.00 | 121.86 | Rt. | S-805 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 51.80 | 51.50 | 0.30 | | 36.00 | 0.059 | 3.29 | | |
| CLI4 | | | **S-805** | | | 0.63 | 20.12 | 0.60 | | | | | | | | | | 57.92 | 57.14 | 0.79 | | 60.00 | 1.838 | 6.69 | | |
| | | | | BW 218 | 42.92 | 0.00 | 0.20 | 0.00 | 19.46 | 0.00 | 5.77 | 19.16 | 0.00 | **131.35** | 0.70 | 61.12 | **3.20** | 56.50 | 56.20 | | 1 | | 0.699 | | 235.88 | |
| 460+43.75 | 118.65 | Rt. | OUT308 | | | 0.00 | 0.00 | 0.00 | | | | | 20.74 | | | | | 51.50 | 51.20 | 0.30 | | 60.00 | 0.030 | 12.01 | | |
| CLI4 | | | **S-806** | | | 1.00 | 2.75 | 0.95 | | | | | | | | | | 58.16 | 57.92 | 0.23 | | 30.00 | 0.351 | 3.83 | | |
| | | | | BW 217 | 66.59 | 0.00 | 0.00 | 0.00 | 10.87 | 0.29 | 7.20 | 2.61 | 0.00 | **18.82** | 0.11 | 61.65 | **3.49** | 58.10 | 54.46 | | 1 | | 5.466 | | 103.89 | |
| 460+44.75 | 48.56 | Rt. | S-805 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 55.60 | 51.96 | 3.64 | | 30.00 | 0.076 | 21.16 | | |
| CLI4 | | | **S-807** | | | 1.11 | 1.75 | 1.05 | | | | | | | | | | 58.53 | 58.16 | 0.37 | | 24.00 | 0.358 | 3.87 | | |
| | | | | BW 217 | 102.93 | 0.00 | 0.00 | 0.00 | 10.43 | 0.44 | 7.31 | 1.66 | 0.00 | **12.15** | 0.12 | 61.35 | **2.82** | 58.14 | 57.60 | | 1 | | 0.525 | | 17.75 | |
| 460+46.18 | 58.36 | Lt. | S-806 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 56.14 | 55.60 | 0.54 | | 24.00 | 0.102 | 5.65 | | |
| CLI4 | | | **S-808** | | | 0.64 | 0.64 | 0.61 | | | | | | | | | | 58.65 | 58.53 | 0.12 | | 18.00 | 0.188 | 2.55 | | |
| | | | | BW 218 | 65.40 | 0.00 | 0.00 | 0.00 | 10.00 | 0.43 | 7.41 | 0.61 | 0.00 | **4.51** | 0.02 | 61.15 | **2.50** | 58.02 | 57.92 | | 1 | | 0.153 | | 4.45 | |
| 460+47.13 | 127.25 | Lt. | S-807 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 56.52 | 56.42 | 0.10 | | 18.00 | 0.150 | 2.52 | | |
| CLI4 | | | **S-809** | | | 0.00 | 13.69 | 0.00 | | | | | | | | | | 58.74 | 57.92 | 0.82 | | 54.00 | 0.323 | 6.11 | | |
| | | | | MH-8J | 252.37 | 0.00 | 0.20 | 0.00 | 18.77 | 0.69 | 5.86 | 13.06 | 0.00 | **97.23** | 0.29 | 62.50 | **3.76** | 58.84 | 56.46 | | 1 | | 0.943 | | 206.88 | |
| 463+00.10 | 121.67 | Rt. | S-805 | | | 0.00 | 0.00 | 0.00 | | | | | 20.74 | | | | | 54.34 | 51.96 | 2.38 | | 54.00 | 0.035 | 13.01 | | |
| CLI4 | | | **S-810** | | | 0.59 | 0.59 | 0.56 | | | | | | | | | | 60.80 | 60.68 | 0.11 | | 18.00 | 0.157 | 2.35 | | |
| | | | | BW 218 | 71.80 | 0.00 | 0.00 | 0.00 | 10.00 | 0.51 | 7.41 | 0.56 | 0.00 | **4.15** | 0.02 | 62.85 | **2.05** | 59.84 | 59.73 | | 1 | | 0.153 | | 4.45 | |
| 466+00 | 137.86 | Lt. | S-811 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 58.34 | 58.23 | 0.11 | | 18.00 | 0.150 | 2.52 | | |
| CLI4 | | | **S-811** | | | 1.42 | 2.01 | 1.35 | | | | | | | | | | 60.68 | 60.50 | 0.18 | | 30.00 | 0.149 | 2.83 | | |
| | | | | BW 217 | 123.23 | 0.00 | 0.00 | 0.00 | 10.51 | 0.72 | 7.29 | 1.91 | 0.00 | **13.91** | 0.06 | 63.68 | **3.00** | 60.59 | 60.50 | | 1 | | 0.073 | | 12.01 | |
| 466+00 | 62.56 | Lt. | S-812 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 58.09 | 58.00 | 0.09 | | 30.00 | 0.076 | 2.45 | | |
| CLI4 | | | **S-812** | | | 1.25 | 3.26 | 1.19 | | | | | | | | | | 60.22 | 59.89 | 0.32 | | 30.00 | 0.480 | 4.49 | | |
| | | | | BW 217 | 67.18 | 0.00 | 0.00 | 0.00 | 11.23 | 0.25 | 7.12 | 3.10 | 0.00 | **22.05** | 0.16 | 63.97 | **3.75** | 60.50 | 57.60 | | 1 | | 4.317 | | 92.32 | |
| 466+00 | 64.67 | Rt. | S-813 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 58.00 | 55.10 | 2.90 | | 30.00 | 0.076 | 18.81 | | |
| CLI4 | | | **S-813** | | | 0.68 | 13.69 | 0.65 | | | | | | | | | | 59.89 | 58.84 | 1.05 | | 54.00 | 0.355 | 6.20 | | |
| | | | | BW 219 | 296.45 | 0.00 | 0.20 | 0.00 | 17.98 | 0.80 | 5.96 | 13.06 | 0.00 | **98.61** | 0.42 | 62.86 | **2.97** | 59.60 | 58.84 | | 1 | | 0.256 | | 107.87 | |
| 466+00 | 135.10 | Rt. | S-809 | | | 0.00 | 0.00 | 0.00 | | | | | 20.74 | | | | | 55.10 | 54.34 | 0.76 | | 54.00 | 0.035 | 6.78 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **308** Designed by **TFS** Date: 7/17/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/17/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | LOWER (ft.) | FALL (ft.) | # BR / LS | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. / VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS ZONE: 7 / FREQ. (Yrs): 10 / MANNINGS n: 0.0120 / TAILW EL (ft): 56.44 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-814** | | | 0.00 | 9.75 | 0.00 | | | | | | | | | | 60.92 | 59.89 | 1.03 | | 48.00 | 0.346 | 6.15 | | |
| | | | | MH-8J | 296.33 | 0.00 | 0.20 | 0.00 | 17.17 | 0.80 | 6.08 | 9.31 | 0.00 | **77.32** | 0.29 | 65.20 | **4.28** | 61.58 | 59.10 | | 1 | | 0.837 | | 142.36 | |
| 469+00.08 | 135.37 | Rt. | S-813 | | | 0.00 | 0.00 | 0.00 | | | | | 20.74 | | | | | 57.58 | 55.10 | 2.48 | | 48.00 | 0.041 | 11.33 | | |
| CLI4 | | | **S-815** | | | 0.52 | 0.52 | 0.49 | | | | | | | | | | 65.41 | 65.32 | 0.09 | | 18.00 | 0.121 | 2.07 | | |
| | | | | BW 218 | 77.37 | 0.00 | 0.00 | 0.00 | 10.00 | 0.62 | 7.41 | 0.49 | 0.00 | **3.66** | 0.01 | 67.80 | **2.39** | 64.79 | 64.67 | | 1 | | 0.155 | | 4.48 | |
| 472+00 | 144.57 | Lt. | S-816 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 63.29 | 63.17 | 0.12 | | 18.00 | 0.150 | 2.54 | | |
| CLI4 | | | **S-816** | | | 1.52 | 2.04 | 1.44 | | | | | | | | | | 65.32 | 65.13 | 0.18 | | 30.00 | 0.154 | 2.87 | | |
| | | | | BW 217 | 119.70 | 0.00 | 0.00 | 0.00 | 10.62 | 0.70 | 7.26 | 1.94 | 0.00 | **14.07** | 0.06 | 67.86 | **2.54** | 64.77 | 64.40 | | 1 | | 0.309 | | 24.70 | |
| 472+00 | 63.70 | Lt. | S-817 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 62.27 | 61.90 | 0.37 | | 30.00 | 0.076 | 5.03 | | |
| CLI4 | | | **S-817** | | | 0.86 | 2.90 | 0.82 | | | | | | | | | | 65.13 | 64.85 | 0.28 | | 30.00 | 0.350 | 3.99 | | |
| | | | | BW 217 | 79.17 | 0.00 | 0.00 | 0.00 | 11.32 | 0.33 | 7.10 | 2.76 | 0.00 | **19.57** | 0.12 | 68.09 | **2.96** | 64.40 | 62.48 | | 1 | | 2.425 | | 69.20 | |
| 472+00 | 60.00 | Rt. | S-818 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 61.90 | 59.98 | 1.92 | | 30.00 | 0.076 | 14.10 | | |
| CLI4 | | | **S-818** | | | 1.13 | 9.75 | 1.07 | | | | | | | | | | 64.85 | 63.50 | 1.35 | | 48.00 | 0.459 | 6.24 | | 10 yr 240 hr per proposed |
| | | | | BW 219 | 295.25 | 0.00 | 0.20 | 0.00 | 16.38 | 0.79 | 6.19 | 9.31 | 5.60 | **78.39** | 0.60 | 67.20 | **2.35** | 63.98 | 63.50 | | 1 | | 0.163 | | 62.74 | ICPR |
| 472+00 | 142.42 | Rt. | S-814 | | | 0.00 | 0.00 | 0.00 | | | | | 20.74 | | | | | 59.98 | 59.50 | 0.48 | | 48.00 | 0.041 | 4.99 | | |
| CLI4 | | | **S-819** | | | 0.00 | 0.00 | 0.00 | | | | | | | | | | 64.85 | 64.85 | 0.00 | | 18.00 | 0.003 | 0.21 | | |
| | | | | DBI-D | 7.99 | 0.20 | 0.20 | 0.05 | 10.00 | 0.07 | 7.41 | 0.05 | 0.00 | **0.37** | 0.00 | 65.00 | **0.15** | 63.39 | 63.10 | | 1 | | 3.630 | | 21.68 | |
| 472+00 | 153.16 | Rt. | S-818 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 61.89 | 61.60 | 0.29 | | 18.00 | 0.150 | 12.27 | | |
| CLI4 | | | **S-820** | | | 0.00 | 5.72 | 0.00 | | | | | | | | | | 65.67 | 64.85 | 0.81 | | 42.00 | 0.277 | 5.15 | | |
| | | | | MH-8J | 293.30 | 0.00 | 0.00 | 0.00 | 15.44 | 0.95 | 6.34 | 5.43 | 0.00 | **49.57** | 0.21 | 69.20 | **3.53** | 65.62 | 63.48 | | 1 | | 0.730 | | 93.10 | |
| 474+99.85 | 137.02 | Rt. | S-818 | | | 0.00 | 0.00 | 0.00 | | | | | 15.14 | | | | | 62.12 | 59.98 | 2.14 | | 42.00 | 0.048 | 9.68 | | |
| CLI4 | | | **S-821** | | | 0.51 | 0.51 | 0.48 | | | | | | | | | | 74.98 | 74.89 | 0.09 | | 18.00 | 0.116 | 2.03 | | |
| | | | | BW 218 | 77.38 | 0.00 | 0.00 | 0.00 | 10.00 | 0.63 | 7.41 | 0.48 | 0.00 | **3.59** | 0.01 | 76.78 | **1.80** | 73.77 | 73.58 | | 1 | | 0.246 | | 5.64 | |
| 478+00 | 144.58 | Lt. | S-822 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.27 | 72.08 | 0.19 | | 18.00 | 0.150 | 3.19 | | |
| CLI4 | | | **S-822** | | | 0.96 | 1.47 | 0.91 | | | | | | | | | | 74.89 | 74.59 | 0.31 | | 24.00 | 0.233 | 3.23 | | |
| | | | | BW 217 | 131.31 | 0.00 | 0.00 | 0.00 | 10.63 | 0.68 | 7.26 | 1.40 | 0.00 | **10.13** | 0.08 | 76.59 | **1.70** | 73.54 | 73.41 | | 1 | | 0.099 | | 7.71 | |
| 478+00 | 63.70 | Lt. | S-823 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 71.54 | 71.41 | 0.13 | | 24.00 | 0.102 | 2.45 | | |
| CLI4 | | | **S-823** | | | 0.97 | 2.44 | 0.92 | | | | | | | | | | 74.59 | 71.14 | 3.45 | | 30.00 | 4.954 | 18.20 | | |
| | | | | BW 217 | 69.58 | 0.00 | 0.00 | 0.00 | 11.31 | 0.06 | 7.10 | 2.32 | 0.00 | **16.47** | 2.58 | 77.30 | **2.71** | 73.91 | 67.93 | | 1 | | 8.594 | | 130.26 | |
| 478+00 | 70.61 | Rt. | S-824 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 71.41 | 65.43 | 5.98 | | 30.00 | 0.076 | 26.54 | | |
| CLI4 | | | **S-824** | | | 0.98 | 5.72 | 0.93 | | | | | | | | | | 71.14 | 67.21 | 3.93 | | 42.00 | 1.338 | 10.17 | | |
| | | | | BW 219 | 293.60 | 0.00 | 0.00 | 0.00 | 14.95 | 0.48 | 6.41 | 5.43 | 0.00 | **50.00** | 1.61 | 76.18 | **5.04** | 71.25 | 68.93 | | 1 | | 0.790 | | 96.89 | |
| 478+00 | 142.44 | Rt. | S-820 | | | 0.00 | 0.00 | 0.00 | | | | | 15.14 | | | | | 67.75 | 65.43 | 2.32 | | 42.00 | 0.048 | 10.07 | | |
| CLI4 | | | **S-825** | | | 0.00 | 2.30 | 0.00 | | | | | | | | | | 71.53 | 71.14 | 0.39 | | 30.00 | 0.132 | 2.98 | | |
| | | | | MH-8 | 294.09 | 0.00 | 0.00 | 0.00 | 13.31 | 1.64 | 6.70 | 2.18 | 0.00 | **14.64** | 0.07 | 73.70 | **2.17** | 71.21 | 67.93 | | 1 | | 1.115 | | 46.93 | |
| 480+99.65 | 137.79 | Rt. | S-824 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 68.71 | 65.43 | 3.28 | | 30.00 | 0.076 | 9.56 | | |
| CLI4 | | | **S-826** | | | 0.31 | 0.31 | 0.29 | | | | | | | | | | 73.68 | 73.64 | 0.04 | | 18.00 | 0.042 | 1.23 | | |
| | | | | BW 218 | 87.81 | 0.00 | 0.00 | 0.00 | 10.00 | 0.73 | 7.41 | 0.29 | 0.00 | **2.18** | 0.00 | 76.78 | **3.10** | 73.77 | 73.64 | | 1 | | 0.148 | | 4.38 | |
| 484+00 | 144.57 | Lt. | S-827 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.27 | 72.14 | 0.13 | | 18.00 | 0.150 | 2.48 | | |
| CLI4 | | | **S-827** | | | 0.48 | 0.79 | 0.46 | | | | | | | | | | 73.27 | 73.08 | 0.19 | | 18.00 | 0.372 | 3.07 | | |
| | | | | BW 217 | 50.85 | 0.00 | 0.00 | 0.00 | 10.73 | 0.28 | 7.23 | 0.75 | 0.00 | **5.43** | 0.07 | 76.84 | **3.57** | 73.64 | 73.07 | | 1 | | 1.121 | | 12.05 | |
| 484+00 | 54.26 | Lt. | S-828 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.14 | 71.57 | 0.57 | | 18.00 | 0.150 | 6.82 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **308** Designed by **TFS** Date: 7/17/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/17/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | LOWER (ft.) | FALL (ft.) | # BR / LS | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. / VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS ZONE: 7 / FREQ. (Yrs): 10 / MANNINGS n: 0.0120 / TAILW EL (ft): 56.44 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-828** | | | 0.38 | 1.17 | 0.36 | | | | | | | | | | 73.08 | 72.96 | 0.12 | | 24.00 | 0.178 | 2.54 | | |
| | | | | BW 217 | 69.08 | 0.00 | 0.00 | 0.00 | 11.01 | 0.45 | 7.17 | 1.11 | 0.00 | **7.97** | 0.05 | 76.08 | **3.00** | 73.03 | 72.96 | | 1 | | 0.101 | | 7.80 | |
| 484+00 | 1.42 | Lt. | S-829 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 71.03 | 70.96 | 0.07 | | 24.00 | 0.102 | 2.48 | | |
| CLI4 | | | **S-829** | | | 0.73 | 1.90 | 0.69 | | | | | | | | | | 72.90 | 72.59 | 0.31 | | 24.00 | 0.462 | 4.06 | | |
| | | | | BW 217 | 67.17 | 0.00 | 0.00 | 0.00 | 11.46 | 0.28 | 7.07 | 1.80 | 0.00 | **12.76** | 0.13 | 77.30 | **4.40** | 72.96 | 72.59 | | 1 | | 0.551 | | 18.19 | |
| 484+00 | 70.66 | Rt. | S-830 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 70.96 | 70.59 | 0.37 | | 24.00 | 0.102 | 5.79 | | |
| CLI4 | | | **S-830** | | | 0.40 | 2.30 | 0.38 | | | | | | | | | | 72.00 | 71.53 | 0.47 | | 30.00 | 0.160 | 3.12 | | |
| | | | | BW 219 | 294.77 | 0.00 | 0.00 | 0.00 | 11.74 | 1.57 | 7.01 | 2.18 | 0.00 | **15.32** | 0.12 | 76.18 | **4.18** | 73.09 | 71.21 | | 1 | | 0.638 | | 35.49 | |
| 484+00 | 141.08 | Rt. | S-825 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 70.59 | 68.71 | 1.88 | | 30.00 | 0.076 | 7.23 | | |
| CLI4 | | | **S-O308A** | | | 0.00 | 0.00 | 0.00 | | | | | | | | | | 71.22 | 71.14 | 0.08 | | 30.00 | 0.181 | 3.08 | | |
| | | | | DBI-D | 45.73 | 0.00 | 0.00 | 0.00 | 10.00 | 0.25 | 7.41 | 0.00 | 15.14 | **15.14** | 0.03 | 72.00 | **0.78** | 70.31 | 70.25 | | 1 | | 0.131 | | 16.09 | |
| 478+03.98 | 190.76 | Rt. | S-824 | | | 0.00 | 0.00 | 0.00 | | | | | 15.14 | | | | | 67.81 | 67.75 | 0.06 | | 30.00 | 0.076 | 3.28 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **3082** Designed by **LNW** Date: 7/ 5/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/ 5/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | AREAS (Ac) TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | FLOWLINE LOWER (ft.) | FLOWLINE FALL (ft.) | # BR / LS | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. / VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-831** | | | 0.00 | 0.00 | 0.00 | | | | | | | | | | 56.53 | 56.44 | 0.09 | | 24.00 | 0.160 | 2.19 | | ZONE: 7 |
| | | | | MH-8 | 55.31 | 0.00 | 5.16 | 0.00 | 23.35 | 0.00 | 5.33 | 1.29 | 0.00 | **6.88** | 0.04 | 58.00 | **1.47** | 55.55 | 53.20 | | 1 | | 4.249 | | 50.52 | FREQ. (Yrs): 10 |
| 469+43.00 | 150.13 | Rt. | OUT3082 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 53.55 | 51.20 | 2.35 | | 24.00 | 0.102 | 16.08 | | MANNINGS n: 0.0120 |
| CLI4 | | | **S-832** | | | 0.00 | 0.00 | 0.00 | | | | | | | | | | 60.73 | 56.53 | 4.20 | | 24.00 | 7.780 | 16.52 | | TAILW EL (ft): 56.44 |
| | | | | DBI-D | 54.02 | 5.16 | 5.16 | 1.29 | 23.30 | 0.05 | 5.34 | 1.29 | 0.00 | **6.89** | 0.00 | 63.90 | **3.17** | 62.35 | 55.55 | | 1 | | 12.589 | | 86.95 | |
| 470+00.00 | 151.50 | Rt. | S-831 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 60.35 | 53.55 | 6.80 | | 24.00 | 0.102 | 27.68 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **308A** Designed by **LNW** Date: 7/18/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/18/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | LOWER (ft.) | FALL (ft.) | # BR / L / S | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. / VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-833** | | | 0.00 | 11.05 | 0.00 | | | | | | | | | | 73.35 | 73.06 | 0.29 | | 48.00 | 0.548 | 4.76 | | ZONE: 7 |
| | | | | MH-8 | 52.79 | 0.00 | 0.96 | 0.00 | 21.19 | 0.00 | 5.57 | 10.74 | 0.00 | **59.78** | 0.21 | 75.40 | **2.05** | 71.40 | 70.50 | | 1 | | 1.705 | | 203.20 | FREQ. (Yrs): 10 |
| 482+39.09 | 151.13 | Rt. | OUT308A | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 67.40 | 66.50 | 0.90 | | 48.00 | 0.041 | 16.17 | | MANNINGS n: 0.0120 |
| CLI4 | | | **S-834** | | | 0.00 | 11.05 | 0.00 | | | | | | | | | | 73.59 | 73.35 | 0.24 | | 48.00 | 0.565 | 4.77 | | TAILW EL (ft): 72.71 |
| | | | | DBI-DJ | 42.49 | 0.96 | 0.96 | 0.24 | 21.04 | 0.15 | 5.58 | 10.74 | 0.00 | **59.96** | 0.18 | 75.40 | **1.81** | 71.60 | 71.40 | | 1 | | 0.471 | | 106.76 | |
| 482+85.56 | 151.15 | Rt. | S-833 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 67.60 | 67.40 | 0.20 | | 48.00 | 0.041 | 8.50 | | |
| CLI4 | | | **S-835** | | | 0.00 | 11.05 | 0.00 | | | | | | | | | | 73.92 | 73.59 | 0.33 | | 48.00 | 0.302 | 4.70 | | |
| | | | | MH-8J | 108.81 | 0.00 | 0.00 | 0.00 | 20.65 | 0.39 | 5.63 | 10.50 | 0.00 | **59.09** | 0.17 | 76.20 | **2.28** | 72.90 | 71.60 | | 1 | | 1.195 | | 170.09 | |
| 484+00.00 | 148.42 | Rt. | S-834 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 68.90 | 67.60 | 1.30 | | 48.00 | 0.041 | 13.54 | | |
| CLI4 | | | **S-836** | | | 0.67 | 0.67 | 0.64 | | | | | | | | | | 76.19 | 76.06 | 0.13 | | 18.00 | 0.206 | 2.67 | | |
| | | | | BW 218 | 65.38 | 0.00 | 0.00 | 0.00 | 10.00 | 0.41 | 7.41 | 0.64 | 0.00 | **4.72** | 0.02 | 79.07 | **2.88** | 76.06 | 75.96 | | 1 | | 0.153 | | 4.45 | |
| 487+52.2 | 144.56 | Lt. | S-837 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.56 | 74.46 | 0.10 | | 18.00 | 0.150 | 2.52 | | |
| CLI4 | | | **S-837** | | | 0.68 | 1.35 | 0.65 | | | | | | | | | | 76.06 | 75.89 | 0.17 | | 24.00 | 0.243 | 2.98 | | |
| | | | | BW 217 | 71.27 | 0.00 | 0.00 | 0.00 | 10.41 | 0.40 | 7.31 | 1.28 | 0.00 | **9.38** | 0.07 | 79.38 | **3.32** | 74.80 | 74.70 | | 1 | | 0.140 | | 9.18 | |
| 487+52.5 | 75.69 | Lt. | S-838 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.80 | 72.70 | 0.10 | | 24.00 | 0.102 | 2.92 | | |
| CLI4 | | | **S-838** | | | 0.82 | 2.17 | 0.78 | | | | | | | | | | 75.89 | 75.75 | 0.14 | | 30.00 | 0.226 | 3.03 | | |
| | | | | BW 217 | 62.49 | 0.00 | 0.00 | 0.00 | 10.81 | 0.34 | 7.22 | 2.06 | 0.00 | **14.88** | 0.07 | 78.29 | **2.40** | 75.20 | 75.10 | | 1 | | 0.160 | | 17.78 | |
| 487+52.5 | 1.42 | Lt. | S-839 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.70 | 72.60 | 0.10 | | 30.00 | 0.076 | 3.62 | | |
| CLI4 | | | **S-839** | | | 1.19 | 3.36 | 1.13 | | | | | | | | | | 75.75 | 75.40 | 0.34 | | 30.00 | 0.512 | 4.64 | | |
| | | | | BW 217 | 67.20 | 0.00 | 0.00 | 0.00 | 11.15 | 0.24 | 7.14 | 3.19 | 0.00 | **22.79** | 0.17 | 79.59 | **3.84** | 75.10 | 75.00 | | 1 | | 0.149 | | 17.14 | |
| 487+52.5 | 64.07 | Rt. | S-840 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 72.60 | 72.50 | 0.10 | | 30.00 | 0.076 | 3.49 | | |
| CLI4 | | | **S-840** | | | 0.73 | 11.05 | 0.69 | | | | | | | | | | 75.40 | 75.14 | 0.26 | | 48.00 | 5.084 | 4.82 | | |
| | | | | BW 219 | 5.13 | 0.00 | 0.00 | 0.00 | 19.44 | 0.02 | 5.77 | 10.50 | 0.00 | **60.61** | 0.25 | 78.46 | **3.06** | 75.24 | 75.14 | | 1 | | 1.948 | | 217.18 | |
| 487+52.5 | 134.52 | Rt. | S-841 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 71.24 | 71.14 | 0.10 | | 48.00 | 0.041 | 17.28 | | |
| CLI4 | | | **S-841** | | | 0.00 | 11.05 | 0.00 | | | | | | | | | | 74.73 | 73.92 | 0.81 | | 48.00 | 0.236 | 4.82 | | |
| | | | | MH-8J | 344.23 | 0.00 | 0.00 | 0.00 | 19.46 | 1.19 | 5.77 | 10.50 | 0.00 | **60.59** | 0.29 | 78.20 | **3.47** | 73.50 | 72.90 | | 1 | | 0.174 | | 64.97 | |
| 487+52.5 | 143.40 | Rt. | S-835 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 69.50 | 68.90 | 0.60 | | 48.00 | 0.041 | 5.17 | | |
| CLI4 | | | **S-842** | | | 0.00 | 6.96 | 0.00 | | | | | | | | | | 75.94 | 75.50 | 0.44 | | 42.00 | 0.181 | 4.06 | | |
| | | | | MH-8 | 244.46 | 0.00 | 0.00 | 0.00 | 18.44 | 1.00 | 5.90 | 6.61 | 0.00 | **39.03** | 0.13 | 80.00 | **4.06** | 76.50 | 75.50 | | 1 | | 0.409 | | 69.71 | |
| 489+99.50 | 124.33 | Rt. | S-840 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 73.00 | 72.00 | 1.00 | | 42.00 | 0.048 | 7.25 | | |
| CLI4 | | | **S-843** | | | 0.70 | 0.70 | 0.66 | | | | | | | | | | 79.91 | 79.75 | 0.17 | | 18.00 | 0.219 | 2.79 | | |
| | | | | BW 218 | 75.59 | 0.00 | 0.00 | 0.00 | 10.00 | 0.45 | 7.41 | 0.66 | 0.00 | **4.93** | 0.02 | 82.37 | **2.46** | 79.36 | 79.25 | | 1 | | 0.146 | | 4.34 | |
| 494+00 | 145.79 | Lt. | S-844 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 77.86 | 77.75 | 0.11 | | 18.00 | 0.150 | 2.46 | | |
| CLI4 | | | **S-844** | | | 0.73 | 1.43 | 0.69 | | | | | | | | | | 79.75 | 79.57 | 0.18 | | 24.00 | 0.288 | 3.16 | | |
| | | | | BW 217 | 62.28 | 0.00 | 0.00 | 0.00 | 10.45 | 0.33 | 7.30 | 1.36 | 0.00 | **9.92** | 0.08 | 83.21 | **3.46** | 79.75 | 79.45 | | 1 | | 0.482 | | 17.01 | |
| 494+00 | 66.70 | Lt. | S-845 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 77.75 | 77.45 | 0.30 | | 24.00 | 0.102 | 5.41 | | |
| CLI4 | | | **S-845** | | | 0.25 | 1.68 | 0.24 | | | | | | | | | | 79.57 | 79.35 | 0.22 | | 24.00 | 0.427 | 3.67 | | |
| | | | | BW 217 | 50.76 | 0.00 | 0.00 | 0.00 | 10.78 | 0.23 | 7.22 | 1.60 | 0.00 | **11.53** | 0.10 | 82.50 | **2.93** | 79.45 | 79.35 | | 1 | | 0.197 | | 10.88 | |
| 494+00 | 1.42 | Lt. | S-846 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 77.45 | 77.35 | 0.10 | | 24.00 | 0.102 | 3.46 | | |
| CLI4 | | | **S-846** | | | 0.36 | 2.04 | 0.34 | | | | | | | | | | 77.43 | 77.30 | 0.13 | | 30.00 | 0.190 | 2.83 | | |
| | | | | BW 217 | 67.24 | 0.00 | 0.00 | 0.00 | 11.01 | 0.40 | 7.17 | 1.94 | 0.00 | **13.90** | 0.06 | 83.80 | **6.37** | 77.40 | 77.30 | | 1 | | 0.149 | | 17.14 | |
| 494+00 | 52.35 | Rt. | S-847 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.90 | 74.80 | 0.10 | | 30.00 | 0.076 | 3.49 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

# FLORIDA DEPARTMENT OF TRANSPORTATION
## STORM DRAIN TABULATION FORM



Financial Prj Id: **242592-4** County: **SEMINOLE** Network: **308A** Designed by **LNW** Date: 7/18/2017
Description: **I-4 BTU SEGMENT 3** Organization **PB AMERICAS, INC.** State Road: **400 (I-4)** Checked by: **MB** Date: 7/18/2017

| LOCATION OF UPPER END / ALIGNMENT NAME / STATION | DIST | SD | STR. NO. / UPPER / LOWER | TYPE OF STR. | LEN. (ft.) | AREAS (Ac) C= 0.95 / C= 0.25 / C= 0.20 INC | TOTAL | SUB-TOTAL (C*A) | TIME OF CONC (min) | TIME OF FLOW SECT. (min) | INTEN (in/hr) | TOTAL (C*A) | BASE FLOW SUMM BASE (cfs) | TOTAL FLOW (cfs) | MINOR LOSS (ft.) | INLET ELEV. (ft.) | HGL CLEAR (ft.) | HYDRAULIC GRADE CROWN / FLOWLINE UPPER (ft.) | LOWER (ft.) | FALL (ft.) | # BR / L / S | PIPE SIZE (in.) / RISE / SPAN | SLOPE % / HGL / PHYS. MIN. | ACTUAL VEL. / PHYS. / VEL. (fps) | FULL FLOW CAP. (cfs) | NOTES & REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLI4 | | | **S-847** | | | 0.24 | 6.96 | 0.23 | | | | | | | | | | 77.24 | 76.50 | 0.74 | | 42.00 | 0.186 | 4.21 | | ZONE: 7 |
| | | | | BW 219 | 397.75 | 0.00 | 0.00 | 0.00 | 16.86 | 1.58 | 6.12 | 6.61 | 0.00 | **40.47** | 0.19 | 82.68 | **5.44** | 76.70 | 76.50 | | 1 | | 0.050 | | 24.44 | FREQ. (Yrs): 10 |
| 494+00 | 122.84 | Rt. | S-842 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 73.20 | 73.00 | 0.20 | | 42.00 | 0.048 | 2.54 | | MANNINGS n: 0.0120 |
| CLI4 | | | **S-848** | | | 0.00 | 4.68 | 0.00 | | | | | | | | | | 77.81 | 77.24 | 0.57 | | 36.00 | 0.192 | 3.97 | | |
| | | | | MH-8 | 297.39 | 0.00 | 0.00 | 0.00 | 15.61 | 1.25 | 6.31 | 4.45 | 0.00 | **28.05** | 0.12 | 84.00 | **6.19** | 76.40 | 76.20 | | 1 | | 0.067 | | 18.74 | |
| 497+00.02 | 114.45 | Rt. | S-847 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 73.40 | 73.20 | 0.20 | | 36.00 | 0.059 | 2.65 | | TAILW EL (ft): 72.71 |
| CLI4 | | | **S-849** | | | 0.65 | 0.65 | 0.62 | | | | | | | | | | 80.59 | 80.46 | 0.13 | | 18.00 | 0.193 | 2.59 | | |
| | | | | BW 217 | 67.22 | 0.00 | 0.00 | 0.00 | 10.00 | 0.43 | 7.41 | 0.62 | 0.00 | **4.58** | 0.02 | 83.57 | **2.98** | 80.56 | 80.46 | | 1 | | 0.149 | | 4.39 | |
| 500+00 | 46.52 | Rt. | S-850 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 79.06 | 78.96 | 0.10 | | 18.00 | 0.150 | 2.48 | | |
| CLI4 | | | **S-850** | | | 0.46 | 4.68 | 0.44 | | | | | | | | | | 78.44 | 77.81 | 0.63 | | 36.00 | 0.213 | 4.09 | | |
| | | | | BW 219 | 297.24 | 0.00 | 0.00 | 0.00 | 14.40 | 1.21 | 6.51 | 4.45 | 0.00 | **28.93** | 0.16 | 83.08 | **4.64** | 76.75 | 76.40 | | 1 | | 0.118 | | 24.79 | |
| 500+00 | 116.99 | Rt. | S-848 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 73.75 | 73.40 | 0.35 | | 36.00 | 0.059 | 3.51 | | |
| CLI4 | | | **S-851** | | | 0.00 | 3.57 | 0.00 | | | | | | | | | | 78.83 | 78.44 | 0.38 | | 36.00 | 0.129 | 3.25 | | |
| | | | | MH-8 | 297.21 | 0.00 | 0.00 | 0.00 | 12.88 | 1.52 | 6.78 | 3.39 | 0.00 | **23.00** | 0.08 | 82.00 | **3.17** | 76.95 | 76.75 | | 1 | | 0.067 | | 18.74 | |
| 502+99.84 | 108.64 | Rt. | S-850 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 73.95 | 73.75 | 0.20 | | 36.00 | 0.059 | 2.65 | | |
| CLI4 | | | **S-852** | | | 1.00 | 1.00 | 0.95 | | | | | | | | | | 79.60 | 79.57 | 0.03 | | 30.00 | 0.033 | 1.43 | | |
| | | | | BW 218 | 77.38 | 0.00 | 0.00 | 0.00 | 10.00 | 0.64 | 7.41 | 0.95 | 0.00 | **7.04** | 0.01 | 80.75 | **1.15** | 77.05 | 76.95 | | 1 | | 0.129 | | 15.97 | |
| 505+85 | 128.23 | Lt. | S-853 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.55 | 74.45 | 0.10 | | 30.00 | 0.076 | 3.25 | | |
| CLI4 | | | **S-853** | | | 1.25 | 2.25 | 1.19 | | | | | | | | | | 79.57 | 79.39 | 0.18 | | 30.00 | 0.214 | 3.16 | | |
| | | | | BW 217 | 84.30 | 0.00 | 0.00 | 0.00 | 10.64 | 0.44 | 7.25 | 2.14 | 0.00 | **15.51** | 0.08 | 81.58 | **2.01** | 76.95 | 76.85 | | 1 | | 0.119 | | 15.30 | |
| 505+85 | 47.35 | Lt. | S-854 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.45 | 74.35 | 0.10 | | 30.00 | 0.076 | 3.12 | | |
| CLI4 | | | **S-854** | | | 0.65 | 2.90 | 0.62 | | | | | | | | | | 79.39 | 79.28 | 0.11 | | 36.00 | 0.164 | 2.79 | | |
| | | | | BW 217 | 67.19 | 0.00 | 0.00 | 0.00 | 11.09 | 0.40 | 7.15 | 2.76 | 0.00 | **19.71** | 0.06 | 81.27 | **1.88** | 77.35 | 77.25 | | 1 | | 0.149 | | 27.88 | |
| 505+85 | 40.95 | Rt. | S-855 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.35 | 74.25 | 0.10 | | 36.00 | 0.059 | 3.94 | | |
| CLI4 | | | **S-855** | | | 0.67 | 3.57 | 0.64 | | | | | | | | | | 79.28 | 78.83 | 0.45 | | 36.00 | 0.161 | 3.39 | | |
| | | | | BW 219 | 282.65 | 0.00 | 0.00 | 0.00 | 11.49 | 1.39 | 7.06 | 3.39 | 0.00 | **23.96** | 0.14 | 81.11 | **1.83** | 77.25 | 76.95 | | 1 | | 0.106 | | 23.54 | |
| 505+85 | 111.39 | Rt. | S-851 | | | 0.00 | 0.00 | 0.00 | | | | | 0.00 | | | | | 74.25 | 73.95 | 0.30 | | 36.00 | 0.059 | 3.33 | | |

**Units: ENGLISH**

**HGL method: Standard FDOT (Jump HGL to pipe crown).**

Automated Storm sewer Analysis & Design (ASAD), copyright 1992-2007, Hiteshew Engineering Systems, Inc. Ph: (352) 383-4191
Portions of ASAD were developed by Kenneth J. Leeming, P.E. at International Engineering Consultants, Inc.

Basin 308
Stormsewer Tailwater - 10-YR. / 240-HR. (No Orifice & Initial Stage set at the Weir Elevation)
Stage at Peak Inflow

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| 010Y240H | Pond 308 | BASIN308 | 182.01 | 55.97 | 57.10 | 140931 | 22.25 | 9.57 | 22.80 | 19.65 |
| 010Y240H | Pond 308 | BASIN308 | 182.09 | 56.00 | 57.10 | 141166 | 22.28 | 9.87 | 22.96 | 19.72 |
| 010Y240H | Pond 308 | BASIN308 | 182.17 | 56.02 | 57.10 | 141373 | 22.30 | 10.14 | 23.10 | 19.78 |
| 010Y240H | Pond 308 | BASIN308 | 182.25 | 56.05 | 57.10 | 141598 | 22.32 | 10.44 | 23.26 | 19.85 |
| 010Y240H | Pond 308 | BASIN308 | 182.34 | 56.07 | 57.10 | 141817 | 22.35 | 10.73 | 23.42 | 19.93 |
| 010Y240H | Pond 308 | BASIN308 | 182.42 | 56.10 | 57.10 | 142031 | 22.37 | 11.02 | 23.57 | 20.01 |
| 010Y240H | Pond 308 | BASIN308 | 182.50 | 56.12 | 57.10 | 142219 | 22.39 | 11.28 | 23.72 | 20.08 |
| 010Y240H | Pond 308 | BASIN308 | 182.59 | 56.14 | 57.10 | 142423 | 22.41 | 11.56 | 23.87 | 20.16 |
| 010Y240H | Pond 308 | BASIN308 | 182.67 | 56.17 | 57.10 | 142622 | 22.43 | 11.83 | 24.03 | 20.24 |
| 010Y240H | Pond 308 | BASIN308 | 182.76 | 56.19 | 57.10 | 142816 | 22.45 | 12.11 | 24.19 | 20.32 |
| 010Y240H | Pond 308 | BASIN308 | 182.84 | 56.21 | 57.10 | 143006 | 22.47 | 12.37 | 24.35 | 20.41 |
| 010Y240H | Pond 308 | BASIN308 | 182.92 | 56.23 | 57.10 | 143167 | 22.49 | 12.60 | 24.49 | 20.49 |
| 010Y240H | Pond 308 | BASIN308 | 183.00 | 56.25 | 57.10 | 143348 | 22.51 | 12.86 | 24.65 | 20.58 |
| 010Y240H | Pond 308 | BASIN308 | 183.09 | 56.27 | 57.10 | 143524 | 22.53 | 13.11 | 24.80 | 20.67 |
| 010Y240H | Pond 308 | BASIN308 | 183.17 | 56.29 | 57.10 | 143695 | 22.55 | 13.36 | 24.96 | 20.76 |
| 010Y240H | Pond 308 | BASIN308 | 183.25 | 56.31 | 57.10 | 143847 | 22.57 | 13.58 | 25.11 | 20.85 |
| 010Y240H | Pond 308 | BASIN308 | 183.34 | 56.33 | 57.10 | 144025 | 22.59 | 13.84 | 25.28 | 20.95 |
| 010Y240H | Pond 308 | BASIN308 | 183.42 | 56.35 | 57.10 | 144174 | 22.60 | 14.06 | 25.43 | 21.05 |
| 010Y240H | Pond 308 | BASIN308 | 183.50 | 56.36 | 57.10 | 144319 | 22.62 | 14.28 | 25.58 | 21.14 |
| 010Y240H | Pond 308 | BASIN308 | 183.58 | 56.38 | 57.10 | 144460 | 22.64 | 14.49 | 25.73 | 21.23 |
| 010Y240H | Pond 308 | BASIN308 | 183.68 | 56.40 | 57.10 | 144621 | 22.66 | 14.73 | 25.91 | 21.35 |
| 010Y240H | Pond 308 | BASIN308 | 183.76 | 56.41 | 57.10 | 144756 | 22.67 | 14.93 | 26.06 | 21.45 |
| 010Y240H | Pond 308 | BASIN308 | 183.84 | 56.43 | 57.10 | 144887 | 22.69 | 15.13 | 26.21 | 21.54 |
| 010Y240H | Pond 308 | BASIN308 | 183.92 | 56.44 | 57.10 | 145015 | 22.70 | 15.32 | 26.36 | 21.65 |
| 010Y240H | Pond 308 | BASIN308 | 184.01 | 56.46 | 57.10 | 145165 | 22.65 | 15.55 | 26.54 | 21.77 |
| 010Y240H | Pond 308 | BASIN308 | 184.10 | 56.47 | 57.10 | 145286 | 22.14 | 15.73 | 26.69 | 21.88 |
| 010Y240H | Pond 308 | BASIN308 | 184.18 | 56.49 | 57.10 | 145387 | 20.76 | 15.88 | 26.84 | 21.99 |
| 010Y240H | Pond 308 | BASIN308 | 184.26 | 56.49 | 57.10 | 145456 | 18.87 | 15.96 | 26.97 | 22.09 |
| 010Y240H | Pond 308 | BASIN308 | 184.35 | 56.50 | 57.10 | 145492 | 17.12 | 15.99 | 27.10 | 22.20 |
| 010Y240H | Pond 308 | BASIN308 | 184.43 | 56.50 | 57.10 | 145499 | 15.71 | 15.96 | 27.21 | 22.31 |
| 010Y240H | Pond 308 | BASIN308 | 184.51 | 56.50 | 57.10 | 145485 | 14.60 | 15.90 | 27.32 | 22.42 |
| 010Y240H | Pond 308 | BASIN308 | 184.60 | 56.49 | 57.10 | 145455 | 13.71 | 15.81 | 27.41 | 22.53 |
| 010Y240H | Pond 308 | BASIN308 | 184.68 | 56.49 | 57.10 | 145412 | 12.97 | 15.71 | 27.51 | 22.64 |
| 010Y240H | Pond 308 | BASIN308 | 184.76 | 56.48 | 57.10 | 145358 | 12.33 | 15.59 | 27.59 | 22.75 |
| 010Y240H | Pond 308 | BASIN308 | 184.85 | 56.48 | 57.10 | 145297 | 11.77 | 15.45 | 27.68 | 22.86 |
| 010Y240H | Pond 308 | BASIN308 | 184.93 | 56.47 | 57.10 | 145228 | 11.29 | 15.31 | 27.76 | 22.96 |

Basin 308A
Stormsewer Tailwater - 10-YR. / 240-HR. (No Orifice & Initial Stage set at the Weir Elevation)
Stage at Peak Inflow

| Simulation | Node | Group | Time hrs | Stage ft | Warning Stage ft | Surface Area ft2 | Total Inflow cfs | Total Outflow cfs | Total Vol In af | Total Vol Out af |
|---|---|---|---|---|---|---|---|---|---|---|
| 010Y240H | Pond 308A | BASIN308 | 182.01 | 72.67 | 73.00 | 104963 | 8.94 | 8.28 | 11.58 | 10.14 |
| 010Y240H | Pond 308A | BASIN308 | 182.09 | 72.68 | 73.00 | 104973 | 8.94 | 8.30 | 11.64 | 10.20 |
| 010Y240H | Pond 308A | BASIN308 | 182.17 | 72.68 | 73.00 | 104981 | 8.95 | 8.31 | 11.70 | 10.26 |
| 010Y240H | Pond 308A | BASIN308 | 182.25 | 72.68 | 73.00 | 104990 | 8.95 | 8.33 | 11.76 | 10.31 |
| 010Y240H | Pond 308A | BASIN308 | 182.34 | 72.68 | 73.00 | 104999 | 8.96 | 8.35 | 11.83 | 10.37 |
| 010Y240H | Pond 308A | BASIN308 | 182.42 | 72.68 | 73.00 | 105008 | 8.96 | 8.37 | 11.89 | 10.43 |
| 010Y240H | Pond 308A | BASIN308 | 182.50 | 72.68 | 73.00 | 105016 | 8.96 | 8.38 | 11.95 | 10.49 |
| 010Y240H | Pond 308A | BASIN308 | 182.59 | 72.69 | 73.00 | 105024 | 8.97 | 8.40 | 12.01 | 10.54 |
| 010Y240H | Pond 308A | BASIN308 | 182.67 | 72.69 | 73.00 | 105033 | 8.97 | 8.41 | 12.07 | 10.60 |
| 010Y240H | Pond 308A | BASIN308 | 182.76 | 72.69 | 73.00 | 105041 | 8.97 | 8.43 | 12.14 | 10.66 |
| 010Y240H | Pond 308A | BASIN308 | 182.84 | 72.69 | 73.00 | 105049 | 8.98 | 8.45 | 12.20 | 10.72 |
| 010Y240H | Pond 308A | BASIN308 | 182.92 | 72.69 | 73.00 | 105055 | 8.98 | 8.46 | 12.26 | 10.77 |
| 010Y240H | Pond 308A | BASIN308 | 183.00 | 72.69 | 73.00 | 105063 | 8.99 | 8.47 | 12.32 | 10.83 |
| 010Y240H | Pond 308A | BASIN308 | 183.09 | 72.70 | 73.00 | 105070 | 8.99 | 8.49 | 12.38 | 10.89 |
| 010Y240H | Pond 308A | BASIN308 | 183.17 | 72.70 | 73.00 | 105078 | 8.99 | 8.50 | 12.45 | 10.95 |
| 010Y240H | Pond 308A | BASIN308 | 183.25 | 72.70 | 73.00 | 105084 | 9.00 | 8.51 | 12.50 | 11.01 |
| 010Y240H | Pond 308A | BASIN308 | 183.34 | 72.70 | 73.00 | 105092 | 9.00 | 8.53 | 12.57 | 11.07 |
| 010Y240H | Pond 308A | BASIN308 | 183.42 | 72.70 | 73.00 | 105098 | 9.00 | 8.54 | 12.63 | 11.13 |
| 010Y240H | Pond 308A | BASIN308 | 183.50 | 72.70 | 73.00 | 105105 | 9.01 | 8.55 | 12.69 | 11.19 |
| 010Y240H | Pond 308A | BASIN308 | 183.58 | 72.70 | 73.00 | 105111 | 9.01 | 8.57 | 12.75 | 11.24 |
| 010Y240H | Pond 308A | BASIN308 | 183.68 | 72.71 | 73.00 | 105118 | 9.01 | 8.58 | 12.82 | 11.31 |
| 010Y240H | Pond 308A | BASIN308 | 183.76 | 72.71 | 73.00 | 105124 | 9.02 | 8.59 | 12.88 | 11.37 |
| 010Y240H | Pond 308A | BASIN308 | 183.84 | 72.71 | 73.00 | 105129 | 9.02 | 8.60 | 12.94 | 11.42 |
| 010Y240H | Pond 308A | BASIN308 | 183.92 | 72.71 | 73.00 | 105135 | 9.02 | 8.61 | 13.00 | 11.48 |
| 010Y240H | Pond 308A | BASIN308 | 184.01 | 72.71 | 73.00 | 105142 | 8.99 | 8.62 | 13.07 | 11.55 |
| 010Y240H | Pond 308A | BASIN308 | 184.10 | 72.71 | 73.00 | 105145 | 8.66 | 8.63 | 13.13 | 11.61 |
| 010Y240H | Pond 308A | BASIN308 | 184.18 | 72.71 | 73.00 | 105140 | 7.76 | 8.62 | 13.19 | 11.67 |
| 010Y240H | Pond 308A | BASIN308 | 184.26 | 72.71 | 73.00 | 105118 | 6.51 | 8.58 | 13.24 | 11.73 |
| 010Y240H | Pond 308A | BASIN308 | 184.35 | 72.70 | 73.00 | 105081 | 5.40 | 8.50 | 13.28 | 11.79 |
| 010Y240H | Pond 308A | BASIN308 | 184.43 | 72.69 | 73.00 | 105031 | 4.58 | 8.40 | 13.31 | 11.84 |
| 010Y240H | Pond 308A | BASIN308 | 184.51 | 72.68 | 73.00 | 104973 | 3.97 | 8.28 | 13.34 | 11.90 |
| 010Y240H | Pond 308A | BASIN308 | 184.60 | 72.66 | 73.00 | 104908 | 3.50 | 8.15 | 13.37 | 11.96 |
| 010Y240H | Pond 308A | BASIN308 | 184.68 | 72.65 | 73.00 | 104840 | 3.12 | 8.00 | 13.39 | 12.01 |
| 010Y240H | Pond 308A | BASIN308 | 184.76 | 72.64 | 73.00 | 104768 | 2.81 | 7.85 | 13.41 | 12.07 |
| 010Y240H | Pond 308A | BASIN308 | 184.85 | 72.62 | 73.00 | 104695 | 2.57 | 7.69 | 13.43 | 12.12 |
| 010Y240H | Pond 308A | BASIN308 | 184.93 | 72.61 | 73.00 | 104621 | 2.37 | 7.52 | 13.45 | 12.17 |

Existing Permits

ERP # 22124-2

Florida Department
of
Environmental Protection,
Delegated Water Management District,
and
U.S. Army Corps of Engineers

Datum = NAVD 88

# JOINT APPLICATION
# For
# Environmental Resource Permit
# and
# Section 404 Dredge and Fill Permit

For

# SR 400 (I-4) WIDENING

## (From West of Lake Mary Blvd. to West of SR 15/600)

## The Florida Department of Transportation

Seminole County, Florida
FPID: 242598-1-52-01
W.P.I. No. 5148847

Prepared by:
HDR ENGINEERING, INC.

HDR

SEPTEMBER 2001

RECEIVED
SEP 12 2001
PDS
ORLANDO
SJR WMD

Datum = NAVD 88

# TABLE OF CONTENTS

PART 1: ERP APPLICATION FORMS A, C, & E

PART 2: ENVIRONMENTAL NARRATIVE AND APPENDICES


| NARRATIVE SECTION | | PAGE NO. |
|---|---|---|
| 1.0 | INTRODUCTION | 1 |
| 2.0 | PROJECT SITE LOCATION | 1 |
| 3.0 | NEED FOR PROJECT | 1 |
| 4.0 | REGULATORY AGENCY COORDINATION | 1 |
| 5.0 | PROJECT SOILS DESCRIPTIONS | 4 |
| 6.0 | WILDLIFE HABITAT ANC CULTURAL RESOURCES | 4 |
| 7.0 | DESCRIPTIONS OF WETLANDS AND SURFACE WATERS | 7 |
| 8.0 | IMPACT AVOIDANCE AND MINIMIZATION | 9 |
| 9.0 | PROJECT IMPACTS | 10 |
| 10.0 | EROSION AND SEDIMENTATION CONTROL | 10 |
| 11.0 | PROPOSED MITIGATION | 10 |


# LIST OF FIGURES


| Figure No. | | Page No. |
|---|---|---|
| Figure 1 | Project Location | 2 |
| Figure 2 | Project Construction Limits | 3 |
| Figure 3 | Project Soils Map (Sheet 1 of 2) | 5 |
| Figure 4 | Project Soils Map (Sheet 2 of 2) | 6 |

Datum = NAVD 88

## APPENDICES


**APPENDIX A:** WETLAND AND SURFACE WATER AERIAL DELINEATIONS

**APPENDIX B:** IMPACT PLAN VIEWS AND CROSS SECTIONS


## ENCLOSURES


**ENCLOSURE 1:** PERMIT APPLICATION DOCUMENTATION REPORT (DRAINAGE DESIGN)

**ENCLOSURE 2:** 11" x 17" DESIGN PLANS

Datum = NAVD 88

## BASIN 3

This basin is comprised of two sub-basins which both discharge to the Heathrow property, which is considered a land-locked or closed basin. The proposed pond site will maintain this drainage pattern by discharging to the International Parkway storm sewer system. The proposed stormwater management pond has been designed to store the water quality and attenuation needs of this project.

Portions of this basin are located in the Wekiva River Hydrologic Basin Most Effective Recharge Area. This area is legally represented as that portion of the project that lies west of the centerline of Interstate-4. This criteria requires that a volume equivalent to three (3) inches times the impervious area, within SCS Type "A" soils in the Most Effective Recharge Area, be recovered within 14 days. Recovery calculations indicate that draw-down of this volume occurs within the 14-day requirement.

Water Quality Volume calculations have been performed and this volume is provided in the pond site. A control structure has been designed to retain this volume and therefore has been set above the water quality volume elevation. This volume is recovered within the 72-hour requirement.

This basin is designed with closed-basin pond criteria. From a volume standpoint, the design storm is the 25-year 96-hour storm event with the SJRWMD-96 rainfall distribution. From a stage and flow rate standpoint, the design storm is the 25-year 24-hour storm event with the SCS Type II rainfall distribution. Both of these storm events were evaluated. To meet closed basin requirements, a control structure was designed for the pond with a slot set at the elevation required to retain the volumetric difference between the pre- and post-development 25-year 96-hour hydrographs.

The Pond-3 site has been designed as a dry pond. The tailwater for this stormwater management system is set at the crown of pipe of the proposed pond outfall pipe at the tie in to the existing Heathrow storm sewer system. Coordination of the storm sewer tie-in with Pizutti, developers of Heathrow, has taken place. The ultimate outfall of this system is the Heathrow development.

The system was modeled using AdICPR 2.20. Results from the routed model are provided on the table below. Post-Development flow rates and volumes do not exceed pre-development for the design storms evaluated. Thus, no impacts to the Heathrow system are anticipated with the design of this project.

Basin 3 Pre-Post Comparison

| | Pre | Post |
|---|---|---|
| Q – 25Y24H (cfs) | 47.05 | 11.59 |
| Volume – 25Y96H (ac-ft) | 24.05 | 23.57 |
| Stage – 25Y96H (ft) | N/A | 54.61 |

Datum = NAVD 88


# Basin 3 – Post Development


Job No. | No.

# HDR Computation

Datum = NAVD 88

| | | | |
|---|---|---|---|
| Project I-4/Lake Mary | Computed GTP | Date 7/9/2001 |
| Subject Basin 3 | Checked [illegible] | Date 9-6-01 |
| Task Post Development Node Diagram | Sheet 1 | Of 1 |






Post Basin 3
Scale 1:4000

/2009 08:44:02 AM H:\Hillsmry\dr\nop\postbasinexhibits.dgn

Advanced Interconnected Channel & Pond Routing (ICPR Ver 2.20) [1]
Copyright 1995, Streamline Technologies, Inc.

I-4 WIDENING: LAKE MARY BLVD TO US 17/92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01; 10:2 am

Datum = NAVD 88

********** Node Maximum Conditions - 25Y24H **********

(Time units - hours)

| Node Name | Group Name | Max Time Conditions | Max Stage (ft) | Warning Stage (ft) | Max Delta Stage (ft) | Max Surface Area (sf) | Max Time Inflow | Max Inflow (cfs) | Max Time Outflow | Max Outflow (cfs) |
|---|---|---|---|---|---|---|---|---|---|---|
| OUTFALL3 | BASE | 0.00 | 49.95 | 49.95 | 0.0000 | 0.00 | 17.04 | 11.59 | 0.00 | 0.00 |
| POND-3 | BASE | 17.04 | 54.61 | 57.75 | 0.0139 | 142167.95 | 12.76 | 55.88 | 17.04 | 11.59 |

(16.65m) ← 24 hr Post Stage

24 hr Post Q

4.15

10-99

Copyright 1995, Streamline Technologies, Inc.

I-4 WIDENING: LAKE MARY BLVD. TO US 17-92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01; 10:3 am

Datum = NAVD 88

********** Node Time Series by Node - 25Y96H **********

| Time (hrs) | Stage (ft) | Surface Ar.(ac) | Inflow Base Q (cfs) | Inflow Onsite (cfs) | Inflow Offsite (cfs) | Inflow Bndry Q (cfs) | Inflow Link Q (cfs) | Link Outflow (cfs) | Cumulative Volume In (ac.ft) | Cumulative Volume Out (ac.ft) |
|---|---|---|---|---|---|---|---|---|---|---|
| *** Group: BASE | | Node: OUTFALL3 | | | | | | | | |
| 199.059 | 49.95 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.00 | 23.5709 | 0.0000 |
| 199.309 | 49.95 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.00 | 23.5710 | 0.0000 |
| 199.559 | 49.95 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.00 | 23.5711 | 0.0000 |
| 199.809 | 49.95 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.00 | 23.5712 | 0.0000 |
| 200.018 | 49.95 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.00 | 23.5713 | 0.0000 |
| *** Group: BASE | | Node: POND-3 | | | | | | | | |
| 199.059 | 53.16 | 2.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 28.9738 | 23.5709 |
| 199.309 | 53.16 | 2.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 28.9738 | 23.5710 |
| 199.559 | 53.16 | 2.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 28.9738 | 23.5711 |
| 199.809 | 53.16 | 2.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 28.9738 | 23.5712 |
| 200.018 | 53.16 | 2.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 28.9738 | 23.5713 |

96hr Post Volume

4-16

8-6-01

Advanced Interconnected Channel & Pond Routing (ICPR Ver 2.20) [1]
Copyright 1995, Streamline Technologies, Inc.

a 9-6-01

I-4 WIDENING: LAKE MARY BLVD. TO US 17-92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01; 12:3 pm

Datum = NAVD 88

********** Basin Summary - 25Y24H **********

---

***

| | |
|---|---|
| Basin Name: | 3POST |
| Group Name: | BASE |
| Node Name: | POND-3 |
| Hydrograph Type: | UH |
| Unit Hydrograph: | UH323 |
| Peaking Factor: | 323.00 |
| Spec Time Inc (min): | 10.26 |
| Comp Time Inc (min): | 10.27 |
| Rainfall File: | SCSII-24 |
| Rainfall Amount (in): | 8.60 |
| Storm Duration (hr): | 24.00 |
| Status: | ONSITE |
| Time of Conc. (min): | 77.00 |
| Lag Time (hr): | 0.00 |
| Area (acres): | 61.72 |
| Vol of Unit Hyd (in): | 1.00 |
| Curve Number: | 55.00 |
| DCIA (%): | 0.00 |
| Time Max (hrs): | 12.83 |
| Flow Max (cfs): | 56.26 |
| Runoff Volume (in): | 3.20 |
| Runoff Volume (cf): | 717134 |

Advanced Interconnected Channel & Pond Routing (ICPR Ver 2.20) [1]
Copyright 1995, Streamline Technologies, Inc.

9-6-01

I-4 WIDENING: LAKE MARY BLVD. TO US 17-92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01; 12:3 pm

Datum = NAVD 88

********** Basin Summary - 25Y96H **********

---

***

| | |
|---|---|
| Basin Name: | 3POST |
| Group Name: | BASE |
| Node Name: | POND-3 |
| Hydrograph Type: | UH |
| Unit Hydrograph: | UH323 |
| Peaking Factor: | 323.00 |
| Spec Time Inc (min): | 10.26 |
| Comp Time Inc (min): | 10.27 |
| Rainfall File: | SJRWMD96 |
| Rainfall Amount (in): | 11.80 |
| Storm Duration (hr): | 96.00 |
| Status: | ONSITE |
| Time of Conc. (min): | 77.00 |
| Lag Time (hr): | 0.00 |
| Area (acres): | 61.72 |
| Vol of Unit Hyd (in): | 1.00 |
| Curve Number: | 55.00 |
| DCIA (%): | 0.00 |
| Time Max (hrs): | 60.57 |
| Flow Max (cfs): | 78.35 |
| Runoff Volume (in): | 5.63 |
| Runoff Volume (cf): | 1262005 |

Advanced Interconnected Channel & Pond Routing (ICPR Ver 2.20) [1]
Copyright 1995, Streamline Technologies, Inc.

Datum = NAVD 88

I-4 WIDENING: LAKE MARY BLVD. TO US 17-92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01; 12:4 pm

********** Input Report **********

--------Class: Node----------

Name: OUTFALL3 Base Flow(cfs): 0 Init Stage(ft): 49.95
Group: BASE Warn Stage(ft): 49.95
Comment: Outfalls to the Heathrow Development

| Time(hrs) | Stage(ft) |
|---|---|
| 0 | 49.95 |
| 300 | 49.95 |

--------Class: Node----------

Name: POND-3 Base Flow(cfs): 0 Init Stage(ft): 51.2
Group: BASE Warn Stage(ft): 57.75
Comment:

| Stage(ft) | Area(ac) |
|---|---|
| 51.2 | 2.57 |
| 56.6 | 3.67 |
| 58.1 | 4.47 |

--------Class: Basin----------

Basin: 3POST Node: POND-3 Status: On Site Type: SCS Unit Hydr
Group: BASE
Unit Hydrograph: UH323 Peak Factor: 323
Rainfall File: SCSII-24 Storm Duration(hrs): 24
Rainfall Amount(in): 8.6
Area(ac): 61.72 Concentration Time(min): 77
Curve #: 55 Time Shift(hrs): 0
DCIA(%): 0

Advanced Interconnected Channel & Pond Routing (ICPR Ver 2.20) [2]
Copyright 1995, Streamline Technologies, Inc.

Datum = NAVD 88

I-4 WIDENING: LAKE MARY BLVD. TO US 17-92
BASIN 3 POST DEVELOPMENT CALCS
07/30/01: 12:4 pm

********** Input Report **********
--------Class: Drop Structure----------
Name: OUTFALL From Node: POND-3 Length(ft): 310
Group: BASE To Node: OUTFALL3 Count: 1

Outlet Cntrl Spec: Use dc or tw Inlet Cntrl Spec: Use dn
Upstream Geometry: Circular Downstream Geometry: Circular

| | UPSTREAM | DOWNSTREAM |
|---|---|---|
| Span(in): | 30 | 30 |
| Rise(in): | 30 | 30 |
| Invert(ft): | 51.18 | 50.52 |
| Manning's N: | 0.012 | 0.012 |
| Top Clip(in): | 0 | 0 |
| Bottom Clip(in): | 0 | 0 |

Entrance Loss Coef: 1 Flow: Both
Exit Loss Coef: 0.5 Equation: Aver Conveyance

Upstream FHWA Inlet Edge Description:
Circular Concrete: Groove end projecting 1 3
Downstream FHWA Inlet Edge Description:
Circular Concrete: Groove end w/ headwall 1 2

DBI TYPE "D" TO STRAIGHT CONCRETE ENDWALL
*** Weir 1 of 2 for Drop Structure OUTFALL *** [TABLE]
Count: 1 Bottom Clip(in): 0
Type: Horiz Top Clip(in): 0
Flow: Both Weir Discharge Coef: 3.3
Geometry: Rectangular Orifice Discharge Coef: 0.6

Span(in): 37 Invert(ft): 56.75
Rise(in): 49 Control Elev(ft): 56.75

*** Weir 2 of 2 for Drop Structure OUTFALL *** [TABLE]
Count: 1 Bottom Clip(in): 0
Type: Mavis Top Clip(in): 0
Flow: Both Weir Discharge Coef: 3.3
Geometry: Rectangular Orifice Discharge Coef: 0.6

Span(in): 24 Invert(ft): 53.15
Rise(in): 43.2 Control Elev(ft): 53.15

**I-4 Widening (Lake Mary to US 17-92)**
Seminole County

Prepared by: GTP Date: 7/29/01
Checked by: CJL Date: 9-6-01

## Water Quality Treatment Volume Requirements
## Basin 3: Pond 3

Datum = NAVD 88

### Basin Parameters:

| | | | | | |
|---|---|---|---|---|---|
| Basin Area (ac) | 61.72 | (24.979 ha) | Roadway Impervious Area (ac) | 15.16 | (6.136 ha) |
| Offsite Area (ac) | 26.55 | (10.745 ha) | Composite Curve Number (CN) | 55 | |
| SHGWT | 48.2 ft | (14.700 m) | | | |

### SJRWMD Water Quality Volume Criteria:

**Wet Detention:** The greater of 1" of Runoff times the Basin Area, or the total runoff of 2.5" times the impervious Area

**Dry Retention (Off-line):** The greater of 0.5" of Runoff times the Basin Area, or the total runoff of 1.25" times the impervious Area

**Dry Retention (On-line):** The greater of 1" of Runoff times the Basin Area, or the total runoff of 1.25" times the impervious Area plus an additional 0.5" of runoff times the Basin Area

**Pond Treatment Method:** Dry Retention (On-line)

### WQV Calculation:

| | | |
|---|---|---|
| 1"of Runoff times Basin Area= | **5.14 ac-ft** | **Control** |
| 1.25" times the Impervious Area plus 0.5" of Runoff times the Basin Area= | **4.15 ac-ft** | |

### Wekiva Basin Most Effective Recharge Area:

**Volume Requirement:** 3" of Runoff times the Impervious Area of Hydrologic Group "A" Soils Located West of the I-4 Centerline.

Impervious Area of Group A soils West of the I-4 Centerline: 6.37 ac (2.578 ha)

3"of Runoff times above Impervious Area= **1.59 ac-ft**

### Treatment Pond Stage-Area-Storage Relationship:

| | Stage | | Area | | Incremental Storage | Cumulative Storage |
|---|---|---|---|---|---|---|
| | ft | M | ac | ha | ac-ft | ac-ft |
| **Pond Bottom** | 51.2 | 15.60 | 2.57 | 1.040 | 0.00 | 0.00 |
| **Low Berm** | 56.6 | 17.25 | 3.67 | 1.487 | 16.90 | 16.90 |
| **Maintenance Berm** | 58.1 | 17.70 | 4.47 | 1.808 | 6.01 | 22.91 |

Water Quality Volume Required = **5.14 ac- ft** @ **52.83 ft**
Water Quality Volume Provided= **6.15 ac- ft** @ **53.15 ft** (16.200 m) **OK**

**I-4 Widening (Lake Mary to US 17-92)**
Seminole County

Prepared by: GTP Date: 7/29/01
Checked by: CJL Date: 9-6-01

## Recovery Calculations for Water Quality / Wekiva Basin Most Effective Recharge Area Volumes

Datum = NAVD 88

**Basin 3**

| | | | | |
|---|---|---|---|---|
| Boring # AB-13 | | | Water Quality Volume = | 6.15 ac-ft |
| Void Ratio: | 0.32 | | Recharge Volume = | 1.59 ac-ft |
| S.H.W.T. (ft)= | 48.2 | (14.700 m) | **Permeability Rate :** | |
| Pond Bottom (ft)= | 51.2 | (15.600 m) | k = | 8 in/hr |
| Unsaturated Storage | | | FS = | 2 |
| Volume Available (ac-ft)= | 2.43 | | | |

**Proposed Pond Elevation - Infiltration Relationship**

| | ELEVATION | | AREA | | INFILTRATION | |
|---|---|---|---|---|---|---|
| | (English) ft | (Metric) m | (English) ac | (Metric) ha | (English) ft3/sec | (Metric) m3/sec |
| Pond Bottom | 51.2 | 15.60 | 2.57 | 1.040 | 20.56 | 0.582 |
| | 56.6 | 17.25 | 3.67 | 1.487 | 29.40 | 0.832 |
| | 58.1 | 17.70 | 4.47 | 1.808 | 35.74 | 1.011 |

**Darcy Equation:**

$Q = KIA/FS$

Where Q = Flow Rate (cfs)
or Required Volume (cf) Divided by Time (sec)
K = Permeability Rate (in/hr)
I = Hydraulic Gradient (Use a gradient of 1)
A = Area of Pond Bottom (ac)

### I. Recovery of Water Quality Treatment Volume

$$\text{Time} = \frac{\text{Water Quality Volume}}{\text{KIA}} =$$ **3.6 hrs** << 72 hours **OK**

Designed as Dry Retention Pond. Water Quality Treatment Volume Must be Recovered within 72 Hours.

### II. Recovery of Wekiva Basin Most Effective Recharge Area Volume

$$\text{Time} = \frac{\text{Most Effective Recharge Volume x Safety Factor}}{\text{KIA}}$$

$$=$$ **0.1 days** << 14 days **OK**

Wekiva Basin Most Effective Recharge Area Volume Must be Recovered within 14 Days

Prepared by: GTP Date: 7/30/01
Checked by: CJL Date: 9-6-01

# SKIMMER BLADE DESIGN
## Pond 3 Outfall

Datum = NAVD 88

SKIMMER BLADE WILL BE ATTACHED AROUND THE PERIMETER OF THE CONTROL BOX WITH THE BOTTOM OF THE BLADE LOCATED 6" BELOW THE CONTROL ELEVATION **53.1 ft** (16.200 m) AND THE TOP OF BLADE LOCATED 6" ABOVE THE DESIGN HIGH WATER ELEVATION (25 YR 96 HR) **54.60 ft** (16.642 m)

| | | |
|---|---|---|
| TOP OF SKIMMER ELEV | **55.1 ft** | (16.794 m) |
| BOTTOM OF SKIMMER EL | **52.6 ft** | (16.048 m) |

## 1) CALCULATION OF SEPARATION BETWEEN SKIMMER & CONTROL BOX (D1)

ASSUMING FLOW UNDER BLADE ACTS AS FLOW THROUGH AN ORIFICE:


$A_{req'c} = Q / ( C \times \text{sqrt} (2 \times g \times H))$

Where:

C = 0.6 (Orifice coefficient)
$A_{req'c}$ = Area between skimmer and control box
$D1_{req'c}$ = distance between skimmer and control box
= $A_{req'c} / (Lc + 2Wc)$
Lc,Wc = control structure inside length & width
g = 32.2 ft/sec*sec
**H = 0.2 ft (allowable head difference)**
P = inside perimeter of control box = Lc (Weir - one side only)
Q = design peak flow rate

| INPUT INFORMATION | |
|---|---|
| Q (cfs) | 11.6 |
| Lc (feet) | 4.1 |
| Wc (feet) | 3.1 |

| OUTPUT INFORMATION | |
|---|---|
| P (feet) | 5.4 |
| $A_{req'c}$ (sq. ft) | 5.4 |
| $D1_{req'c}$ (ft) | 1.0 |
| D1 (min) (ft) | 1.0 |
| D1 (design) (ft) | **1.0** |




**Type "D" DBI**

**PLAN VIEW**

Prepared by: GTP Date: 7/30/01
Checked by: CJL Date: 9-6-01

## 2) CALCULATION OF SEPARATION BETWEEN SKIMMER & POND BOTTOM (D2)

Datum = NAVD 88

ASSUMING FLOW UNDER BLADE ACTS AS FLOW THROUGH AN ORIFICE:


$A_{req'c} = Q / ( C \times \text{sqrt} (2 \times g \times H))$

Where:

C = 0.6 (Orifice coefficient)
$A_{req'c}$ = Area between skimmer and pond bottom
$D2_{req'c}$ = distance between skimmer and pond bottom
= $A_{req'c} / (Lc + 2Wc)$
Lc,Wc = control structure inside length & width
g = 32.2 ft/sec*sec
**H = 0.2 ft (allowable head difference)**
Q = design peak flow rate

| INPUT INFORMATION | |
|---|---|
| Q (cfs) | 11.6 |
| Lc (feet) | 4.1 |
| Wc (feet) | 3.1 |

| OUTPUT INFORMATION | |
|---|---|
| P (feet) | 7.4 |
| $A_{req'c}$ (sq. ft) | 5.4 |
| $D2_{req'd}$ (ft) | 0.7 |
| D2 (min) (ft) | 1.0 |
| D2 (design) (ft) | **1.0** |




**CROSS SECTION VIEW**

## WORKSHEET 2: Runoff curve number and runoff

Datum = NAVD 88

Project: I-4 Widening (Lake Mary to US 17-92) By: GTP Date: 7/28/2001
Location: SEMINOLE COUNTY Checked: W Date: 9-6-01

Circle One: Present (Developed) **Basin 3**

1. Runoff curve number (CN)

| Soil name and hydrologic group (appendix A) | Cover description (cover type, treatment, and hydrologic condition, percent impervious area ratio) | CN [1] Table 2-2 | Fig 2-3 | Fig 2-4 | Area ☑ acres ☐ mi² ☐ % | | |
|---|---|---|---|---|---|---|---|
| Soil # 2 Group C | Fair Grassland | 79 | | | 0.38 | 30.06 | (0.154 ha) |
| Soil # 6, 7, 8, 31 Group A | Fair Grassland | 49 | | | 15.46 | 757.71 | (6.258 ha) |
| Soil # 10 Group B/D | Fair Grassland Assume Group C | 79 | | | 4.17 | 329.12 | (1.686 ha) |
| Impervious Roadway | | 98 | | | 15.16 | 1485.88 | (6.136 ha) |
| Soil # 6, 7, 31 Group A | Meadow (Offsite) | 30 | | | 26.55 | 796.53 | (10.745 ha) |
| | | | | | | | |
| [1] Use only one CN source per line. | | Totals = | | | 61.72 | 3399.31 | 24.979 ha |

CN (weighted) = total product/total area = 3399.31 / 61.72 = 55.07 Use CN = 55

## WORKSHEET 3: Time of Concentration (Tc) or Travel Time (Tt)

Datum = NAVD 88

Project: I-4 Widening (Lake Mary to US 17-92) By: GTP Date: 7/28/2001
Location: SEMINOLE COUNTY Checked: [illegible] Date: 7-6-01

Circle One: Present **Developed** Basin 3
Station 146+00 to Station 159+75 (median)

Circle One: **$T_c$** $T_t$ through subarea

NOTES: Space for as many as two segments per flow type can be used for each worksheet.
Include a map, schematic, or description of flow segments.

| Sheet flow (Applicable to $T_c$ only) | Segment ID | | | |
|---|---|---|---|---|
| 1. Surface Description (table 3-1.) | - | | | |
| 2. Manning's roughness coeff., n (table3-1.) | - | | | |
| 3. Flow length, L (total L <= 300 ft.) ft | - | | | |
| 4. Two-yr 24-hr rainfall, $P_2$ in | - | | | |
| 5. Land slope, s ft/ft | - | | | |
| 6. $T_t = \frac{0.007\ (nL)^{0.8}}{P_2^{0.5}\ s^{0.4}}$ Compute T...hr | Assume 0.170 | + | | = 0.17 |


| Shallow concentrated flow | Segment ID | | | |
|---|---|---|---|---|
| 7. Surface Description (paved or unpaved) | AB | | | |
| 8. Flow length, L ft | unpaved | | | |
| 9. Watercourse slope, s ft/ft | 4512 | | | |
| 10. Average velocity, V (figure 3-1) ft/s | 0.0048 | | | |
| 11. $T_t = \frac{L}{3600\ V}$ Compute $T_t$ .....hr | 1.12 | | | |
| | 1.120 | + | | = 1.12 |

| Channel flow | Segment ID | | | |
|---|---|---|---|---|
| 12. Cross sectional flow area, a ft$^2$ | | | | |
| 13. Wetted perimeter, $P_w$ ft/ft | | | | |
| 14. Hydraulic radius, $r = a/P_w$ Compute r ft | | | | |
| 15. Channel slope, s ft/ft | | | | |
| 16. Manning's roughness coeff., n | | | | |
| 17. $V = 1.49\ r^{2/3}\ s^{1/2}/n$ Compute V ft/s | | | | |
| 18. Flow length, L ft | | | | |
| 19. $T_t = L / 3600\ V$ Compute T hr | | + | | = 0.00 |
| 20. Watershed or subarea $T_c$ or $T_t$ (add $T_t$ in steps 6, 11, and 19) hr | | | | 1.29 |

77 minutes


4-26

Datum = NAVD 88



Datum = NAVD 88


| FINANCIAL PROJECT ID | SHEET NO. |
|---|---|
| 242598-1-52-01 | |





PLAN VIEW
N.T.S.

| | POND | 2 | 3 |
|---|---|---|---|
| | STRUCTURE | S-205 | S-310 |
| | STATION | 142+00.000 | 148+14.000 |
| | OFFSET | 56.80 | 56.40 |
| | SIDE | RT. | RT. |
| | INLET TYPE | D | D |
| "A" | SKIMMER TOP EL. | 16.96 | 16.79 |
| "B" | GRATE EL. | 17.35 | 17.30 |
| "C" | WEIR SLOT EL. | 16.10 | 16.20 |
| "D" | SKIMMER BOTTOM EL. | 15.94 | 16.04 |
| "E" | SKIMMER OFFSET (mm) | 300 | 300 |
| "F" | WEIR WIDTH (mm) | 305 | 610 |
| "G" | PIPE F.L. | 14.50 | 15.60 |
| "H" | PIPE SIZE | 600 | 750 |
| "I" | LOW BERM EL. | 17.20 | 17.25 |
| "J" | SKIMMER CLEARANCE | 300 | 300 |

NOTE: THE 100mm CONCRETE DITCH PAVEMENT SHALL INCLUDE 150x150, No. 10 WELDED WIRE FABRIC. PAYMENT OF THE WELDED WIRE FABRIC AND 5 mm FIBERGLASS SKIMMER SHALL BE INCLUDED IN THE UNIT PRICE OF DITCH BOTTOM INLET.




SECTION A-A
N.T.S.




SECTION B-B
N.T.S.

4-28

| REVISIONS | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |


HDR ENGINEERING, INC.
12015 ORLANDO AVENUE, SUITE 200
WINTER PARK, FLORIDA 32789
PE LICENSE NUMBER: 51288



FLORIDA DEPARTMENT OF TRANSPORTATION

# CONTROL STRUCTURE DETAILS S.R. 400 (I-4)

09/05/2004 09:05:55 AM h:\14\mkr\drainage\pond structrd3.dgn

Basin 317D

- Basin Maps
- Basin and Pond Calculations
- Basin and Pond Routing (ICPR)
  - Pre-Development
  - Post-Development




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |



MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# EXISTING BASIN 317 & 318

SHEET NO. 1




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# DRAINAGE MAP
# PROPOSED BASIN 317 & 318

SHEET NO. 2


Littlec 7/18/2017 3:57:10 PM T:\Sys\Projects\24259245201\drainage\REPORT\DRMP_Basin317_318_Prop .dgn

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 4, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 317D | **CHECKED BY:** | MB |

I ***PRE DEVELOPMENT***
***RUNOFF CURVE NUMBER (CN) CALCULATIONS***
***Basin 317D***

COMPUTED BASIN AREA (Ac) 1.53

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 1.06 | 103.88 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 1.06 | 103.88 |
| Pervious | | | | |
| Open Space, Fair Condition | A/D | 80 | 0.47 | 37.60 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 0.47 | 37.60 |
| | | TOTAL | 1.53 | 141.48 |

**COMPOSITE CN** **92.5**

II ***POST DEVELOPMENT***
***RUNOFF CURVE NUMBER (CN) CALCULATIONS***
***Basin 317D***

COMPUTED BASIN AREA (Ac) 6.69

**DETERMINE BASIN RUNOFF CURVE-NUMBER-CN**

| LAND-USE DESCRIPTION | SOIL GROUP | CN | AREA | PRODUCT |
|---|---|---|---|---|
| | | | | |
| Impervious | | | | |
| Roadway, Shoulder and sidewalk | | 98 | 2.38 | 233.24 |
| Future Orange Blvd. Typical (bike & sidewalk) | | 98 | 0.16 | 15.68 |
| | | | | |
| Sub-total for Impervious Land Uses | | | 2.54 | 248.92 |
| Pervious | | | | |
| Open Space, Fair Condition | A/D | 80 | 3.65 | 292.00 |
| | | | | |
| Pond Site - Wet Detention | | 100 | 0.50 | 50.00 |
| | | | | |
| Sub-total for Pervious Land Uses | | | 4.15 | 342.00 |
| | | TOTAL | 6.69 | 590.92 |

**COMPOSITE CN** **88.3**

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 4, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 317D | **CHECKED BY:** | MB |

III ***GEOTECHNICAL INFORMATION***

| **Estimated Seasonal High Water Table (SHWT)** | |
|---|---|
| | **Estimated SHWT (Ft)** |
| Boring P317D-1 and P317D-2 | 8.50 |
| | |
| **Estimated SHWT** | 8.50 |

| **REQUIRED TREATMENT VOLUME CALCULATION (WET DETENTION)** | AC-FT |
|---|---|
| 1.0 inch of Runoff over the Basin Area | 0.56 |
| Total Runoff from 2.5 inches over the Impervious Area | 0.53 |

***<< CONTROLS>>***

V ***PROVIDED TREATMENT & ATTENUATION VOLUME CALCULATIONS***

**REQUIRED ATTENUTATION CACULATION**

| **PRE-DEVELOPED CONDITION** | | **POST-DEVELOPED CONDITION** | |
|---|---|---|---|
| AREA (AC): | 1.53 | AREA (AC): | 6.69 |
| CN: | 92.5 | CN: | 88.3 |
| IMPERVIOUS AREA (AC): | 1.06 | IMPERVIOUS AREA (AC): | 2.54 |
| PERVIOUS AREA (AC): | 0.47 | PERVIOUS AREA (AC): | 4.15 |
| | | NEW IMPERVIOUS AREA (AC): | 1.48 |

| **POND STAGE, AREA & STORAGE** | | | |
|---|---|---|---|
| **DESCRIPTION** | **STAGE (FT)** | **AREA (AC)** | **CUMMULATIVE STORAGE (AC-FT)** |
| Pond Bottom | 3.50 | 0.26 | 0.00 |
| SHWT / Orifice Elevation | 8.50 | 0.50 | 1.90 |
| Weir Crest Elevation | 9.55 | 0.56 | 2.46 |
| Top of Bank Elevation (Inside) | 12.00 | 0.70 | 4.00 |
| Top of Berm | 12.01 | 0.95 | 4.01 |

| **PROVIDED TREATMENT VOLUME** | AC-FT |
|---|---|
| Treatment Volume Provided = Volume between Seasonal High and Weir Crest Elevation | 0.56 |

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 4, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 317D | **CHECKED BY:** | MB |

VI ***PERMANENT POOL VOLUME CALCULATIONS FOR POND 300***

$$PPV = \frac{DA * C * R * RT}{WS * CF}$$

PPV: Permanent Pool Volume (ac-ft)
DA: Drainage Area to the Pond (ac)(excluding water body)
C: Drainage Area Runoff Coefficient
R: Wet Season Rainfall Depth (in)(Figure 29-1)
RT: Residence Time (days)
WS: Length of Wet Season (June - October = 153 days)(days)
CF: Conversion Factor (12 in/ft)

Special Basin: N/A
Additional 50% (7-days) for OFW or Class I or Class II or Class III

| | | | |
|---|---|---|---|
| DA = | 6.69 | acres | |
| C = | 0.50 | | |
| R = | 31 | inches | (See Figure 26-1, SJRWMD) |
| WS = | 153 | days | |
| RT = | 14 | days | |
| Non-Littoral Zone Option RT = | 7 | days | (50% of Residence Time & Non-Littoral Zone Option) |
| Special Water RT = | 0 | days | |
| Design RT = | 21 | days | |

**Required Permanent Pool Volume:**

| | | |
|---|---|---|
| PPV = | 1.189 | ac-ft |
| | 51,807 | cu.ft |

**Permanent Pool Volume Check:**

Proposed Orifice Invert Elevation: 8.50 feet

| | | |
|---|---|---|
| Actual Pond Volume: | 1.900 | ac-ft |
| | 82,764 | cu.feet |

| | | |
|---|---|---|
| Required Permanent Pool Volume: | 1.189 | ac-ft |
| Actual Permanent Pool Volume: | 1.900 | ac-ft |
| Additional Permanent Pool Volume: | 0.711 | ac-ft |

**Exceeds Requirement**

**POND DEPTH**

Pond Depth Criteria:
*Maximum Pond Depth Shall Not Exceed 12 feet*

| | | |
|---|---|---|
| Control Elevation: | 8.50 | feet |
| Pond Bottom Elevation: | 3.50 | feet |
| Pond Depth: | 5.00 | feet |

**Does Not Exceed Maximum Pond Depth Requirement**

| | | | |
|---|---|---|---|
| **PROJECT TITLE:** | I-4 BtU Segment 3 | **DATE:** | May 4, 2017 |
| **PROJECT NUMBER:** | 242592-4-52-01 | **MADE BY:** | JLL |
| **BASIN DESIGNATION:** | Basin 317D | **CHECKED BY:** | MB |

**PERMANENT POOL MEAN DEDPTH**

Mean Depth Equation:

$$\text{Mean Depth} = \frac{\text{Pond Volume at Control Elevation}}{\text{Pond Area at Control Elevation}}$$


Mean Depth Criteria:

*Permanent Pool Depth Shall Vary Between 2 and 8 feet*

| | | |
|---|---|---|
| Control Elevation: | 8.50 | feet |
| Volume at Control Elevation: | 1.90 | ac-ft |
| Area at Control Elevation: | 0.50 | ac |
| Mean Depth: | 3.80 | feet |

**Meets Mean Depth Requirement**

Pre Development




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |


MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462


STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM EXISTING BASIN 317

SHEET NO.
N/A

Synychak 7/11/2017 3:05:07 PM T:\Sys\Projects\24259245201\drainage\REPORT\ICPR Link_Node\Exist_Link Node.dgn

BASIN 317
Existing Conditions Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| DM RV Pond | BASIN317 | SJRWMD | 12.00 | 10.50 | 12.00 | 0.00 | 0 | 12.03 | 8.39 | 0.00 | 0.00 |
| OUT 317A | BASIN317 | SJRWMD | 48.00 | 7.50 | 8.50 | -0.00 | 0 | 12.17 | 128.27 | 0.00 | 0.00 |
| OUT 317B | BASIN317 | SJRWMD | 12.00 | 6.00 | 8.50 | 0.00 | 0 | 12.33 | 9.74 | 0.00 | 0.00 |
| OUT 317C | BASIN317 | SJRWMD | 48.00 | 7.50 | 8.50 | -0.00 | 0 | 12.73 | 47.81 | 0.00 | 0.00 |
| Pond 1(CR15) | BASIN317 | SJRWMD | 13.20 | 7.78 | 8.50 | 0.00 | 64902 | 12.10 | 41.41 | 13.36 | 7.92 |
| Pond QQ-3 | BASIN317 | SJRWMD | 48.10 | 7.49 | 8.50 | 0.00 | 97420 | 12.13 | 64.04 | 12.96 | 33.88 |
| Pond QQ-5 | BASIN317 | SJRWMD | 12.89 | 8.14 | 8.50 | -0.00 | 84300 | 12.23 | 94.75 | 12.88 | 51.89 |

Existing Discharge Rates:
Basin 317A
Q-SJRWMD (25-yr/24-hr)= 128.27 cfs

Basin 317B
Q-SJRWMD (25-yr/24-hr)= 9.74 cfs

Basin 317C
Q-SJRWMD (25-yr/24-hr)= 47.81 cfs

```
================================================================================
==== Basins ====================================================================
================================================================================

         Name: Basin 317A              Node: Pond QQ-3             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 19.10
              Area(ac): 12.230                    Time Shift(hrs): 0.00
           Curve Number: 90.70                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00

Tc = 19.1 min. per ERP Permit No. 64105-7

--------------------------------------------------------------------------------------------------------
         Name: Basin 317B              Node: Pond 1(CR15)          Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 19.31
              Area(ac): 9.510                     Time Shift(hrs): 0.00
           Curve Number: 92.80                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00

Tc = 19.31 min. per ERP Permit No. 64105-7

--------------------------------------------------------------------------------------------------------
         Name: Basin 317C              Node: Pond QQ-5             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 32.93
              Area(ac): 28.760                    Time Shift(hrs): 0.00
           Curve Number: 89.70                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00

Tc = 32.93 min. per ERP Permit No. 64105-7

--------------------------------------------------------------------------------------------------------
         Name: Basin 317D              Node: DM RV Pond            Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 10.00
              Area(ac): 1.530                     Time Shift(hrs): 0.00
           Curve Number: 92.50                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00



--------------------------------------------------------------------------------------------------------
         Name: BSN 317A-Direct         Node: OUT 317A              Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 20.00
              Area(ac): 28.350                    Time Shift(hrs): 0.00
           Curve Number: 83.10                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00



--------------------------------------------------------------------------------------------------------
         Name: BSN 317B-Direct         Node: OUT 317B              Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod                Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600                  Time of Conc(min): 15.00
              Area(ac): 1.330                     Time Shift(hrs): 0.00
           Curve Number: 81.40                Max Allowable Q(cfs): 999999.000
                DCIA(%): 0.00

Wetland and infield areas

--------------------------------------------------------------------------------------------------------
         Name: Orange Blvd.            Node: OUT 317C              Status: Onsite
```

Group: BASIN317 Type: SCS Unit Hydrograph CN

Unit Hydrograph: Uh323 Peaking Factor: 323.0
Rainfall File: Flmod Storm Duration(hrs): 24.00
Rainfall Amount(in): 8.600 Time of Conc(min): 40.00
Area(ac): 8.600 Time Shift(hrs): 0.00
Curve Number: 82.40 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

==========
==== Nodes ==========
==========

Name: DM RV Pond Base Flow(cfs): 0.000 Init Stage(ft): 9.000
Group: BASIN317 Warn Stage(ft): 12.000
Type: Time/Stage

DM = Donnie Myer

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 9.000 |
| 12.00 | 10.500 |
| 24.00 | 9.000 |

---

Name: OUT 317A Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 5.000 |
| 24.00 | 5.500 |
| 48.00 | 7.500 |
| 72.00 | 4.500 |
| 336.00 | 4.000 |

---

Name: OUT 317B Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 6.000 |
| 24.00 | 4.000 |
| 336.00 | 4.000 |

---

Name: OUT 317C Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 5.000 |
| 24.00 | 5.500 |
| 48.00 | 7.500 |
| 72.00 | 4.500 |
| 336.00 | 4.000 |

---

Name: Pond 1(CR15) Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

Permitted Weir El. = 5.85
Permitted Grate El. = 8.5
Permit No. 64105-7

| Stage(ft) | Area(ac) |
|---|---|
| -3.750 | 0.1600 |
| 4.500 | 0.8500 |
| 5.850 | 1.1100 |
| 6.000 | 1.1400 |
| 8.490 | 1.6300 |
| 8.500 | 1.6300 |
| 9.500 | 2.2700 |

Name: Pond QQ-3 Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 4.500 | 1.6300 |
| 8.500 | 2.4400 |
| 9.500 | 3.1700 |

Name: Pond QQ-5 Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 4.500 | 1.3390 |
| 8.500 | 1.9930 |
| 9.500 | 2.6020 |

## Pipes

Name: P-317AC From Node: Pond QQ-5 Length(ft): 940.00
Group: BASIN317 To Node: Pond QQ-3 Count: 1
Friction Equation: Automatic
Solution Algorithm: Most Restrictive
Flow: Both
Entrance Loss Coef: 0.50
Exit Loss Coef: 1.00
Bend Loss Coef: 0.00
Outlet Ctrl Spec: Use dc or tw
Inlet Ctrl Spec: Use dc
Stabilizer Option: None

| | UPSTREAM | DOWNSTREAM |
|---|---|---|
| Geometry: | Circular | Circular |
| Span(in): | 36.00 | 36.00 |
| Rise(in): | 36.00 | 36.00 |
| Invert(ft): | 2.980 | 2.770 |
| Manning's N: | 0.012000 | 0.012000 |
| Top Clip(in): | 0.000 | 0.000 |
| Bot Clip(in): | 0.000 | 0.000 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

## Drop Structures

Name: DS-317A From Node: Pond QQ-3 Length(ft): 225.00
Group: BASIN317 To Node: OUT 317A Count: 2
Friction Equation: Automatic
Solution Algorithm: Automatic
Flow: Both
Entrance Loss Coef: 1.000
Exit Loss Coef: 0.500
Outlet Ctrl Spec: Use dc or tw
Inlet Ctrl Spec: Use dc
Solution Incs: 10

| | UPSTREAM | DOWNSTREAM |
|---|---|---|
| Geometry: | Circular | Circular |
| Span(in): | 24.00 | 24.00 |
| Rise(in): | 24.00 | 24.00 |
| Invert(ft): | 2.950 | 2.820 |
| Manning's N: | 0.012000 | 0.012000 |
| Top Clip(in): | 0.000 | 0.000 |
| Bot Clip(in): | 0.000 | 0.000 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

*** Weir 1 of 3 for Drop Structure DS-317A ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 151.00 | Invert(ft): | 6.000 |
| Rise(in): | 999.00 | Control Elev(ft): | 6.000 |

*** Weir 2 of 3 for Drop Structure DS-317A ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 79.00 | Invert(ft): | 6.750 |
| Rise(in): | 36.00 | Control Elev(ft): | 6.750 |

*** Weir 3 of 3 for Drop Structure DS-317A ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Circular | Orifice Disc Coef: | 0.600 |
| Span(in): | 5.00 | Invert(ft): | 4.500 |
| Rise(in): | 5.00 | Control Elev(ft): | 4.500 |

---

| | | | |
|---|---|---|---|
| Name: | DS-317B | From Node: | Pond 1(CR15) |
| Length(ft): | 163.00 | | |
| Group: | BASIN317 | To Node: | OUT 317B |
| Count: | 1 | | |

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| | | | Friction Equation: | Automatic |
| Geometry: | Circular | Circular | Solution Algorithm: | Automatic |
| Span(in): | 18.00 | 18.00 | Flow: | Both |
| Rise(in): | 18.00 | 18.00 | Entrance Loss Coef: | 1.000 |
| Invert(ft): | 4.000 | 3.500 | Exit Loss Coef: | 0.500 |
| Manning's N: | 0.012000 | 0.012000 | Outlet Ctrl Spec: | Use dc or tw |
| Top Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| Bot Clip(in): | 0.000 | 0.000 | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

*** Weir 1 of 3 for Drop Structure DS-317B ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 15.00 | Invert(ft): | 5.850 |
| Rise(in): | 31.38 | Control Elev(ft): | 5.850 |

*** Weir 2 of 3 for Drop Structure DS-317B ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Horizontal | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Rectangular | Orifice Disc Coef: | 0.600 |
| Span(in): | 79.00 | Invert(ft): | 8.500 |
| Rise(in): | 36.00 | Control Elev(ft): | 8.500 |

*** Weir 3 of 3 for Drop Structure DS-317B ***

TABLE

| | | | |
|---|---|---|---|
| Count: | 1 | Bottom Clip(in): | 0.000 |
| Type: | Vertical: Mavis | Top Clip(in): | 0.000 |
| Flow: | Both | Weir Disc Coef: | 3.200 |
| Geometry: | Circular | Orifice Disc Coef: | 0.600 |

```
              Span(in): 4.50                      Invert(ft): 4.500
              Rise(in): 4.50                  Control Elev(ft): 4.500


-------------------------------------------------------------------------------------------------
         Name: DS-317C            From Node: Pond QQ-5         Length(ft): 95.00
        Group: BASIN317             To Node: OUT 317C              Count: 2

               UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                  Solution Algorithm: Automatic
     Span(in): 24.00          24.00                                Flow: Both
     Rise(in): 24.00          24.00                     Entrance Loss Coef: 1.000
   Invert(ft): 3.920          3.820                         Exit Loss Coef: 0.500
  Manning's N: 0.012000       0.012000                    Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                        Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                          Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall



*** Weir 1 of 3 for Drop Structure DS-317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Vertical: Mavis           Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 36.00                      Invert(ft): 6.000
               Rise(in): 999.00                Control Elev(ft): 6.000

*** Weir 2 of 3 for Drop Structure DS-317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Horizontal               Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 79.00                      Invert(ft): 8.000
               Rise(in): 36.00                 Control Elev(ft): 8.000

*** Weir 3 of 3 for Drop Structure DS-317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Vertical: Mavis           Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Circular             Orifice Disc Coef: 0.600

               Span(in): 5.00                       Invert(ft): 4.500
               Rise(in): 5.00                  Control Elev(ft): 4.500


===============================================================================================
==== Hydrology Simulations ====================================================================
===============================================================================================

         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.R32

      Override Defaults: No

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
96.000          5.00

===============================================================================================
==== Routing Simulations ======================================================================
===============================================================================================

         Name: SJRWMD              Hydrology Sim: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\I-4 Existing\SJRWMD.I32

      Execute: Yes         Restart: No            Patch: No
  Alternative: No


        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
```

Start Time(hrs): 0.000 End Time(hrs): 120.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 6.000 | 5.000 |
| 14.000 | 1.000 |
| 96.000 | 5.000 |
| 120.000 | 5.000 |

| Group | Run |
|---|---|
| BASIN317 | Yes |

Post Development




| REVISIONS | | | |
|---|---|---|---|
| DATE | DESCRIPTION | DATE | DESCRIPTION |
| | | | |

MICHAEL J. QUARTETTI, P.E.
P.E. LICENSE NUMBER 45976
WSP USA Inc.
2202 N WEST SHORE BLVD., SUITE 300
TAMPA, FL 33607
CERTIFICATE OF AUTHORIZATION 00001462

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| 400 | SEMINOLE | 242592-4-52-01 |

# ICPR LINK NODE DIAGRAM
# PROPOSED BASIN 317

SHEET NO.
N/A

AndersonT 7/11/2017 4:51:08 PM T:\Sys\Projects\24259245201\drainage\REPORT\ICPR Link_Node\Prop_Link Node.dgn

BASIN 317
Proposed Condition Output

| Name | Group | Simulation | Max Time Stage hrs | Max Stage ft | Warning Stage ft | Max Delta Stage ft | Max Surf Area ft2 | Max Time Inflow hrs | Max Inflow cfs | Max Time Outflow hrs | Max Outflow cfs |
|---|---|---|---|---|---|---|---|---|---|---|---|
| OUT 317A | BASIN317 | SJRWMD | 48.00 | 7.50 | 8.50 | -0.0021 | 0 | 12.82 | 27.46 | 0.00 | 0.00 |
| OUT 317B | BASIN317 | SJRWMD | 12.00 | 6.00 | 8.50 | 0.0028 | 0 | 12.10 | 10.52 | 0.00 | 0.00 |
| OUT 317C | BASIN317 | SJRWMD | 48.00 | 7.50 | 8.50 | -0.0021 | 0 | 12.38 | 46.78 | 0.00 | 0.00 |
| Pond 317A | BASIN317 | SJRWMD | 12.82 | 7.57 | 8.50 | 0.0047 | 132152 | 12.08 | 112.61 | 12.82 | 27.46 |
| Pond 317B | BASIN317 | SJRWMD | 13.14 | 7.12 | 8.50 | 0.0040 | 59167 | 12.07 | 35.06 | 13.29 | 5.04 |
| Pond 317C | BASIN317 | SJRWMD | 12.81 | 7.57 | 8.50 | 0.0050 | 72036 | 12.07 | 69.36 | 12.45 | 22.04 |
| Pond 317D | BASIN317 | SJRWMD | 12.33 | 11.00 | 11.00 | 0.0050 | 28006 | 12.05 | 34.38 | 12.33 | 20.53 |

Proposed Discharge Rates:
Basin 317A
Q-SJRWMD (25-yr/24-hr)= 27.46 cfs

Basin 317B
Q-SJRWMD (25-yr/24-hr)= 10.52 cfs

Basin 317 C
Q-SJRWMD (25-yr/24-hr)= 46.78 cfs

```
================================================================================
==== Basins ====================================================================
================================================================================

         Name: Basin 317A              Node: Pond 317A             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600              Time of Conc(min): 16.00
              Area(ac): 22.050                Time Shift(hrs): 0.00
          Curve Number: 96.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: Basin 317B              Node: Pond 317B             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.400              Time of Conc(min): 15.00
              Area(ac): 7.610                 Time Shift(hrs): 0.00
          Curve Number: 90.10             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: Basin 317C              Node: Pond 317C             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600              Time of Conc(min): 15.00
              Area(ac): 14.340                Time Shift(hrs): 0.00
          Curve Number: 92.80             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: Basin 317D              Node: Pond 317D             Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600              Time of Conc(min): 11.00
              Area(ac): 6.690                 Time Shift(hrs): 0.00
          Curve Number: 88.30             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00



--------------------------------------------------------------------------------------------------
         Name: BSN 317A-Direct         Node: OUT 317A              Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 96.00
    Rainfall Amount(in): 8.600              Time of Conc(min): 15.00
              Area(ac): 20.070                Time Shift(hrs): 0.00
          Curve Number: 80.00             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00

Represents Basins 317A-1 thru Basin 317A-4 (See Drainage Map)

--------------------------------------------------------------------------------------------------
         Name: BSN 317B-Direct         Node: OUT 317B              Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
    Rainfall Amount(in): 8.600              Time of Conc(min): 15.00
              Area(ac): 2.270                 Time Shift(hrs): 0.00
          Curve Number: 80.20             Max Allowable Q(cfs): 999999.000
               DCIA(%): 0.00

Wetland and infield areas

--------------------------------------------------------------------------------------------------
         Name: Orange Blvd.            Node: OUT 317C              Status: Onsite
        Group: BASIN317                Type: SCS Unit Hydrograph CN

        Unit Hydrograph: Uh323                   Peaking Factor: 323.0
          Rainfall File: Flmod            Storm Duration(hrs): 24.00
```

Rainfall Amount(in): 8.600 Time of Conc(min): 20.00
Area(ac): 3.710 Time Shift(hrs): 0.00
Curve Number: 80.00 Max Allowable Q(cfs): 999999.000
DCIA(%): 0.00

==========
==== Nodes ==========
==========

Name: OUT 317A Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 5.000 |
| 24.00 | 5.500 |
| 48.00 | 7.500 |
| 72.00 | 4.500 |
| 336.00 | 4.000 |

---

Name: OUT 317B Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 6.000 |
| 24.00 | 4.000 |
| 336.00 | 4.000 |

---

Name: OUT 317C Base Flow(cfs): 0.000 Init Stage(ft): 4.000
Group: BASIN317 Warn Stage(ft): 8.500
Type: Time/Stage

Tailwater conditions obtained from the Lake Monroe
Basin Engineering Study dated December 1999.
Elevations converted to NAVD (NGVD - 1.04)

| Time(hrs) | Stage(ft) |
|---|---|
| 0.00 | 4.000 |
| 12.00 | 5.000 |
| 24.00 | 5.500 |
| 48.00 | 7.500 |
| 72.00 | 4.500 |
| 336.00 | 4.000 |

---

Name: Pond 317A Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

SHWT = 4.5'

| Stage(ft) | Area(ac) |
|---|---|
| -3.500 | 1.7700 |
| 4.500 | 2.7100 |
| 5.030 | 2.8600 |
| 6.000 | 2.9100 |
| 7.000 | 2.9100 |
| 8.500 | 3.2300 |
| 9.500 | 3.9400 |

---

Name: Pond 317B Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|

| | |
|---|---|
| -3.500 | 0.1900 |
| 4.500 | 0.8500 |
| 5.850 | 1.1100 |
| 6.980 | 1.3300 |
| 7.180 | 1.3700 |
| 8.500 | 1.6300 |
| 9.500 | 2.2700 |

---

Name: Pond 317C Base Flow(cfs): 0.000 Init Stage(ft): 4.500
Group: BASIN317 Warn Stage(ft): 8.500
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| -3.500 | 0.1900 |
| 4.500 | 1.2700 |
| 5.850 | 1.4400 |
| 6.000 | 1.4600 |
| 7.000 | 1.5800 |
| 8.500 | 1.7700 |
| 9.500 | 2.0800 |

---

Name: Pond 317D Base Flow(cfs): 0.000 Init Stage(ft): 8.500
Group: BASIN317 Warn Stage(ft): 11.000
Type: Stage/Area

| Stage(ft) | Area(ac) |
|---|---|
| 3.500 | 0.2600 |
| 8.500 | 0.5000 |
| 12.000 | 0.7000 |
| 12.010 | 0.9500 |

==========
==== Pipes ====
==========

Name: P-317AC From Node: Pond 317C Length(ft): 940.00
Group: BASIN317 To Node: Pond 317A Count: 1
Friction Equation: Automatic

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Solution Algorithm: | Most Restrictive |
| Span(in): | 36.00 | 36.00 | Flow: | Both |
| Rise(in): | 36.00 | 36.00 | Entrance Loss Coef: | 0.50 |
| Invert(ft): | 2.980 | 2.770 | Exit Loss Coef: | 1.00 |
| Manning's N: | 0.012000 | 0.012000 | Bend Loss Coef: | 0.00 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Stabilizer Option: | None |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

==========
==== Drop Structures ====
==========

Name: S-0317D From Node: Pond 317D Length(ft): 275.00
Group: BASIN317 To Node: OUT 317C Count: 1

| | UPSTREAM | DOWNSTREAM | | |
|---|---|---|---|---|
| Geometry: | Circular | Circular | Friction Equation: | Automatic |
| Span(in): | 24.00 | 24.00 | Solution Algorithm: | Most Restrictive |
| Rise(in): | 24.00 | 24.00 | Flow: | Both |
| Invert(ft): | 5.500 | 5.100 | Entrance Loss Coef: | 0.500 |
| Manning's N: | 0.012000 | 0.012000 | Exit Loss Coef: | 1.000 |
| Top Clip(in): | 0.000 | 0.000 | Outlet Ctrl Spec: | Use dc or tw |
| Bot Clip(in): | 0.000 | 0.000 | Inlet Ctrl Spec: | Use dc |
| | | | Solution Incs: | 10 |

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

```
*** Weir 1 of 3 for Drop Structure S-0317D ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Vertical: Mavis           Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Rectangular           Orifice Disc Coef: 0.600

            Span(in): 49.00                       Invert(ft): 9.550
            Rise(in): 17.40                  Control Elev(ft): 9.550

*** Weir 2 of 3 for Drop Structure S-0317D ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Horizontal               Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Rectangular           Orifice Disc Coef: 0.600

            Span(in): 36.00                       Invert(ft): 11.420
            Rise(in): 79.00                  Control Elev(ft): 11.420

*** Weir 3 of 3 for Drop Structure S-0317D ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Vertical: Mavis           Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Circular              Orifice Disc Coef: 0.600

            Span(in): 2.30                        Invert(ft): 8.500
            Rise(in): 2.30                   Control Elev(ft): 8.500


-------------------------------------------------------------------------------------------------
        Name: S-O317A             From Node: Pond 317A         Length(ft): 305.00
       Group: BASIN317              To Node: OUT 317A              Count: 2

              UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
    Geometry: Circular       Circular                  Solution Algorithm: Automatic
    Span(in): 24.00          24.00                                Flow: Both
    Rise(in): 24.00          24.00                    Entrance Loss Coef: 1.000
  Invert(ft): 4.100          4.000                        Exit Loss Coef: 0.500
 Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
Top Clip(in): 0.000          0.000                       Inlet Ctrl Spec: Use dc
Bot Clip(in): 0.000          0.000                         Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Per the permit plans:  Weir Length = (6'+3')*2 = 216

*** Weir 1 of 3 for Drop Structure S-O317A ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Vertical: Mavis           Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Rectangular           Orifice Disc Coef: 0.600

            Span(in): 144.00                      Invert(ft): 6.000
            Rise(in): 18.96                  Control Elev(ft): 6.000

*** Weir 2 of 3 for Drop Structure S-O317A ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Horizontal               Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Rectangular           Orifice Disc Coef: 0.600

            Span(in): 79.00                       Invert(ft): 8.000
            Rise(in): 36.00                  Control Elev(ft): 8.000

*** Weir 3 of 3 for Drop Structure S-O317A ***
                                                                                TABLE
                Count: 1                      Bottom Clip(in): 0.000
                 Type: Vertical: Mavis           Top Clip(in): 0.000
                 Flow: Both                    Weir Disc Coef: 3.200
            Geometry: Circular              Orifice Disc Coef: 0.600

            Span(in): 5.90                        Invert(ft): 4.500
            Rise(in): 5.90                   Control Elev(ft): 4.500


-------------------------------------------------------------------------------------------------
        Name: S-O317B             From Node: Pond 317B         Length(ft): 163.00
       Group: BASIN317              To Node: OUT 317B              Count: 1
```

```
              UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                 Solution Algorithm: Automatic
     Span(in): 18.00          18.00                                 Flow: Both
     Rise(in): 18.00          18.00                    Entrance Loss Coef: 1.000
   Invert(ft): 4.000          3.500                        Exit Loss Coef: 0.500
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                       Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                         Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Outfall not modified from existing condition.

*** Weir 1 of 2 for Drop Structure S-O317B ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Vertical: Mavis           Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 15.00                       Invert(ft): 5.850
               Rise(in): 31.38                Control Elev(ft): 5.850

*** Weir 2 of 2 for Drop Structure S-O317B ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Horizontal               Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 79.00                       Invert(ft): 8.500
               Rise(in): 36.00                Control Elev(ft): 8.500


-------------------------------------------------------------------------------------------------
        Name: S-O317C             From Node: Pond 317C          Length(ft): 95.00
       Group: BASIN317              To Node: OUT 317C                Count: 2

              UPSTREAM       DOWNSTREAM                 Friction Equation: Automatic
     Geometry: Circular       Circular                 Solution Algorithm: Automatic
     Span(in): 24.00          24.00                                 Flow: Both
     Rise(in): 24.00          24.00                    Entrance Loss Coef: 1.000
   Invert(ft): 3.920          3.820                        Exit Loss Coef: 0.500
  Manning's N: 0.012000       0.012000                   Outlet Ctrl Spec: Use dc or tw
 Top Clip(in): 0.000          0.000                       Inlet Ctrl Spec: Use dc
 Bot Clip(in): 0.000          0.000                         Solution Incs: 10

Upstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Downstream FHWA Inlet Edge Description:
Circular Concrete: Square edge w/ headwall

Outfall not modified from existing condition.

*** Weir 1 of 3 for Drop Structure S-O317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Horizontal               Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 79.00                       Invert(ft): 8.000
               Rise(in): 36.00                Control Elev(ft): 8.000

*** Weir 2 of 3 for Drop Structure S-O317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Vertical: Mavis           Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Rectangular          Orifice Disc Coef: 0.600

               Span(in): 35.00                       Invert(ft): 6.000
               Rise(in): 18.96                Control Elev(ft): 6.000

*** Weir 3 of 3 for Drop Structure S-O317C ***
                                                                                    TABLE
                  Count: 1                      Bottom Clip(in): 0.000
                   Type: Vertical: Mavis           Top Clip(in): 0.000
                   Flow: Both                   Weir Disc Coef: 3.200
               Geometry: Circular             Orifice Disc Coef: 0.600

               Span(in): 4.00                        Invert(ft): 4.500
               Rise(in): 4.00                 Control Elev(ft): 4.500
```

```
================================================================================
==== Hydrology Simulations =====================================================
================================================================================

         Name: 003Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\003Y08H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 8.00
          Rainfall File: Fdot-8
    Rainfall Amount(in): 4.16

Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          1.00

------------------------------------------------------------------------------------------------------------
         Name: 010Y001H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y001H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 1.00
          Rainfall File: Fdot-1
    Rainfall Amount(in): 3.25

Time(hrs)       Print Inc(min)
--------------- ---------------
2.000           2.50

------------------------------------------------------------------------------------------------------------
         Name: 010Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y008H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 8.00
          Rainfall File: Fdot-8
    Rainfall Amount(in): 5.60

Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          1.00

------------------------------------------------------------------------------------------------------------
         Name: 010Y024H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y024H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Fdot-24
    Rainfall Amount(in): 7.68

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
30.000          5.00

------------------------------------------------------------------------------------------------------------
         Name: 010Y072H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y072H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 72.00
          Rainfall File: Fdot-72
    Rainfall Amount(in): 9.00

Time(hrs)       Print Inc(min)
--------------- ---------------
73.000          5.00

------------------------------------------------------------------------------------------------------------
         Name: 010Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 13.50

Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.00

------------------------------------------------------------------------------------------------------------
         Name: 050Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y008H.R32
```

```
      Override Defaults: Yes
    Storm Duration(hrs): 8.00
          Rainfall File: Fdot-8
    Rainfall Amount(in): 7.52

Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          1.00

-------------------------------------------------------------------------------------------------
         Name: 050Y024H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y024H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 24.00
          Rainfall File: Fdot-24
    Rainfall Amount(in): 10.08

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
30.000          5.00
75.000          10.00

-------------------------------------------------------------------------------------------------
         Name: 050Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 17.50

Time(hrs)       Print Inc(min)
--------------- ---------------
250.000         5.00

-------------------------------------------------------------------------------------------------
         Name: 100Y072H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y072H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 72.00
          Rainfall File: Fdot-72
    Rainfall Amount(in): 13.80

Time(hrs)       Print Inc(min)
--------------- ---------------
73.000          5.00

-------------------------------------------------------------------------------------------------
         Name: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.R32

      Override Defaults: Yes
    Storm Duration(hrs): 240.00
          Rainfall File: Fdot-240
    Rainfall Amount(in): 18.50

Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.00

-------------------------------------------------------------------------------------------------
         Name: SJRWMD
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.R32

      Override Defaults: No

Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.00
14.000          1.00
96.000          5.00

=================================================================================================
==== Routing Simulations ========================================================================
=================================================================================================

         Name: 003Y008H            Hydrology Sim: 003Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\003Y008H.I32

      Execute: Yes         Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
```

```
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                  End Time(hrs): 16.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          5.000

Group           Run
--------------- -----
BASIN317        Yes


-------------------------------------------------------------------------------------------------
         Name: 010Y001H           Hydrology Sim: 010Y001H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y001H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                   Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                  End Time(hrs): 2.00
     Min Calc Time(sec): 0.0100              Max Calc Time(sec): 60.0000
        Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
2.000           2.500

Group           Run
--------------- -----
BASIN299        Yes


-------------------------------------------------------------------------------------------------
         Name: 010Y008H           Hydrology Sim: 010Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y008H.I32

      Execute: Yes         Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                   Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                  End Time(hrs): 16.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          5.000

Group           Run
--------------- -----
BASIN317        Yes


-------------------------------------------------------------------------------------------------
         Name: 010Y024H           Hydrology Sim: 010Y024H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y024H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                   Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                  End Time(hrs): 30.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                        Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.000
14.000          1.000
30.000          5.000

Group           Run
--------------- -----
BASIN316        Yes
```

---

```
--------------------------------------------------------------------------------------------------
         Name: 010Y072H            Hydrology Sim: 010Y072H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y072H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 73.00
     Min Calc Time(sec): 0.0100              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
73.000          5.000

Group           Run
--------------- -----
BASIN299        Yes


--------------------------------------------------------------------------------------------------
         Name: 010Y240H            Hydrology Sim: 010Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\010Y240H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 240.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.000

Group           Run
--------------- -----
BASIN300&301    Yes
BASIN302        Yes
BASIN303        Yes
BASIN304        Yes
BASIN307        Yes
BASIN308        Yes
BASIN309        Yes
BASIN310        Yes
BASIN311        Yes


--------------------------------------------------------------------------------------------------
         Name: 050Y008H            Hydrology Sim: 050Y008H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y008H.I32

      Execute: Yes         Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 16.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
16.000          5.000

Group           Run
--------------- -----
BASIN317        Yes


--------------------------------------------------------------------------------------------------
         Name: 050Y024H            Hydrology Sim: 050Y024H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y024H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No
```

```
        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 75.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
6.000           5.000
14.000          1.000
30.000          5.000
75.000          10.000

Group           Run
--------------- -----
BASIN316        Yes


-------------------------------------------------------------------------------------------------
         Name: 050Y240H           Hydrology Sim: 050Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\050Y240H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 240.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
240.000         5.000

Group           Run
--------------- -----
BASIN300&301    Yes
BASIN302        Yes
BASIN303        Yes
BASIN304        Yes
BASIN307        Yes
BASIN308        Yes
BASIN309        Yes
BASIN310        Yes
BASIN311        Yes


-------------------------------------------------------------------------------------------------
         Name: 100Y072H           Hydrology Sim: 100Y072H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y072H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 73.00
     Min Calc Time(sec): 0.0100              Max Calc Time(sec): 60.0000
        Boundary Stages:                         Boundary Flows:


Time(hrs)       Print Inc(min)
--------------- ---------------
73.000          5.000

Group           Run
--------------- -----
BASIN299        Yes


-------------------------------------------------------------------------------------------------
         Name: 100Y240H           Hydrology Sim: 100Y240H
     Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\100Y240H.I32

      Execute: No          Restart: No           Patch: No
  Alternative: No

        Max Delta Z(ft): 1.00                    Delta Z Factor: 0.00500
    Time Step Optimizer: 10.000
        Start Time(hrs): 0.000                    End Time(hrs): 336.00
     Min Calc Time(sec): 0.5000              Max Calc Time(sec): 60.0000
```

Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 336.000 | 15.000 |

| Group | Run |
|---|---|
| BASIN300&301 | Yes |
| BASIN302 | Yes |
| BASIN303 | Yes |
| BASIN304 | Yes |
| BASIN307 | Yes |
| BASIN308 | Yes |
| BASIN309 | Yes |
| BASIN310 | Yes |
| BASIN311 | Yes |

---

Name: PERC Hydrology Sim:
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\PERC.I32

Execute: No Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 720.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 720.000 | 1.000 |

| Group | Run |
|---|---|
| BASIN299 | Yes |
| BASIN300&301 | Yes |
| BASIN302 | Yes |
| BASIN303 | Yes |
| BASIN304 | Yes |
| BASIN305&306 | Yes |
| BASIN307 | Yes |
| BASIN308 | Yes |
| BASIN309 | Yes |
| BASIN310 | Yes |
| BASIN311 | Yes |

---

Name: SJRWMD Hydrology Sim: SJRWMD
Filename: J:\185708 I-4 BtU Seg3\6.0FinalDesign\6.12Drainage\ICPR\SJRWMD.I32

Execute: Yes Restart: No Patch: No
Alternative: No

Max Delta Z(ft): 1.00 Delta Z Factor: 0.00500
Time Step Optimizer: 10.000
Start Time(hrs): 0.000 End Time(hrs): 120.00
Min Calc Time(sec): 0.5000 Max Calc Time(sec): 60.0000
Boundary Stages: Boundary Flows:

| Time(hrs) | Print Inc(min) |
|---|---|
| 6.000 | 5.000 |
| 16.000 | 1.000 |
| 96.000 | 5.000 |
| 120.000 | 5.000 |

| Group | Run |
|---|---|
| BASIN317 | Yes |

**Appendix D**
**Property Owner Coordination**

First Property Owner Mailing

# Florida Department of Transportation

RICK SCOTT
GOVERNOR

719 S. Woodland Boulevard
DeLand, Florida 32720-6834

JIM BOXOLD
SECRETARY


December 7th, 2016

LMLD New Century I LLC
390 N Orange Ave Ste 2400
Orlando, FL 32801

Dear Property Owner:

The Florida Department of Transportation (FDOT) seeks your input as it moves forward with the construction plans for the widening and reconstruction of State Road 400 (I-4) from 1 mile East of State Road 434 to East of State Road 15/600/US 17/92 Seminole / Volusia County Line.

As part of the design process, your property has been selected as a preferred site for one of the stormwater management facility areas. These stormwater management facilities are part of the drainage design to fulfill St. Johns River Water Management District permitting requirements. Enclosed is a sketch showing the location and approximate size of the stormwater management area.

Your input is important. FDOT would like your input on the location of this pond, including any suggestions you might have on reconfiguring the pond to better fit the future use of your property. We would also be willing to meet with you to discuss any concerns you might have with the pond location. Please respond by January 16th, 2017 so that we can incorporate your input.

Thank you for your cooperation. Please direct all questions and comments to:

Eileen LaSeur
I-4 BTU Public Information Officer
(Quest Corporation of America, Inc.)
17220 Camelot Court
Land O'Lakes, FL 34638
Eileen.LaSeur@QCAusa.com
Office: 866-662-6273
Cell: 407-883-8257
Fax: 813-926-2962


You may also contact me directly, Catalina.Chacon@dot.state.fl.us, (386) 943-5039

Sincerely,

Catalina Chacon, P.E.
Project Manager
Florida Department of Transportation
District Five

Enclosure

cc: Ferrell L. Hickson, Jr., P.E., District Drainage Engineer
Karen A. Snyder, P.E., Assistant District Drainage Engineer
Suzanne S. Phillips, P.E., District Consultant Project Management Engineer
Michael L. McPhail, MAI, Cost Estimate / Design Support Manager
Eileen LaSeur, Quest Corporation of America / Public Information Officer




MICHAEL J. QUARTETTI
P.E. LICENSE NO. 45976
PARSONS BRINCKERHOFF, INC.
2202 N. WEST SHORE BLVD, SUITE 300
TAMPA, FL 33607
PH (813) 520-4444 FAX (813) 520-4290
CERTIFICATE OF AUTHORIZATION NO. 00001462

**STATE OF FLORIDA**
**DEPARTMENT OF TRANSPORTATION**

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| SR 400 | SEMINOLE | 242592-4 |

# POND SITING PARCEL SKETCHES

SHEET NO.

robert.martinl 12/7/2016 8:37:37 AM c:\pwworking\aecom_na\rmartinl\dms63673\Pond308A 07-20-30-5MK-0000-0020.dgn

# Florida Department of Transportation

RICK SCOTT
GOVERNOR

719 S. Woodland Boulevard
DeLand, Florida 32720-6834

JIM BOXOLD
SECRETARY


December 7th, 2016

TLC Properties Inc.
5321 Corporate Blvd
Baton Rouge, LA 70808

Dear Property Owner:

The Florida Department of Transportation (FDOT) seeks your input as it moves forward with the construction plans for the widening and reconstruction of State Road 400 (I-4) from 1 mile East of State Road 434 to East of State Road 15/600/US 17/92 Seminole / Volusia County Line.

As part of the design process, your property has been selected as a preferred site for one of the stormwater management facility areas. These stormwater management facilities are part of the drainage design to fulfill St. Johns River Water Management District permitting requirements. Enclosed is a sketch showing the location and approximate size of the stormwater management area.

Your input is important. FDOT would like your input on the location of this pond, including any suggestions you might have on reconfiguring the pond to better fit the future use of your property. We would also be willing to meet with you to discuss any concerns you might have with the pond location. Please respond by January 16th, 2017 so that we can incorporate your input.

Thank you for your cooperation. Please direct all questions and comments to:

Eileen LaSeur
I-4 BTU Public Information Officer
(Quest Corporation of America, Inc.)
17220 Camelot Court
Land O'Lakes, FL 34638
Eileen.LaSeur@QCAusa.com
Office: 866-662-6273
Cell: 407-883-8257
Fax: 813-926-2962


You may also contact me directly, Catalina.Chacon@dot.state.fl.us, (386) 943-5039

Sincerely,

Catalina Chacon, P.E.
Project Manager
Florida Department of Transportation
District Five

Enclosure

cc: Ferrell L. Hickson, Jr., P.E., District Drainage Engineer
Karen A. Snyder, P.E., Assistant District Drainage Engineer
Suzanne S. Phillips, P.E., District Consultant Project Management Engineer
Michael L. McPhail, MAI, Cost Estimate / Design Support Manager
Eileen LaSeur, Quest Corporation of America / Public Information Officer




MICHAEL J. QUARTETTI
P.E. LICENSE NO. 45976
PARSONS BRINCKERHOFF, INC.
2202 N. WEST SHORE BLVD, SUITE 300
TAMPA, FL 33607
PH (813) 520-4444 FAX (813) 520-4290
CERTIFICATE OF AUTHORIZATION NO. 00001462

**STATE OF FLORIDA**
**DEPARTMENT OF TRANSPORTATION**

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| SR 400 | SEMINOLE | 242592-4 |

# POND SITING PARCEL SKETCHES

SHEET NO.

robert.martinl 12/7/2016 8:06:21 AM c:\pwworking\aecom_na\rmartinl\dms63673\Pond303-B2 24-20-29-300-0090-0000.dgn

Second Property Owner Mailing

# Florida Department of Transportation

RICK SCOTT
GOVERNOR

719 S. Woodland Boulevard
DeLand, Florida 32720-6834

RACHEL D. CONE
INTERIM SECRETARY


February 27, 2017

LMLD New Century I LLC
390 N Orange Ave Ste 2400
Orlando, FL 32801

Dear Property Owner:

The Florida Department of Transportation (FDOT) sent notice to you, dated December 7, 2016, requesting your input as it moves forward with the construction plans for the widening and reconstruction of State Road 400 (I-4) from 1 mile East of State Road 434 to East of State Road 15/600/US 17/92 Seminole / Volusia County Line.

As part of the design process, your property has been selected as a preferred site for one of the stormwater management facility areas. These stormwater management facilities are part of the drainage design to fulfill St. Johns River Water Management District permitting requirements. Enclosed is a sketch showing the approximate location and size of the stormwater management area.

Your input is important. FDOT would like your input on the location of this pond, including any suggestions you might have on reconfiguring the pond to better fit the future use of your property. We would like to get your input by March 30, 2017, so that we can finalize all pond sites.

Thank you for your cooperation. Please direct all questions and comments to:


Beata Styś-Pałasz, P.E.
Senior Project Manager
State of Florida Department of Transportation
719 South Woodland Boulevard
Mail Station 542
Deland, Florida 32720
Office: 386-943-5418
Fax: 386-736-5153


You may also contact me directly, **beata.stys-palasz@dot.state.fl.us**


Sincerely,




Beata Styś-Pałasz, P.E.
Senior Project Manager
Florida Department of Transportation
District Five


Enclosure

cc: Ferrell L. Hickson, Jr., P.E., District Drainage Engineer
Karen A. Snyder, P.E., Assistant District Drainage Engineer
Suzanne S. Phillips, P.E., District Consultant Project Management Engineer
Michael L. McPhail, MAI, Cost Estimate / Design Support Manager
Eileen LaSeur, Quest Corporation of America / Public Information Coordinator




MICHAEL J. QUARTETTI
P.E. LICENSE NO. 45976
PARSONS BRINCKERHOFF, INC.
2202 N. WEST SHORE BLVD, SUITE 300
TAMPA, FL 33607
PH (813) 520-4444 FAX (813) 520-4290
CERTIFICATE OF AUTHORIZATION NO. 00001462

**STATE OF FLORIDA**
**DEPARTMENT OF TRANSPORTATION**

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| SR 400 | SEMINOLE | 242592-4 |

# POND SITING PARCEL SKETCHES

SHEET NO.

robert.martinl 12/7/2016 8:37:37 AM c:\pwworking\aecom_na\rmartinl\dms63673\Pond308A 07-20-30-5MK-0000-0020.dgn

# Florida Department of Transportation

RICK SCOTT
GOVERNOR

719 S. Woodland Boulevard
DeLand, Florida 32720-6834

RACHEL D. CONE
INTERIM SECRETARY


February 27, 2017

TLC Properties Inc.
5321 Corporate Blvd
Baton Rouge, LA 70808

Dear Property Owner:

The Florida Department of Transportation (FDOT) sent notice to you, dated December 7, 2016, requesting your input as it moves forward with the construction plans for the widening and reconstruction of State Road 400 (I-4) from 1 mile East of State Road 434 to East of State Road 15/600/US 17/92 Seminole / Volusia County Line. We appreciate the feedback you have provided from this letter.

As part of the design process, your property has been selected as a preferred site for one of the stormwater management facility areas. These stormwater management facilities are part of the drainage design to fulfill St. Johns River Water Management District permitting requirements. We understand from your coordination with the FDOT that the original pond site is acceptable and we will continue to coordinate with you regarding relocation of the billboard on your property. Enclosed is a sketch showing the approximate location and size of the stormwater management area.

Your continued input is important. FDOT would like any additional input or suggestions you might have on reconfiguring the pond to better fit the future use of your property. We would like to get your input by March 30, 2017, so that we can finalize all pond sites.

Thank you for your cooperation. Please direct all questions and comments to:


Beata Styś-Pałasz, P.E.
Senior Project Manager
State of Florida Department of Transportation
719 South Woodland Boulevard
Mail Station 542
Deland, Florida 32720
Office: 386-943-5418
Fax: 386-736-5153


You may also contact me directly, **beata.stys-palasz@dot.state.fl.us**


Sincerely,



Beata Styś-Pałasz, P.E.
Senior Project Manager
Florida Department of Transportation
District Five

Enclosure

cc: Ferrell L. Hickson, Jr., P.E., District Drainage Engineer
Karen A. Snyder, P.E., Assistant District Drainage Engineer
Suzanne S. Phillips, P.E., District Consultant Project Management Engineer
Michael L. McPhail, MAI, Cost Estimate / Design Support Manager
Eileen LaSeur, Quest Corporation of America / Public Information Coordinator




MICHAEL J. QUARTETTI
P.E. LICENSE NO. 45976
PARSONS BRINCKERHOFF, INC.
2202 N. WEST SHORE BLVD, SUITE 300
TAMPA, FL 33607
PH (813) 520-4444 FAX (813) 520-4290
CERTIFICATE OF AUTHORIZATION NO. 00001462

**STATE OF FLORIDA**
**DEPARTMENT OF TRANSPORTATION**

| ROAD NO. | COUNTY | FINANCIAL PROJECT ID |
|---|---|---|
| SR 400 | SEMINOLE | 242592-4 |

# POND SITING PARCEL SKETCHES

SHEET NO.

robert.martinl 12/7/2016 8:06:21 AM c:\pwworking\aecom_na\rmartinl\dms63673\Pond303-B2 24-20-29-300-0090-0000.dgn

# MEMO

**TO:** File

**FROM:** John Littlefield

**SUBJECT:** Pond 303-B2 (Parcel 48) Coordination with property owner representative

**DATE:** **February 21, 2017**

---

**Attendees:** Beata Stys-Palasz, FDOT, Catalina Chacon, FDOT, Abhay Thorat, WSP, Michael McPhail, FDOT, Peter Costanza, Lamar Outdoor Advertising, & John Littlefield, WSP.

This property is owned by TLC Properties Inc. which also owns the existing electronic billboard on the property. Peter Costanza requested this meeting after receiving the pond letter dated December 7th, 2016 indicating that their site is one of the preferred pond site for the I-4 project.

Peter indicated that they did not have an issues with the purchase of the property with the exception of the billboard.

Peter went on to explain that the electronic billboard on this property generates more revenue than any other billboard the company owns. This billboard is very important to their company.

FDOT staff indicated that they are proposing to relocate the billboard within the proposed pond site and allow The Lamar maintenance staff to access the billboard through the adjacent property owner as they currently do today.

Peter didn't seem to have any issues with this proposal.

We discussed the maintenance access from the adjacent property. Peter indicated that since this is an electronic billboard that maintenance access is very seldom.

John indicated that the pond design is preliminary and once it is final we can discuss the relocation of the billboard.

All agreed to have a follow-up meeting in June to discuss the relocated billboard.

# MEMO

**TO:** File

**FROM:** John Littlefield

**SUBJECT:** Pond 303-B2 (Parcel 48) Coordination with property owner representative

**DATE:** **June 28, 2017**

---

**Attendees:** Beata Stys-Palasz, FDOT, Abhay Thorat, WSP, Michael McPhail, FDOT, Peter Costanza, Lamar Outdoor Advertising, Nick Truncone, FDOT, & John Littlefield, WSP.

This property is owned by TLC Properties Inc which also owns the existing billboard on the property. The purpose of the call was to continue discussion of the property taking and the proposed relocation of the existing electronic billboard in the proposed condition. Mr. Peter Costanza is the owner's representative.

John mentioned that pond design with the proposed relocated billboard at the southern end of the proposed pond. This provides that required 15-foot offset from the existing ROW.

It was discussed that the maintenance access from the adjacent property would remain unchanged.

Peter mentioned that a significant portion of the revenue for the sign is the side facing west so he wants to make sure that we won't be obstructing the view with the relocation.

He asked if the view to the relocated billboard site will be the same or better than the existing location.

We discussed relocating the billboard on the north side of the property

desirable DDI design criteria with FDOT, District 5 design staff.

Mike, asked what would the desirable design speed would be. We discussed the criteria published in the new FHWA DDI design manual.

Mark stated that 30-35 mph would be acceptable.

Mike asked what desirable deflection angles would be acceptable at the diverging intersections.

Mark acknowledged that FHWA would allow 40 degrees in cases, but FDOT considers 45 degrees more desirable.

Mike asked what the FDOT would consider is a desirable signal clearance time.

Mark stated a time of 3-4 seconds would be preferable.